This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at http://books.google.com/



A handbook on modern explosives

Manuel Eissler

Chem 7508.97.2

HARVARD
COLLEGE
LIBRARY

FROM THE
Subscription Fund
BEGUN IN 1858

SCIENCE CENTER LIBRARY

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

A HANDBOOK

ON

MODERN EXPLOSIVES

Digitized by Google

WORKS BY THE SAME AUTHOR.

THE METALLURGY OF GOLD. A Practical Treatise on the Metallurgical Treatment of Gold-bearing Ores. Including the Processes of Concentration, Chlorination, and Extraction by Cyanide, and the Assaying, Melting, and Refining of Gold. Fourth Edition, Enlarged. With about 250 Illustrations and numerous Folding Plates and Working Drawings. Large crown 8vo, cloth, 16*s.*

"This book thoroughly deserves its title of a 'Practical Treatise.' The whole process of gold-milling, from the breaking of the quartz to the assay of the bullion, is described in clear and orderly narrative and with much, but not too much, fulness of detail."—*Saturday Review.*

THE CYANIDE PROCESS OF GOLD-EXTRACTION: and its Practical Application on the Witwatersrand Gold-fields in South Africa. With Diagrams and Working Drawings. Large crown 8vo, cloth, 7*s.* 6*d.*

"This book is just what was needed to acquaint mining men with the actual working of a process which is not only the most popular, but is, as a general rule, the most successful for the extraction of gold from tailings."—*Mining Journal.*

THE METALLURGY OF SILVER. A Practical Treatise on the Amalgamation, Roasting, and Lixiviation of Silver Ores. Including the Assaying, Melting, and Refining of Silver Bullion. Third Edition. With 150 Illustrations. Crown 8vo, cloth, 10*s.* 6*d.*

"A practical treatise, and a technical work which, we are convinced, will supply a long-felt want amongst practical men, and at the same time be of value to students and others indirectly connected with the industries."—*Mining Journal.*

THE METALLURGY OF ARGENTIFEROUS LEAD. A Practical Treatise on the Smelting of Silver-Lead Ores and the Refining of Lead Bullion. Including Reports on various Smelting Establishments and Plants in Europe and America. With 183 Illustrations. Crown 8vo, 400 pp., cloth, 12*s.* 6*d.*

"The present volume fully maintains the reputation of the author. Those who wish to obtain a thorough insight into the present state of this industry cannot do better than read this volume."—*Industries.*

Digitized by Google

A HANDBOOK

ON

MODERN EXPLOSIVES

A PRACTICAL TREATISE

on the Manufacture and Use of Dynamite, Gun-Cotton, Nitro-Glycerine, and other Explosive Compounds, including Collodion-Cotton

WITH CHAPTERS ON

EXPLOSIVES IN PRACTICAL APPLICATION

BY

M. EISSLER

MINING ENGINEER AND METALLURGICAL CHEMIST

AUTHOR OF "THE METALLURGY OF GOLD," "THE METALLURGY OF SILVER," ETC., ETC.

Second Edition, Enlarged

WITH ONE HUNDRED AND FIFTY ILLUSTRATIONS

LONDON

CROSBY LOCKWOOD AND SON

7 STATIONERS' HALL COURT, LUDGATE HILL

1897

[*All rights reserved*]

Digitized by Google

Chem 7508.91.2

HARVARD COLLEGE
MAY 1 1901
LIBRARY

Subscription fund

Digitized by Google

PREFACE.

FOR over four hundred years the science of Explosives remained *in statu quo.* Chroniclers record the name of a Franciscan friar—one Berthold Schwartz, of Freiberg—as the inventor, in or about the year 1328, of what has since been known as Gunpowder; although many records are in existence which indicate that prior to that date the Arabs knew the use of an explosive mixture which they called *Medfaa.* This consisted of—

10 drachmas of saltpetre,
2 ,, ,, charcoal, and
1½ ,, ,, sulphur;

and it is noteworthy that these proportions closely resemble those of the present formula of English gunpowder—namely,

74·07 saltpetre,
14·82 charcoal, and
11·11 sulphur.

To whom the credit really belongs of inventing gunpowder is so far not cleared up, but there is no doubt that explosive mixtures existed and were utilised by the Chinese as far back as the beginning of the Christian era.

The first advance leading to the introduction of the modern High Explosives was made in 1832 by the

Digitized by Google

French chemist Barconnot, of Nancy, who discovered that "when starch, fibres, and analogous substances are acted upon by concentrated nitric acid, they are changed into highly combustible materials." In 1838 Pelouze continued these researches, and he ascertained that this new inflammable material—which he called *Xyloidine*—took fire at 180° C. when submitted to strong pressure, such as a rapid blow. He also found that cotton, paper, and indeed all vegetable matters, could be employed in the preparation of similar substances. All these researches, however, were without any practical value until Schönbein, of Bale, in 1845, devised methods for the manufacture of a new explosive on a commercial scale by treating cotton with a mixture of nitric and sulphuric acids. Schönbein, therefore, may be considered as the inventor of what English-speaking people call Gun-cotton; the Germans, *Schiessbaumwolle;* the French, *Fulmicoton*, or *Pyroxyle*—whence the generic name Pyroxyline.

It is also interesting to note that soon after—in the year 1847—the Italian chemist, Sobrero, discovered in Pelouze's laboratory in Paris the explosive properties of Pyro-glycerine or Nitro-glycerine; but the discovery remained without practical application until 1860, when the Swedish engineer, Alfred Nobel, devised methods for the manufacture of the substance on a large scale, and also succeeded in exploding it with certainty when under confinement. He patented it under the name of Nobel's Blasting Oil; and subsequently he discovered the ready means of absorbing the oil in porous substances, thereby producing the now famous Dynamite or (as it is called in America) *Giant Powder.*

The great benefits which have been conferred upon

Digitized by Google

the world at large by the invention of these explosive compounds need not be expatiated on here. From the first introduction of dynamite into mining operations I fully appreciated the great boon which had been conferred on the mining community by the application of this substance, and I studied its properties and effects with great interest. The result was the appearance in New York, in 1884, from my pen, of the first English treatise on the subject, under the title 'The Modern High Explosives,' published by Messrs. J. Wiley and Sons.

In bringing out this further treatise on the same subject, I have had in view the many discoveries of new compounds which have been made during the last few years, and their application to other than mining uses. A new group of compounds—the fundamental idea of which is due to Sprengel—has now been brought into existence ; and these may prove very beneficial to coal-miners in particular, if their *flameless* character should be verified by prolonged use and experiment.

In the following pages I have restricted myself to the outlines of the manufacture of the various nitro-glycerine compounds and varieties of gun-cotton, but I have added some particulars of their physical and chemical properties, and also a condensed account of such modern explosives of other types as are now manufactured in different parts of the globe.*

In the adaptation of modern explosives as propelling agents in guns and for use in artillery, a great deal has already been accomplished, but much remains to be

* For the name and composition of all explosives now known to be in use or patented, I may refer the reader to Major Cundill's 'Dictionary of Explosives,' from which I have the Author's permission to make the extract quoted by me at p. 50.

Digitized by Google

done. If one considers the short space of time, barely exceeding twenty years, since the modern explosives were brought into general notice, one must confess that the strides made in adapting them to new uses have been great indeed.

As to their application in the removal of obstacles which nature has placed in the way of the engineer, I have attempted only to give some simple rules and regulations for their safe and successful manipulation, and to show the beneficial results which are derived from their use in the hands of practical men.

How terrible an agent of destruction an explosive may become is seen in the new Pneumatic Dynamite Gun, which is capable of firing 600 lbs. of nitro-gelatine. There is no ship afloat to-day which would be able to resist the explosion of such a charge. Let us hope, however, that modern explosives may find their exclusive employment in the grander and more useful field of operations provided for them by the civil and the mining engineer.

In the preparation of this volume I have tried to avoid, wherever possible, the repetition of matter included in my American work, but it will be readily understood that in certain cases such repetition could not be avoided—for example, in the rules which are laid down for the preparation of bore-hole charges. In this case, also, a few of the sketches included in the former work have been reproduced.

In an Appendix I have given the principal results of the labours of Captain Hess, of the Austrian military service, in the analysis of the various modern explosive compounds. Coming from so distinguished an authority on the subject, the particulars here afforded cannot fail

Digitized by Google

to be acceptable to the English reader. I have also set out the instructions issued by the English Home Office (1) for instituting tests for explosives, and (2) in regard to applications for inclusion in the list of Authorised Explosives; and I have added an abstract of the principal provisions of the Explosives Act, 1875, which has been prepared at my request, and which will be found useful by all concerned in the production and sale, or the use, of explosives.

* * * * *

In the body of the work, I have indicated in several instances the particular sources to which I have been indebted for useful information and material. Here, also, I desire to acknowledge my obligations to the published writings of the distinguished Head of the Chemical Department of the War Office—Sir Frederick Abel, C.B., F.R.S., D.C.L.—appearing in the *Transactions of the Royal Society* and elsewhere: and to various German, French, and American publications which I have consulted—including Dr. J. Upman and E. Meyer's *Das Schiesspulver, die Explosivkörper, und die Feuerwerkerei; Dingler's Polytechnisches Journal; Jahresberichte;* Dr. Guido Wolfram *Ueber Nitroverbindungen der Cellulose;* Roux and Sarrau's *Force et Travail;* Berthelot's *Sur la force de la poudre*, etc. etc.; the *Encyclopædia of Chemistry* (Lippincott, Philadelphia); papers by Professor Munroe in the *Proceedings of the United States Naval Institute* (Annapolis, 1886); Lieutenant Quinan's *Report on Vigorite Powder*, etc., etc.

* * * * *

In the absence of any similar work on the subject in

Digitized by Google

this country, I sincerely trust that the mining community of England and the Colonies will find in these pages sufficient information for their practical assistance in the selection and handling of explosives—a subject of vital importance to the large and increasing number of persons who are interested in mining operations.

17 BELSIZE CRESCENT, SOUTH HAMPSTEAD.
September, 1889.

PUBLISHERS' NOTE TO SECOND EDITION.

SUBSTANTIAL additions having been made to the present edition—including an entirely new chapter (XVI.), and involving the enlargement of the volume by about one hundred pages, with fifty additional illustrations—it is hoped that the acceptability and usefulness of the work will be found materially augmented.

It is right to mention that the Second Edition has passed through the press in the Author's absence in New South Wales. In the revision of the proofs of new matter, the Publishers have had the advantage of the assistance of Mr. P. Gerald Sanford, F.I.C., to whom their cordial acknowledgments are due.

October, 1896.

Digitized by Google

CONTENTS.

CHAPTER I.

CHARACTERISTICS OF MODERN EXPLOSIVES.

PAGE

EXPLOSIVES Defined—Progress made in their Manufacture—Their Mode of Action—Several Grades required—Downward Force of Explosives—Springing or Chambering Holes 1

CHAPTER II.

ATTEMPTS AT SUBSTITUTES FOR GUNPOWDER.

EMPLOYMENT of Nitrate of Soda in Blasting Powders—Barium Nitrate—Potassium Chlorate Mixtures—Picrates—Experiments of Designolle, Abel, and Barbe—Dynamite—Gun-cotton—Sprengel Explosives 6

CHAPTER III.

PREPARATION OF NITRO-GLYCERINE.

COMPOSITION of Nitro-glycerine—Process of Manufacture—Stockholm Dynamite Works—Rudberg's Continuous Process—Pellet and Champion's Method—Continental Dynamite Factories—G. M. Mowbray's Process—Compressed Air Mixing Apparatus at Forcite factories—Test of Ingredients—Concentration of Spent Acids—Nobel's Apparatus 10

Digitized by Google

CHAPTER IV.

PROPERTIES OF NITRO-GLYCERINE.

PAGE

ITS Physical Properties—Its Effect on the Human System—Decomposition—Gases Evolved—Detonation—Nitro-glycerine in Use—Accidents when in the Liquid State—Rendered Non-explosive with Methylic Alcohol—Gelatinised Nitro-glycerine or Nitro-gelatine—General Abbot on Explosive or Blasting Gelatine . 35

CHAPTER V.

VARIETIES OF DYNAMITE.

INVENTION of Dynamite — Kieselguhr Dynamite — Influence of Kieselguhr on Explosive Efficiency—Experiments of Captain Hess and Lieutenant Schwab—Colonia and Hercules Dynamite—Vulcan—Seranine and Horsley's Powder—Dualine—Lithofracteur—Ammonia Powder—Giant Powder No. 2—Sebastin—Brain's Powder—Rhenish Dynamite—Forcite—Atlas Powder—Gelatine Dynamite—Glukodine—American Hercules Powder—Judson Powder—Paleine or Straw Dynamite—Trautzl's Dynamite—Carbo-Dynamite—Smolianinoff Explosive—Snyder Explosive—Von Dahmen's Safety Dynamite—Classification of Dynamites—American and Belgian Forcite Powder Works 47

CHAPTER VI.

APPLICATIONS OF GUN-COTTON.

EARLIER Experiments—Results of Sir F. Abel's Researches—Manufacture of Gun-cotton rendered Harmless—Diluted and Undiluted Gun-cotton—Wet Gun-cotton for military purposes—Compressed Gun-cotton for Submarine mining—Transmission of Detonation in Water—Transmission of Detonation through Air 75

Digitized by Google

CHAPTER VII.

MANUFACTURE OF GUN-COTTON.

PAGE

OUTLINE of the Process—Gun-cotton distinguished from Collodion-cotton—Gun-cotton an Ether of Nitric Acid—Manufacture of Gun-cotton at Le Bouchet—Manufacture at Waltham Abbey—Messrs. Mackie and Faure's Granulated Gun-cotton . . . 84

CHAPTER VIII.

PROPERTIES OF GUN-COTTON.

PHYSICAL Appearance of Gun-cotton—How does Gun-cotton explode?—How to render it less sensitive—Detonation of Wet Gun-cotton—Gases produced by the Explosion of Gun-cotton—Spontaneous Decomposition—Advantages and Disadvantages of Gun-cotton in use 101

CHAPTER IX.

VARIETIES OF GUN-COTTON AND OTHER NITRO-COMPOUNDS.

PYROXYLINE — Schultze's Powder—Lannoy's White Powder—Uchatius' White Powder — Nitric Acid and Sugar — Nitro-Mannite — E. C. Powders — Johnson's Powders — Punshon's Gun-cotton—Totten's Gunpowder—Tonite—Professor Attfield's Experiments with Tonite—General Abbot on Tonite—California Gun-cotton. 109

CHAPTER X.

COLLODION-COTTON.

ITS importance in Practical Use—Processes of Manufacture—Compounds of Cellulose—Celluloid—Tribouillet and Besaueile's Process—Proportions in which Cellulose is found in Natural Products 118

Digitized by Google

CHAPTER XI.

VARIOUS OTHER EXPLOSIVES.

PAGE

THE Sprengel Explosives—Flameless Explosives—Roburite—Experiments with Roburite and other Explosives—Mr. Hilton's Rules for using Roburite—Bellite—Securite—Trench's Fire-extinguishing Compound — Favier's Explosive — Hellhoffite — Romite — Rack-a-rock — Panclastite — Melinite — Picric Acid — Turpin's Shell 133

CHAPTER XII.

DETERMINATION OF THE RELATIVE STRENGTH OF EXPLOSIVES.

ELEMENTS of Comparison of Explosives—Methods of Comparison—Experiments of Captain Noble, Sir F. Abel, MM. Roux and Sarrau, and M. Berthelot—Nobel's Ballistic Test—Calculating the Effect of Dynamite—Apparatus of Kostersitz and Hess for Measuring Shattering Power of High Explosives—Iron Plate Test for Surface Charges of Dynamite—Pressure Gauge—Measurement of Strength of Explosives—Foot-pounds Machine—Quinan's Diagram for Measurement of Pressure—Initial Detonation . 163

CHAPTER XIII.

CONDITIONS TO WHICH MODERN EXPLOSIVES SHOULD RESPOND.

CONDITIONS of Strength—Quick Explosion desirable for Blasting—Internal Resistance to Detonation—Conditions of Safety—Immunity against Fire—Decomposition—Leakage—Deliquescence—Unstable Character of Deliquescent Explosives—Resistance to High Temperature—Insensitiveness to Friction, Shocks, and Jars—Percussion—Concussion—Transmission of Explosion—Tamping—Purity of Explosion Gases—Detection of Nitroglycerine in the Human Body—Precautions during Manufacture of Explosives—Explosions due to External Causes—Action of Explosives Department of Home Office 186

Digitized by Google

CHAPTER XIV.

GENERAL DIRECTIONS FOR USING DYNAMITE.

PAGE

GRADES of Dynamite—General Rule for its Use—Materials for use in Blasting—Drill Holes, Charges, etc.—Charging with Cartridges — Priming — Tamping — Explosion of Blast — Miss-shots—Imperfect Explosions—Explosion by Sympathy—Frozen Dynamite—Safe Mode of Thawing—Frozen Nitro-glycerine Compounds—Precautions 206

CHAPTER XV.

EXPLOSIVES IN PRACTICAL APPLICATION.

EFFICIENCY of Dynamite in removing Tree Stumps and Boulders —Blasting Tree Stumps—Blasting Boulders—Sinking Wells—Breaking Ice—Breaking Boulders—Removing Piles under Water—Pile-driving with Dynamite—Rock-blasting—Tunnelling and Blasting in Headings—Musconetcong Tunnel—Tunnelling with Hand-labour — Königshütte Tunnel — Pfaffensprung Tunnel—Blasting Large Mines—Underground Drilling with Compressed Air—Mining with Power Drills—Quantity of Explosives used in Blane Valley Contract 222

CHAPTER XVI.

NITRO-GELATINE AND GELATINE DYNAMITE IN PRACTICAL APPLICATION.

NITRO-GELATINE and Gelatine Dynamite as used in Mining and in Tunnelling—Removal by Gelatine Dynamite of Obstruction in a Blast Furnace—Iron-plate Tests with Nitro-glycerine—Experiments with Military Explosive Gelatine 252

CHAPTER XVII.

APPLICATION OF ELECTRICITY IN FIRING MINES.

ECONOMICAL Value of Blasting by Electricity—Sir Frederick Abel's Test—Electric Blasting Apparatus—Magneto Machine No. 3—Directions for Blasting—Influence of Heat on the Conductivity of Gutta-percha-covered Wires—Low and High-tension Fuzes . 271

Digitized by Google

CHAPTER XVIII.

USE OF EXPLOSIVES IN FIERY MINES.

PAGE

SIR F. ABEL on the Prevention of Fire-damp Explosions during Blasting—A New Method of Exploding Charges in Fiery Mines —Compressed Lime Cartridges for bringing down Coal . . 288

CHAPTER XIX.

APPLICATION OF EXPLOSIVES IN SUBMARINE ENGINEERING.

REMOVAL of Obstacles in Rivers and Harbours—Methods of Submarine Blasting—Pontoon Drilling—Machine Drills—Drilling and Blasting—Blowing up Sunken Wrecks 298

CHAPTER XX.

APPLICATION OF EXPLOSIVES FOR MILITARY PURPOSES.

MODERN Explosives as applied in Warfare—Zalinsky's Pneumatic Gun—Essential Conditions of Dynamite Firing—How Zalinsky's Gun was Invented—Official Report upon the Gun—The German and the Maxim Pneumatic Guns—The Graydon Dynamite Shell —Gun-cotton Shells—Blasting Gelatine as a Military Explosive . 304

APPENDICES.

APPENDIX A.—*CAPTAIN HESS ON THE ANALYSIS OF EXPLOSIVES* 326

APPENDIX B. — *DETERMINATION OF STABILITY.* — *INSTRUCTIONS AS TO TESTS ISSUED BY THE HOME OFFICE* 351

APPENDIX C. — *APPLICATIONS FOR AUTHORISATION OF EXPLOSIVES.* — *INSTRUCTIONS ISSUED BY THE HOME OFFICE* 362

APPENDIX D.—*THE EXPLOSIVES ACT*, 1875.—*ABSTRACT OF THE PRINCIPAL PROVISIONS OF THE ACT* . 364

INDEX 399

Digitized by Google

LIST OF ILLUSTRATIONS.

FIG.		PAGE
1.	Rudberg's Nitro-Glycerine Apparatus	13
2.	Do. do. do. Section	14
3.	Mowbray's Nitro-Glycerine Apparatus	18
4.	Do. do. do. Section	19
5.	Mowbray's Nitro-Glycerine Washing Apparatus	20
6.	Nobel's Apparatus for Concentrating Spent Acids: Sectional Elevation	30
7.	Nobel's Apparatus for Concentrating Spent Acids: Sectional Plan	31
8.	Do. do. Vertical Section of Chamber	31
9.	Do. do. Cross-Section of Chamber	32
10.	Do. do. Sectional Elevation	33
11.	Do. do. Front Elevation	33
12.	Kieselguhr Dynamite under the Microscope	50
13.	Do. do. Another Sample	51
14.	Plan of Forcite Works at Baelen-sur-Nethe, Belgium	*facing* 74
15.	Fesca's Centrifugal Hydro-Extractor	87
16.	Centrifugal Hydro-Extractor: Another Form	88
17.	Stone Jar for Steeping Gun-cotton	88
18.	Machine for Carding Gun-cotton	90
19.	Drying Cylinder, and Section of Drying Tube	91
20.	Dipping Apparatus	91
21.	Washing Apparatus	92
22.	Hollander or Pulping Engine: Section	93
23.	Do. do. Plan	93

Digitized by Google

FIG.		PAGE
24.	Poacher for Washing Gun-cotton Pulp	95
25.	Vat or Mixing Machine	95
26.	Hydraulic Press	96
27.	Do. Another Form	97
28.	Nitrating Basin for Pyroxyline: Section	123
29.	Do. do. Plan	123
30.	Cylindrical Press: Section	124
31.	Do. Plan	124
32.	Filter	125
33.	Washing Vessels	125
34.	Plan of Pyroxyline Factory	126
35.	Enamelled Wire Basket	128
36.	Press	129
37.	Plan of Condensing Chamber	130
38.	Application to Cartridges of Trench's Fire-extinguishing Compound	146
39.	Turpin's Shell	161
40.	Apparatus for Measuring Shattering Power of Explosive	170
41.	Collar on which Steel Discs are Exploded	172
42.	Steel Disc: before Explosion	172
43.	Do. after Explosion	172
44.	Fuze and Cartridge	172
45.	Steel Plate after Explosion	173
46.	Do. do.	173
47.	Pressure Gauge	174
48.	Piston of Pressure Gauge	174
49.	Shot of Pressure Gauge	174
50.	Lead Plug	175
51.	Trautzl's Apparatus for Testing Strength of Explosives	176
52, 53.	Diagrams illustrating Results with do. (Dynamite)	177
54, 55.	Do. do. do. (Reime Gelatine)	177
56.	Foot-pounds Machine	179
57.	Micrometer Calipers	179
58.	Drawn Lead Plug after Compression	179
59.	Cast Lead Plug after Compression	179
60.	Section of Plug showing Reduction in Pressure Gauge	180
61.	Quinan's Diagram for Measurement of Pressure	181
62.	Friction Test for Nitro-Glycerine	192

Digitized by Google

FIG. PAGE
63. Percussion Gauge 193
64. Diagram illustrating Test of Transmission of Explosion . . . 197
65. Tamping Test 199
66, 67. Dynamite Cartridges 208
68. Fuze Cutter and Nipper 209
69. Fuze and Cap 209
70. Charging Bore-hole 211
71. Fastening Cap 211
72. Primer 212
73. Do. 215
74. Firing the Charge 215
75. Stump of Tree before Blasting 223
76. Do. after Blasting 223
77. Rock before Blasting 225
78. Do. after Blasting 225
79, 80. Piles with Charges Electrically connected 226
81. Pile containing Charge 226
82. Stump with Three Charges 227
83. Stump with External Charge 227
84–94. Pile-driving with Dynamite 229–232
95. Application of Bore-holes in Rock 235
96. Bore-hole not bottomed 235
97. Bore-hole parallel with Face 235
98. Blasting Out Cuts 236
99. Blasting on an Incline 236
100. Heading of Musconetcong Tunnel 238
101. Do. do. Plan of the Heading . . . 238
102. Bench-work at Musconetcong Tunnel: Section 240
103. Do. do. Plan 240
104, 105. Face of Tunnel 241
106, 107. Do. 243
108, 109. Sections of Königshütte Tunnel 243
110, 111. Sections of Pfaffensprung Tunnel 244
112. Blast of Rock in Port of Genoa: Plan 245
113, 114. Do. do. Sections 246
115. Stoping Ore in an Iron-Mine 248
116. Experiment in Coal-Mines of Königshütte, Prussia 253
117. Experiment in a Mine at Lugen, Saxony 254

Digitized by Google

FIG. PAGE
118. Experiment in the Silver-Lead Mines, Friedrichssegen, near Oberlahustein 254
119. Experiment at the Pfaffensprung Tunnel 255
120. Experiment in the Spiral Tunnel, near Faido. 256
121. Experiment in a Coal-Mine near Tankerode, Saxony . . . 257
122. Removal by Gelatine Dynamite of Obstruction in a Blast Furnace 259
123. Drill-holes made in Removing Obstruction from Blast Furnace 259
124–127. Diagrams illustrating Iron-Plate Tests with Nitro-Gelatine 261
128, 129. Iron-Plate Tests with Frozen Explosives 264
130. Experiments to Determine Strength of Primers 267
131–133. Magneto Machine for Electric Firing of Blasts 274
134. Platinum Electric Fuze 276
135. Connecting Wire 277
136. Mines Electrically Connected 277
137. Firing by Electricity at Bottom of Shaft 278
138. Do. do. the Blast Fired . . 279
139. Conducting Wires 281
140, 141. Abel's Electrical Fuze 285
142–144. Lauer's System of Firing Charges. 294
145. Exploder for Pneumatic Dynamite Gun 309
146. Dynamite Shell with Exploder 309
147. Zalinsky's 8-inch Dynamite Gun 310
148. Test of Insensibility of Explosive Gelatine to Pressure . . . 321
149. Apparatus for Analysis of Nitro-compounds 327
150, 151. Sir F. Abel's Heat Test Apparatus 352
152, 153. Do. do. 355

Digitized by Google

A HANDBOOK

ON

MODERN EXPLOSIVES.

CHAPTER I.

CHARACTERISTICS OF MODERN EXPLOSIVES.

EXPLOSIVES Defined—Progress made in their Manufacture—Their Mode of Action—Several Grades required—Downward Force of Explosives—Springing or Chambering Holes.

THROUGHOUT the following pages I shall use the term "Explosives" for the Modern High or Strong Explosives, in contradistinction to the term "Powder," by which is meant a Low Explosive, such as Gunpowder.

In no department of human industry has more rapid progress been made of late years than in explosives. Their rapidly extending use for the removal of masses of rock has directed attention to their nature and mode of action; and has also led to numerous attempts to increase their effectiveness, to modify their action to suit their different uses, and to reduce their danger.

The ablest chemists and the best engineers have found in the study of explosives a fruitful field; and the results of their labours are to be seen in the perfected explosives of to-day—explosives which are marvels of chemical perfection; which are so modified and varied in their method of action as to be adapted to all varieties of practical work; and which, with all their enormous power, stored up in their particles, are so completely under control, that they may be handled freely in

Digitized by Google

any class of work with perfect safety, when in the hands of careful and experienced operators.

The advantages of using *strong explosives* are manifold and manifest. So obvious, indeed, are they, that explanation would hardly seem to be needed. If of two explosives of equal price, one be stronger than the other, it is evident that less may be employed to do the same work. But economy, as the consequence of strength, is to be sought mainly in another direction; and the principal economy in the use of strong explosives remains, even where the stronger commands the higher price. For, as every practical man knows, the cost of the explosive in blasting operations is small in comparison with the cost of the labour employed. In other words, the main expense of blasting is the labour of drilling, loading, &c.—the cost of the explosive being one of the minor items.

If therefore by using the stronger explosive (even at a higher price) we can accomplish more with the same amount of labour, we shall find that true economy lies in the use of this explosive.

The completion of the work in a shorter space of time must also be taken into account. For, if we wish to complete a work in order to obtain a profit, the sooner the work is completed the sooner we shall commence to realise the profit.

Strength, however, is not the only merit of an explosive. In many cases, indeed, it is a matter of secondary importance; and in certain classes of work the *mode of action*—always a very important point—becomes the paramount consideration.

If we take two explosives, one of which will exert a very powerful action upon a small surface, while the other will throw a milder but more sustained action upon a larger mass, it is evident that both explosives will be useful, each in its own way. The one will exert a shattering force; the other will produce a rending action.* Experience has shown that we need both of these explosives, each for its own work.

* See my work on 'Modern High Explosives,' pp. 240 to 251, "Force and Effect of Explosive Bodies." J. Wiley and Sons, New York.

Digitized by Google

If we have to deal with hard rock, and desire, therefore, to exert great force upon a small surface, we shall find economy in the use of the strongest grade of explosives, or No. 1. But if we have to do our blasting in a softer material, we shall find that No. 1 is too local in its action, and that we can break a larger mass with a weaker or slower explosive, or No. 2. Hence, we shall here use No. 2, as giving the most economical results.

The relative cost of the two explosives need not be considered; as a general rule, *it pays* to have explosives adapted to the work, without regard to the small difference in cost.

The custom, which still prevails in some European countries, of using one grade of explosives for all work indiscriminately, is open to serious objections: explosives ought to be modified so as to suit the character of the rock which they have to break down.

Still another mode of action is in many cases desirable—a heaving action, similar to that of black powder or gunpowder, but many times more powerful. It is important, however, that this excess of power should be exerted in breaking up a larger quantity of rock, and not in throwing an equal quantity to a great distance.

As compared with black or common gunpowder, for stoping and for work in light ground, the advantage of a still weaker explosive—such as a No. 3—is obvious, from the fact that smaller holes may be used, and consequently much less labour required in drilling. For instance, if an ordinary compressed gunpowder-cartridge, such as is used for coal mining—say 16 inches long by 2 inches in diameter—is required to break down two cubic yards of coal, and we can store the same amount of energy (which means work) in the cartridge of an explosive No. 3, which is 8 inches long and 1 inch in diameter; the miner, instead of drilling a 2-inch bore-hole, needs only to drill a hole of 1 inch diameter, thus saving both labour and time, or the equivalent in money.

Moreover, the force of black powder, especially in seamy rock, escapes at every crack, and thus much is wasted, as

Digitized by Google

thousands upon thousands of miners will testify. On the contrary, the No. 3 explodes instantaneously and perfectly, and thus the whole force is utilised, no matter how shelly the rock may be.

Every miner knows the importance of having *as much as possible of the charge at the bottom of the bore-hole:* it is there that the maximum amount of work is exerted; and as the explosives contain the stored-up energy in a smaller volume than the ordinary gunpowder or blast powder, they allow of the concentration of the charge nearer the bottom of the bore-hole. Let us suppose two bore-holes, each 1 inch in diameter, and say 6 feet deep. We charge the first hole with gunpowder to a depth of 4 feet, and give it 2 feet of tamping; we charge the second hole with No. 3 explosive to a depth of $2\frac{1}{2}$ feet, and give it $3\frac{1}{2}$ feet of tamping: then "fire" both charges. It will be found that the second hole has given far better results, for the reasons above stated.

The *downward force* exerted by explosives is surprising. This is a benefit in most blasting operations, but its advantage will be specially recognised by those who practise springing or chambering of deep holes.

In deep bore-holes, when it is a question of removing large masses of rock—as in quarrying stone, or in railway cuttings—the practical miner has always recognised the importance of concentrating his charges in the bottom of his bore-holes, and the introduction of explosives has enabled him to produce capacious chambers in the bottom of his bore-holes wherein to lodge his charge. I am a strong believer in "springing" or "chambering" holes, and consider that in the future it will be more largely practised than at present. By its means a small hole is converted into a larger one, and thereby much labour is saved.* Both No. 1 and No. 2 explosives are admirably adapted for springing, but the enormous strength of No. 1 fits it specially for this work. Experiments have shown that it springs a larger "pot-hole" than No. 2 when

* See 'Modern High Explosives,' *art.* "The Big Mole of the Central Pacific Railway at Oakland."

Digitized by Google

used in rock. In soft or medium ground many experienced blasters use No. 2 with excellent results.

Every expert at blasting has his own method of doing this work. Nevertheless I give the way which has afforded me the best results. Pack a small quantity of No. 1 or No. 2 explosive, according to the nature of the ground, firmly in the bottom of the hole. Now, lower upon it a small primer, being sure that the primer is well in contact with the charge. Pour in a handful of dry sand, to exclude the air; then explode.

By this means the hole at the very bottom becomes enlarged and fissured, and a large volume of powder or explosive can now be packed *well down* into it, where it will do the most good. It is wonderful how much better execution powder will do when packed in this way in the *very bottom* of the hole.

Digitized by Google

CHAPTER II.

ATTEMPTS AT SUBSTITUTES FOR GUNPOWDER.

EMPLOYMENT of Nitrate of Soda in Blasting Powders—Barium Nitrate —Potassium Chlorate Mixtures—Picrates—Experiments of Designolle, Abel, and Barbe—Dynamite—Gun-cotton—Sprengel Explosives.

ATTEMPTS to replace gunpowder as a mining and blasting agent, either by modifications of that material prepared with a view to economy, or by explosive mixtures more violent in their action, have been very numerous; few, however, have so far resulted in any permanent success.

The substitution of the comparatively cheap **Sodium Nitrate** for saltpetre, as in the blasting powders of *Oxland*, *Davy*, *Schwarz*, and *De Tret*, has been to some extent successful, though the hygroscopic character of that salt constitutes an insuperable difficulty to the production with it of any but comparatively weak powders.

Barium Nitrate has also been substituted for saltpetre, in the so-called *Saxifragin* powder manufactured by *Wynants* of Brussels, which was originally devised exclusively for industrial purposes, but was afterwards proposed, though without result, for use in heavy guns, on account of the comparatively gradual development of its explosive force. Charcoal has been partly or entirely replaced in powder by other artificial varieties of carbon, and also by organic substances more or less rich in hydrogen. It has been proposed even to use wood fibre itself, instead of the carbonized product.

Potassium Chlorate.—But the chief direction which attempts to produce useful powder substitutes has taken is

Digitized by Google

that of applying the comparatively violent oxidising properties of potassium chlorate. It has been proposed by not a few inventors to substitute this salt, partly or entirely, for saltpetre in mixtures similar to gunpowder; and numerous preparations consisting of the chlorate more or less intimately mixed with oxidisable substances, both mineral and organic, have been experimented with, and in a few instances have received some amount of practical application. So far, however, no perfect preparation, such as would suggest to the practical powder-maker a good preparation, has come under my notice: they are mostly rough mixtures of chemicals; but no doubt, one of these days, some inventor will be able to produce a good and perfect chlorate of potash powder.

Among those preparations which are best known are the modifications of the original white or German gunpowder—that is, mixtures of sugar and prussiates of potassium with the chlorate, as made by *Reveley;* or preparations consisting of mixtures of tannin, powdered nut-galls, or cream of tartar, with the oxidising agent, as devised by *Horseley*, *Ehrhardt*, *Sharp* and *Nisser;* others, such as *Teutonite*, consist of a small proportion only of the chlorate, mixed with sulphur and metallic sulphides, containing perhaps also free sulphur. Exceedingly crude mixtures of spent tan or sawdust, with saltpetre or other oxidising salts, together with a little sulphur, have been devised apparently rather with a view to comparative safety, than to compete in effects with gunpowder (though the power of victorious competition has been claimed for some): *Kellow's Powder*, *Pyrolithe*, and *Pudrolithe* are preparations of this kind. Lastly, picric acid in the form of the potassium and ammonium compounds, mixed with oxidising salts, has been made the basis of powerful explosive agents, with which experiments (to be described hereafter) have been carried on in England; and lately *Melinite,* which is a picrate compound, has been adopted, with some modifications, by the French Government for the filling of shells: but the exact composition of this French preparation has, so far, been kept secret. A substance called *Lydite* is now being ex-

Digitized by Google

perimented with by the English Government, which no doubt bears much resemblance to the French melinite.

The potassium salt, when intimately mixed with the chlorate, furnishes a product which in susceptibility to detonation and violence of action more nearly resembles nitro-glycerine and gun-cotton than any explosive mixture composed of solid substances, but hitherto it has not been made applicable to practical uses on account of the great readiness with which it is exploded by friction and percussion. Whenever inventors can so modify the composition of the chlorate mixtures as to reduce their sensitiveness, a most valuable ingredient will be available in the manufacture of explosives. Indeed, chlorate of potash seems by its nature destined to play an important part among explosives, as it possesses all the necessary properties of strength and absence of injurious fumes; but we have first to learn how to control it and to confine it within definite bounds. No doubt modern chemistry will furnish us with the means of overcoming what heretofore has been considered an immovable obstacle.*

Picrates.—Mr. Designolle devoted much attention, some years ago, to the production of safer explosive preparations, containing potassium picrate, for use in artillery and small arms. One of these, in which that salt was mixed with charcoal, saltpetre, and potassium chlorate, was experimented with at Le Bouchet on a considerable scale, with some favourable results, but the experiments were abandoned in consequence of a fearful explosion at a factory in Paris, where a large quantity of potassium picrate was stored. Much more satisfactory results have been obtained in experiments carried on by the British Government with a powder proposed by Sir Frederick Abel, and devised at about the same time by M. Barbe, composed of equivalent proportions of ammonium picrate and saltpetre. This mixture is said to be as safely and readily prepared as gunpowder, is perfectly stable in character,

* See 'Modern High Explosives': "Chlorates," pp. 138 to 140; also "Picrates," pp. 135 to 137.

Digitized by Google

and is not more susceptible than the latter to explosion by friction and percussion. It has furnished satisfactory results when employed in shells and in submarine mines; the explosive force exerted by it is not greatly inferior to that of gun-cotton and dynamite.

The mere contact of a very crude admixture of metallic oxides or nitrates—notably litharge, lime, and the nitrates of lead and strontium—with picric acid, is sufficient, with the application of heat, to cause detonation, and such detonation will extend to contiguous masses of the unmixed picric acid. The heat first induces the formation of picrates, and its continued application causes their detonation.*

The possibility of replacing gunpowder to an important extent, in its application to ordnance, by other explosive agents, appears at the present time quite feasible, and as a disruptive agent for mining purposes it has already in great measure been replaced by the two modern explosives—*Dynamite* and *Gun-Cotton*. Other nitro-compounds are gradually being brought forward, and a new series of explosives, which we will class under the term of *Sprengel Explosives*, are making their way with some success in the United States of America and also in Europe.

The foremost rank amongst modern explosives is at present occupied by dynamite and gun-cotton preparations, and in the following chapters will be found an account of their manufacture and of their chemical and physical properties. As nitro-glycerine forms the base of the dynamites, this important substance has to be considered first.

* See the special Report by Colonel Majendie, H.M.'s Chief Inspector of Explosives, on "The Circumstances attending a Fire and Explosion at Messrs. Roberts, Dale and Co.'s chemical works, near Manchester, on the 22nd of June, 1887."

Digitized by Google

CHAPTER III.

PREPARATION OF NITRO-GLYCERINE.

COMPOSITION of Nitro-Glycerine—Process of Manufacture—Stockholm Dynamite Works — Rudberg's Continuous Process — Pellet and Champion's Method—Continental Dynamite Factories—G. M. Mowbray's Process—Compressed Air Mixing Apparatus at Forcite factories — Test of Ingredients — Concentration of Spent Acids — Nobel's Apparatus.

NITRO-GLYCERINE was discovered at Paris in 1847 by Sobrero, who obtained it by acting with nitric acid on glycerine, and called it, on account of its explosiveness when the temperature is suddenly raised, *Pyro-glycerine.* At first it was put to no practical use; but later it met with pharmaceutical application, chiefly in America, under the name of *Glonoin.* Its value as an explosive was demonstrated by Alfred Nobel in 1863.

Nitro-glycerine, according to *Williamson,* is either a compound of glycerine, a glycerine of nitric acid, or a glycerine trinitrin; the hydrogen atoms of the three hydroxyls of glycerine being replaced by the radical of nitric acid. Its formula, $C_3H_5N_3O_9$ resolves itself into—

$$CH_2.O.NO_2$$
$$CH\ .O.NO_2$$
$$CH_2.O.NO_2.$$

But the nitro-glycerine of commerce is rarely, if ever, pure glycerine trinitrin; it contains, according to *Captain Hess,* more or less quantities of glycerine mononitrin and glycerine dinitrin. Hess found 13·7 to 16·6 per cent. of nitrogen in commercial samples, whilst pure glycerine trinitrin requires 18·5 per cent. of nitrogen.

Nitro-glycerine is formed. as already stated, through the

Digitized by Google

action of concentrated nitric acid on glycerine. The process is represented by the equation—

$$\underset{\text{Glycerine.}}{C_3H_5(OH)_3} + 3\,\underset{\text{Nitric Ac'd.}}{NHO_3} = \underset{\text{Nitro-Glycerine.}}{C_3H_5(O.NO_2)_3} + 3\,\underset{\text{Water.}}{H_2O}.$$

By using a mixture of nitric acid and sulphuric acid, the latter binds the water eliminated in the reaction; and by thus preventing a dilution of the glycerine, aids the formation of the nitro-glycerine.

Process of Manufacture.—According to *Sobrero*, two volumes of sulphuric acid, of 1·831 specific gravity, and one volume of nitric acid, of 1·525 specific gravity, are mixed and permitted to cool, and half a volume of glycerine, ~~of syrupy consistency~~, is then introduced with constant stirring. The mixture is again cooled, not necessarily below 0° C., and, after having become turbid and separated into two layers, poured into fifteen to twenty times its bulk of cold water. The oily nitro-compound sinks quickly to the bottom, is freed from unchanged acid and glycerine by repeated washing with water, and lastly, dried *in vacuo*.

Praeger and *Bertram* use one part by weight of glycerine to eight parts of a mixture of one part of concentrated nitric acid and two parts fuming sulphuric acid.

Liebe recommends pouring one part by weight of glycerine into a mixture of two parts of nitric acid, of 1·525 specific gravity, and four parts of concentrated sulphuric acid; keeping the mixture below 25° C.; and drying the washed nitro-glycerine in the steam bath. Various other methods have been proposed.

In preparing nitro-glycerine on a large scale, the glycerine is obtained from some candle factory; the sulphuric acid, likewise, from some outside works; but the nitric acid is produced on the spot. The nitro-glycerine works must be so placed that, in case of an accident, the destruction should be limited to the factory. The nitric acid is distilled in a compartment by itself. The manufacture of the nitro-glycerine

Digitized by Google

is sometimes carried on in three wooden sheds of light structure separated from one another by strong earth banks, of 25 to 30 feet in thickness at their base; the walls and roofs are lined with straw, and the temperature, by means of hot-water pipes, is kept day and night at 15° C.

In the one shed the glycerine is brought together with the mixture of acids; in the second shed the nitro-glycerine is poured into the water, and otherwise washed; in the third shed the complete elimination of acid from the oily compound is effected, and eventually the nitro-glycerine is worked up into dynamite. These three operations are now usually effected in one building, by means of more modern appliances, but in some of the older factories the above system is still adhered to. The sheds are sunk into the ground, so that their flat roofs are barely above the level of the ground; they are lit up by reflecting lamps placed outside on the roofs; the floor is covered with fine sand. At some distance from these sheds are the huts in which the cartridges are made. They likewise are separated from one another by earth banks, and so is another shed in which the packing takes place. Quite away from all these buildings are the store-houses, sunk into the ground. There are usually also cellars for the keeping of ice, which latter serves for cooling the wash water and the mixing tanks. The storing of the raw glycerine and the sulphuric acid requires no special precaution.

Stockholm Dynamite Works.—*Rudberg* recommended the following process here in 1868. Figs. 1 and 2 show, respectively, vertical sections of front and side views of the apparatus. Vessel 1 contains the acid mixture which had previously been cooled in a vat lined with lead; vessel 2 contains the glycerine; and 3, cold water. All these have outlet tubes which are provided with taps. The contents of 1 and 2 are permitted to flow, on opening the taps *a* and *b*, through the tubes A and B, into the vessel provided with the funnel C; this latter vessel is suspended over the channel D, which is fitted with stair-like shelves, and surrounded by a

Digitized by Google

water-tight wooden trough. According to the arrangement represented in Fig. 1, the vessel receiving the contents of 1 and 2 is not suspended, but is provided with wheels, so that it can be caused to move continuously to and fro on the rails *c*. The lower ends of the outlet tubes A and B are slightly bent, and are situated at the opposite side of the bulb of a thermometer T, placed between them. In this way the glycerine and the acid mixture meet just below the thermometer, and the rise of temperature caused by the chemical



FIG. 1.—RUDBERG'S NITRO-GLYCERINE APPARATUS.

reaction can thus be accurately measured. For the sake of greater caution, there is a second thermometer fixed in the tube of the funnel C. The water from 3 enters through tube *g*, by tap *m*, the space between the channel D and the surrounding trough, and finally leaves through tube *n*.

The working of the apparatus is easily understood. The channel D is surrounded with cold water from 3, through *g* and *m*, and now the acid mixture is allowed to flow slowly into the funnel C, which is set in oscillating motion, so that the tube of the funnel should alternately be over the different

Digitized by Google

compartments of the channel D. As soon as the acid begins to run simultaneously from all the compartments, the glycerin, is turned on and allowed to mix with the acid. The reaction between the two takes place immediately; it is completed as soon as the mixture has passed through the channel D which is carefully to be kept cool by a constant supply of cold water. From D the mixture flows into the large vat 4, where



FIG. 2.—SECTION OF RUDBERG'S NITRO-GLYCERINE APPARATUS.

the nitro-glycerine separates as an oily layer. It is drawn off, washed first with solution of sodium carbonate, then with water.

The remaining diluted acid can be concentrated with very little expense, and used again for nitrifying glycerine. If no such re-application of the acid mixture is intended, the vessel 4 is filled with water, whereupon the nitro-glycerine sinks to the bottom, and can easily be separated from this supernatant

Digitized by Google

acid liquid. Washing with sodium carbonate solution and with water concludes the process.

Pellet and *Champion* noticed in 1871, that if the whole quantity of glycerine required in one operation be suddenly poured into the acids, and the mixture stirred with a glass rod for ten seconds, the formation of the nitro-glycerine will have been completed, and yet there has been no time for a rise of temperature to take place; on throwing, therefore, the mixture into a large mass of water, the nitro-glycerine will separate. But the syrupy condition of glycerine makes it difficult to let a quantity of it flow quickly into the acid. Champion recommends, therefore, to allow the glycerine to run down the sides of the mixing vat, so as to accumulate on the surface of the acids, and when the desired quantity is floating above the acids, to mix the two quickly with a glass rod for ten minutes, and then to pour the mixture into fifteen to twenty times its bulk of cold water. Washing with soda and water, and drying by means of calcium chloride, or by heating to 30° or 40° C., conclude the process. The quantity of nitro-glycerine thus obtained is double that of the glycerine used.

Continental Dynamite Factories.—In European factories, where the daily production is two tons and over, the nitro-glycerine is prepared in the following manner:—

The glycerine used is of 1·26 specific gravity. The nitric acid is obtained by distilling a mixture of equal parts of Chili saltpetre and sulphuric acid in cast-iron retorts of about 180 cubic feet contents; it is red from nitrous acid, and contains also chlorine, derived from chlorides in the saltpetre; but nevertheless it can be employed without further purification for the nitrification of the glycerine.

The nitric acid is brought to the specific gravity of 1·48, and 1300 lbs. of this acid are mixed in four cast-iron pans with twice that weight of sulphuric acid; this mixture, which is left to cool for a day, serves for the treatment of 630 lbs. of glycerine. The acid is drawn from the pans into a wooden cylindrical vat,

Digitized by Google

about 6 feet in height and $3\frac{1}{2}$ feet in diameter, lined inside with thick lead, and containing along its lining two spiral lead pipes of about 1 inch diameter, which reach from the bottom to the top. Each of these spirals, or worms, forms a system by itself, through which cold water circulates, and one may serve as substitute for the other in case of leakage of one of the spirals.

The mixture of acids is stirred first by itself in this vat; the stirring is effected by two iron discs, covered with lead—disc and covering being perforated—which glide up and down on a vertical iron shaft, the gliding motion being effected by pulling the rope attached to the discs over a pulley. The two or three workmen who perform this task stand at a distance of 30 to 40 feet from the vat behind a strong earth bank. When the acids have been introduced into the vessel, and the agitation has commenced, water of 6° to 8° C. is let into the worms; the temperature of the acid can be maintained in this way at 14° to 16° C., as may be ascertained from a thermometer which reaches through the lead cover of the vessel into the acid. The glycerine, which is kept in a zinc tank on the roof of the shed in which is the mixing vat, is now allowed to run into the latter vessel. The flow is regulated by means of a tap, and also by letting the glycerine first run into perforated zinc boxes, placed on the lid of the mixing vat, and corking up, if occasion requires, some of the perforations.

As soon as the glycerine falls into the acid the temperature rises at once; but by carefully regulating the supply of glycerine it may be kept at 18° C., or lower.

It is advisable not to allow the temperature to rise above that degree, though experience shows that a higher temperature yields a larger quantity of nitro-glycerine. It requires, according to the season and the temperature of the cooling water, half an hour to two and a-half hours for 630 lbs. of glycerine to pass into the mixing-vat; the stirring must not be stopped for a moment during the process.

When all the glycerine has been added to the acids the mixture is at once drawn off through a leaden pipe to the so-called wash shed, where it passes into a tank about 8 feet

Digitized by Google

high and 12 feet diameter, which is half filled with cold water. The inlet tube carries a sieve, to retain lead sulphate that may have been brought from the mixing-vat. Whilst the nitro-glycerine flows in, stirring with wooden poles is begun, and continued until the nitro-compound has settled below the dilute acid. The bottom of the wash vessel is slightly inclined so as to allow a complete drawing off of the nitro-glycerine. The outlet taps are of stoneware. The nitro-glycerine is now twice washed with water, freed from acid and lead sulphate, and finally washed with water to which some sodium carbonate has been added.

But even after this purifying process there remain traces of acid; to eliminate these the nitro-glycerine is transferred to a third shed, where it is agitated for about an hour in a rotating vessel, called the Butter Machine, with about 50 lbs. of a concentrated solution of sodium carbonate; after this time it will no more redden litmus paper. It is now separated from the alkaline solution, filtered through felt, and collected for further use in leaden reservoirs.

The yield by this method is from 950 to 1200 lbs., according to the condition of the raw glycerine, the concentration of the acids, and the temperature. It is considerably below the theoretically calculated quantity. This shortcoming is due to the formation of glycerides, which dissolve in the wash waters. As a rule, the yield in winter is greater than that in summer.

Mowbray's Process.—*G. M. Mowbray*, whose factory is situate near North Adams in Massachusetts, U.S.A., gives an account* of the process there adopted, from which the subjoined particulars are taken :—

In the first place, the nitric acid is distilled from five retorts, each of them about 100 cubic feet contents, which are placed in a well-ventilated building; each retort receives 300 lbs. of Chili saltpetre, and 375 lbs. of sulphuric acid; the vapours pass through stoneware pipes into a series of four receivers, likewise

* In his work on 'Tri-Nitro-Glycerine.'

Digitized by Google

of stoneware, and placed on a bank about one foot above the ground; the first two receivers contain each 150 lbs. of sulphuric acid, the third 100 lbs., the fourth nothing. The sulphuric acid in the receivers facilitates the condensation of the nitric acid vapours, and the mixture of acids required for the nitrification of the glycerine is obtained at once. The distillation is finished after twenty-four hours; the mixture of acids,



FIG. 3.—MOWBRAY'S NITRO-GLYCERINE APPARATUS.

altogether about 600 lbs., is then drawn off into carboys, and from these emptied into a stone trough, which is capable of holding the contents of 18 carboys. In order to effect a uniform mixing of the acids, and also to remove nitrous gas, a current of air is passed for five minutes through the liquor in the trough.

The nitrification of the glycerine takes place in stoneware jars; 116 of these, *a*, *a*, *a* (see Fig. 3), are distributed over nine wooden troughs, A, A, A, which latter are filled to within a few

Digitized by Google

inches from the top of the jars with ice-cold water, or a mixture of ice and salt. Each jar receives 17 lbs. of acid mixture, and into this 2 lbs. of glycerine is introduced drop by drop from glass vessels *b*, *b*, *b*, which are placed on a shelf B, B, just above the acid jars. Below this shelf runs an iron tube, about $1\frac{1}{2}$ inch wide, through which cold dry air is conducted; from



FIG. 4.—SECTION OF MOWBRAY'S NITRO-GLYCERINE APPARATUS.

this tube F, F, F, glass pipes *d*, *d* branch off, joined by means of indiarubber tubes, into each jar, which thus receives during the dropping in of the glycerine a constant current of cold air, acting both as cooler and as stirrer. A very beneficial influence is ascribed to this air current, which also oxidises nitrous acid vapours.

As there is a large disengagement of nitrous vapours during this process, provision to carry these vapours out of the building

Digitized by Google

is made, by placing the troughs with the pots around chimneys, D, D, Fig. 4, and above each pot a, a, is a flue C_1, C_2, leading into D, which carries the fumes outside the building.

The nitrating house, in which this operation is performed, measures 150 feet in length.

The introduction of the glycerine into the acid must be finished within an hour and a-half; there should be no rise in temperature, and certainly no appearance of red vapours. After the transformation of the glycerine, the jars are emptied into a large vat A, Fig. 5, containing water of 21° C. or 68° F.;



FIG. 5.—MOWBRAY'S NITRO-GLYCERINE WASHING APPARATUS.

the nitro-glycerine sinks to the bottom and remains covered with about 6 feet of water for a quarter of an hour, when first the water is drawn off from above at faucet b_1, then the nitro-glycerine from below at b_2. The latter is transferred to the oscillating cask B, in which it is washed three times with water, and twice with soda solution, a current of air passing through the liquid all the time. The wash waters pass into a tub, from thence into two casks C sunk into the ground, where such nitro-glycerine as had been carried away by the water is retained.

The nitro-glycerine is carried in copper vessels to a shed, about 100 yards distant, and poured into stoneware jars, of

Digitized by Google

60 lbs. contents, and the jars placed in reservoirs filled with water of 21° C., and left there three days. Impurities rise to the surface, and are skimmed off.

The nitro-glycerine is now ready for commerce. It is filled in canisters of galvanised sheet-iron, coated inside with paraffin, and capable of holding 56 lbs.; the floor of the shed where the filling takes place is covered with a thick layer of calcined plaster of Paris, in order that any spilt nitro-glycerine may be absorbed at once. The canisters are then exposed to the cold of ice and salt for the sake of freezing their contents; in this state they are stored, 30 to 40 to a batch, in magazines 100 yards from all the other buildings of the factory. The transport of the nitro-glycerine takes place also whilst it is frozen.

The yield in Mowbray's factory amounts to 223 per cent. of the glycerine employed.

Compressed Air Mixing Apparatus.—At the forcite works in America, Belgium, and Spain, the nitro-glycerine is prepared by means of a mixing apparatus worked by compressed air. In a large vat, lined with heavy sheet lead, the acids are mixed every evening in the proportion of 650 lbs. of nitric acid to 1300 lbs. sulphuric, and left over night to cool. These vats are located under an open shed on high ground, and in the morning they are let flow by gravitation through lead pipes into the nitrating apparatus.

This apparatus consists of a large cylinder made of ½-inch sheet lead, closed at top and bottom and set in a wooden tank, which is larger than the cylinder, so as to leave a space of 2 or 3 inches around its sides and bottom. This space serves as a water-jacket for the continual circulation of cold water outside the cylinder. Inside the cylinder are several coils of 1-inch lead pipes, so arranged that the inlet and outlet of these pipes pass through the top cover. This top cover can be occasionally removed for repairs. There are also two small openings in the top cover for the insertion of long thermometers; one central opening for the insertion of an injector, which is a very ingenious instrument for the admission of compressed air and

Digitized by Google

glycerine, and can be regulated so as to control the flow of glycerine as well as the compressed air. There is also an escape-pipe for the nitrous gas.

When the acids have been charged into this nitro-glycerine apparatus, the water is turned on and allowed to circulate freely through the jacket and coils, which cools the acid mixture. The injector is now connected with the glycerine tank (located on the roof of the building) and with the air receiver by means of indiarubber pipes, and the compressed air agitates the mixture while a small stream of glycerine flows in; when the charge of glycerine, say 310 lbs., has been run in the nitrating process is finished, a large faucet of stoneware is opened, and the contents of the cylinder discharged into another open lead-lined vat located on a lower story of the building.

It must be mentioned that while the glycerine flows into the nitrating apparatus the operator should closely watch the thermometers, and see that the temperature of the mixture in the cylinder does not exceed 28° C. or 80° F. There are special thermometers made for this purpose which have the number 80 marked in red, indicating thereby the danger point. During the manipulation, should the temperature for some cause rise to this point, the flow of glycerine should at once be interrupted, and the influx of compressed air continued; if in spite of this the temperature rises—*let the operator not lose his presence of mind*, but open the discharge faucet and let its contents flow into a large tank placed on the lowest floor of the building, which is always half filled with water. Here the charge is drowned, and all danger of premature explosion is avoided.

If the charge works well it takes about an hour to nitrate 310 lbs. of glycerine, and when the same has been discharged into the lead tank or separator, where it is allowed to remain quietly for a few minutes, the nitro-glycerine, owing to its lighter specific gravity, will collect on top of the acids; there it is skimmed off by means of a dipper as it rises to the surface, and is poured into washing vessels to be freed by repeated washings, first with clear water, and then with solutions of carbonate of soda, from any acid which it may contain. The

Digitized by Google

washing is effected by agitating the water and nitro-glycerine with a current of compressed air.

The acids remaining from the separator are now allowed to flow into a species of tower filled with quartz pebbles, where by a special process the last traces of nitro-glycerine are destroyed, and then the acids are ready for reconcentration and further use.*

Test of Ingredients.—The most important features of the nitro-glycerine process are—the strength of the acids, and the complete washing of the products. The nitric acid should be of the greatest strength, since upon this depends the completeness of the conversion. With such acid the maximum production of nitro-glycerine is attained, and the oxidising action is lessened, the heat of the operation is reduced, and the temperature of the reaction becomes of less importance. With the strongest acid the limits of temperature heretofore assigned may be considerably exceeded without any injurious result. It has been stated that the mixing of the glycerine with the acid should be slowly performed. This should be understood to mean that the mixing is to be slowly performed in order to preserve a low temperature during the operation; but if the temperature is within the limit, the mixing should be performed as rapidly as possible, and the nitro-glycerine removed from the sphere of action. Rapidity of working is largely dependent upon the quality of acids employed, since the heat evolved is least when the strongest acid is used. In general, with highly concentrated acid, not only is the proportional product increased, but also the reaction goes on more uniformly and is more easily controlled.

Nitric acid of 1·49 to 1·51 specific gravity (48° to 49° B.) should be taken, and this strength should be *real* and not fictitious, as is often the case with acids nominally testing 50° and 52° Beaumé.

The proportion of nitro-glycerine obtained is dependent

* At Nobel and Co.'s works the process for manufacturing nitro-glycerine differs only in small details from the description here given.

Digitized by Google

almost entirely upon the acid used. If the glycerine is weak, the product will fall off, but the small difference in strength of glycerine ordinarily found exercises little effect. But if the acids are weak, the product is less in a marked degree. This does not depend to any extent upon the method or form of apparatus used, but only upon the acids which are employed. Weak acids will carry down smaller quantities of glycerine, and give lower proportional products than strong ones. Consequently, statements of relative products obtained are of comparatively little value, unless accompanied by a statement of the kind of acid employed, and the relative amount of glycerine treated.

In all forms of apparatus for making nitro-glycerine, the greatest care must be taken to prevent any accidental mixture of water with the charge in the converter. The presence of water shows itself in the greater trouble required to mix properly, by the slowness experienced in running, and by the falling off in the product. But if more water enters, the heat developed would be greater than can be carried away by the usual means of cooling, and the charge is "fired." Usually this means only an active decomposition, accompanied by clouds of nitrous vapour. Slight "fires" may be stopped by vigorous agitation, but if the firing is persistent, the contents of the tub should be run off as rapidly as possible. During the drawing off there should be constant agitation of the liquid, to prevent separation of nitro-glycerine.

The amount of water contained in glycerine is determined by its specific gravity. For this purpose either the weight of one litre of glycerine (1·05656 quart) is ascertained, or a Baumé areometer is dipped into the glycerine and the degrees Baumé read off. The relation between the specific gravity of the glycerine, the degree of Baumé, and the proportion of water, is shown in the following table :—

Digitized by Google

Weight of 1 lit. glycerine in grammes.	Degree of Baumé areometer.	Water in 100 parts glycerine.	Weight of 1 lit. glycerine in grammes.	Degree of Baumé areometer.	Water in 100 parts glycerine.
1264·0	31·2	—	1236·2	28·6	10·5
1262·5	31·0	0·5	1235·0	28·5	11·0
1261·2	30·9	1·0	1233·5	28·4	11·5
1260·0	30·8	1·5	1232·2	28·3	12·0
1258·5	30·7	2·0	1230·7	28·2	12·5
1257·2	30·6	2·5	1229·5	28·0	13·0
1256·0	30 4	3·0	1228·0	27·8	13·5
1254·5	30·3	3·5	1227·0	27·7	14·0
1253·3	30·2	4·0	1225·5	27·6	14·5
1252·0	30·1	4·5	1224·2	27·4	15·0
1250·5	30·0	5·0	1223·0	27·3	15·5
1249·0	29·9	5·5	1221·7	27·2	16·0
1248·0	29·8	6·0	1220·2	27·0	16·5
1246·5	29·7	6·5	1219·0	26·9	17·0
1245·5	29·6	7·0	1217·7	26·8	17·5
1244·0	29·3	7·5	1216·5	26·7	18·0
1242·7	29·2	8·0	1215·0	26·5	18·5
1241·2	29·0	8·5	1213·7	26·4	19·0
1240·0	28·9	9·0	1212·5	26·3	19·5
1239·0	28·8	9·5	1211·2	26·2	20·0
1237·5	28·7	10·0	1210·0	26·0	20·5

Commercial glycerine usually contains 2 to 6 per cent. of water. Liquid glycerine at a temperature of 60° F. has a specific gravity of 1·261, and, when mixed with nitrate of silver, oxalate of ammonium, or acetate of lead, ought not to give any precipitate.

Glycerine is occasionally falsified with sugar or dextrin. To detect the presence of sugar, dilute 100 grams of glycerine with 50 cubic centimetres of chloroform, and, as sugar is insoluble in chloroform, if present it will be thrown down as a crystalline precipitate. To detect dextrin, boil a few drops of glycerine with 4 cubic centimetres of water, add some drops of molybdate of ammonium slightly acidified with nitric acid, and the least trace of dextrin will give a blue coloration.

Sulphuric Acid.—This should have a density of 1·840 to 1·843, and must not contain more than 0·1 per cent. of arsenic, or any trace of nitrous acid. It is preferable to measure the specific gravity with the densimeter, graduated from 1·800 to

Digitized by Google

2·000, than to use Beaumé's areometer, which is not so exact. The density should be taken at a temperature of 15° C.

When trying to determine the relative proportions of nitric and sulphuric acids in the mixed acids, the former is driven out, for otherwise the analysis with chloride of baryta would give too high results. Three grams of the acids, therefore, are neutralised with carbonate of soda, and the solution is evaporated on a sand-bath with the addition of hydrochloric acid; the mass, having become almost dry, is allowed to cool, and a few drops of hydrochloric acid are added. When no more yellow vapours are evolved, the mass is diluted with hot water, and the solution filtered so as to separate the precipitate from it. On heating the solution to the boiling point, a solution of baric chloride is added, which is also boiled till no precipitate becomes visible. After a few seconds the whole of the sulphate of baryta is deposited, and is filtered off by means of Piccard's apparatus.

The filtering paper is pressed against the sides of the funnel and moistened with distilled water, so that no air can enter between the paper and the funnel. The clear liquid is poured off carefully, and distilled water added to the precipitate; and, after adding a few drops of hydrochloric acid, it is boiled for an instant, then filtered, and the operation repeated three times, but without adding any hydrochloric acid. The filtrate is washed carefully on the filter, and is now perfectly pure and neutral.

The dried filter is burned in a platinum crucible, and the cinders added to the precipitate and heated to redness for ten minutes; the crucible, after cooling under the dessicator, is weighed.

$$180\ BaSO_4 = 42{\cdot}06\ H_2SO_4 = 34{\cdot}34\ SO_3.$$

Nitric Acid.—The nitric acid ought to have a density of 1·500 to 1·520, and if below 1·48 should not be used. It should not be red, but a yellow colour is admissible, and when there is any suspicion that sulphuric acid is mixed with it, the nitrate of baryta test is applied. Sometimes the two acids (sulphuric and nitric) are bought mixed, when their density at

Digitized by Google

15° C. ought to be between 1·710 and 1·725. With the nitrometer they should give 31·3 to 35 per cent. of HNO_3.

In many nitro-glycerine factories the nitric acid is manufactured from nitrate of soda or Chili saltpetre, which often contain a large percentage of chlorides and sulphates, such as chloride of sodium and sulphate of soda. These two substances have to be quantitatively determined, as their presence in large proportions deteriorates the value of the nitrates. For this purpose 10 grams of nitrate are dried, pulverised, and then dissolved in 100 grams of water. After solution it is divided into two equal portions, in one of which the sulphuric acid is determined by barium chloride, and the chlorine in the other by nitrate of silver. 100 parts of chloride of silver are equal to 24·74 chlorine.

In drying the chloride of silver the precaution should be taken to use a porcelain crucible, and not one of platinum, which would be attacked by the chloride of silver.

$$100\ AgCl = 24{\cdot}74\ Cl.$$

Red fuming nitric acid has generally a specific gravity of 1·5, or 49° B.; its colour is reddish yellow, and it has the strong peculiar odour of nitrous acid, of which it can be freed with more facility the greater the percentage of water. Red acid of less than 1·48 sp. gr., or 47° B., can be freed of its nitrous acid by heating continuously till the acid becomes white. With stronger acids it is necessary to distil over chromate of potash or other oxidising materials, like peroxide of manganese.

According to *Pelouze*, an addition of peroxide of lead will dissipate all the nitrous acid completely, and not a trace of lead is dissolved, so that the acid does not need to be purified by distillation.

According to *Millon*, red fuming nitric acid is freed of the nitrous acid by heating and leading a current of carbonic acid gas through it. But it is preferable to use air instead of carbonic acid gas, as, according to *Smith*, the red acid at 77° C. is completety decolorised by a current of dry air, and is converted into clear nitric acid, by the oxidation of the

Digitized by Google

nitrous acid into nitric acid by the action of the oxygen of the air.

When, as is very often the case, sulphuric and nitric acids are bought mixed from the manufacturers, they are mixed at the acid works in the desired proportions, and shipped in wrought-iron drums holding from 1000 to 1200 lbs. To determine analytically the proportions of the two acids, the following method is employed: The nitric acid has to be eliminated, and for this purpose 50 grams of the acid mixture are neutralised with carbonate of soda solution, and the whole evaporated on a sand-bath while adding some hydrochloric acid. When the whole is nearly dry, it is allowed to cool, and a few drops of hydrochloric acid are added; and when the yellow vapours have disappeared, the mass is diluted with hot water and filtered. The filtrate is heated to boiling, and solution of barium chloride added till no more precipitate appears, when, after a few minutes' standing, the sulphate of baryta will settle, and is then collected in a filter, where it is washed, then dried and placed in a platinum crucible and heated for a few minutes to redness. The quantity of sulphuric acid is calculated from the formula—

$$180\ BaSO_4 = 42{\cdot}06\ H_2SO_4.$$

To determine qualitatively the presence of nitric acid in sulphuric acid, it is only necessary to put a crystal of sulphate of iron into a small portion of the acid, and, if nitrous acid is present, a red colouring will appear around the crystal.

To determine quantitatively the nitric acid in the mixture, Lunge's apparatus is used in most factories.

Arsenic in sulphuric acid can be determined by the following method: 50 grams of the sulphuric acid are diluted with 150 grams of water, and then a current of hydrosulphuric acid gas is passed through it for about an hour. The acid ought to be contained in a bottle which is corked up, and remains intact for about four hours, after which it is filtered; on the filter where the precipitate has been collected, 15 cubic centimetres of bisulphide of carbon are poured to dissolve the

Digitized by Google

sulphur in the precipitate, which, after drying, is weighed. The precipitate is sulphide of arsenic (As_2S_3).

$$100\ As_2S_3 = 60{\cdot}93\ As.$$

Concentration of Spent Acids.—After the nitro-glycerine has been skimmed off from the acid, these undergo a reconcentration so as to be used again in the manufacture of nitro-glycerine. Care has to be taken to drive out the last traces of the nitro-glycerine by heating the acids to about 150° F. In the subsequent manipulation the nitric acid is decomposed by heating, and the nitrous fumes condensed. From 15 to 10 per cent. of the nitric acid originally employed may be regained. As the sulphuric acid, during the nitrating process, only played the *rôle* of an absorbent for the water which is produced during the reaction, nearly all the sulphuric acid is present, only in a diluted state, and for this reason it has to undergo concentration.

Formerly the only metal for forming vessels in which acids, especially sulphuric, could conveniently be brought to a high degree of concentration, was platinum. Cheaper metals could not be practically employed, from their liability to rapid corrosion by the acids, and the use of glass retorts was objectionable because of their liability to break, and from their want of heat-conducting power. An apparatus specially adapted for this purpose has been invented by Mr. A. Nobel, and is thus described in the specification—

"The present invention relates to the construction of apparatus whereby the use of the cheaper metals, such as iron, for the aforesaid purpose is rendered practicable. Experiment has shown that metals which are rapidly corroded by the direct action of fluid acids are nevertheless well able to resist the action of the fumes of such acids, and it is upon this fact that the present invention is based.

"To this end a tower constructed of tubes of cast iron is built up within a furnace, and into this tower is admitted the weak acid intended to be concentrated. The acid, as it falls from the top of the tower, will flow over intercepting

Digitized by Google

surfaces of earthenware or glass, with which the tower is fitted, and these being heated by the flame of the surrounding furnace, the acid descending to the base of the tower will be partially vaporised and proportionately concentrated. The form of apparatus employed for this purpose admits of considerable variation, but the arrangement which has been found to answer well I will now proceed to describe.



FIG. 6.—NOBEL'S APPARATUS FOR CONCENTRATING SPENT ACIDS: SECTIONAL ELEVATION.

"In the accompanying drawings Fig. 6 shows, in sectional elevation, the improved apparatus for concentrating acids, taken on the line W W of Fig. 7, which is a sectional plan view of the same taken on the line X X of Fig. 6; Figs. 8 and 9 show on an enlarged scale details of the construction of the concentrating tower or chamber, Fig. 8 being a partial vertical section of the chamber, and Fig. 9 a cross-section on the line Y Y of Fig. 8; Fig. 10 is a partial sectional elevation of the apparatus taken at right angles to Fig. 6; and Fig. 11 is a partial front elevation of the apparatus.

"A A is the tower, or concentrating chamber, consisting of the several lengths of socketed pipes of cast iron, *a*, *a*, *a*, *a*, set one upon the other, the joints being made tight with asbestos or other suitable material capable of resisting the corrosive action of acid fumes.

"The tower, or concentrating chamber, is closed at the top

Digitized by Google

by a cover, a^1, which is furnished with a hole through which the acid to be treated is supplied to the concentrating chamber.

"This tower is set up in a furnace, B, which is provided with a cylindrical chamber, C, for the reception of the tower in communication with the fireplace D. The base of the tower rests upon the bottom of the chamber C, but the pipes of which the tower is composed are also supported by means of projections from the brickwork of the chamber. This chamber is closed by a plate, E, and it is brought into communication, by means of the flue F, with an adjacent chimney for carrying off the gases of combustion from the furnace. The pipes *a*, *a*, *a* are cast with projections *b*, *b*, *b*, *b*, *b*, *b* on their inner periphery for supporting trays *c*, *c*, *c*, *c*, *c*, *c*, made of porcelain, fire-clay, glass, tempered glass, or equivalent material that will resist the corrosive action of the acids which are to be concentrated. The acid to be treated is conveyed from a tank through the cock *e* into a funnel, *f*, inserted in the hole in the cover a^1, and from whence it passes into the



FIG. 7.—NOBEL'S APPARATUS FOR CONCENTRATING SPENT ACIDS: SECTIONAL PLAN.



FIG. 8.—VERTICAL SECTION OF CHAMBER.

Digitized by Google

concentrating tower. The trays *c*, *c* are provided with overflow holes *g*, *g*, through which the acid passes to the tray beneath. In order to prevent splashing, small glass or porcelain tubes or cylinders *h*, *h*, *h*, *h* are inserted in these holes and allowed to rest on the tray beneath. The overflow liquid will therefore spread over the surface of these loosely fitting cylinders *h*, and trickle down them into the tray on which they rest; *i* is a small platinum tube connected with the lowest tray, *c*, and through which the fully concentrated acid escapes into a cooling worm of the usual form and construction; *k* is a pipe of cast iron connected with the lowest section of the tower, and through it the acid fumes given off in the course of concentration make their escape into a condenser of any approved construction. This pipe *k* is kept hot to prevent the condensation of the acid fumes therein as they pass off to the condenser, and the joint *l* between the pipe *k* and the tower A is also made tight with asbestos or other suitable material.

"The form of the trays *c*, *c*, and the manner in which they are arranged in the chamber A so as to provide a zigzag course for the passage downwards of the fumes and vapour, are clearly shown in the enlarged views, Figs. 8 and 9, the trays being made circular, with a portion of their periphery cut away to leave a passage for the fumes.



FIG. 9.—NOBEL'S APPARATUS FOR CONCENTRATING SPENT ACIDS: CROSS-SECTION OF CHAMBER.

"Figs. 10 and 11 indicate the position of the fireplace, which presents no peculiar feature needing special description. It will be observed that the frame acts directly on the cast-iron tower or chamber A, in which an atmosphere of high temperature is consequently maintained.

"The action of the apparatus is as follows, viz.: The acid to

Digitized by Google

be treated is first allowed to flow from a supply tank through the tap *e* and funnel *f* into the tower A, until all the trays *c*, *c* in the tower are full. This will be indicated by the escape of acid through the small platinum tube *i*. Upon the fire being lighted, the walls of the chamber A will become heated, and the heat radiating from the walls will act upon the acid contained in the trays *c*, *c*, and cause it to give off vapours and fumes. These vapours, as they pass downwards in a zigzag course (consequent upon the peculiar form and arrangement of the trays) to the pipe *k*, will come alternately in contact



FIG. 10.—NOBEL'S APPARATUS FOR CONCENTRATING SPENT ACIDS: SECTIONAL ELEVATION.



FIG. 11.—NOBEL'S APPARATUS FOR CONCENTRATING SPENT ACIDS: FRONT ELEVATION.

with the sides of the tower A, from which they will take up heat, and with the acid in the trays *c*, *c*, to which they will impart the heat just taken up. The acid becomes more and more concentrated as it descends, and the tap *e* is so regulated as to admit only the quantity of acid requisite in order to obtain its full concentration when it escapes through the tube *i*. The pipe *k*, through which the acid fumes escape, may be adapted to any part of the tower A, but it is preferred to place it in the position shown in the drawing, viz. at the bottom of

Digitized by Google

the tower, as offering thereby the greatest guarantee against eventual condensation of the acid fumes on the metallic surface, which would thereby be corroded. Since the heat which raises the temperature of the acid is derived from the sides of the tower A, it is evident that the temperature of the metal will always be somewhat higher than that of the acid, so that no condensation of acid fumes against the metallic surface can take place.

"When nitric acid is being concentrated, it is better to replace the small platinum tube *i* by a small glass or porcelain tube.

"It will be evident that the construction of the tower or apparatus as herein described may be greatly varied without departing from the principle of the invention; the sole object of which is to prevent the corrosive action of sulphuric and nitric acids on iron, cast iron, and other metals which those acids in their liquid form attack."

Most manufacturers keep the details of their manufacture secret, and it is well to mention here that only those who already possess a practical knowledge of the manufacture should undertake the making of nitro-glycerine.

Digitized by Google

CHAPTER IV.

PROPERTIES OF NITRO-GLYCERINE.

ITS Physical Properties—Its Effect on the Human System—Decomposition—Gases Evolved—Detonation—Nitro-Glycerine in Use—Accidents when in the Liquid State—Rendered Non-explosive with Methylic Alcohol—Gelatinised Nitro-Glycerine or Nitro-Gelatine—General Abbot on Explosive or Blasting Gelatine.

NITRO-GLYCERINE is at ordinary temperatures an oily liquid, clear, colourless, or yellowish, refracting light, of sweetish and burning taste, without odour, of 1·6 specific gravity. At lower temperatures it becomes solid, the degree at which it solidifies greatly varying. *Champion's* was at —15° C. syrupy, but became solid after continued keeping at —20° C.;* *Mowbray's* solidified at 7·20 C., and contracted by $\frac{1}{12}$ of its bulk; *Nobel's* nitro-glycerine became solid at 12·8° C. In water it is insoluble, but it dissolves easily in ether, wood spirit, benzol, chloroform, and hot alcohol.

It produces serious consequences when taken into the human system, causing vertigo, weakening of sight, stupor, pains in the cardiac region; in larger doses it acts like strychnine, being fatal when more than 10 grains are swallowed. Even mere contact with the skin produces serious symptoms, though workmen get used to it after a time.

Decomposition.—Pure nitro-glycerine does not decompose spontaneously at ordinary temperatures, but at higher temperatures nitrous acid vapours are disengaged. It may be gradually heated to 100° C., but becomes very sensitive to slight

* It is so reported, but this could not have been pure tri-nitro-glycerine. —M. E.

Digitized by Google

shocks. According to *Kopp*, it may even be evaporated by being dropped upon a moderately hot plate; but, if the plate is hot enough to bring the nitro-glycerine to boiling, it explodes, according to *Group Besanez*. Experiments of *Champion* have shown that it evaporates at 185° C., boiling and evolving red fumes, burns briskly at 217° C., and detonates with violence at 257° C. I may say that these phenomena may take place at lower temperatures.

The decomposition of exploding nitro-glycerine takes place, as *Berthelot's* researches show, according to the equation

$$2\ C_3H_5\ (ONO_2)_3 = 6\ CO_2 + 5\ H_2O + N_6 + O.$$

Nobel has calculated that one volume of nitro-glycerine disengages 1298 volumes of gases of 100° C. at a barometric pressure of 760 mm., consisting of 554 water vapour, 469 carbonic acid, 236 nitrogen, and 39 oxygen. *List* estimates the bulk of the liberated gases at 1504·9 volumes. Nitro-glycerine evolves, therefore, at the lowest estimate, nearly six times as much gas as gunpowder, computed for a temperature of 100° C.; but a far higher degree of heat is produced by the instantaneous combustion of nitro-glycerine, which, according to Nobel, expands the bulk of the freed gases to eight times the original 1298 volumes, whilst the gases of gunpowder would not be trebled at a like temperature; the explosive force of nitro-glycerine, therefore, stands to that of gunpowder as 13 to 1, according to volume.

Detonation.—Putting a light directly to nitro-glycerine does not lead necessarily to detonation. Poured out in a thin layer, the liquid burns away like gunpowder. A red-hot iron rod, applied by Nobel to nitro-glycerine, had no effect whatever; a burning wooden splinter kindled it to a quiet flame, but, on removing the match, the flame of the nitro-glycerine went out immediately; according to Nobel's experiments, when it is set on fire it will burn away quietly long before it is heated to the degree at which it will explode, but this has never been

Digitized by Google

proven on a large scale, and I would not recommend such an experiment.

It is only on being heated in a closed space that its entire mass explodes, when the temperature reaches 257°. Such a heating can be effected by the electric spark. Sir Frederick Abel placed two poles, connected with a Ruhmkorff coil, into some nitro-glycerine, and allowed a number of sparks to pass between them; the surface of the nitro-glycerine became agitated, turned black, and after half a minute exploded.

Gradually increasing pressure is unable to explode liquid nitro-glycerine; but a sudden blow will do it, though it detonates only that portion with which it came in contact. The explosion produced in the part that had been directly exposed to the blow will not communicate itself to the rest of the nitro-glycerine. If, however, nitro-glycerine is in a solid condition—frozen, for instance—a blow given to a portion will be transmitted at once to the entire mass. Several accidents are on record where the explosion could be traced to some mechanical force having acted on frozen nitro-glycerine. One kind of mechanical force—shaking—seems to form an exception to this observation; for, as already mentioned, Mowbray's nitro-glycerine is safer to move in a frozen than a liquid state, and Nobel also mentions that liquid nitro-glycerine is extremely sensitive to vibration.*

The detonation of gunpowder, gun-cotton, or fulminate, causes nitro-glycerine to explode, whether it is loose or under confinement.

Exposure to the solar rays transforms nitro-glycerine into a very unstable, easily explosible substance; and *Jouglet* observed spontaneous explosions of nitro-glycerine in air charged with ozone. Dynamite loses its strength in tropical countries by gradual evaporation of nitro-glycerine. I have made this observation on the Isthmus of Panama, where dynamite refused to explode after several months' storage.

* See 'Modern High Explosives': art. "Accidental Explosion at Hoosic Tunnel"—an accident which was the result of vibration.

Digitized by Google

Nitro-Glycerine in use.—At the first nitro-glycerine was used in conjunction with gunpowder; the latter was exploded by any of the usual methods, and through its explosion the nitro-glycerine was detonated. A tin cartridge was filled first with gunpowder, then with nitro-glycerine, closed by a cork, and placed in the bore-hole, which had to be about a quarter of an inch wider than the cartridge; the space between was filled with coarse-grained gunpowder, which covered the cartridge about an inch high; a fuze was inserted, and the bore-hole tamped with sand. Later a special detonating capsule was used by Nobel, consisting of a wooden box filled with fine powder, and provided with a fuze. The nitro-glycerine was poured directly into the bore-hole, which had to be lined with plastic clay.

In March, 1865, blasting on a large scale was carried out in the granite quarries near Stockholm. A bore-hole of about 10 feet in depth was charged with 5 lbs. of nitro-glycerine; after explosion, about 200 cubic yards of granite, weighing something like 350 tons, were found torn away, and the main rock was traversed by long fissures. This result created much sensation, and caused a great demand for the new explosive. The application of nitro-glycerine increased in the next following years, and amongst other uses, it was soon used for breaking up large masses of old iron, such as anvils, cylinders, &c.

The efficiency of nitro-glycerine in water was shown by experiments which Nobel performed in 1866 in a pond near Hamburg. A canister, containing about 2½ lbs. of nitro-glycerine, was lowered under the surface of the water and fired; the explosion sent up a column of water of about 9 feet in diameter to a height of about 300 feet. A like quantity of gunpowder in a similar canister, on firing, lifted the water to no more than a few feet.

The highly favourable reports on the explosive value of nitro-glycerine were soon followed by statements of its being one of the most dangerous of known blasting agents. In 1866 a West Indian mail packet was blown up, a wharf torn down,

Digitized by Google

a number of adjacent ships were injured, and many lives lost at Colon, through an explosion of nitro-glycerine.* Not long after that a fearful accident occurred in San Francisco at Wells, Fargo & Co.'s express office. A box was noticed to leak some oily substance, and one of the employés took a hammer to drive in a fresh nail so as to keep the box tighter together, when on hammering the box exploded. Later on, a Newcastle magistrate and several other persons fell victims to an accident with this explosive body. In 1868 a factory at Stockholm where nitro-glycerine is manufactured was blown up and a number of men killed, and not long after that an explosion attended with fearful loss of life occurred in Belgium. This last-named accident led to the authorities altogether prohibiting the use of this explosive compound in that kingdom.

The exact cause of these explosions was never ascertained, but general opinion ascribed them to violent concussion of the liquid nitro-glycerine, or to its spontaneous decomposition. Mr. Nobel thinks that the manufacturers were not aware at the time of the immense influence which the metallic packing then used (in the form of tin canisters) exercises, even when inclosed in wooden boxes, on the liability of nitro-glycerine to explode by concussion and vibration of the metal packing.

It was then proposed, and adopted as a temporary measure, to render nitro-glycerine inexplosive, or rather much less sensitive, by adding methylic alcohol, which it readily dissolves. On shaking it with water, which takes up the alcohol, the explosive properties are fully restored, and the same detonator cap, which has not the slightest effect on the mixture of nitro-glycerine and wood naphtha, explodes it after a moment's washing with water. Since the invention of nitro-gelatine, nitro-glycerine has ceased to be used in the liquid state, as the former is just as strong.

* I arrived in Colon in May, 1866, on my way to California, and saw in the harbour the wrecks of several mail steamers which had been destroyed by this explosion.

Digitized by Google

Gelatinised Nitro-Glycerine.—Nobel has patented a process for solidifying nitro-glycerine by means of gun-cotton collodion. The explosive compound becomes more and more gelatinous in proportion to the quantity of nitrated cellulose which is dissolved therein; and it forms (when 7 to 8 per cent. of the nitrated cellulose has been incorporated) a solid jelly—known as *Nitro-gelatine*—which the inventor claims to be very safe and highly suitable for every purpose to which very powerful explosives can be applied. The details given in the patentee's specification are here set out.*

In some explosive liquids (such as nitrate of methyl) collodion-cotton readily dissolves at the ordinary temperature, and forms a thick explosive gum or jelly. In the case of nitro-glycerine, however, the incorporation of the above-named gelatinising substance is facilitated by adding a small quantity of a substance which promotes the solubility upon which the gelatinisation depends. Such substances are the acetic ethers of glycerine, ethyl, methyl, acetic acid, a mixture of alcohol and ether, acetone, nitro-benzol, dinitro-benzol, the nitrates of methyl, ethyl, and other analogous substances. The quantity of the solvent which has to be added depends upon the nature of the substance chosen; but, as a rule, about 10 per cent. of the weight of nitro-glycerine which has to be gelatinised will be found in practice to be amply sufficient. Moreover, by gently heating nitro-glycerine (in a water bath or otherwise), it acquires the property of dissolving nitrated collodion cellulose without the addition of the promoting solvent; or when it is found advantageous to use the promoting solvent, the application of heat will enable the quantity used to be reduced to 2 per cent., or even less, of the weight of the nitro-glycerine. Since nitrated cellulose is rarely, if at all, of a homogeneous composition, and therefore its solubility in nitro-glycerine will be found to vary, the necessity for adding a promoting solvent must be ascertained by experiment.

The above-described process of gelatinisation necessitates:—

* The patent is dated 13th October, 1876.

Digitized by Google

1. That the explosive liquid shall contain no impurity or foreign matter capable of counteracting its power of dissolving nitrated cellulose, or other substance possessing the same property, as hereinbefore described.

2. That only such nitrated cellulose or other analogous substance is to be used which readily dissolves in and gelatinises the explosive liquid.

3. That the solution of the nitrated cellulose or other analogous substance (especially if that substance is twisted or compressed) shall be facilitated by mechanical stirring or kneading so as to allow of the necessary access to all the parts of the nitrated cotton intended to be dissolved.

The explosive jelly which is obtained by this process can be easily pressed into cartridges, or any other forms found convenient for use. For certain purposes, and especially for military use, it is important to be able to dilute or modify the explosive sensitiveness of gelatinised nitro-glycerine in a measure exactly suited to the purpose in view. This is done by adding more or less of a non-explosive or sluggishly explosive substance, possessed of the property of dissolving both nitro-glycerine and the substance which serves to gelatinise it. Such are the acetic ethers of glycerine, methyl, ethyl, and acetone, acetic acid, nitro-benzol, dinitro-benzol, the nitrates of methyl and ethyl, or other solvents of an analogous character. An addition of the above-named, or of any analogous substance, serves not only the purpose of rendering the gelatinised nitro-glycerine less sensitive to concussion, but also reduces its quickness of explosion; it facilitates, as above described, the process of gelatinisation; and it lowers the temperature at which nitro-glycerine becomes hardened or congealed. The least volatile substances, such as the acetic ethers of glycerine, nitro-benzol, dinitro-benzol, deserve preference, inasmuch as they cannot become inactive through evaporation.

Gelatinised nitro-glycerine, when properly confined, can be exploded by a common fuse; but, as a rule, detonators, containing a strong charge of fulminate, are used, as also for firing dynamite. When hardened in cold weather, gela-

Digitized by Google

tinised nitro-glycerine explodes more readily than frozen dynamite; still it is a good precaution always to head the charge with a primer, consisting of a small cartridge of gun-powder or gun-cotton, or dynamite, or uncongealed gelatinised nitro-glycerine, or an analogous substance.

Experiments have demonstrated its insensibility to shock, to friction, and to the pressure or action of water; and, further, that to produce complete explosion in a free state, and to develop the great force corresponding to its chemical composition, it would be necessary to use, even in its soft state, a peculiarly powerful detonator.

One gram of fulminate of mercury is insufficient to detonate a charge in a soft state contained loosely in a tin case. Fragments of gelatine as large as a pin's head, or even as a small pea, were found scattered about after an explosion.

Under the blow of a pile engine, the gelatine was insensible to a blow of 3·5 kilogrammetres; while dynamite instantly explodes under one kilogrammetre.

The gelatine is unaffected by submersion in water, even at a temperature of 158° F., and showed no exudation after eight days, at a temperature of 113° F.

Camphor is generally added to render nitro-gelatine insensible to blows, even of projectiles at short range. Nitro-gelatine thus treated is the *Gelatine explosive de guerre*, which is largely used by various Governments for military engineering purposes. A specially prepared primer is required for its complete detonation.

In appearance it is gelatinous, elastic, transparent, and pale yellow in colour. Its density is 1·6; it can be cut with a knife; and under the severest pressure it shows no trace of nitro-glycerine. At a temperature of 122° F. to 140° F., it softens a little, but seldom becomes greasy. When inflamed in the open air, it burns like dynamite, or dry compressed gun-cotton.

Camphorised nitro-gelatine evaporates very little even at a temperature of 158° F., and if it is exposed to that degree of heat for one week.

Digitized by Google

Pure explosive gelatine, slowly heated, detonates at 400° F., or rapidly at 460° F. Mixed with from 4 to 10 per cent. of camphor, this substance will not explode at the same temperature as gunpowder—viz. 570° to 600° F.—but simply burns, producing sparks.

The more camphor nitro-gelatine contains, the more difficult it is to explode, and with a certain admixture of camphor the compound may even be fired into with rifle-bullets without detonation resulting.

General Abbot on Explosive or Blasting Gelatine.—General Abbot (U.S.A.) reports as follows concerning his investigations of this explosive:—

"This explosive—called by the Nobel's Company No. 1 blasting gelatine—consists of 92 per cent. of nitro-gelatine and 8 per cent. of nitro-cotton. They do not add camphor for the trade; but state that the incorporation, if desired, may be made on the spot, 'by warming gently, by means of water at 60° C., and when the gelatine attains a soft plastic state, with a temperature of 40° C. in the mass, 5 per cent. of camphor dissolved in alcohol may be added to it and completely incorporated by mixing with the hand until the gelatine and the camphorated spirit form a homogeneous mass. The warming is best done in a copper basin surrounded by water at 60° C. Quantities of 40 or 50 lbs. may be readily camphorated in the above manner.'

"Its appearance at ordinary temperatures is that of a beautiful straw-coloured jelly, quite elastic to the touch. No free nitro-glycerine has as yet made its appearance, and no headache results from the handling. The specific gravity for four samples was respectively 1·53, 1·51, 1·54, and 1·54. Its composition is that usually adopted by Nobel's Company—92 per cent. of nitro-glycerine and 8 per cent. of nitro-cotton.

"Forty-five ring trials with this explosive have been made during the past season.

"One remarkable incident which occurred during these trials should be mentioned. A charge of 3 lbs. containing a fuze

Digitized by Google

embedded in a 3-oz. tonite primer, was lowered as usual to a depth of 33 feet, and the electric current was sent through its circuit. No explosion occurred. A second trial gave the same result. While examining the wires to detect the cause (several seconds after the first attempt), a cloud of red nitrous fumes appeared rising from the surface of the water round the motionless buoy. Soon blazing cartridges appeared, like little volcanoes, over a circle a dozen feet in diameter—but chiefly round its circumference. On raising the ring the tin can was recovered quite uninjured, the cover being off. Evidently the fuze failed to detonate the tonite, and simply set fire to the blasting gelatine; but how this could happen with a service fuze containing 24 grains of fulminating mercury is not clear. The thick mass of tonite surrounding the copper cap would naturally protect the explosive gelatine against detonation; but why the tonite failed to explode, and how the gelatine was set on fire, are not easily explained. The incident has had no parallel in these trials.

"The following experiments to determine the degree of sensibility of blasting gelatine to sympathetic explosion from shocks communicated through water, were made in August, 1884. The primary charge was 1 lb. of dynamite No. 1 contained in a tin can. The secondary charge was ½ lb. of blasting gelatine rolled in thin rubber cloth. The submergence was 5 feet in water 15 feet deep. No sympathetic explosion occurred when the charges were separated by horizontal distances of 15 feet, 10 feet, 8 feet, 6½ feet, and 5¾ feet—but at 5 feet the secondary charge detonated.

"To determine the sensibility of this uncamphorated explosive gelatine to impact in air, several musket-shots were fired at half-pound charges backed by wooden boards. The Springfield rifle was used at a range of twenty paces. In every case the material blazed when struck by the bullet; and once a small explosion occurred, which threw unignited fragments of the cartridges a few feet from the target. Lighted by a match, this explosive burns with an intense white flame characteristic of nitro-glycerine compounds.

Digitized by Google

"In short, these trials seem to warrant the conclusion that explosive gelatine without camphor is most admirably suited to submarine mining, in so far as strength and ordinary physical properties are concerned. For military operations on land a small percentage of camphor should not be omitted.

"The question of permanency in store remains to be tested for both classes of work—especially in view of the results obtained with the American sample experimented with in 1881. The experience of the Nobel's Company, however, is encouraging, and gives good ground for anticipating no further trouble in this respect.

"Thus, under date of July 1, 1882, Mr. Cuthbert wrote, 'We have sent blasting gelatine now to all the Australian Colonies, New Zealand, India, Burmah, Ceylon, South Africa, Chili, and Brazil; and from all these places we are now receiving the most satisfactory accounts of the keeping properties of the stuff, and the most wonderful accounts of the work it does.'

"Also, under date of February 5, 1883: 'It may interest you to know that the blasting gelatine which we have sent to India, and which arrived at Bombay on the 21st of May last, is keeping remarkably well. Harris, our instructor, writing from Calcutta on the 1st of January, says that when he was at Kundalani Gorge in the Bolan Pass, on the 19th of December, he used some blasting gelatine, and examined some of it in the Government magazine there. He found it in perfect order. The paper came off the cartridges and was perfectly dry, and had not the slighest trace of any exudation of nitro-glycerine. The stuff, before being sent to Beluchistan, passed through a hot season in the company's magazine in Bombay, the maximum and minimun temperatures of which for several months together averages 86° to 80° F., and at times the magazine was as high as 90° F.'

"The Italian Government, in February, 1884, officially adopted blasting gelatine in the place of dynamite No. 1 for all military purposes, and entered into a contract with a private firm to furnish the needed supply for about five years. Two grades are ordered—one consisting of 88 per cent. of

Digitized by Google

nitro-glycerine, 7 per cent. of nitro-cellulose, and 5 per cent. of camphor; and the other of 93 per cent. of nitro-glycerine and 7 per cent. of nitro-cellulose. The service fuze for the latter contains 1·3 gram of fulminating mercury in a copper capsule; and the detonating primer for the former, 30 grams of dry gun-cotton (density 1·20 to 1·28) ignited by an ordinary fuze charged with 1 gram of fulminating mercury in a copper capsule.

"In Austria the manufacture of dynamite No. 1 had been nearly or quite superseded by that of explosive gelatine as early as 1883. The Government required from 2 to 4 per cent. of camphor to be added for military supplies, but for industrial purposes this addition was not favoured. For exploding the camphorated gelatine, a tin primer, charged with 25 per cent. of gun-cotton and 75 per cent. of nitro-glycerine, reinforced the usual fuze containing 1 gram of fulminating mercury in a copper cap.

"It is to be hoped that the manufacture of explosive gelatine on a large scale will soon be undertaken in the United States. At present, forcite is the only representative of this latest and strongest class of high explosives."

Digitized by Google

CHAPTER V.

VARIETIES OF DYNAMITE.

INVENTION of Dynamite—Kieselguhr Dynamite—Influence of Kieselguhr on Explosive Efficiency—Experiments of Captain Hess and Lieutenant Schwab—Colonia and Hercules Dynamite—Vulcan—Seranine and Horsley's Powder—Dualine—Lithofracteur—Ammonia Powder—Giant Powder No. 2—Sebastin—Brain's Powder—Rhenish Dynamite—Forcite—Atlas Powder—Gelatine Dynamite—Glukodine—American Hercules Powder—Judson Powder—Paleine or Straw Dynamite—Trautzl's Dynamite—Carbo-Dynamite—Smolianinoff Explosive—Snyder Explosive—Von Dahmen's Safety Dynamite—Classification of Dynamites—American and Belgian Forcite Powder Works.

DYNAMITE consists of nitro-glycerine absorbed in a porous substance, particularly the silicious infusorial earth, occurring in Hanover, called "kieselguhr." It is erroneously believed to have been discovered accidentally through a leakage of nitro-glycerine into kieselguhr. But the first dynamite made contained no silica; it consisted of porous charcoal and nitro-glycerine; and numerous experiments were made with various absorbents, such as porous terra-cotta, sawdust, ordinary paper, and nitrated paper soaked in the liquid explosive and rolled into cartridges, before porous silica was finally adopted. Kieselguhr absorbs from three or four times its own weight of nitro-glycerine, and possesses the advantage over other absorbents of resisting a greater degree of pressure without parting with any of the nitro-glycerine which it holds. At first the new blasting agent made but slow progress, owing in a great measure to the strong prejudice existing against its chief ingredient. But gradually it has grown into favour and is now universally adopted as a blasting agent.

Digitized by Google

Dynamite (*Kieselguhr Dynamite*).—The infusorial earth, to be employed as an absorbent, must be freed from organic admixtures, water, and coarse silicious grains. The first two are eliminated by calcination, which is carried out in furnaces situated one above another, usually four of them; the kieselguhr is pushed from the uppermost to the lowest. The calcined mass is then crushed between cylinders and passed through wire sieves.

The saturation of the infusorial earth with the nitro-glycerine takes place in the same building in which the liquid is finally washed. According to *F. Capitaine*, 50 lbs. of kieselguhr are put with treble the weight of nitro-glycerine into flat wooden trays and mixed by hand; the workmen ought to have gutta-percha gloves, but they mostly neglect this precaution. In about half an hour the mixture is completed; the mass is now pressed by hand through sieves, and is ready for being filled in cartridges. The cartridges are of cardboard paper or of vegetable parchment; their mode of filling is very simple and is usually done by hand.

The impression has prevailed until lately, that a chemically inactive absorbent like kieselguhr in dynamite could not exert any influence on the explosive efficiency of a nitro-glycerine mixture; but *Capt. P. Hess* and *Lieut. John Schwab*, while making some comparative experiments with a pressure gauge on two kinds of kieselguhr dynamite, noticed some remarkable differences in their action, which led to the investigation of these substances.

Two samples of dynamite were experimented with, supplied from Nobel & Co.'s factories, one of which came from the factory at Zamky, made in 1872, and the other from the factory at Pressburg, made in 1876.

These samples were compacted into small cartridges, each containing 17 grams, and they were placed on the top of two lead cylinders, each 20 mm. high and 31 mm. in diameter, the lower one of which was placed on a cast-iron plate. The cartridges did not rest directly on the upper lead cylinder, but a

Digitized by Google

thin steel disc, 3·5 mm. in thickness, was interposed between the cartridge and the cylinder.

The effect of the explosion made itself manifest by the compression of the two lead cylinders, which, measuring 40 mm. before the explosion, were reduced by the explosion to the following heights :—

1°. Six shots with dynamite of 1872—

27·8 mm.
28·2 ,,
27·6 ,,
27·2 ,,
27·4 ,,
27·8 ,,

} Height of the compressed cylinders.
Average 27·67 mm.

2°. Six shots with dynamite of 1876—

26·5 mm.
26·6 ,,
26·3 ,,
26·1 ,,
26·8 ,,
25·7 ,,

} Height of the compressed cylinders.
Average 26·33 mm.

The 1876 dynamite showed a greater intensity than the 1872 sample. The chemical examination of the two dynamites gave—

DYNAMITE OF 1872.

Nitro-glycerine	70·8 per cent.
Kieselguhr	28·2 ,, ,,
Water	1·0 ,, ,,

Three determinations of the nitrogen in the nitro-glycerine by Dumas' method denoted the following percentages—

I.	II.	III.	Average.
16·13	16·12	16·12	16·12

DYNAMITE OF 1876.

Nitro-glycerine	70·08
Kieselguhr	28·82
Water	1·10

Nitrogen found in the nitro-glycerine by Dumas' method—

I.	II.	III.	Average.
15·72	15·65	15·68	15·68

Digitized by Google

According to the preceding analysis, the composition of the two dynamites does not vary sufficiently to account for the difference of intensity-effect which the pressure gauge showed. Still, as there was quite a difference in the effect of the two samples, and as this was in favour of the dynamite of 1876, as this also contained not only less nitrogen in its nitro-glycerine, but also less nitro-glycerine in the mixture than the sample of

FIG. 12.—KIESELGUHR DYNAMITE UNDER THE MICROSCOPE : SAMPLE OF 1876.

1872, the cause for this variation in the effect must be looked for in the structure of the kieselguhr, which in reality shows a great many variations.

The figures 12 and 13 exhibit the appearance of the two kieselguhrs when magnified to 300 times their natural size, used in these dynamites and extracted from them.

The kieselguhr of the 1876 dynamite shows the long tubular well-preserved bacillariæ, whereas the kieselguhr of the 1872

Digitized by Google

dynamite shows only fragments of the tubular diatomaceæ, but in larger proportion the pleurosigmata and dictyocheæ, which are round, and also numerous granules of quartz.

It is well known that the long tubular bacillariæ absorb the nitro-glycerine much better than the short fragments of the other two kinds. In the dynamite of 1876 every drop of nitro-glycerine was, as it were, packed away in a little vessel and was



FIG. 13.—KIESELGUHR DYNAMITE UNDER THE MICROSCOPE: SAMPLE OF 1872.

well absorbed, and the explosion met thereby with a primary resistance in the absorbent, which acted as a kind of tamping in itself, which increased the intensity of the dynamite. In the dynamite of 1872, which appeared and felt fatty to the touch, a portion of the nitro-glycerine was not absorbed, and did not get the tamping effect from its absorbent, and hence it showed less intensity. Therefore, not only through considerations of safety should fatty nitro-glycerine mixtures be avoided,

Digitized by Google

but also because their intensity-effect is lessened by this condition.

The great success of kieselguhr dynamite has given rise to numerous other nitro-glycerine compounds, of the best known of which I proceed to give a more or less brief account.

Colonia and **Hercules** dynamite are mealed gunpowder mixed with about 35 per cent. of nitro-glycerine, and resemble the first nitro-glycerine preparation brought out in 1863. They are manufactured at Cologne by Wasserfuhr.

Vulcan is also a dynamite, composed of mealed gunpowder holding 43 per cent. of nitro-glycerine.

Seranine and **Horsley's Powder** are chlorate of potash preparations mixed with nitro-glycerine. The substitution of a chlorate for a nitrate is said not to add to the power, while it adds to the expense of the compound, and also somewhat increases its danger.

Dualine was brought out by Ditmar in Germany. It consists of sawdust, nitrate of potash, and nitro-glycerine.

Lithofracteur.—Its ingredients are, nitro-glycerine, 55 per cent.; kieselguhr, 21 per cent.; charcoal, 6 per cent.; barium nitrate and bicarbonate of soda, or either of them, 15 per cent., sulphur and manganese oxide, or either of them, 3 per cent. Manufactured by Krebs, in Deutz.

Ammonia Powder, invented by Ohlson and Norrbin, though comparatively unknown, is far stronger than lithofracteur, and surpasses even dynamite in point of power. Its only drawback is the hygroscopic nature of its chief ingredient, which is ammonium nitrate. But in every other respect it is a very superior blasting agent when freshly prepared, but it has no keeping qualities. It consists of eighty parts by weight of nitrate of ammonium, six parts of charcoal, and fourteen to twenty of nitro-glycerine.

Digitized by Google

Giant Powder No. 2 (*Dynamite No. 2*) consists of 40 per cent. of nitro-glycerine added to a mixture of forty parts nitrate of soda or potash, six parts resin, six parts sulphur, and eight parts infusorial earth. Other nitrates may be substituted for those above named, and other carbonaceous substances for the resin.

Sebastin, patented by G. Fahnejelm of Stockholm, contains a specially prepared charcoal as the absorbing material. The carbonisation or coking (according to the patentee) must be so done as to completely destroy the organic substances, and to produce as porous a charcoal as possible.

For this purpose young trees or saplings, or branches of poplar, hazelwood, or elder-tree, are selected and burned in an open fire. When the wood has been consumed the fire is not put out by means of water, but left to go out of itself. In this way a very inflammable and very porous charcoal is obtained, which can absorb more than five and nearly six times its weight of nitro-glycerine. The charcoal is pulverised in a wooden mortar, but should not be reduced to too fine a powder, else it will not so completely absorb the nitro-glycerine.

The charcoal produced in the ordinary way is quite different as regards absorbing power. Charcoal of fir-tree may, however, be used, if charred a second time in a special oven.

By mixing different kinds of charcoal a material may be obtained possessing the required absorbing qualities, and an explosive compound may then be obtained of the required power without loss of the necessary consistency; that is, without being too dry, which is undesirable. The charcoal not only serves as a good absorbent for the nitro-glycerine, but it plays also an important part in the combustion. The nitro-glycerine in exploding decomposes into steam, carbonic acid, nitrogen and oxygen.

In the explosion of dynamite with inert base, the oxygen goes away without being utilised; but in the explosion of this new compound a part of the absorbent charcoal is burned by

Digitized by Google

means of the liberated oxygen; the quantity of gas is thus augmented, and also the development of heat, whereby again the tension of the gas is augmented. As, however, the quantity of charcoal necessary for the complete absorption of the nitro-glycerine is in all cases much larger than that which can reduce the excess of oxygen produced at the explosion, nitrate of potash is added.

Brain's Powder contains chlorate, in the place of nitrate of potash; and, as an absorbent, coal dust, sugar, starch, or any carbonaceous material.

Rhenish Dynamite. — This product of the Rhenish Dynamite Company is composed of seventy parts of a solution of 2 to 3 per cent. of naphthalene in nitro-glycerine, three parts of chalk, seven parts of heavy spar, and twenty parts of purified infusorial earth.

Forcite was the invention of Captain J. M. Lewin, of the Swedish service, and is a mixture of nitro-glycerine with cellulose, the latter being gelatinised by heating in water under considerable pressure; but nitrated cellulose is also used in admixture with oxidising salts. As manufactured on a very large scale in America and in Belgium, forcite consists of a thin blasting gelatine, nitro cotton, incorporated with a mixture of nitrate of soda coated with molten sulphur and wood tar. To this 1 per cent. of wood pulp is added to counteract the sticky qualities of the tar, while the latter prevents the thin blasting gelatine from soaking into the base, which is thus used as a carrier rather than as an absorbent. The explosive meets with remarkable success in America, where the factory on Lake Hopatkong in New Jersey, two hours from New York City (erected under the supervision of the author in 1884), has a capability of turning out six tons of forcite daily; three grades are manufactured there.* Forcite manufactured in Belgium is

* A description of these works, and also a plan of the Belgian forcite works at Baelen-sur-Nethe, will be found at the close of this chapter.

Digitized by Google

also meeting with success, and is being used largely in many European and South American countries.*

The subjoined Report † of *General H. L. Abbot*, Lieutenant-Colonel of Engineers, U.S. Army, concerning the forcite compounds, will be read with interest:—

"Forcite presents the appearance of a plastic mass having the power of nitro-glycerine, and being attended in its making, carrying, and keeping with less danger than explosive compounds before known, and even than 'blasting' or 'mining 'powder' properly called.

"It has the remarkable and most advantageous property of exploding when confined or charged in a drill hole, as well by the action of special primers or caps, and if specially prepared for the purpose, with a fuze alone, and of burning without explosion in the open air. Its manufacture is less costly than other compositions of nitro-glycerine. The nitro-glycerine is so perfectly united with the other materials that it is not separated by sulphuric ether or alcohol, and that water has no action upon it. The nitro-glycerine therefore preserves its properties without alteration, even under water." [I have kept forcite under water for 24 hours without its losing any of its explosive properties.—M. E.]

"The base for all grades of forcite is, as described in the nitro-glycerine patent, mixed with a special kind of cellulose, which permits the operation and manufacture to be carried on cold, ensuring entire safety in handling and storage, the properties of the nitro-glycerine being unchanged by the avoidance of the intense heat heretofore necessary, as in the case of Nobel's formula, which requires a high temperature for the gelatinising process. This is overcome in the forcite formula, which produces a plastic waterproof compound ranging from

* Forcite (after examination by H.M.'s Inspectors of Explosives) has been put upon the list of "authorised explosives" in this country under the Explosives Act, 1875.

† Published in his 'Report upon Investigations to develop a System of Submarine Mines for defending the Harbours of the United States,' constituting 'PROFESSIONAL PAPERS, No. 23, CORPS OF ENGINEERS' 1884.'

Digitized by Google

80 to 30 per cent. of nitro-glycerine; and by the addition of saltpetre, as an absorbent, the quantity of nitro-glycerine can be reduced, while preserving a high standard of explosive strength. The use of a hydro-carbon as a solvent of the forcite mixture renders forcite waterproof as a result. It will be perceived that forcite, in many respects, resembles Nobel's explosive gelatine, which is not as yet manufactured in the United States. Possessing special interest as the only American representative of this latest order of modern high explosives, it has been carefully tested at Fort Willet's Point during the past season.

"The following grades were selected for trial:—

Forcite gelatine, containing	95%	nitro-glycerine and	5%	cellulose.			
Forcite No. 1	,,	75%	,,	,,	25%	explosive	base.
Forcite No. 3	,,	40%	,,	,,	60%	,,	,,
Forcite No. 3 A.	,,	30%	,,	,,	70%	,,	,,

"The varieties used in my trials all had the yellow tint characteristic of explosive gelatine, but less bright—the base being apparently sodium nitrate with a trace of rosin, from a rough test made after partial deliquescence.

"The strongest sample (95 per cent. of nitro-glycerine) looked quite like the explosive gelatine made in this country, and tested by me in 1881. It was more mottled and slightly darker than the Scotch gelatine, which has a beautiful semi-transparent yellow tint. Exposed for several hours to a temperature of 100° F., a slight exudation of nitro-glycerine was detected in the forcite gelatine, but none in Nobel's; but it must be remarked that the latter only contained 93 per cent. of nitro-glycerine, not 95 like the forcite gelatine.

"The specific gravity of forcite, by careful measurement, was found to be the following:—

Forcite gelatine	1·51
,, No. 1	1·60
,, No. 3	1·66
,, No. 3 A.	1·69
That of the Scotch explosive gelatine was	1·53

"All the forcites were somewhat elastic to the touch, the

Digitized by Google

lower grades being the harder. The lowest grade exhibited a decided hardness and friability as compared with the highest.

"Fourteen shots were fired with each of these grades of forcite in the four or five foot rings submerged about 35 feet in water about 80 feet deep. The charges were contained in the usual tin cans, and were exploded with the service fuze containing 24 grains of fulminating mercury. Four of the charges with each grade also contained a 3-ounce tonite primer, to indicate whether the fuze alone was sufficient to ensure perfect detonation. The registered pressures were not thereby increased, indicating that no extra primer is required.

"The results of my tests and their analysis justifies the claim of the Forcite Powder Company, that the higher grades of their explosives are far more powerful than any others in our market, at least when fired under water in the manner of these trials. The permanency of its composition when in store for long periods remains to be tested by time. Cartridges of the three lower grades, stored for a few weeks in a damp magazine, showed an incipient deliquescence of the sodium nitrate." [This could be obviated by using the potassium nitrate.—M. E.]

"The following trials were made to determine the degree of sensitiveness of forcite to the rough treatment it might receive if carried in the engineer trains of an army in the field :—

"Half a pound of forcite gelatine was lashed to a board and fired at with a Springfield rifle at twenty yards' range. The first shot grazed the cartridge without effect; but the second caused a loud explosion, shattering the board. The same test was applied to No. 1 with a like result. Hence forcite cannot be regarded as safe when exposed to musketry fire. A small quantity ignited by a match blazes with a hot flame, but does not explode. No trials were made with large amounts, but the usual dangerous result may be anticipated." [An addition of camphor ought to obviate this defect.—M. E.]

"The following trials were made to determine the sensitiveness of forcite to shocks of neighbouring mines transmitted through the water, a very important matter in submarine mining :—

Digitized by Google

"The primary charges each consisted of one pound of dynamite, No. 1, submerged 5 feet in water 16 feet deep. The secondary charges each consisted of half or three-quarters of a pound of forcite wrapped in thin rubber cloth. The following results were obtained :—

"*Forcite-Gelatine.*—The secondary charges failed at 10 feet, 8 feet, 7 feet, and 6½ feet. At 6 feet one charge failed and three charges probably exploded. At 5 feet one charge certainly exploded.

"*Forcite*, No. 1.—The secondary charges failed at 20 feet, 14 feet, 10 feet, 8 feet, 6 feet, 5 feet, and 4 feet (2 trials). At 3 feet, one charge certainly, and another probably, exploded.

"These experiments prove that the higher grade is the more liable to sympathetic explosion, but that both are far less sensitive than dynamite No. 1, which under like conditions explodes at about 20 feet. In fine, these investigations indicate that forcite, now for sale in our market, must be classed as one of the explosives worthy of serious consideration when it becomes necessary to defend our coast with submarine mines. Its great strength is fully established; its permanency for long periods of time remains to be studied.

"Assuming dynamite No. 1 as the standard, and giving it the value of 100, the different grades, as fired under water, gave in a horizontal plane through the charge the following relative intensity :—

Forcite gelatine	95%	nitro-glycerine =	133	intensity.
,, No. 1	75%	,, ,,	124	,,
,, No. 3	40%	,, ,,	95	,,
,, No. 3 A.	30%	,, ,,	88	,,
Dynamite	75%	,, ,,	100	,,
Explosive gelatine from Glasgow	93%	,, ,,	142	,,
Compressed gun-cotton			87	,,
Pure nitro-glycerine			81	,,

"From the above we see that :—

"1. Pure nitro-glycerine does not give great intensity when fired under water.

"2. The opinion that the value of a dynamite is proportionate

Digitized by Google

to the percentage of nitro-glycerine the same contains is erroneous, at least for submarine mining.

"3. The addition of an explosive base increases enormously the value of a dynamite."

Atlas Powder is a form of dynamite which has a rather unenviable reputation in England, due to its having been the explosive used in the outrages which were committed in London a few years ago by the so-called dynamiters. It is manufactured at the Repauno Chemical Works, near Philadelphia, and it is a composition of nitro-glycerine, wood fibre, and nitrate of soda, with 2 to 3 per cent. of carbonate of magnesia. Seven grades of it are made, containing from 20 to 75 per cent. of nitro-glycerine. They are lignum dynamites.

Gelatine Dynamite consists of a thin blasting gelatine mixed with other substances, such as nitrate of potash and wood meal. There are two grades manufactured in England, one containing 80 and the other 60 per cent. of nitro-glycerine. The great advantage of the plastic dynamites like gelatine dynamite, and also of forcite, is that they can remain in water without being affected or losing their strength.

Amongst other varieties of gelatine dynamite which may be mentioned is gelatine dynamite No. 1, the composition of which is as follows:—

65% gelatinised nitro-glycerine	97·5% nitro-glycerine. 2·5% collodion-cotton.
35% of dry admixture . .	75·0% nitrate of potash. 24·0% wood pulp. 1·0% soda.

The composition of gelatine dynamite No. 2 is—

45% gelatinised nitro-glycerine	97·5% nitro-glycerine. 2·5% collodion-cotton.
55% of dry admixture . .	75·0% nitrate of potash. 24·0% wood pulp. 1·0% soda.

From this it will be seen that the gelatine dynamites very

Digitized by Google

much resemble (and indeed they probably suggested) the lower grades of forcite discussed above.

Another variety has the following composition in the principal grades :—

Grade A.—Sodium nitrate	. . . .	2
Wood fibre	. . . . .	21
Magnesium carbonate	. .	2
Nitro-glycerine	. . . .	75
		100
Grade B.—Sodium nitrate	. . . .	34
Wood fibre	. . . . .	14
Magnesium carbonate	. .	2
Nitro-glycerine	. . . .	50
		100

The consumer of dynamite must not always judge the economic value of explosives by the percentage of nitro-glycerine which they contain, as a judiciously selected base adds enormously to the energy developed by the nitro-glycerine alone. Experience also has proved that there is a decided advantage in gelatinising the nitro-glycerine before its absorption.

The exact preparations of the base must be calculated—this being, both practically and theoretically, an important matter—and with any particular kind of base there is an economic gain in increasing the percentage of nitro-glycerine up to a certain point; but *beyond a certain point*, which exceeds the point of saturation, *there is no advantage.* It will be found that with dynamites having an active base as an absorbent, 50 per cent. of nitro-glycerine is the largest quantity which the absorbent will safely hold, and it is questionable whether greater intensity will be obtained when some of the oxidising salt is replaced by nitro-glycerine.

There is also a limit where the dope becomes explosive, and I think that less than 25 per cent. of nitro-glycerine should not be absorbed, as the liquid may become too divided for a perfect explosion or be altogether inexplosive. Of course,

Digitized by Google

this is not the case with compounds where the base is coated with the nitro-glycerine, as in Judson powder.

I also consider that it would be prejudicial to make gelatinised compounds with less than 25 to 30 per cent. of nitro-glycerine.

Glukodine (as described by the late Colonel Cundill*) is a whitish liquid produced by the nitration of a saturated solution of cane sugar in glycerine. Free sugar dissolves in it, and it is soluble in ether. Two sorts of glukodine powder are made, white and black.

Samples of it showed the following composition :—

	White.	Black.
Matter soluble in ether (glukodine) . .	36·40	34·24
Free sugar	8·40	8·76
Soda salts (mostly nitrate)	31·20	37·84
Nitro-cellulose	23·36	—
,, ,, and charcoal	—	19·31

Another analysis of the same samples showed that the glukodine in the white powder consisted of 33·19 parts of nitro-glycerine to 3·21 parts of nitro-saccharose, and in the black powder of 30·23 and 4·03 parts of the same ingredients respectively. Subsequent experiments appeared to show that glukodine was simply a mechanical mixture of those ingredients, as the nitro-glycerine could be readily evaporated off from the nitro-saccharose.

American Hercules Powder.—This is identical with *Nitro-Magnite*, as magnesia alba (or carbonate of magnesia) is used as the absorbent. It is manufactured on a very large scale in America, and I have usually heard the miners speak very favourably of it, claiming that the fumes were not so bad as from other dynamites. The reason of this I ascribe to the presence of the alkaline absorbent, which, in exploding, gives off explosion gases in which no carbonic oxide is present, and possibly the nitrogen also may enter into combinations which do not affect the organism. Its composition is as follows :—

* In his 'Dictionary of Explosives.'

Digitized by Google

	No. 1.	No. 2.
Carbonate of magnesia	20·85	10·00
Nitrate of potash	2·10	31·00
Chlorate of potash	1·05	3·34
White sugar	1·00	15·66
Nitro-glycerine	75·00	40·00

Judson Powder differs from dynamite, as in the latter the nitro-glycerine is absorbed, whereas the principle of the Judson powder is to render the oxidising salts (nitrates) non-absorbent, by coating them with a varnish of hydrocarbons, which on hardening renders the granules non-absorbent, and also non-hygroscopic. To the "dope" so prepared 10 per cent. of coarsely-ground anthracite is added, and to this mixture 5 per cent. or 6 per cent. of nitro-glycerine is added, forming a coating or film over the granules, which renders the dope explosive. This explosive has met with great success in America, it being very cheap and more powerful than the common mining powder. A detailed account of its composition is appended.

"This explosive—manufactured by the Giant Powder Company of California—is said to be a mixture of nitro-glycerine with various explosive salts, but it differs from those previously made in that the grains or particles of the absorbent are coated, cemented, varnished, or smeared with some combustible substance offering resistance to the absorption of nitro-glycerine and water. The object of this coating is to save and render effective that proportion of nitro-glycerine which, with ordinary dry (so called) absorbent mixtures, is so closely absorbed and taken up that it is rendered practically inexplosive. The result of using such a coating has been found to be that the proportion of nitro-glycerine used in the compound may be much lower—that, in fact, one, two, or three per cent. only of nitro-glycerine will give a powerful explosive compound; or the proportion may be increased, if desirable, to 15 per cent. or more.

"The following is an example of such a coated absorbent in parts by weight: sulphur, 15; resin, 3; asphalt, 2; nitrate of soda, 70; anthracite coal, 10. Let the sulphur, resin,

Digitized by Google

and asphalt be melted together and well stirred. Into this mixture, while melted, the nitrate of soda and the coal, both pulverised and thoroughly dried, are to be mixed and well stirred until thoroughly varnished, cemented, or coated by the melted mixture, care being used that the degree of heat be not sufficient to cause firing of the mass. It is better that both the nitrate and coal be hot when introduced. The entire mixture should be gently stirred until so cool that the grains cease to adhere to each other. The mixture is then complete and ready to receive the nitro-glycerine, which may be added as desired.

"The ingredients which form the coating may be applied without first melting them. To do this, first grind each of the materials of the dry mixture. Then leaving out the carbon, mix the others all together and proceed to heat them well, stirring all the time, and continue until the whole is thoroughly coated. While the mixture is cooling, the stirring must be carefully continued until the grains cease to adhere to each other; then add the pulverised carbon, which must be perfectly dry; mix well, and afterwards put in the nitro-glycerine.

"When carbon is used that is not porous or absorbent, it is not necessary that it should be coated. In that case it may only be necessary to coat the nitrate."

While this mixture above described may not be entirely non-absorbent after it has been coated, it is claimed to be sufficiently so as to mainly counteract the absorption of the nitro-glycerine, as well as to check the tendency to deliquescence in the original salts.

Judson powder has been very extensively used in California in hydraulic mining to blow down the bluff and aid the action of the water-jets. As much as 20,000, 30,000, and even 40,000 lbs. are used at a time. It has been used very extensively on the Northern Pacific Railroad for tunnelling and to blow down the enormous basaltic walls in Oregon.

At Glendon, Pennsylvania, 23,000 lbs. of Judson powder were used in a blast by Mr. Firmstone. He drove a tunnel under the hill of stone about 40 feet and ran cross-galleries

Digitized by Google

from it. The face of the quarry was 171 feet high above the chambers, 140 feet in length, and the breast 46 feet thick. The powder was rammed in four sections with an explosive in each. It brought down, it is estimated, 100,000 tons of stone. Mr. Firmstone was quite confident that 18,000 lbs. would have been sufficient.

The powder is also manufactured at Drakesville, N.J. There are three grades, called respectively R.R.P., or common Judson powder, F., and F.F. The R.R.P. (Railroad powder), is intended as a substitute for black powder, and its efficiency in hard rock is as 1 to 1½ of black powder; and in seamy ground, such as slate, sandstone, hard-pan, clay, and in all kinds of earth-blasting, 1 lb., it is claimed, will do the work of 2 lbs. of black powder. For railroad and quarry work it is claimed to be the best in the market, and great saving can be made, not only in the amount of powder used, but also in the number of holes drilled. It is sold at the same price as black powder.

It is always best to tamp the charge as thoroughly as possible. In the case of a seam blast, the seam should be well filled up with sand or earth; and in general, to obtain the best results the tamping should be as carefully attended to as when using black powder.

The powder becomes hard at about 45° F. When in this state, it readily breaks up into grains by a little pressure, and can then be poured like sand into a crevice. When using the frozen powder, a *soft* cartridge of dynamite should be used as a primer.

When so desired, the powder is put up into water-proof cartridges of any specified size.

The manufacture of Judson powder is carried out as follows: The three first-named ingredients are ground separately as fine as possible, and then thoroughly incorporated in an ordinary barrel mixer, forming a coarse-mealed powder. This is next heated on a steam pan (150 lbs. pressure per square inch, and 350° F.), and constantly stirred until the sulphur melts and coats the particles of the sodium nitrate and coal. The whole is then thrown out and allowed to cool,

Digitized by Google

forming conglomerate grains, which are next sorted by passing through sieves, and then coated with the nitro-glycerine by stirring.

The extraordinary strength of this powder is astonishing, and some wonderful work has been accomplished with it.

General Abbot (U.S.A.), in his "Report on Submarine Mines," writes as follows of the Judson powder :—

"For economic blasting there appears at present to be a wide divergence between the practice here and in Europe. With us, the tendency is strongly toward the use of cheap low-grade dynamites which derive their power from a small charge of nitro-glycerine acting so as to develop to the maximum the potential power residing in an explosive base. Abroad, the tendency is understood to be toward the use of small charges of the most powerful explosives known to modern practice. In the one case, economy results from the low price of the powders; and in the other, from small drill-holes and cheap manipulation. The study of Judson powder possesses great interest as an illustration of advanced American practice.

"In my experimental study of mica powder, in 1875, Mr. Mowbray's claim that his non-absorbent base promoted quickness of explosion was shown to be well-founded (Professional Papers Corps of Engineers, No. 23, pages 93 and 111). This is the fundamental idea upon which rests the patent of Mr. Egbert Judson, of San Francisco, dated October 31, 1876. He claims (1) a powder consisting of particles of gas-producing materials rendered conglomerate and non-absorbent by his treatment, and explosive by a coating of nitro-glycerine; (2) the process of forming the conglomerate grains by stirring the dry powdered gas-producing materials into a melted adhesive, combustible, non-absorbent material.

"This explosive was first manufactured by the Giant Powder Company of San Francisco, in 1877, and it has been largely used in California for railroad work and bank-blasting. Works were established at Drakesville, New Jersey, in 1881; and during the past three years a very large business (4,000,000 pounds) is reported. The R.R.P. grade is sold at the price

Digitized by Google

of common blasting saltpetre powder, while its strength is immensely greater, as will soon appear.

"The composition of Judson powder is varied according to the special use for which it is designed. The highest grade (3 F.) contains 20 per cent. of nitro-glycerine; but the grade generally used for railroad work, stump-blasting, &c., and known as the R.R.P. powder, has the following composition:—

Sodium nitrate	64
Sulphur	16
Cannel coal	15
Nitro-glycerine	5
	100

"Special care and skill are required as to materials, proportions, and workings. The extraordinary strength of this powder should be witnessed to be properly appreciated, but the figures below will be not without value in this connection.

"During the past season samples of it were subjected to tests by the ordinary ring measurements. Samples were delivered to me in 1882, designated 'Coal-mining' and 'R.R.P. for railroad work.' They were identical in composition, but differed in fineness of grain, the former being the finer. The first sample received in 1884, designated 'coarse,' was identical with the 'railroad' of 1882, but was manufactured by machinery, the former being hand-made. The second and third samples of 1884—designated 'improved coarse' and 'improved fine'—were identical in composition with the above, but were more thoroughly incorporated, and were given a more granular form, to make a dry and free-running powder which will not freeze as the others would do. To effect these advantages the grains became more absorbent, and thus a certain amount of strength was sacrified.

"The 'fine' sample was passed through a No. 12 sieve; and the 'coarse,' after failing to pass a No. 12 sieve, was passed through a No. 6. The fourth sample ot 1884 was the 3 F. powder made by conbining 20 per cent. of nitro-glycerine with the coarse and fine respectively. The fifth sample of

Digitized by Google

1884 contained 17½ per cent. of nitro-glycerine combined with a base of which the composition was communicated confidentially. The able directors of this establishment, Mr. T. C. Schrader and Mr. R. S. Penniman, are constantly studying to improve their manufacture, and I was glad to assist by testing this experimental product.

"Finally, at their suggestion, I combined the 3 F. powder with a mixture of equal parts of the No. 2 and No. 3 grades of orange lightning powder tested in 1871, so as to give the mixture 5 per cent. of nitro-glycerine. This base is a high grade of sporting powder sold at $1.00 per lb.; and the object of the trial was to determine whether one part, consisting of grains highly charged with nitro-glycerine, thoroughly incorporated with three parts of good fine-grain black powder, would be sufficient to fully develop the potential energy of the whole. The result sufficiently showed that this is not a direction in which to seek for improvement.

"Charges of these several samples were placed in the ordinary tin cans and submerged, in the three-foot or four-foot rings, about 35 feet in water 80 feet deep. They were each exploded by a single service low-tension fuze, containing a detonating charge of 24 grains of fulminating mercury enclosed in a copper cap.

"The following figures show the relative intensity of action of the several samples when fired under water. (The standard of comparison is dynamite No. 1, containing 75 per cent. of nitro-glycerine and 25 per cent. of an inert base) :—

Dynamite No. 1 . .	(75% nitro-glycerine)				K = 5·80	intensity 100
Judson coal-mining .	(5%	,,	,,	) 1882	K = 17·24	,, 44
Judson railroad . .	(5%	,,	,,	) 1882	K = 14·42	,, 39
Judson railroad . .	(5%	,,	,,	) 1884	K = 13·52	,, 38
Judson improved coarse	(5%	,,	,,	)	K = 9·15	,, 29
Judson improved fine	(5%	,,	,,	)	K = 9·15	,, 29
Judson 3 F. coarse .	(20%	,,	,,	)	K = 28·31	,, 62
Judson 3 F. fine . .	(20%	,,	,,	)	K = 28·31	,, 62
Judson special base .	(17·5%	,,	,,	)	K = 40·42	,, 78
Judson 3 F. coarse and lightning powder	(5%	,,	,,	)	K = 8·30	,, 28
Judson 3 F. fine and lightning powder	(5%	,,	,,	)	K = 1·55	,, 9

Digitized by Google

"That a 5 per cent. nitro-glycerine powder, costing no more than ordinary black powder, should give such results will, I think, be astonishing even to experts.

"Ever since the announcement, in 1874, that Messrs. Roux and Sarrau had succeeded in obtaining from musket powder more than four times the usual explosive force, by the use of primers so large as to apply a detonating shock simultaneously to all parts of the mass, attempts have been made to accomplish a like result in blasting. Judson powder has apparently solved the problem by its fine subdivision and thorough incorporation, combined with its thin surface of nitro-glycerine permeating the mass, which enables a central fuze to envelop every grain nearly simultaneously with the heat and shock of detonation, and thus to fully develop the stored energy even when only lightly encased under water.

"For submarine mining, where the highest possible intensity of action is demanded, this powder, of course, cannot compete with many other modern explosives, but for military land-mining its value has yet to be tested. This it is proposed to do in the near future at Willet's Point. The two grades supplied in 1882 were tested to determine their sensitiveness to the shock of a ball fired from a Springfield rifle at twenty paces. Charges of $1\frac{1}{4}$ lb., enclosed in cloth bags and backed by inch boards, were thus perforated, and always without causing ignition. When fired by a match, such charges burned for about forty-five seconds with a strong yellow flame, but with no flashing like ordinary black gunpowder. It would seem, therefore, that Judson powder could probably be carried with the engineer train of an army in the field without the dangers from chance bullets which higher-grade dynamites entail. But this matter requires further investigation before a positive opinion is warranted.

"For economic blasting in dry sites, the powder appears to be well worthy of consideration; in damp localities its base might probably collect moisture and deliquesce, although no trouble of this kind has occurred in the magazines here."

Digitized by Google

Paleine or **Straw Dynamite** is a mixture of nitro-cellulose, made from straw with nitro-glycerine; it is manufactured in Sardinia and Belgium.

Trautzl's Dynamite is a mixture of nitro-glycerine and gun-cotton pulp, consisting of

Nitro-glycerine	75 parts
Gun-cotton	25 ,,
Charcoal	2 ,,

Carbo-dynamite.—Carbo-dynamite is of British invention, and owes its origin to Messrs. W. D. Borland and W. F. Reid. The base of this explosive is nitro-glycerine, and the absorbent is carbon. It is as cheap as ordinary dynamite, and is alleged to possess several advantages over it. For example, it has much greater explosive force, seeing that 90 per cent. of the compound is pure nitro-glycerine, and that the absorbent itself is highly combustible. In addition, it is claimed that, when the dynamite is wet, no exudation of nitro-glycerine takes place from the absorbent. It is even declared that some carbo-dynamite which had lain for eight months in water presented at the end of that period the same appearance as when first immersed, and had suffered no deterioration of its explosive qualities.

Smolianinoff Explosive.—The Smolianinoff explosive, which also has been experimented with (in America) of late, consists of 80 per cent. of nitro-glycerine combined with a certain fluid, the nature of which is a secret.

It was used as a bursting charge for shells, and seems to withstand the shock produced by heavy gunpowder charges when fired from guns. A 100-pounder Parrott gun was employed, and three shells were fired, the first two weighing 89 lb., and carrying 4·6 lb. of Smolianinoff explosive, and the third weighing 82 lb., and having a 4·1 lb. bursting charge. The firing charge in each case was 18 lb. of Dupont powder, the range was 101 yards, and the muzzle velocity was about 1490 feet. The first shell was not fused. It struck the target

Digitized by Google

and broke up with a low explosion, doing only superficial damage. The second shell was fitted with a detonating percussion fuze. It struck the target, exploded with much more force than had been developed by the unfused shell, did some surface damage, and badly injured the target's foundations. The third shell produced much the same results. No damage was done to the gun, and the weakness of the cast-iron shells which were used, as well as the shape of the heads, which were suitable only for a nose fuze, were held to be mainly responsible for the unsatisfactory nature of the experiments. These, we hear from other sources, are to be repeated under more favourable conditions.

Snyder Explosive.—The Snyder explosive has recently been tested in Turkey as a bursting charge for shells, with very successful results. It consists of 94 per cent. of nitro-glycerine and 6 per cent. of a compound of collodion, gun-cotton, camphor, and ether; and it is exploded by mere percussion against any hard body. It is, nevertheless, said to be safe to handle. The gun employed was a 6-inch rifled piece. The target, 220 yards away, was composed of twelve 1-inch steel plates, welded together and backed with 12-inch and 14-inch oaken beams. It measured 14½ feet by 4½ feet, and weighed more than 20 tons. The charge of Snyder explosive was 10 lb. The target was utterly destroyed at the first shot, and nine other shots were fired without accident of any kind. Experiments have also been made with this explosive in other countries, by firing it from a gun as a bursting charge for shells.

The explosive is the invention of Mr. F. H. A. Snyder, of New York, and appears to have an important future.

Von Dahmen's Safety Dynamite. — According to reports recently published, *Baron von Dahmen*, a German scientist, has discovered the means of preventing nitro-glycerine compounds from being affected by a low temperature, as already at 40° F. a congelation of the oil takes place (see page 35), and of rendering all classes and grades of dynamite

Digitized by Google

non-sensitive to the initial explosion of the detonators, thus dispensing with the troublesome and dangerous operation of thawing.

I am not aware what means Baron von Dahmen employs to prevent the congelation of the nitro-glycerine, but if this discovery is a true one it will be of great importance, especially for northern countries, and even those lying within the temperate zone. I see no reason why some substance should not be introduced which, when blended with the nitro-glycerine, would change the character of the latter, rendering it less sensitive to cold, without affecting its other valuable properties.

It is stated that when Von Dahmen's dynamite is left in an ice machine for twenty-four hours, exposed to a freezing temperature, it maintains not only its plasticity but also explodes readily, whereas ordinary dynamite submitted to similar conditions failed to explode, even with triple force detonators. Such an invention, if practically demonstrated, will certainly meet with great favour among all classes of miners and blasters, who are fully aware of the great chapter of accidents resulting from the thawing operation, and the many "miss shots" from frozen dynamite.

Classification of Dynamites.—From the above enumeration of the many compounds which have been brought before the public, it will have been seen that in nearly all of them the nitro-glycerine is mixed with or absorbed by an active base, or "dope," as the Americans style it; and for this reason the dynamites may be divided into two groups:—

1. Dynamites with an inert base, such as kieselguhr, which acts merely as an absorbent for the liquid nitro-glycerine. This was Nobel's original invention.

2. Dynamites with an active—*i.e.*, a combustible or explosive—base.

The idea of substituting an active base which in itself is a combustible—or, in the sense of the Explosives Act, an "explosive" proper—in lieu of the inert kieselguhr, is an

Digitized by Google

excellent one: the strength of the explosive itself is increased by rendering the absorbent matter explosive, and a more perfect combustion is insured when the charge is fired.

Colonel Cundill, besides adopting the classification just indicated, has made a subdivision of group 2 into three minor classes—viz., those which contain as a base,

a. Charcoal.
b. Gunpowder, or other nitrate or chlorate mixtures.
c. Gun-cotton, or other nitro-compounds.

He also gives* the following rough-and-ready tests for ascertaining whether a given substance contains nitro-glycerine :—

"If a liquid is oozing out or can be squeezed out from the substance, put the drop on to blotting-paper. If this is nitro-glycerine it will make a greasy stain, not disappearing or drying away; struck with a hammer on iron a loud report will be heard; lit and burnt, it will give a crackling sound and a greenish flame. If gradually heated by a flame underneath, it will give a sharp report.

"Again, put a portion of the substance into a test tube and shake it up with methylic alcohol (wood spirit), first ascertaining that the spirit poured into water causes no turbidity or milky appearance. Filter the contents of the tube into another tube, and add pure water to the latter. If nitro-glycerine is present, a milky appearance will be produced, and the heavy liquid will eventually settle at the bottom of the tube.

"A much more delicate test is to use aniline and concentrated suphuric acid as re-agents. In the presence of nitro-glycerine a purple colour is produced, which changes to green on the addition of water.

"Nitro-glycerine explosives, unless carefully made from pure ingredients, are apt to decompose spontaneously. Any indication of acid fumes, or any tinge of green in them, should be followed by their prompt destruction, with suitable precautions."

---

* 'Dictionary of Explosives,' p. 39.

Digitized by Google

Forcite Powder Works.—The following description of these works (which are previously referred to in this chapter) appeared in the *Mining Herald and Colliery Engineer* of Philadelphia (March, 1884) :—

"The works of the American Forcite Powder Manufacturing Company, at Lake Hopatkong, Morris county, New Jersey, are completed, and the manufacture of explosives has commenced. The works are the most extensive in the country, numbering upwards of forty buildings, covering an area of several acres, heavily wooded. The narrow gauge railroad which connects them is nearly a mile in length. The buildings where the powder manufacturing is to be done are situated from 100 to 200 feet apart, and placed in excavations in the side hills, so that only one side is exposed. All these buildings are lined, ceiled, heated by steam, and furnished with water. The building containing the machinery is 84 × 44 feet, and is divided into four fire-proof compartments. Embraced in the very excellent machinery plant is an Ingersoll duplex air compressor. The glycerine converting house is a three-story frame building 32 × 32 feet. The converter is in the third story, the separating tanks and washing tanks are on the lower floors. The spent acid flows through leaden pipes to the acid house, where it is regenerated and forced back to the converting house, 900 feet away, by means of compressed air. The acid regaining factory is a brick building 25 × 65 feet, and contains four large retorts and condensing towers for regenerating the spent acids.

"The nitro-glycerine is carried from the converting house to the mixing houses, by gravity, through large indiarubber pipes, well protected and laid under ground. After passing the two mixing houses, through a cut in the hill are reached three buildings where the forcite is modelled into cartridges by machines which are run by compressed air, and the power is transmitted to the other buildings with wire ropes; then come two packing houses where the cartridges are boxed, and then two magazines which are built in excavations in the hill, so that the roofs are below the surface of the ground. The structures are of brick with roofs of corrugated iron. This

Digitized by Google

roof forms a lightning conductor, and has rods leading from the four corners into the ground, as in the Belgian Government magazines. A system of ventilation, through hollow bricks, allows the air to enter at the bottom and escape at the top. A reservoir, capable of furnishing 60,000 gallons of water daily, is connected with the works, fed from an artesian well giving water at 8° C. The concern has a capacity of 6 tons of powder per day, and, beginning with a force of fifty men, it is expected soon to increase the same to a hundred.

"These works have been erected under the personal supervision of Mr. M. Eissler, the manager, who has had a large experience in the manufacture of powder in California, and who has combined the experience and practice of the largest powder manufacturers of the world in the new works."

Belgian Forcite Works.—The annexed plate (Fig. 14) shows the plan of the Belgian Forcite Works at Baelen-sur Nethe.

Digitized by Google



FIG.

NOTE.—All dangerou
accident, and to localis
provided with all moder
houses for the raw mate
for the spent acids; I,
glycerine washing appa
powder magazines.

Digitized by Google

Digitized by Google

CHAPTER VI.

APPLICATIONS OF GUN-COTTON.

EARLIER Experiments—Results of Sir F. Abel's Researches—Manufacture of Gun-cotton rendered Harmless—Diluted and Undiluted Gun-cotton—Wet Gun-cotton for Military Purposes—Compressed Gun-cotton or Submarine Mining—Transmission of Detonation in Water—Transmission of Detonation through Air.

SINCE the introduction and speedy abandonment in Austria, about twenty-three years ago, of gun-cotton arranged in the form of compactly wound thread (Von Lenk's system), as an explosive agent for field guns, attempts to use it as a substitute for gunpowder for artillery have been limited to experiments conducted at Woolwich in 1867 and 1868 with cannon cartridges of compressed gun-cotton. Considerable progress was made at that time towards the production of a thoroughly safe cartridge for field guns, but the experiments were suspended when much evidently remained to be accomplished before the requisite uniformity of action could have been secured. The difficulties since encountered in moderating and regulating the explosive force of gunpowder, when employed in very large charges, have shown how remote is the prospect of successfully applying explosive agents of greater violence to artillery, excepting in the smallest calibres. Success has on many occasions attended the employment, in small arms, of explosive agents differing considerably in character from each other, but all of them more rapidly explosive, and therefore more violent, than gunpowder. The chief advantages claimed, and more or less established, for some of them

Digitized by Google

over gunpowder were the production of comparatively little or no smoke, the reduction of fouling, and increased projectile power, with the employment of comparatively small charges.*

The first attempts to apply gun-cotton in small arms, soon after its discovery in 1846, were disastrous in their results; and the success which, long afterwards, was believed to have been achieved by Von Lenk's indefatigable labours in this direction, was not confirmed by experience. Several methods of reducing the rapidity and increasing the uniformity of action of gun-cotton in small arms have since been experimented with in England. Some of these, which consisted in the uniform dilution of gun-cotton, either with ordinary cotton or with the less explosive varieties of the material, have furnished tolerably efficient cartridges for sporting purposes; but the only direction in which substantial prospect of success has hitherto attended the employment of gun-cotton in arms of precision has been that of converting the very finely divided substance into pellets or grains, of which the rapidity of explosion has been retarded by their uniform impregnation with small quantities of some perfectly inert material, each small particle of gun-cotton being enveloped and separated from those surrounding it by a film of non-explosive substance (*e.g.* paraffin, stearine, or caoutchouc).

Von Lenk's persevering efforts to improve the manufacture and devise methods of application of gun-cotton, though in themselves not crowned with any permanent success, have contributed considerably to secure an unassailable position for that material as a valuable and safe explosive agent, by leading to its systematic study in England, and the consequent development of its manufacture, and the discovery of its most valuable properties.

* I have been informed lately on good authority that the French Government are using a powder in their Lebel rifle, which proved, at a trial where five cadavres (corpses) were placed at certain distances one behind the other, that the bullets passed through the five bodies when fired at from a distance of 400 metres. Such results, no doubt, will ultimately lead to the abandonment of gunpowder in small arms.

Digitized by Google

Result of Sir F. Abel's Researches.—It is especially through the persevering efforts, and the results of analytical and synthetical researches of *Sir Frederick Abel*, that gun-cotton has taken rank as the modern explosive *par excellence* for war purposes, and also for special mining work.

Pure gun-cotton has the formula $C_6 \left\{ \frac{H_7}{3\,NO_2} \right\} O_5$. Sir Frederick Abel found that the instability of gun-cotton, as manufactured by Von Lenk's process, arose from imperfect purification, and the presence of minute quantities of foreign substances (susceptible of removal by searching purification) of comparatively unstable character, produced by the action of nitric acid upon resinous and fatty substances retained by the cotton fibre.

The practical trials made, for the English Government, of gun-cotton in the different forms proposed by Von Lenk for employment in artillery, shells, small arms, and mines, and Abel's investigations on the influence of the mechanical condition of gun-cotton upon the rate of its explosion under different circumstances, proved that the control believed to have been obtained by Von Lenk's system of preparation, over the explosive power of gun-cotton, was very limited; and that, while it was indispensable to the development of its full explosive force, that it should be very strongly confined, even the most compact arrangement of the gun-cotton fibres, composing a cartridge to be used in a cannon or small arm, did not impede the almost instantaneous penetration of the heated gases (produced by the first ignition throughout the mass), and could therefore not be at all relied upon to reduce the rapidity of explosion of gun-cotton when ignited in a nearly closed chamber, as in the bore of a gun.

The system of manufacture devised by Sir Frederick Abel, which assimilated gun-cotton in its mechanical condition to gunpowder, the finely divided material being converted by pressure into uniformly compact masses of any convenient form, led, as already pointed out, to a great advance in the safe and efficient application of the substance to small arms, and

Digitized by Google

was also productive of results in the application of gun-cott for filling of shells.

Its development into a manufacturing process resulted in very important improvements in the directions of economy, facility and rapidity of production, and had the effect of considerably raising the standard of purity of the material.

The cheapest description of cotton (machinery waste) became available as a source of gun-cotton, and the reduction of the fibre to a fine state of division greatly facilitated the application of very searching purifying processes.

Manufacture of Gun-cotton rendered harmless.—The manufacturing operations became absolutely safe throughout, as even the conversion of the finished product into the compressed masses of the various forms in which it receives application is carried out with the material in a wet, and therefore perfectly non-inflammable, state. How harmless the manufacture of gun-cotton is considered, it is sufficient to state that the Stowmarket factory lies within the town limits, and is surrounded by dwelling-houses.

The minute state of division of the gun-cotton also permits of its being readily and intimately mixed with substances of a nature calculated to moderate the rapidity and violence of its explosion, or with the full proportions of oxidising salts required for the attainment of the maximum amount of work from the carbon of the cellulose.

Lastly, the conversion of gun-cotton into homogeneous highly compressed masses has resulted, as will presently be seen, in the establishment of other most valuable and previously unsuspected properties of gun-cotton.

The only, though very serious check which the development of gun-cotton has experienced in England, namely the severe explosion which occurred at the manufactory of Messrs. Prentice, at Stowmarket, in 1871, has been productive of beneficial results; firstly, because a very searching inquiry, instituted by the Government, into the cause of that explosion demonstrated that it was quite unconnected with any defect in the stability of

Digitized by Google

the material when purified according to the present system; and, secondly, because the violent explosion of a considerable store of compressed gun-cotton, which in small quantities only burns rapidly, even when moderately confined, led to an investigation of the conditions attending violent explosion consequent upon the accidental ignition of gun-cotton stores.

Diluted and Undiluted Gun-cotton.—*Sir Frederick Abel* has also investigated the influence of dilution by solids and liquids on the susceptibility of explosive compounds, generally, to detonation, and has demonstrated that, if a finely divided solid explosive body, such as gun-cotton, be diluted with a solid inert substance, soluble in water, and the mixture be compressed into compact masses with the aid of water, it is obtained in a condition of greater rigidity (by the crystallisation of the soluble diluent), and therefore in a form more susceptible to the detonating effect of a small fulminate charge, than when the undiluted explosive by itself is very highly compressed, because the particles of the hard mass oppose greater resistance to the force developed by detonation. The reduction of activeness due to even considerable dilution is consequently almost counterbalanced by the greater rigidity of the mass; and, if in the case of gun-cotton the diluent be a soluble oxidising agent (such as saltpetre), the predisposition to chemical reaction between the two substances operates, in conjunction with the effects of the crystallised salt, in imparting rigidity to the compressed mass, and the latter is consequently quite as sensitive to detonation as though it consisted only of gun-cotton. If this substance is diluted with a liquid, its sensitiveness to detonation is very greatly reduced; thus a considerably increased amount of mercuric fulminate is required to detonate gun-cotton containing 10 to 15 per cent. of water, as will be shown hereafter.

Wet Gun-cotton for Military Purposes.—The readiness and certainty with which wet gun-cotton may be applied to the various operations hitherto carried out with dry gun-

Digitized by Google

cotton, or with nitro-glycerine preparations, have been demonstrated by numerous explosive experiments, and there is no question that for all military purposes a most important advantage in point of safety and simplicity has been gained, as the stores of this explosive agent may not only be kept in an absolutely uninflammable condition, but may be issued in that state for actual use. Thus the requisite material for the rapid destruction of bridges, stockades, or fortifications,* may be carried out with an army in the field without any risk of accident. Experiments which have been carried out by the Austrian artillery and engineer committees, and by the Government committee on gun-cotton in England, have shown that, if ammunition wagons containing packages of dynamite are fired into from military rifles, even from a distance of 1000 paces, explosion invariably results; dry compressed gun-cotton under the same conditions is frequently inflamed by the penetration of a bullet fired from a much shorter distance, but is never exploded, while wet gun-cotton in a condition ready for service cannot possibly be ignited by the same means, even at the shortest ranges.

Compressed Gun-cotton for Submarine Mining.—The application of compressed gun-cotton to submarine mines has been made the subject of extensive experiment in England; and the comparative force exerted at various distances and depths of immersion, by large and small quantities of that material, confined in various ways, as well as of dynamite and other explosive agents, has been examined by means of the so-called crusher gauges, which have been applied to the measurement of the pressures exerted by exploding gunpowder. Many results of interest and importance have been obtained, of which it may be mentioned that dry compressed gun-cotton and Nobel's dynamite prove to be on an equality with each other,†

* See 'Modern High Explosives,' art. "Their application for Military purposes."

† These results are not corroborated by General Abbot's researches, whose measurements of intensity under water are given on page 44.

Digitized by Google

but that very decidedly greater effects were obtained by employing gun-cotton saturated with water, when closely but not strongly confined round an initiative charge of dry gun-cotton. Another important observation made in these investigations is that, provided the wet gun-cotton closely surrounds the detonator of dry gun-cotton, any small spaces between them and between the individual masses comprising a charge, may be filled with water without in any way interfering with the transmission of detonation throughout, or with the attainment of the maximum of destructive effect. Thus results, fully equal to the highest ever obtained by the explosion of gun-cotton in strong metal cases under water, have been furnished by charges which were simply held together by means of an ordinary fishing-net.

Transmission of Detonation in Water.—In examining into the power of water to transmit the force developed by detonation, *Abel* was led to make experiments of a novel character in hollow projectiles, which have furnished results of considerable interest, and have been shown, by experiments carried on at Okehampton, near Dartmoor, to possess great practical value. If only a small piece from 0·25 to 1 oz. of compressed gun-cotton be exploded, by means of a detonator, in the interior of a shell which is filled up completely with water, and closed, the force developed is so suddenly and uniformly transmitted in all directions that the thick hollow sphere or cylinder is broken up into seven or fourteen times the number of fragments produced by filling the shell completely with gunpowder or a more violent explosive agent (that is, from 30 to 60 times the weight of the gun-cotton used). In this simple way a hollow projectile of ordinary construction may be made to exercise the functions of a shrapnel shell. Detonations less sudden than those obtained with the small cylinder of compressed gun-cotton produced much inferior results, although considerably larger quantities of the explosives were used. Again, by filling a shell completely with a mixture of water and finely-divided gun-cotton, and detonating in it a

Digitized by Google

charge of 1½ or 2 ozs. of dry gun-cotton, the shell being tightly closed, the resistance opposed at the first instant, by the strongly confined mixture of solid and liquid, to the force developed, being similar to that offered by a powerful solid body, the small particles of gun-cotton, though enveloped in and separated from each other by water, are in a position favourable to detonation, and hence a mixture absolutely harmless under all ordinary circumstances becomes a most formidable exploding agent in shells. The difficulty of employing gun-cotton in hollow projectiles, arising out of the liability of their premature explosion by the concussion to which they are subject on firing the guns (and which has been found to apply equally to dynamite), appears thus to have been satisfactorily overcome.

Transmission of Detonation through Air.—This also has been made a subject of investigation by *Sir Frederick Abel*, following up some interesting results on the transmission of detonation through tubes which had been obtained by Trauzl with dynamite, and by Champion and Pellet with iodide of nitrogen.

He has traced to very simple causes some remarkable differences in the apparent power of tubes of different kinds to transmit detonation, and has furnished several demonstrations of the influence of the volume and quality of a detonation upon the results obtained. He has also proved, by small and large experiments, that the *explosion* of a substance may be brought about as a phenomenon distinct from that of its *detonation*, in regard both to the conditions to be fulfilled for its development and the mechanical effects produced by it. Lastly, he has successfully applied a Noble's electric chronoscope to the determination of the velocity with which detonation is transmitted along a continuous mass or a row of distinct masses (either touching each other or spaced) of compressed gun-cotton, of dynamite and nitro-glycerine. Trains or rows of the materials, varying between 24 and 50 feet in length, were employed, and the records of the rate of progress of detonation

Digitized by Google

at different parts of the train were generally remarkably uniform, being mostly quite as high at the termination as at the commencement of the line of explosive material. The velocity with which detonation is transmitted along continuous rows of gun-cotton slabs or cylinders ranged from 17,000 to 20,000 feet per second, varying with the extent of contact between the individual masses employed, and with their density or compactness, but being unaffected by their form or by very considerable variations in their weight. The compressed mixtures of gun-cotton and saltpetre (nitrated gun-cotton) did not, as might have been anticipated, transmit detonation as rapidly as pure gun-cotton; but the velocity of transmission of dynamite was somewhat more rapid, ranging between 19,500 and 21,500 feet per second. It was remarked, however, that while the intervention of spaces of 0·5 inch, and even more, between the individual pieces of a row of compressed gun-cotton masses of a particular weight did not, or only very slightly, affect the rate at which detonation was transmitted, a similar spacing of masses of corresponding weight of dynamite had the effect of reducing the velocity of its detonation to less than one-third that of the velocity observed with a continuous row of cartridges. This result of unconfined nitro-glycerine itself was ascribable to the physical peculiarities of the substances. Compressed gun-cotton saturated with water transmitted detonation with decidedly greater velocity than the air-dried material, a result which is in accordance with the greater sharpness or violence of action observed in practical experiments with the wet material, and is due to its increased rigidity at the moment of its exposure to the force of detonation, consequent upon the replacement of air in the pores by the comparatively incompressible liquid. In iron tubes containing small charges of gun-cotton separated by intervals of 2 and 3 feet, the detonation was transmitted, from the initiative explosion to the first charge, at a rate of about 12,000 feet, but after that it travelled from charge to charge only at an average rate of about 6000 feet per second.

Digitized by Google

CHAPTER VII.

MANUFACTURE OF GUN-COTTON.

OUTLINE of the Process—Gun-cotton distinguished from Collodion-cotton—Gun-cotton an Ether of Nitric Acid—Manufacture of Gun-cotton at Le Bouchet—Manufacture at Waltham Abbey—Messrs. Mackie and Faure's Granulated Gun-cotton.

THE nitric acid used in the manufacture of gun-cotton is of 1·45 to 1·50 sp. gr., and must be perfectly pure—that is, free from chlorine—because an acid containing the latter substance produces a less effective gun-cotton. It is also of great importance that the nitric acid be of the greatest strength.

In the production of gun-cotton large quantities of water are formed, and hence if nitric acid *alone* were used it would soon become so diluted as to be unable to produce gun-cotton, but in its stead the less explosive collodion-cotton. For that reason Schönbein and Böttger used a mixture of nitric and sulphuric acids. Thus the nitric acid remained during the process in a tolerably concentrated condition, the water formed during the reaction being absorbed by the sulphuric acid. English sulphuric acid of 1·85 sp. gr. is used.

Heating of the acid mixture is to be avoided, because otherwise products are formed similar to those formed by the spontaneous decomposition which sometimes occurs after long years of storage. The resulting product is not then explosive.

The gun-cotton, when formed, must be most carefully freed by washing from the still adhering acids. If not so freed, it will be liable to spontaneous decomposition or explosion. In former years this important point was often neglected, and the result was the explosion of several factories.

Digitized by Google

The drying of the perfectly washed gun-cotton is now the most dangerous part of the whole process of manufacture; it must be done with the greatest caution, and the temperature should not rise above 50° to 60° C.

In a well-managed factory, 100 parts of cotton yield from 155 to 175 parts of gun-cotton. Theoretically the yield should be about 185 parts. The following are some of the results obtained with 100 parts of cotton:—

Pelouze (1848)	168 to 170
Schmidt and Heckn (1848)	169·0
Van Kerckhoff and Reuter (1849)	176·2
W. Crum (1850)	178·0
Redtenbachn, Scrotter and Schneider (1864) .	178·0

Gun-cotton distinguished from Collodion-cotton.—Explosive gun-cotton is easily distinguished from collodion-cotton by its *insolubility in alcoholic ether.* It is shown by experiments, the results of which are given in the table below, that it is necessary in practice to avoid a dilution of the acid mixture.

Acid Mixture.	Parts of Water.	No parts of compound obtained from 100 parts cotton.	Nature of the compound.
Equal parts of Nitric and Sulphuric Acids . . .	..	177·0	Insoluble.
Do.	1	176·0	Do.
Do.	1½	171·7	Slightly soluble.
Do.	1¾	166·4	Entirely soluble.
Do.	1⅞	160·5	Do.
Do.	2	157·0	Easily soluble.
Do.	2½	140·0	Very easily soluble.

By an increase of the proportion of water the proportion of product obtained is lessened.

Gun-cotton an Ether of Nitric Acid.—Neither gun-cotton nor collodion-cotton is in an exact sense a nitro-compound, such for example as picric acid is, but they are rather ethers of nitric acid. This conclusion is based upon

Digitized by Google

the chemical behaviour of gun-cotton with concentrated sulphuric acid and alkalies. Concentrated sulphuric acid in the cold sets the nitric acid free from the gun-cotton, and moderately concentrated potassium or sodium lye forms slowly at ordinary temperature, very quickly at 60° to 80° C. from the gun-cotton nitrates of potassa and soda respectively. These chemical operations, Böckmann claims, can be clearly accounted for only on the assumption that gun-cotton is an ether of nitric acid. Nitro-glycerine also gives by treatment with potassium or sodium lye the corresponding nitro-salt and glycerine, and therefore it also is an ether of nitric acid.

Calloxyline, or collodion-cotton, will be discussed further in a separate chapter (p. 117).

Many changes and improvements have been made in the course of time in the manufacture of gun-cotton. Here it will be sufficient to give in some detail two illustrative examples of the process—namely, the course of manufacture at Le Bouchet and Waltham Abbey respectively.

Manufacture of Gun-cotton at Le Bouchet.—At Le Bouchet, gun-cotton was made in the following manner. Two hundred grams of cotton were steeped for an hour in two litres of a mixture of one volume of concentrated nitric acid and two volumes of concentrated sulphuric acid. Then the cotton was taken out and pressed, whereby seven-tenths of the mixture was recovered; after this it was washed for one to one-and-half hour in running water; strongly pressed again; allowed to lie for twenty-four hours in wood-ash lye; then well washed in running water; then pressed and finally dried on a wide linen sheet through which was forced air heated to 60° C. The average yield from 100 parts of cotton was 165 parts of gun-cotton. The strong pressings of the gun-cotton while still impregnated with acids caused the subsequent washings to be difficult and laborious. By the Lenk process strong pressing is entirely avoided.

This process has been thus described :—

Digitized by Google

The cotton, in loosely twisted threads of various spun dimensions and formed into skeins of 85 grams weight, is hung in little hooks in a boiling potash solution of 1·02 sp. gr. to free it from fatty substances. After the cotton has remained in this solution for two or three minutes it is freed from the solution in a centrifugal machine.

Fig. 15 represents a centrifugal drier, the invention of M. Fesca. It consists of an open drum *a* of fine meshed wire-work caused to revolve in the cast-iron case *b b*, by means of the bevel-wheel *c d*, gearing with a motive power, the drum making 1000 to 1500 revolutions per minute. The



FIG. 15.—FESCA'S CENTRIFUGAL HYDRO-EXTRACTOR.

motion of the drum can be stopped by means of the brake *e*, and regulated by the weights placed at *o*. The substance to be dried is placed in the drum, which, being set in motion, the liquid is by centrifugal force driven through the sieve, the dry substance remaining. The action of the machine is aided by the cone *g*.

Fig. 16 shows a machine with an inner cylinder *m*, and an outer one, both revolving in concert and driving outwardly the liquid to the chamber *A* from which it trickles through a discharge pipe. The wet substance is placed around the cone *B*.

The cotton is taken from the centrifugal machine, washed with water, again whirled in the machine and thoroughly dried.

Digitized by Google

Nitric acid of at least 1·48 to 1·49 sp. gr., and sulphuric acid of 1·835 sp. gr., flow in thin streams from delivery cocks into an earthen vessel and become mixed in the proper time by weight of 1 to 3. The mixture is allowed to cool before being used.

Two of the skeins with 300 parts, by weight of the acid



FIG. 16.—CENTRIFUGAL HYDRO-EXTRACTOR.

mixture, are placed together in a cast-iron tube-like steeping apparatus, gently stirred, and pressed with a shovel.

The cotton, when completely impregnated, has a fatty appearance.

When the point of saturation is attained (after a few minutes) the skeins are placed on gratings over reservoirs and the surplus acid allowed to drip off. This dripping is accelerated by gentle pressure on the cotton. One part of cotton will after this process have increased to at least 9½ parts. When about 2 kilograms of cotton have been steeped, the acid mixture is entirely renewed.



FIG. 17.—STONE JAR.

When six skeins have been prepared (which should then weigh about 5½ kilograms) they are placed in a stone jar (Fig. 17) to remain from twenty to forty-eight hours. A cloth is placed over the skeins and held down by a light weight, in order that the skeins may be kept under the impregnating acid. During this time, in which the transformation of the cotton into gun-cotton is completed, the jar stands in a place

Digitized by Google

the temperature of which is not allowed to pass below 5° or above 25° C. In winter, therefore, heating, and in summer sometimes cooling by means of running water, is necessary. During the first two to six hours the jar must be watched so that any possible heating may be prevented by seasonable cooling. After remaining in the jar for the proper length of time, the crude gun-cotton is freed from surplus acid in the centrifugal machine, then washed with a large quantity of water in copper washing drums and finally subjected for from three to six weeks to the action of running water in so-called "wool washing vessels." The gun-cotton cleaned in this way is treated with a boiling potash-solution of 1·02 sp. gr., then whirled in the centrifugal machine, washed again with water, again whirled, and then dried by a heat of 25° C. in the air.

When the last remaining acid has thus been removed the gun-cotton is steeped for a time in a sodium-silicate solution of 1·072 sp. gr. When taken out it is whirled and then exposed to the air for three days. During that time, the silicate of soda is decomposed by the air, and an insoluble silicate is precipitated on the fibres of the cotton. This is the so-called "silicate process."

In conclusion, the product is again washed in the softest possible running water, then whirled and dried, by a heat of 35° at the most, in the open air or in a drying-room.

Direct rays of the sun are to be avoided.

The average production after many years' experience is 165 to 167 parts of the explosive from 100 parts of cotton. The gun-cotton thus made was subjected to careful tests as to its structure and by means of an eprouvette as to its strength. Skeins with broken threads were discarded as unfit for use.

The above described Lenk method of making gun-cotton is in its essential outlines retained in this country at Stowmarket, but all the improvements introduced by Sir Frederick Abel have been added.

Manufacture of Gun-cotton at Waltham Abbey.—The manufacture of compressed gun-cotton has been actively

Digitized by Google

pursued at Stowmarket, and at the Government factory at Waltham Abbey, since the commencement of 1872. The following is a brief outline of the process :—

Carding the Cotton.—The clippings and other waste from cotton mills (of the description in general use for cleaning machinery), after purification from oil and fatty matters by treatment with alkali, and removal of other extraneous substances, as pieces of string and rag, are passed through a machine somewhat similar to a carding engine (Fig. 18) for the purpose of opening up the material, and then through a cutting



FIG. 18.—CARDING MACHINE FOR GUN-COTTON.

machine to reduce it to a suitable condition for ready immersion in the acid.

Drying the Cotton.—The cotton rolls thus obtained are dried in a double cylinder, called a drying tube. The cotton is placed in the central chamber D, Fig. 19, while steam circulating in the surrounding jacket J, keeps the whole tube at a high temperature. By means of a blower attached to the pipe P, a blast of air enters the outside chamber at the bottom; and heated as it is during its passage to the top, is led to the central tube and forced through the loose mass of the cotton. The latter is in this way rapidly robbed of its moisture, and when completely dried is placed in large tins and carefully covered.

Digitized by Google

After standing in these till quite cold, the cotton is weighed out in quantities of 1 lb. each, and carried by a boy to the dipping vessel.

Steeping the Cotton.—The contents of each box are separately immersed, by small quantities at a time, each pan containing a mixture of about 12 gallons, made up of three volumes of sulphuric acid, specific gravity 1·84, and one volume of the strongest nitric acid, the whole being kept cool during the action by currents of cold water, which circulate round the vessel. In this mixture the cotton is dipped, and after it has been in about three minutes, the workman lifts it on to a grating, just above the acids. Then, with a movable lever, he gently squeezes it until, roughly speaking, it retains about ten times its weight of the liquid. In this condition it is transferred to earthenware pots (Fig. 17)



FIG. 19.—DRYING CYLINDER, AND SECTION OF DRYING TUBE.



FIG. 20.—DIPPING AND PLACING THE STEEPED COTTON IN POTS.

closed with well-fitting lids, in which it remains for twenty-four hours, these pots being placed into a shallow artificial

Digitized by Google

basin, where cold water is made to circulate around them continually. The chemical change in the cotton is now complete.

Whirling out the Acid.—The large excess of acid which the cotton contains is got rid of by placing the cotton into a centrifugal hydro-extractor, as described in Figs. 15 and 16, and the waste acids discharged from these machines are collected in the waste acid tanks.

Washing the Cotton.—On leaving the centrifugal machine the gun-cotton has to be washed—an operation which requires great care, because the acids which the gun-cotton yet retains would give rise to a considerable development of heat if mixed slowly with water. At such an increased tem-



FIG. 21.—WASHING THE GUN-COTTON.

perature the gun-cotton would be decomposed, or "fired," as it is technically called. At Stowmarket an artificial cascade is made by leading a stream of water along a trough, and allowing it to fall from a height into the washing vessel, Fig. 21. The gun-cotton is thrown on the falling stream, and is immediately carried deep down into the vessel, the agitation of the water being further promoted by the workmen. In this way the cotton comes in contact with such a large quantity of water that the rise of temperature is inappreciable, and the pyroxyline becomes almost altogether free from acids.

But to perfect the washing, the pyroxyline is passed through the centrifugal hydro-extractor, and then thrown into tanks, where it is subjected to the action of water for one, two, or three weeks, and afterwards boiled in large vats by the

Digitized by Google

injection of steam; but the temperature of the boiling waters should not exceed 100° C. The soluble impurities of unstable character, produced by the action of the acid upon small quantities of resinous and fatty substances which existed in the fibre, are very effectually extracted by this treatment, and the gun-cotton, after a further rinsing, is then transferred to the beating or pulping engine, of a kind ordinarily used by paper-makers, for preparing paper pulp; it is technically termed a



FIG. 22.—SECTION OF HOLLANDER OR PULPING ENGINE.



FIG. 23.— PLAN OF HOLLANDER.

"hollander." There it is brought into a state of fine subdivision, which is necessary for the subsequent transformation into a homogeneous compressed mass. Figs. 22 and 23 represent respectively a section and plan of a half hollander.

"The chief characteristics of the hollander are: 1. Speed of revolution of the trimming knife. 2. The box of knife edges under the revolving cylinder. 3. The trough and revolving cylinder. 4. The cap or partition above the trough to prevent the mass being cast out when in motion. The trough C, C is a long oblong cistern of cast iron, stone, or wood lined with

Digitized by Google

lead. The cover rests upon a partition *x*, *x* of equal height with the outside wall. The machine is divided into two parts, the working side in which the rags are torn or shredded between the knife edges in the cylinder and those in the box, and the running side into which the shredded rags are thrown by the revolving cylinder. Under the cylinder is a massive oak block *t*, *the craw*, its concave surface comprising the fourth part of the circumference of the cylinder. The side *y* is a little and *z* much inclined. Half-way between *h*, *i* are two strong beams *l*, *m*, supporting the metal bearings in which works the axle *o*, *o* of the cylinder. From the roller Q a number of cutters run parallel to the axis. The knives are of soft steel, and in the whole hollander sometimes bronze. Beneath these a series of knives is placed, against which the rags are drawn by the cylinder. In order that by the movement of the cylinder none of the material should be thrown out a cover is provided, the dirty water thrown up falling through the sieve *u*, *u*, and flowing through the opening *g*, *g*. Clean water flows in from the top of the hollander. The washing finished, the water-pipe is shut by means of a sliding partition, each partition having an inner one to prevent the pulp passing away. The rags are poured into the top of the hollander with the requisite quantity of water. The roller revolves 100 to 150 times a minute, the knives cutting more readily in the fluid. Having passed the cylinder and the lower set of knives, the mass flows over the steep slope of the craw *z*, while the roller continues its work." In a similar manner the gun-cotton is drawn between the knives and reduced to a state of pulp. The bottom of the tub is movable, and thus the space through which the gun-cotton must pass may be contracted as the operation proceeds. The pulping completed, the contents of the hollander are run into a "poacher."

The poacher is a washing machine, similar in construction to the so-called "poaching engine" in common use at paper mills (see Fig. 24). Here the water in which the gun-cotton has been pulped is first drained off, and the pulp is very thoroughly washed by being continuously agitated together

Digitized by Google

with a large volume of water for several hours, until, in fact, samples collected at intervals satisfactorily pass the heat test for purity. In the poacher, the pulp is agitated with a large quantity of water by a wheel. A strainer at the bottom of the poacher enables the workman to draw off the water and replace it by a fresh supply, in which the gun-cotton is washed.



FIG. 24.—POACHER FOR WASHING GUN-COTTON PULP.



FIG. 25.—VAT OR MIXING MACHINE.

This final washing process secures a high degree of uniformity in the explosive power of the finished product, as 1000 lbs. of gun-cotton are washed in one operation, and the products of many hundred distinct converting operations are thus thoroughly mixed together.

The pulp is now transferred to the *vat or mixing machine*

Digitized by Google

(Fig. 25), and mixed with 2 per cent. of alkaline carbonate, when it is ready for the final operation.

Compressing the Gun-cotton.—The further processes of abstracting the water and moulding the pulp into given weights and shapes are performed in hydraulic presses of various kinds. Figs. 26 and 27 show the cylinder of the press and also the ram.

There are numerous devices employed for compressing gun-cotton, and among them are cylinders movable round a vertical



FIG. 26.—HYDRAULIC PRESS.

support, and having a closely perforated plate fixed on their bottom ends.

The cylinder being brought into the proper position, a measured quantity of the pulp is poured down a pipe. By the action of a suction pump connected with a tap, most of the water is at once drawn off through the perforated bottom of the cylinder. The latter is then turned round to the position, and the press set to work. In a very short time the gun-cotton is taken out in the form of a slab or cylinder. These are further pressed in a more powerful machine, as shown in Fig. 27, and afterwards soaked in water till they contain about 25 per cent. of that liquid.

Digitized by Google

Granulating the Gun-cotton.—Under the specification of Sir Frederick Abel, the gun-cotton is sometimes granulated by the following process :—

When the gun-cotton in the poacher has been washed sufficiently to pass the chemical tests for purity, it is placed in a centrifugal machine similar to that used for the purpose of extracting the large excess of acids after the conversion into gun-cotton. In this machine the pulp loses water till it



FIG. 27.—HYDRAULIC PRESS.

contains only about 33 per cent., and is reduced to a condition more or less fibrous. It is then taken to the granulating room, where it is first passed through sieves or perforations, which break up the mass, and to some extent determine the ultimate size of the granule. The material is then transferred to a revolving drum, like a large barrel mounted on a horizontal axis, in which it is kept revolving for about a quarter of an hour. Water is from time to time sprinkled on the granules, or the sides of the drum are moistened, to assist the hardening

Digitized by Google

action. The drum, in revolving, carries the granules partially round with it, but under the action of gravity they descend after reaching a certain point, and thus are caused to roll over one another. The speed of the drum decides, to a great extent, the rapidity of the granulating process. The speed should be just such that the material is carried by the drum sufficiently forward on the surface to be compelled to run down sharply. On the other hand, it must not be too great, as none of the granules must be carried round by the centrifugal force of the drum. On removal from this machine, the completing operation is the removal of the water either to dryness or to the extent desired in properly arranged drying chambers.

Messrs. Mackie and Faure's Granulated Gun-cotton.—This form of gun-cotton is produced by a patent which is described by the inventors as follows :—

"(1) Gun-cotton in a fibrous state, as when made from cotton waste or skeins, and without being previously reduced to a pulp or to powder, is subjected to such a pressure that it will assume permanently the form of the moulds it is pressed in, or will be made into such solid form that it can be broken into lumps.

"It is preferable that the cotton waste or skeins, or cotton fibre, in such-like fibrous condition, should first be carded on a carding engine to form it into a bat or fleece, and should then be manufactured into gun-cotton in the ordinary manner. The gun-cotton thus prepared is then either passed between powerful pressing-rollers to compress it into cakes or scales, or with a powerful hydraulic or other press the fibrous gun-cutton is compressed between indented plates to compress it into sheets offering the counterpart of such indentations, and which, by being broken up, will divide according to the lines of least resistance, and therefore form granules of premeditated size and form.

"This system can be applied to any mixture or compound of gun-cotton in a fibrous condition, and not reduced to a pulp

Digitized by Google

or powder with any other substance, such as nitre, sugar, and alkalies. By thus taking gun-cotton in a fibrous state, and at once compressing it into cakes or granules, we are enabled to manufacture cakes or granules of compressed gun-cotton at a much less cost than heretofore.

"(2) Gun-cotton reduced to an impalpable powder by being crushed between rollers or otherwise, and more or less mixed with some other materials, has been caused to granulate by the natural tendency of the material to do so, and by sifting; but when granules are so made they are generally light and deficient in compactness, and therefore, to give these granules the requisite degree of compactness, they are put in a closed vessel with a movable rod or piston, and subjected to an energetic pressure; and in order to prevent them from sticking together, they may have their surface prepared with some powder, such as pipe-clay or any other substance in powder. We prefer to employ for the purpose finely divided pipe-clay, which should be intimately mixed with the granules, so that they may all be thinly coated with it before they are placed in the compressing vessel and subjected to pressure therein. The substance, on leaving the compressing vessel, will, however, assume the appearance of a solid lump, but will easily break up into granules if put into a corning machine or treated similarly, and the granules will have a tendency to separate according to the outer surface of the former granules.

"(3) The drying of gun-cotton in a current of, or in contact with, a dessicated atmosphere is another feature of the process. The substance to be dried is put into bins upon shelves or trays, and the dessicated air or gas at the ordinary temperature, more or less heated, is introduced into the bins by pipes or channels, and by its tendency to saturate itself with the vapours either of water or of any other volatile fluid with which the substance may be mixed, the air will cause the substance to be dried.

"As to the manner in which the air is dried, chloride of calcium is placed in a chamber in which are partitions so placed that a stream of air introduced at one end of the chamber

Digitized by Google

shall be caused to travel in a zigzag course through it before passing away from the opposite end, and at the bottom of the chamber are trapped outlets by which all liquid may pass away as quickly as it is formed. The air thus dried is then caused to enter a chamber in which is a coil of steam-pipe, and is thereby slightly heated, and from thence it is conducted into a horizontal flue or channel, over the top of which are placed trays with perforated bottoms upon which the gun-cotton or other solid explosive is laid, and the dried air rising up through such perforated bottoms quickly carries off all moisture from the gun-cotton; or the dried air may pass into a chamber in which are trays with the explosive. The room ought not to be heated over 100° F.

"(4) Included in the same invention is a process for the manufacture of gunpowder from finely crushed or divided gun-cotton, gun-sawdust, gun-starch, xyloidin, pyroxylin, and other nitrogenous products of cellulose, linen, wood, or such-like, by incorporating or mixing the same with resin, shell-lac, ozokerit, collodion, glycerine, charcoal, or soot, and adding thereto nitre or saltpetre. For example, a gunpowder suitable for blasting purposes may be produced by combining from 5 to 10 parts of gun-cotton with 2 parts of resin and 1 part of saltpetre. To produce a gunpowder suitable for use where more rapid explosion is required, less resin would be used. If glycerine or ozokerit be used in the manufacture, an explosive compound of a plastic nature will be obtained, specially suitable for use for mining charges; or mining charges of a plastic nature may be obtained by incorporating oleaginous fluids or substances with the other ingredients."

Digitized by Google

CHAPTER VIII.

PROPERTIES OF GUN-COTTON.

PHYSICAL Appearance of Gun-cotton—How does Gun-cotton explode?—How to render it less sensitive—Detonation of Wet Gun-cotton—Gases produced by the Explosion of Gun-cotton—Spontaneous Decomposition—Advantages and Disadvantages of Gun-cotton in use.

IN outward appearance cotton does not change on its conversion into gun-cotton, notwithstanding that very remarkable chemical changes have taken place in its nature. In fact, gun-cotton can hardly be distinguished by outward appearance from cotton. At the most it is rather less white, it generally feels somewhat harsher to the touch, and it grates slightly in squeezing it. It is heavier than cotton. Viewed under the polariscope the threads of gun-cotton are indistinct and exhibit little or no colour, while the threads of cotton are very distinct, and exhibit the most beautiful play of colours. Gun-cotton, however, can be easily distinguished from cotton by rubbing, when the former, particularly in moderate heat, will become strongly electrified, so that the threads will stick in lumps between the fingers of a dry hand.

How does Gun-cotton explode?—Gun-cotton will explode from a blow or impact of hard bodies, by heating to a certain temperature, and particularly by ignition. If it be subjected to a blow or impact of a hard body, an explosion as a rule ensues. The explosion, however, does not extend to the whole mass, but only to the portions directly struck. The threads which are not struck fly off intact. Sir Frederick Abel found that, when an explosion was caused by the blow of

Digitized by Google

a hammer or by the fall of a weight, only a small portion of the mass was detonated, the remainder being scattered by the gases developed at the moment of explosion of that portion of the mass directly struck. This was the certain deduction from a series of experiments, most carefully made with cylinders or disks of compressed gun-cotton of equal weights and diameters subjected between polished brass plates on an anvil to the impact of a 22·7 kilograms weight, falling from a fixed height between leaders. When the weight fell from a height of 914 millimetres the gun-cotton was compressed to one-half its original length without explosion. The fall from a height of 1·828 metre produced a slight detonation by which the greater portion of the gun-cotton was scattered about. By a greater fall a somewhat larger portion was detonated, but even by the fall from the greatest attainable height of 11·883 metres, only a small portion was detonated, the remainder being scattered about.

How to render Gun-cotton less sensitive.—Gun-cotton, when saturated with a liquid or with a body which is solid at ordinary temperature, but added to the cotton in liquid form, is less susceptible of detonation than when mixed with a corresponding proportion of a solid body. The inert liquid envelopes each little portion of the gun-cotton, isolates it from the adjacent portions, and thus establishes a strong resistance to the propagation of the explosion.

The absorption by gun-cotton of 3 per cent. of water, in addition to the 2 per cent. which it contains in its normal condition, renders detonation by the ordinary agents uncertain.

Detonation of Wet Gun-cotton.—*Mr. Brown* (an assistant of Sir Frederick Abel) conceived the idea in 1874 of using *dry* gun-cotton to detonate wet compressed charges. According to his experiments gun-cotton containing as much as 17 per cent. of water is easily detonated (although not with absolute certainty) by the explosion of 6·6 grains of air-dried compressed gun-cotton when the initiating explosion

Digitized by Google

was produced by fulminate of mercury. It must be in direct contact with the dry cotton. If the amount of water be increased to 20 per cent. detonation does not surely follow the use of 31·2 grains of air-dried cotton as the primer, and if the amount be increased to 30 to 35 per cent., which is generally the maximum amount that the gun-cotton will absorb, one cannot count with certainty in the detonation when less than 112 grains of air-dried cotton are used in direct contact. Wet compressed gun-cotton will be more easily detonated when dry gun-cotton and fulminate of mercury are used, than when the fulminate alone is used. The mixture of compressed gun-cotton and nitre or potassium chlorate is in a moist state and under otherwise similar conditions as susceptible of detonation as ordinary compressed gun-cotton, and the mechanical effects produced are the same. Compressed and wet gun-cotton which has been allowed to freeze is as susceptible of detonation as the mixture of gun-cotton and crystallized salts.

By heating gun-cotton, explosion is produced accompanied with brilliant flames and a hissing sound, but without a loud report. The temperature required for the explosion depends upon the quality of the gun-cotton and upon the rapidity with which it is heated. If it be heated very gradually it will decompose at 60° C., giving off acid fumes, but as a rule it will not explode under 130° C. Nevertheless, it sometimes explodes at much lower temperatures. Explosions have taken place when it was dried to 70° to 100° on sheets of metal. It has also been exploded by air heated from 25° to 80°. By rapid heating it will explode between 136° and 180°. It explodes more quickly and at a lower temperature than gunpowder. It can therefore be burned on the latter without the powder taking fire. The following is a very interesting experiment: On a piece of paper lay some gunpowder, on the latter lay a small portion of gun-cotton, and hold the whole about a foot above the flame of a lamp. The radiating heat of the flame will be sufficient to ignite the gun-cotton, while the powder lying under it and nearer to the source of heat will remain entirely unchanged.

Digitized by Google

Under pressure combustion takes place more gradually. *In vacuo* and also in nitrogen, hydrogen, carbonic acid or carbonic oxide gas, very small quantities of gun-cotton threads, ignited by very fine platinum wire heated by electricity, burn gradually with a greenish phosphorescent light. By increasing the pressure a slightly yellowish flame appears with the greenish light, and increases in intensity with increased pressure, until finally it passes into the brilliant orange flame of quickly burned gun-cotton.

Wet compressed gun-cotton burns up quietly in the open air. If it contain 12 to 14 per cent. of water it is ignited "with much difficulty in applying a highly heated body. As it leaves the hydraulic press upon being converted from the pulped state to masses, it contains about 15 per cent. of water; in this condition it may be thrown into a fire or held in a flame without exhibiting any tendency to burn; the masses may be perforated by means of a red-hot iron or with a drilling tool, and they may with perfect safety be cut into slices by means of saws revolving with great rapidity. If placed upon a fire and allowed to remain there a feeble and transparent flame flickers over the surface of the wet gun-cotton from time to time, as the exterior becomes sufficiently dry to inflame; in this way, a piece of compressed gun-cotton will burn away very gradually indeed."

A rifle bullet shot through it will not cause explosion. "If it be fired, however, by a strongly charged percussion cap, it will explode with great violence."

Gases produced by the explosion of Gun-cotton.—The combustion products *in vacuo* are carbonic oxide, steam and nitrogen; in the open air the same gases with a nitro-acid and cyanogen.

One pound of gun-cotton gives in combustion about 22,165 cu. in. of gas and produces the effect of from 4 to 6 pounds of gunpowder. *Drinker* says: "As to the gases evolved by combustion, it is said that from one gram (0·035 oz. avoir.) of gun-cotton there are evolved at combustion *in vacuo* in round

Digitized by Google

numbers 588 cu. cm. (35·87 cu. in.) of gas, measured according to Hecker and Schmidt at a temperature of 32° F. (0° C.) and a barometrical height of 760 mm. (29,922 inches). Károlyi found at a temperature of 32° F. (0° C.) and a barometrical height of one metre (3281 ft.) (hence under high pressure) 574 cu. cm. (35,014 cu. in.) of gas.

"Blondran obtained from one gram (0·035 oz. avoir.) of gun-cotton saturated with ammonia 955 cu. cm. (58·25 cu. in.) of gas, and other statements go as far up as 1200 cu. cm. (73·2 cu. in.).

"The temperature of combustion of the gases amounts in round numbers to 8132° F. (4500° C.)."

The *chemical constituents of the gases* evolved on combustion are, according to *Károlyi* (in percentage of volume):—

	In vacuo.	Under high pressure.
Carbonic oxide . . .	28·55	28·95
Carbonic acid. . . .	19·11	20·82
Fire-damp	11·17	7·24
Nitrous oxide . . .	8·83	..
Nitrogen	8·56	12·67
Steam	21·93	25·34
Hydrogen	..	3·16
Carbon in excess . .	1·85	1·82

If the combustion take place under high pressure, the nitrous oxide entirely disappears from among the explosion gases, and in its place is formed a greater proportion of carbonic oxide, carbonic acid, steam and nitrogen.

Trautzl says that, "assuming 4500° C. (8132° F.) as the temperature of gases of combustion of gun-cotton, the theoretical maximum pressure in atmospheres is 15,300, and the theoretical power in kilograms equals 200,000."

The explosion gases are, in consequence of the large proportions of carbonic oxide and fire-damp, easily ignited, and burn with a blue flame. In consequence of the large proportions of carbonic acid and carbonic oxide, they are poisonous, and assail the eyes quite strongly.

Digitized by Google

Spontaneous decomposition begins with the evolution of gases (for example, gas of a nitro-acid); the gun-cotton gradually diminishes considerably in volume; and the residue contains small portions of a nitrogenous substance, traces of formic acid and acetic acid, also sugar, oxalic acid, and so-called gums. This decomposition appears to take place only when the cotton has not been sufficiently freed from fats, and the gun-cotton has not been completely washed. Lenk's gun-cotton, which, as is known, was produced in a high degree of cleanliness, was, according to Sir Frederick Abel, absolutely durable. Sunlight, although acting for a long time on Abel's gun-cotton, did not affect it. It is also not affected by quick heating to 90° C. Sir Frederick Abel heated boxes filled with gun-cotton for six minutes to 50° C., and no decomposition took place. He claims that this result settled the great and vital question of the durability of pure gun-cotton.

To increase its durability it has sometimes been impregnated with a soluble silicate, or with paraffin.

Advantages and Disadvantages in use.—The chief advantage of gun-cotton is its comparative insensibility to shocks, in consequence of which it is safe from explosion by hostile bullets or sympathetic explosion; but nitro-gelatine is also insensible to water, hostile shots, or sympathetic explosion, besides being very much stronger than gun-cotton.

The failures to introduce pure gun-cotton as a substitute for gunpowder in small-arms have already been alluded to (see page 55). But when diluted and mixed with certain other ingredients, its action is so modified that it can be used as an explosive in fire-arms. Gun-cotton is the agent most extensively used for all kinds of military engineering and submarine operations in Great Britain, being especially manufactured by the Government for that purpose. But it is not now so extensively used by civilians as formerly. Frost has no effect on dry gun-cotton, but causes a mechanical disintegration of the wet compressed variety.

Digitized by Google

Gun-cotton as manufactured by the old system was not serviceable for guns and small-arms. The experiments made in various European countries soon after the discovery of gun-cotton showed that infantry guns which withstood the effects of 3000 shots with powder became unserviceable on an average after 500 shots with about equally effective charges of gun-cotton. Gun barrels which permitted a charge of 27·5 grams of powder were burst by a charge of 7 to 8 grams of gun-cotton.

Another disadvantage was that the manufacture of gun-cotton cartridges was very slow, because they could not, like gunpowder, be *measured*, but had to be *weighed*. But a greater disadvantage is its very rapid explosion. It belongs to the very disruptive class of explosives. Powder possesses a certain pliability, inasmuch as its ingredients may be so proportioned as to regulate the rate of combustion, and hence its fitness for ballistic work. The explosive gases of gun-cotton are instantaneously developed, they occupy instantaneously a very large space, but a *continuous* force is not exerted. The stiffness, too, of gun-cotton cannot well be diminished by artificial means.

In order to overcome the inconvenience attending this great disruptive force, attempts were made to regulate the velocity of combustion. The gun-cotton was carded together with ordinary cotton; it was worked up with paper material in the hollander; metal cartridges were used, the front end, which was to be ignited first, containing mining powder, the explosion of which was to overcome the inertia of the ball; in the other end was the gun-cotton, the explosive gases of which were to furnish the projectile force. For the Austrian batteries Von Lenk employed gun-cotton in the following manner:—

A fixed weight of spun gun-cotton was wound as a flat jacket around a hollow wooden cone or cylinder. The rear end was ignited. The wooden body prevented a rapid burning up in the first instant of time, since the ignition could be propagated only along the periphery. As soon as the tension of the gas reached a certain height, the wooden cylinders were burst, and the combustion was complete.

Digitized by Google

The cartridge made at Stowmarket contains an envelope of strongly compressed gun-cotton, which is covered over with a thin waterproof layer of gutta-percha. For blasting purposes the pulp is pressed into forms and pricked with punches, to produce cavities to increase the velocity of ignition.

Gen. Abbot experimented, at Willett's Point, with Abel's compressed gun-cotton, dry, containing also 25 per cent. of water, and granulated gun-cotton wetted to a like extent, all made at Stowmarket. He found no marked difference in strength between these varieties and conditions of gun-cotton, although the addition of water seemed to cause a small loss of about 2 per cent.; and that gun-cotton in the wet state was safe, but its disk or slab form inconvenient, and when granulated it was bulky.

In blasting operations, gun-cotton acts with considerably greater effect in hard than in soft or well-fissured rock. *Schoen* states that in soft rock it exhibits twice, in hard rock five to six times, the blasting effect of gunpowder.

It is insoluble in and unaffected by water; and as it can be fired wet there is no need of ever drying it. For firing it a "primer" is used, which consists of a cake of dry gun-cotton, to which is attached a fulminate fuze. This primer must be enclosed in a waterproof bag or box. Large charges of wet gun-cotton can be exploded in this way. It is not sensitive to friction. Dry gun-cotton is very hygroscopic. Compressed gun-cotton is stored in a wet state, but should not be exposed to a temperature that will freeze the water in the cakes. It is made into disks of various dimensions, or it may be pressed into slabs or blocks which may be sawn, cut, or drilled as desired. In the form of disks it stows badly, and it is desirable that a charge to be exploded should be as solid as possible.

Sir Frederick Abel's caution to keep gun-cotton in a wet condition is worthy of special attention, since in that condition it may be kept for years without decomposing, and is perfectly safe to handle.

Digitized by Google

CHAPTER IX.

VARIETIES OF GUN-COTTON AND OTHER NITRO-COMPOUNDS.

PYROXYLINE—Schultze's Powder—Lannoy's White Powder—Uchatius' White Powder—Nitric Acid and Sugar—Nitro-Mannite—E. C. Powders—Johnson's Powders—Punshon's Gun-cotton—Totten's Gunpowder—Tonite—Professor Attfield's Experiments with Tonite—General Abbot on Tonite—California Gun-cotton.

Pyroxyline.—This term may be used to designate all nitro-compounds resulting from the action of concentrated nitric acid on cellulose or wood fibre—as, for instance, cotton, paper, sawdust, straw, &c. Sometimes it is used to designate solely gun-cotton, and in that case *Collodion-cotton* (of which an account will be found in the next chapter) is called *Soluble Pyroxyline.*

In the present chapter will be found particulars of various substances sometimes classed under this term.

Schultze's Gunpowder.—This is practically a nitrated, purified, and pulped wood-fibre, formed into grains. It is now manufactured by the Schultze Gunpowder Company, who appear to have overcome the difficulties which beset the inventor in the early stages of its production. Their process consists in macerating soft timber of clean growth, which is chemically treated until all resinous and fatty matter is extracted, and pure, finely-divided cellulose remains. After drying, this is treated with acids, and thoroughly purified till it stands Sir F. Abel's heat test. The nitro-compound is then finely ground and waterproofed; the proper density is given to the particles, and it is finally dried and sifted.

Digitized by Google

The properties claimed for the powder are, that it gives less pressure on the powder chamber than ordinary gunpowder; that it is smokeless, its explosion-gases being very light; that, weight for weight, it has more than twice the *propelling* power of black powder, and that it leaves less residue in the gun-barrel; also, the residue being alkaline and dry, no corrosion takes place. Quickness of ignition and slowness of combustion are also claimed for it. This means that the primer ignites the powder readily, and when once ignited it burns slowly, which reduces the strain on the powder chamber.

Lannoy's White Powder.—Wood or sawdust is nitrated by treatment with strong nitric acid, and twenty-two parts of the resulting nitro-cellulose are mixed with sixty-five parts of sodium nitrate and thirteen parts of sulphur.

It is claimed that this powder rends rock without great shattering, and hence with but few flying fragments. It is difficult of ignition and burns slowly. The experiments made at Altenberg, near Aachen, did not prove favourable. It is very costly, and leaves on explosion a strong and stinking smoke.

Uchatius' White Powder.—Starch is of a composition similar to that of cellulose, and can also, by treatment with strong nitric acid, be converted into an explosive nitro-compound called *Nitro-starch.* Uchatius' powder consists of this latter substance. For its production he dissolved one part by weight of potato-starch in eight parts of fuming nitric acid, care being taken to keep the mixture cool. The thick fluid was poured in thin streams into sixteen parts of concentrated sulphuric acid, constantly stirred. The resulting jelly remained standing for twelve hours, and was then repeatedly washed alternately with pure water and a soda solution. Finally the white powder was dried by a heat of 50° to 60° C. It is strongly hygroscopic, and is too strong and rending in its effects for use in fire-arms.

Nitro-compounds also result from the action of nitric acid on the various kinds of sugar. Thus there is known a

Digitized by Google

Nitro-raw-sugar, with an alcoholic solution of which it was proposed to coat ordinary gunpowder in order to render it impervious to water, and also to increase its explosiveness. A *Nitro-milk-sugar* is also known as *Nitro-lactus.*

Nitro-mannite is obtained from the action of nitro-suphuric acid on the species of sugar of the mannites found widely distributed throughout the vegetable kingdom, but principally found in the manna ash.

The manna sugar is dissolved in four parts of nitric acid (kept cool) and English sulphuric acid is added until no further separation takes place. The separated product is well washed and dried by a heat of 40° C.

Nitro-mannite in a pure state exists in snow-white, needle-shaped crystals, which are soluble in hot alcohol and in ether. It is an extremely explosive substance, approaching in this respect fulminate of mercury. It is detonated by a moderate blow. Nevertheless it is not so sensitive to heat or friction as fulminate of mercury. It is easily ignited, but is not very dangerous to handle. It has been proposed as the safest filling for percussion caps. It is said to decompose on long storage.

E. C. Powders are known also as *Rifle Gun-cotton.* They are divided into two divisions, *Sporting Powder* coloured with aurine, free from mineral acid, dissolved in ether, alcohol, and benzoline; and *Rifle Powder*, coloured with picric acid (free from mineral acid) dissolved in the same solvent. They are small round granules coloured respectively orange and yellow, and consist essentially of diluted nitrated gun-cotton.*

Two samples gave :—

Nitro-cellulose soluble	27·95	21·79
,, ,, unsoluble	28·35	25·58
Cellulose (unconverted)	3·15	4·17
Nitrates of potassium and barium	37·80	38·32
Matters soluble in benzole	0·60	1·95
,, ,, alcohol	2·15	6·32
Moisture	—	1·87

* 'Dictionary of Explosives.'

Digitized by Google

Johnson's Powders.—In these powders dinitro-cellulose or lower forms of nitro-cellulose are employed, impregnated with barium or potassium nitrates and incorporated with charcoal or other carbonaceous material. Two examples given in the specification consist of the following :—

	For military arms.	For sporting arms.
Nitro-cellulose	50 parts	50 parts.
Potassium nitrate	40 ,,	22 ,,
Barium nitrate	—	25 ,,
Torrefied starch or lamp-black	10 ,,	3 ,,

The powders are formed into grains, or blocks, and impregnated with a solution of camphor and phenol, or camphor alone, in a suitable volatile solvent, in the proportion of one part of camphor (or camphor and phenol) in five parts of solvent to ten parts of the powder. The solvent is driven off at a gentle heat, and the camphor is subsequently driven off at a temperature not exceeding 100° C.

It is claimed that by this method powders can be produced of any required degree of hardness and density, thereby regulating the energy of action of the explosive, and it is stated that "these results are obtained not by the presence of camphor in large or small quantities in the finished explosive, but by a remarkable gelatinizing and perhaps some other action exerted by the camphor upon the nitro-cellulose when these are heated together at varying temperatures up to 100° C., whereby the hardness and density of the explosive may be regulated at will by the proportion of camphor used."

Punshon's Gun-cotton was coated, covered, or incorporated with sugar, either raw or refined, in such a manner as to separate or isolate the particles or fibres of the gun-cotton and thus regulate the rapidity of the combustion. He also added nitre.

Totten's Gunpowder consists of grains, the kernel of which is pure gun-cotton. It is lighter than ordinary cannon powder, and is four and a half times more effective. The

Digitized by Google

diameter of the kernel is thirteen millimetres, and the diameter of the entire grain is twenty-six millimetres.

Tonite.—Under this name is manufactured at Faversham, by the Cotton Powder Company, Limited, and at San Francisco, by the Tonite Powder Company, an explosive, into the composition of which gun-cotton enters very largely.

Tonite consists of finely divided or macerated gun-cotton, compounded with about the same weight of nitrate of baryta. At Faversham two qualities are made, known in the market as White No. 1 and Black No. 2. The White is composed of about 50 per cent. of gun-cotton and 50 per cent. of nitrate of baryta, while the Black has a larger proportion of baryta with a small percentage of charcoal.

The white is used for blasting hard stone, such as quartz, and where the object is to smash up as much as possible locally. It is essentially a "shattering" compound to be employed where a great local disruptive action is required.

The black is for use in softer stone, such as limestone, in quarries, where large blocks of building material are extracted. The explosion of this compound is therefore slower, and does *not* produce the sphere of pulverisation, only a middling-sized sphere of rupture, but a proportionately large sphere of fracture, therefore its application for quarrying stone is advantageous.

For the same reason it is used in torpedoes for submarine blasting in the removal of obstacles to navigation, such as destroying sunken wrecks, where the object to be gained is to shake and shatter the frame of a vessel to pieces, and therefore the area of disruption must also necessarily be a large one, so as to avoid multiplicity of charges. If the No. 1 white were to be employed for such works, its explosion would blow a big hole through the side of the vessel without breaking up the frame. But when it is a question of use for military submarine purposes, be it offensive or defensive, as in torpedoes, the No. 1 white has to be used, as it is quite sufficient to blow a big hole through the enemy's vessel (without shaking the frame),

Digitized by Google

and to sink her, as the vessel can be raised afterwards and made use of again.

The No. 2 black being not so sensitive to detonation, the white tonite is used as a primer to give the initial detonation. In loading a bore-hole with the black, first insert the cartridges in the bottom, and the white is placed on top of the charge with the cap and fuze inserted. By using good caps or detonators, or strong electric exploders, no miss-fire need be apprehended.

The gun-cotton which is used in the manufacture of tonite is mainly common cotton waste steeped in mixed nitric and sulphuric acid; and on the excess of acids being forced out by hydro-extractors, it is left for some time for digestion, in stone jars, as already described elsewhere under the heading of manufacture of gun-cotton. Necessarily, while in the moist state, the fibres are macerated or disintegrated between crushing rollers. This perfectly purified macerated gun-cotton is intimately mixed up between edge runners with about the same weight of nitrate of baryta. This compound is then compressed into candle-shaped cartridges, formed with a recess at one end for the insertion of a fulminate of mercury detonator, and covered with paraffined paper.

Among the special advantages claimed for tonite are, that if it is wetted by accident, it can be dried in the hot sun or a warm atmosphere. The use of nitrate of baryta, a salt containing a great amount of oxygen in a very small volume, makes tonite a compound which readily explodes by the use of a proper detonator, while its great density makes it slow to the influence of ordinary combustion. Its great density causes it to burn slowly if set fire to, and so slowly that all danger from a too violent generation of gases is obviated. While, therefore, the railways of England refuse to carry dynamite, they regularly take tonite on the same footing as gunpowder. The tonite cartridges are generally waterproofed. The density is such that it takes up the same space as dynamite, and two-thirds of gun-cotton. It is also ready and available at any climatic temperature. It can be employed in wet holes, and

Digitized by Google

can be tamped with water; but as all detonators are sensitive to moisture, they should be protected after insertion in the cartridge by tallow. The better the tamping the greater its effect.

Owing to the large proportion of the oxidising salt present in this compound, its detonation is perfect, and this accounts for the absence of noxious gases when it is used in close drifts and workings, and commends it for underground workings with bad ventilation.

The following report gives the results of experiments made with tonite by *Professor Attfield*, as a safety test:—

"1. A mass of iron, weighing half a ton, was let fall from a height of 15 feet on to a box containing 10 lbs. of tonite. It did not ignite the powder.

"2. An unusually well-made powder barrel, strongly hooped and headed, containing 30 lbs. of tonite in the form of cartridges of various sizes, was placed over some faggots saturated with tar, and a large bonfire kindled. In four minutes the cartridges ignited, and merely burned quietly for some 30 or 40 seconds. Every cartridge was entirely consumed without any explosion whatever.

"3. A box holding 10 lbs. of tonite was next fired into from a rifle, at a distance of about 20 yards. The bullet ignited the powder, which burned rapidly but quietly away without explosion.

"4. A cartridge was placed in an open box containing 2 lbs. of common gunpowder, and the latter fired by a fuze. The cartridge was blown some yards, but not exploded. The same cartridge was afterwards fired by the usual means.

"5. Strong sparks of electricity were next passed through some of the tonite without effect.

"6. Many blows of an iron hammer on an iron anvil failed to ignite portions of the powder, and when ignition was at last effected the adjacent portions of powder were merely blown on one side without being exploded.

"7. Concentrated acids (oil of vitriol and fuming nitric acid) were both successively and together poured on to portions of the powder without ignition.

Digitized by Google

"8. Lastly, to show the power of this patent cotton powder, when intentionally exploded by detonation, a 12-in. balk of timber was shattered by four small cartridges; a fountain of water 80 or 100 feet high was thrown up by the explosion of a floating box of the powder; and a hole in the marshes, 8 feet across and 4 feet deep, was instantly produced on exploding 1 lb. of the powder."

In a report made to the United States Government by *General Abbot* on the tonite manufactured by the Tonite Powder Company, he makes the following observations:—

"The standard tonite made by this company consists of 52·5 parts of gun-cotton and 47·5 parts of nitrate of baryta; but for special purposes and by request a part of the latter is sometimes replaced by potassium or sodium nitrate.

"At Willett's Point two varieties were received—one dry in compacted cartridges, and the other damp in bulk.

"The dry cartridges were $1\frac{1}{4}$, $1\frac{1}{2}$, $1\frac{3}{8}$, and $1\frac{3}{4}$ inch in diameter, and weighed from 3 to 12 oz. each. The smaller sizes were 3 in. long, and the largest 6 in. They were of two kinds, 'solids' and 'primers.' Both were encased in a paper wrapping compressed to a specific gravity of about 1·28, and coated with paraffin. The 'solids' were simple cylinders exposing plane ends; the 'primers' were similar in form, but they had a small hole at the top for receiving a fulminating fuze—for securing which the wrapping was extended into a short neck. The cartridges were such as are sold to miners.

"The damp lot was in the condition in which it is taken from the incorporating mill, and in which it goes to the press-room. In that condition it is supposed to contain 18 per cent. of moisture. It is slow to burn and difficult to detonate, and a compressed primer must be used with it in close contact. In this condition it is not sold at present to the company's customers. It would appear that the strength of the explosive is not reduced by moisture.

"The relative efficiency in a horizontal plane of tonite, as shown by Abbot's experiments, is compared to dynamite No. 1 for dry compressed variety as 0·81 to 1, and for the

Digitized by Google

other as 0·85 to 1, or a mean of 0·83 to 1. The substitution of a portion of nitrate of baryta tends rather to reduce than to increase the normal intensity of action of gun-cotton, pound for pound, when fired under water, but this is not the case when fired in the open air or under confinement in rock."

The Home Office has lately granted a licence for a *Tonite*, or *Cotton Powder No.* 3, and its manufacture has been commenced by the Cotton Powder Company. Its composition is as follows:—

Gun-cotton.
Nitrate of potash.
Meta-di-nitro-benzole.

It is of a yellowish colour, and rather slower in its explosive action than tonite No. 1, and appears well adapted to blasting coal.

California Gun-cotton.—The Tonite Powder Company of San Francisco manufacture gun-cotton by a process which appears from its circulars to be essentially that of Sir Frederick Abel—omitting the compression into cartridges. It was delivered to General Abbot damp in the state of loose powder, which when dry became a fine dust.

It is claimed that the average product contains about 93 per cent. of insoluble nitro-cellulose and 7 per cent. of soluble gun-cotton, and when shipped contains about 24 per cent. of moisture. *Abbot* states that it may be confidently assumed that the gun-cotton made by the company is not inferior in explosive intensity of action to the best English manufacture.

Digitized by Google

CHAPTER X.

COLLODION-COTTON.

ITS importance in Practical Use—Processes of Manufacture—Compounds of Cellulose—Celluloid—Tribouillet and Besaueile's Process—Proportions in which Cellulose is found in Natural Products.

COLLODION-COTTON is a variety of nitrated cotton which has attained greater importance than gun-cotton itself through its diversified employment—for instance, in photography, for the preparation of the exposed plate; in blasting, for the production of explosive gelatine from nitro-glycerine; in surgery, for uniting the edges of wounds; and in the manufacture of "fancy goods," for the production of *Celluloid.*

It is really different from gun-cotton in its chemical nature, although the same raw materials serve for the production of both. Gun-cotton is extremely explosive, while collodion-cotton is very slightly so; the former is insoluble in alcoholic ether, while the latter is soluble in that menstruum.

Ménard and Flores Domonte were the first to obtain a gun-cotton soluble in alcoholic ether.

Béchamp investigated it, and found it to be dinitro-cellulose.

	Found.	Calculated.
Carbon	28·22	28·57
Hydrogen	3·57	3·17
Oxygen	57·43	57·15
Nitrogen	10·78	11·11

Digitized by Google

In 1847 there was imported into Germany from America a solution which bore the name of *Collodion*, and which performed excellent service in surgery.

It was soon found that not all gun-cotton was suitable for the manufacture of collodion, and that the most easily explosible was the most insoluble in alcoholic ether. Since the strongest nitric acid produced the strongest gun-cotton, it was concluded and shown that a cotton suitable for collodion manufacture was to be obtained by employing a less concentrated acid. It was also obtained by using potassium nitrate and sulphuric acid instead of the two acids, since in the former case the nitric acid was gradually evolved from the nitrate, and the action in the cotton was less energetic.

In 1851 *Archer and Fry* discovered their collodion process.

Manufacture of Collodion-cotton.—The following are brief descriptions of the principal processes:—

According to *Dawson*, particular stress being laid upon the quality of the cotton, the long-fibred varieties, such as Sea Island and Egyptian, are to be preferred.

According to *Mann*, good collodion-cotton is obtained in the following manner:—

Pour 31 parts of sulphuric acid of 1·83 sp. gr. over 20 parts of powdered potassium nitrate, stir until the nitre is dissolved, and after it has cooled to below 50° C. mix in 1 part of cotton; work the whole well through, cover the vessel with a plate, and let the mixture stand at a temperature of about 30° for about 24 hours; then wash the preparation with water; finally wash with warm water to remove all sulphate of potassa and dry. Many experiments conducted on a large scale have shown that the soluble collodion-cotton is formed in from 5 to 7 minutes, but that 5 to 6 days' action of the acid solution in the cotton is productive of good, as long as the temperature does not exceed 30° C.

According to *F. Luchs*, one steeps 1 kilogram of cotton in a solution of 20 kilograms of sulphuric acid and 9 kilograms of powdered potassium nitrate; lets it lie therein until a sample

Digitized by Google

of the cotton taken out, washed with water, pressed, wetted with alcohol and again pressed, is easily and entirely dissolved in a mixture of 2 parts of ether and 1 part of alcohol. Then the preparation is thoroughly washed with water, pressed between linen cloths, alcohol poured over it until the yellow colour disappears, and again pressed for 24 hours. In summer the solution of sulphuric acid and nitre remains standing for some ten minutes before the cotton is steeped in it; in winter it is first heated slightly in order to prevent the separation of potassium sulphate. Instead of the salt, nitric acid may be used, provided the two acids be not too strong. Suitable proportions are 89 parts of nitric acid of 1·424 sp. gr., and 104 parts of sulphuric acid of 1·833 sp. gr.

Another recipe is as follows: 13 parts of sulphuric acid of 1·632 sp. gr. and 12 parts of nitric acid of from 1·512 to 1·518 sp. gr. are mixed and cooled to 5° C. In this mixture is steeped 1 part of cotton, care being taken that the temperature does not rise above 8°. After 24 hours' steeping the cotton is removed, thoroughly washed with water and dried.

Hager gives the following: Clean carded cotton is washed with a 3 to 4 per cent. solution of carbonate of soda and distilled water and dried. By simply dipping it into nitric acid of 1·4 sp. gr. it is transformed into colloxyline (collodion-cotton). Such an acid is not always to be obtained, and therefore its place is supplied by a mixture of dilute nitric acid and concentrated sulphuric acid or by a mixture of potassium nitrate and concentrated sulphuric acid. The time required for the change of cotton into colloxyline depends upon the strength of the nitric acid. The more concentrated it is, the quicker is the transformation accomplished. The colloxyline once formed, the same acid has no effect upon it. The temperature of the acid mixture must be lowered to a medium degree before dipping the cotton. A temperature of 30° C. is without any perceptible influence in the formation, as well as upon the gain in weight of the colloxyline.

At higher degrees other compounds of cellulose are formed, which may be enumerated as follows:—

Digitized by Google

1. *Pentanitro-cellulose.*—This is produced by the treatment of cotton with strong concentrated acid mixtures at low temperatures, and increase of the percentage of sulphuric acid assists in its production. The pentanitro-cellulose is never perfectly pure when produced in this manner, but contains some hexanitro-cellulose (gun-cotton) or tetranitro-cellulose; the former in case the acids were too concentrated, and the latter in case the acids were too dilute.

Pure pentanitro-cellulose can be obtained if collodion-cotton is dissolved in warm nitric acid and the clear solution is precipitated by means of a surplus of sulphuric acid; for this purpose, the collodion-cotton is put into nitric acid of a temperature of 40° to 60° C. and 1·40 sp. gr. till the solution takes a strong yellow colour, which is the case after heating the acid about one hour. After cooling the vessel in the air, it is introduced into a refrigerator surrounded with ice, and is then passed through an asbestos filter. The filtrate is cooled on ice again and four times its volume of concentrated sulphuric acid of 1·80 sp. gr., also cooled previously on ice, is added to it. The vessel should always remain in the refrigerator.

After the separation of the pentanitro-cellulose, the liquid is poured into a large volume of water, and the collodion-cotton is collected afterwards on a filter; for the further purification of the collodion-cotton, it is dissolved in a mixture of alcohol and ether, from which the same is separated by adding water.

2. *Tetranitro-cellulose* is produced by the treatment of cotton with a mixture of concentrated sulphuric acid and not too concentrated nitric acid, at a moderately high temperature. A mixture of one volume sulphuric acid of 1·845 sp. gr. and one volume nitric acid of 1·38 sp. gr. at 65° C., when acting on the cotton from 5 to 10 minutes.

3. *Trinitro-cellulose*, or rather a combination of tri- and tetranitro-cellulose, is obtained by the treatment of cotton with a mixture of sulphuric acid, and not too concentrated a nitric acid at a sufficient temperature; for instance, by taking a mixture of five parts of sulphuric acid of 1·845 sp. gr. and four volumes nitric acid of 1·38 sp. gr. at 65° C., and by letting it

Digitized by Google

act on the cotton from 5 to 10 minutes; or if cotton is acted upon during 15 minutes at a temperature of 80° Celsius with a mixture of equal volumes of sulphuric acid of 1·845 sp. gr. and nitric acid of 1·40 sp. gr.

4. *Dinitro-cellulose* is produced by the action of very dilute and hot nitric sulphuric acid on cellulose, and also by the action of potash or ammonium on ordinary collodion-cotton (on tetranitro-cellulose).

In this last manner a dinitro-cellulose is obtained, if 2 to 4 grammes of collodion-cotton are dissolved in 100 cubic centimetres of a mixture of ether and alcohol, and an alcoholic solution of potash added in excess. The collodion becomes very fluid and of a brown-yellow colour. After one or two hours it is diluted with water, and the free alkali neutralised with sulphuric acid.

The dinitro-cellulose collects on the surface of the liquid as a white, flocculent precipitant, which is filtered, washed and dried. The dinitro-cellulose is a yellow-coloured, gum-like mass.

From what has been said, it is evident that in the preparation of collodion-cotton a dilute nitric acid is employed, and that the nitrating has to be carried on at an elevated temperature, from 50° to 70° C.

The solubility of collodion-cotton varies with the quality. A good product will dissolve in 7 to 8 parts of ether to which 1 part of alcohol has been added. The fluid so obtained has a syrupy consistency.

Celluloid.—The pyroxylines have been largely applied of late years in the production of celluloid from which (as intimated above) are made various fanciful imitations of ivory, horn, corals, malachites, *lapis lazuli*, amber, and the like. To enumerate, indeed, all the wares produced by it would furnish a very long list of *articles de luxe*.

Tribouillet and Besaueile's Process.—Messrs. V. Tribouillet and L. Auguste de Besaueile, of Paris, have intro-

Digitized by Google

duced an improved method for the manufacture and treatment of pyroxyline, and for the production of a solid compound therefrom in association with camphor and like substances.

For the production of pyroxyline the raw materials employed are paper and rags of cotton, linen, and hemp fabrics thoroughly cleaned, and especially free from fatty matter; certain white woods, stalks of fibrous plants, such as esparto, which consist chiefly of cellulose, and contain few incrusting ingredients. The cellulose material is thoroughly dried in a stove at a temperature of 212° Fahr.; then disintegrated and bruised in a



FIG. 28.—Section.



FIG. 29.—Plan.

NITRATING BASIN.

mill or other suitable apparatus, after which it is kept free from damp, and finally transformed into pyroxyle by means of the following apparatus :—

There are required three basins A, a vertical section of one of which is shown at Fig. 28 of the accompanying drawings, and a plan at Fig. 29. Each of the basins may be made of one or more plates of glass, or plate enamelled with a glaze containing little alkali or lead to prevent it from being attacked by powerful acids. They might also be made of ceramic ware, or of thin cast-iron enamelled or not. Each basin rests on a lower basin made of wood or metal, through which circulates a gentle stream of water to the bottom of the basin A. Each basin is enclosed by a glazed cover V to prevent the weakening of the acids by access of damp air, and to protect the workmen from

Digitized by Google

the fumes. This cover is surmounted by a hopper T closed at its bottom by a valve *s*, and it has a lateral orifice *c* opening like a window, and two circular orifices *o*, to which are attached sleeve tubes *m* of caoutchouc or gutta-percha, by which the arms of workmen can be inserted to agitate the contents. Two of the basins serve for treatment with acid, and the third for washing with pure water.



FIG. 30.—Section.

There are also required three cylindrical vessels, one of which is shown in vertical section and sectional plan at Figs. 30 and 31. The internal diameter is the same throughout, but the external diameter increases downwards. These vessels are made of cast-iron enamelled both inside and outside, and are perforated, and especially at the lower parts, with numerous small holes, permitting issue of liquid when the contents are subjected to pressure. The pressing piston P is of cast-iron enamelled, or of ceramic ware or granite provided with a rod *t*.



FIG. 31.—Plan. CYLINDRICAL PRESS.

The material pressed in the cylinder is taken out by a door E extending half round the circumference, and about three-fifths of the height. This door is securely bolted to resist pressure. For each cylinder is required a screw press of any known kind. They act on the pistons of the vessels D, which are placed on a stage for the extraction of liquid from the material treated. Two of the basins of the cylinders and of the presses are employed for treatment of the cellulose with acids; the third of each for preliminary washing with water.

For the succeeding washings wooden vessels are employed, F, shown in vertical section at Fig. 32. The bottom only is perforated with small holes, and covered with fabric G of cloth, felt, or the like, which acts as a filter retaining the pyroxyle. Under the filter is placed a receiver H of wood to receive the

Digitized by Google

liquid, which has passed through the pyroxyle. The size and number of the washing vessels and receivers depend on the extent of the manufacture. The washing vessels may be arranged in stages, so that the liquid from each receiver may flow by gravity through the successive masses of pyroxyle. The washing vessels may in such case be of less height, as shown in Fig. 33, and may have unequal wheels, so that they may be placed on an incline, and run therefrom when the washing is completed.



FIG. 32.—FILTER.

In conducting the manufacturing operations, the acids employed are contained in close vessels placed at a higher level than the basins, so that their contents may flow into the latter by gravity. The acid vessels may be of enamelled iron, or of ceramic ware, or thin granite. The acid liquid consists of 3 parts sulphuric acid at 66° to 2 parts of the concentrated nitric acid of commerce. In the



FIG. 33.—WASHING VESSELS.

mixture is dissolved nitrous gas, which renders the pyroxyle more soluble.

Fig. 34 is a general plan of the arrangement of a pyroxyline factory. The acid mixture cooled to 45° to 55° Fahr.

Digitized by Google

is introduced into the second basin A^2 to a depth of an inch or more. Into the first basin A^1 is introduced a somewhat larger quantity of acid that has already been used, and in this is immersed the dry divided cellulose introduced by the hopper T, Fig. 28, in such quantity as the liquid will moisten. An operator then passing his arm into one of the sleeve tubes *m*, violently stirs the mass for 10 to 15 minutes, after which the whole contents are placed in one of the cylinders D^1; he then introduces the piston P, and puts the press X^1 in action. The liquid pressed out is received in a special reservoir. The press is then unscrewed, the piston is removed, and the pressed cake is taken out by the side door and plunged in the concentrated acid in A^2. A sort of trowel worked by the hands, inserted at the sleeve tubes, breaks up the cake. Stirring is



FIG. 34.—PLAN OF FACTORY.

continued until the cellulose is quite dissolved, the mass is discharged into the second cylinder D^2, and subjected to a considerably greater pressure than in the first cylinder. The acid liquids pressed out are charged into the first basin A^1 to act in the first place on the cellulose. The cake of pyroxyle remains impregnated with about one-third of the acid employed.

Acid may be economised by employing a bath of that which has previously served, raising its temperature to about 50° Fahr., but the material must be kept for several hours in this bath. The temperature and the time of immersion may be reduced by adding to the bath that has served about one-third of its weight of a mixture of nitric and sulphuric acids, or sulphuric acid alone, or sulphate or bisulphate of soda, or any other sulphate soluble in water, adding it quite dry in powder. After its transformation into pyroxyle, the material is pressed as

Digitized by Google

already described. The washing of the pyroxyline is intended to clear the nitrated cellulose from the acids which would destroy it and render it spontaneously combustible, and at the same time to collect those acids which if run to waste would be noxious. The first washing of the cakes charged with concentrated acid is effected in a basin Z, Fig. 34, like those employed for treating the cellulose; and it is then pressed in the cylinder D^3. For the second washing the cake is divided in a vat Q of wood, containing acidulated water, then the whole is charged into the first of the wooden filters F^1 mentioned above. The washing then proceeds methodically, that is to say, the first becomes the second F^2, then the third F^3, the first receiving the washing liquid from the second, the second from the third, and the last receiving pure water. The washing might, if required, be rendered more complete by employing three or four basins with a like number of presses.

Finally the material is washed in water containing a very small proportion of carbonate of soda or ammonia, or rather silicate of soda; and then with water only, the greater part of the moisture being then removed from the pyroxyle by means of a centrifugal machine or strong pressure. The pyroxyline is kept for further use immersed in water. The acids which cannot further serve for treating the cellulose may be employed for various purposes, particularly for the manufacture of sulphuric acid. The liquor from the washings can be used for the manufacture of oxalic acid, dextrine, pickling liquor, and other purposes. From the acid waste by saturation with carbonate of lime may be collected the soluble nitrate, to which may be added sulphate from the washing; the whole may be subjected to evaporation and disposed of. Or the nitrates may be treated with sulphate of potash or soda, so as to produce nitrates solidified by evaporation and crystallisation.

As the cost of pyroxyline is greatly enhanced by the large quantity of acid required for its production, it is of importance to economise this expenditure by mixing with the sulphuric and nitric acids that have been already used, and have consequently become weakened, a variable quantity of bisulphate and a little

Digitized by Google

nitrate of potash or soda. These salts should be separately dried at a temperature which does not decompose them, and then pulverised. Sufficient concentration is thus obtained to enable the acids to be used several times in treating cellulose. For the alkaline, bisulphate and nitrate may be substituted, a proportion of nitric acid at 45° to 48° Beaumé, and sulphuric acid a few degrees above 66°. By treating the acids in either of these ways they become finally available for the production of nitric acid by adding the nitrate of potash or soda. The sulphuric acid assisted by heat dissolves the salt, leaving the nitric acid free, which is separated by distillation. Should it be preferred to prepare the pyroxyline by the old method, that is to say by treatment with a nitrate and sulphuric acid, the operation may be conducted as follows :—

The pulverised nitrate is mixed with the acid in a vessel, where after agitation the mixture is allowed to settle. The liquid portion is decanted into a vessel, where the cellulose is immersed in it. After removal of the pyroxyline, the liquid as well as the deposit is heated and treated in the usual way for production of nitric acid. The acid liquors, after having transformed cellulose into pyroxyline, may also be applied in the treatment of phosphate of lime, to produce a soluble bi-phosphate with sulphate and nitrate of lime.

The cellulose in the cheap condition of thin unsized paper, cotton waste, or rags, is treated in the known manner with suitable proportions of acid at the usual temperatures, and for the usual periods in apparatus consisting of a large basin heated by steam-pipes at the bottom, and a number of baskets or vessels of enamelled wire or perforated plate, or of ceramic ware. One of these vessels is shown in sectional plan at Fig. 35. It is of segmental form, with its sides perforated. This being charged with the cellulose in a state of division, is immersed in the acid bath, and agitated. After the cellulose is transformed into pyroxyline, the vessel with its contents is placed in a sloping position to let it drain, and then a number of the vessels are

FIG. 35.—ENAMELLED WIRE BASKET.

Digitized by Google

placed on a centrifugal machine for the more complete expulsion of moisture. After this, the vessels are plunged in a basin containing the acidulated water coming from the other basins.

All this apparatus is arranged within a glass chamber, the manual operations being effected by means of flexible sleeve tubes, as above described, attached to holes in the sides of the chamber. The vapours are conducted from the chamber to a condenser. The vessels or baskets containing the pyroxyline to be washed are introduced successively into basins mounted on trucks, the washing being carried on methodically, that is to say, when the first vessel or basket is taken from one of the basins, the second takes its place, and so on.



FIG. 36.—PRESS.

The pyroxyline is bleached by permanganate of potash and sulphurous acid. For 4 cwt. of pyroxyline about 1 lb. of permanganate is dissolved, mix the whole with 2 to 3 tons of water, agitate and blow through the mass a current of sulphurous acid till the bleaching is complete. This may be done in a vat with revolving agitators or in a rag mill, whereby the pyroxyline is at the same time reduced to pulp. Instead of the current of sulphurous acid, sulphuric acid and salt may be employed, mixing about 150 lbs. of the former and 60 or 70 lbs. of the latter with the mass containing the permanganate; or instead of these materials about 5 lbs. of hyposulphite of soda, with about 50 gallons of water, and 11 lbs. of hydrochloric acid may be added slowly to the mass under agitation, causing the colour given by the permanganate to disappear entirely. Hyposulphite alone may be used for

Digitized by Google

bleaching, or for final bleaching after a preliminary bleaching, as above described.

The apparatus employed in compounding the pyroxyline are as follows:—1. A paper or rag mill or beater to bruise the pyroxyline and camphor. 2. An apparatus similar to the heated presses used for the manufacture of stearine with the following modifications, as shown in Fig. 36. The cakes, rectangular, square, or round, are placed horizontally, to avoid a preliminary pressure which solidifies the mixture of camphor and pyroxyline; the press, which may be a screw or hydraulic, is entirely surrounded by a casing of plate provided with a door. The rod of the press passes



FIG. 37.—PLAN OF CONDENSING CHAMBER.

through a stuffing box in the casing, at the side of the casing an opening connected to a coil for condensing vapours a chamber with which the coil communicates for receiving the condensed camphor and other solid matters.

This chamber, shown in section at Fig. 37, is provided with removable trays over which water flows. To complete the apparatus, there are required a press with steam-heated rollers to complete the compression previously made; moulds of various forms; an air pump to exhaust the chamber; a stove or chamber, having a capacity of about 100 cubic feet, made with tight joints, having a casing for steam or hot air to heat the exterior, while steam or hot-air pipes heat the interior. A

Digitized by Google

large opening permits the placing or removal of the trays, and it is closed quite tight so that a vacuum can be maintained within; lastly, a still and its condenser.

The pyroxyline is treated as required with solid or liquid solvents. The liquid are to be preferred for the production of transparent and even translucent pyroxyline, for the solution can be filtered and then distilled in a retort to remove the solvent, the pyroxyline being then in a state of paste, which can be moulded and then completely dried. For imitations of ivory and other opaque substances camphor is employed, which is bruised with water, 42 to 50 parts of camphor being added to 100 parts of pyroxyline, both being considered as dry. After a thorough mixture the material is enclosed in strong fabric and placed in a hair bag between the plates of the heated press, where it is pressed for an hour or more. The cakes left in the fabric covers may then be subjected to the action of the hot roller press, and then placed in the vacuum chamber in presence of absorbents, such as chloride of calcium or concentrated sulphuric acid, to remove all moisture.

During the hot pressing superheated steam or air or liquid heated above 212° Fahr. may be employed, the higher temperature being required to effect the solution of pyroxyline in camphor. The thin plates can then be united by heat and pressure, moistening them or not with alcohol, ether, and the like. Into the products may be introduced any resinous or other substance or colouring matter, making paste of uniform colour, or spotted, or marbled. The pyroxyline is rendered less combustible by washing it before compounding in a solution of silicate of soda, and introducing into it phosphate of ammonia or of soda, or borate of lead, or the more fusible fluxes used for painting on porcelain or glass. As pyroxyline is not readily attacked by acids, it may be used as a material for many parts of the apparatus employed for its manufacture.

Proportions in which Cellulose is found. — The following analyses of raw cotton, wheat and barley straw,

Digitized by Google

and of a number of woods, afford illustrations of the extent to which cellulose is associated with other substances in various vegetable products:—

	Water.	Aqueous Extract.	Alcohol-benzene Extract.	Cellulose.	Incrusting substances.
Cotton	7·00	0·50	0·40	91·35	0·87
Barley straw . . .	11·75	9·34	1·99	49·22	27·70
Wheat straw . . .	10·39	8·52	1·58	49·17	30·34
Alder	10·70	2·48	0·87	54·62	31·33
Beech	12·57	2·41	0·41	45·47	39·14
Birch	12·48	2·65	1·14	55·52	28·21
Black Poplar . . .	12·10	2·88	1·37	62·77	20·88
Box	12·90	2·63	0·63	48·14	35·70
Chestnut	12·03	5·41	1·10	52·64	28·82
Ebony	9·40	9·99	2·54	29·99	48·08
Fir	13·87	1·26	0·97	56·99	26·91
Lime	10·10	3·56	3·93	53·09	29·32
Mahogany	12·39	9·91	1·02	49·07	27·61
Oak	13·12	12·20	0·91	39·47	34·30
Scotch Fir	12·87	4·05	1·63	53·27	28·18
Teak	11·05	3·93	3·74	43·12	38·16
Willow	11·66	2·65	1·23	55·72	28·74

Digitized by Google

CHAPTER XI.

VARIOUS OTHER EXPLOSIVES.

THE Sprengel Explosives—Flameless Explosives—Roburite—Experiments with Roburite and other Explosives—Mr. Hilton's Rules for using Roburite—Bellite—Securite—Trench's Fire-extinguishing Compound—Favier's Explosive—Hellhoffite—Romite—Rack-a-rock—Panclastite—Melinite—Picric Acid—Turpin's Shell.

The Sprengel Explosives. — Amongst the variety of explosives which of late years have been brought to the public notice, such excellent results have been attained with one class amongst them—the *Sprengel Explosives*—that it may not be impossible in the near future that the dynamites may find some successful rivals among that class. *Rack-a-rock* may be especially mentioned, as it was this compound which the investigations of the officers of the United States Government induced General Newton to adopt in the great blasting operation at Hell Gate in 1885.

In all the Sprengel explosives the essential principle is the admixture of an oxidising with a combustible agent at the time of, or just before, being required for use, the constituents of the mixture being non-explosive when separate.

Sprengel followed up the idea that an explosion is a sudden combustion, and he submitted a variety of mixtures of oxidising and combustible agents to the violent shock of a detonating cap. These mixtures were made in such proportions, that their mutual oxidation and deoxidation should be theoretically complete.

Among them are the following :—

a. 1 chemical equivalent of nitro-benzene to 5 equivalents of nitric acid.

Digitized by Google

b. 5 chemical equivalents of picric acid to 13 equivalents of nitric acid.

c. 87 chemical equivalents of nitro-naphthalene to 413 equivalents of nitric acid.

d. Porous cakes or lumps of chlorate of potash exploded with a variety of substances.*

All explosives of this class require a detonator. When nitric acid is one of the ingredients, the greatest care is necessary to avoid its coming into contact with the explosive contained in the detonator.

The Sprengel explosives consist of two ingredients, which when kept separate are harmless, but when mixed form powerful compounds; and the mixing is therefore executed at the mines, generally before their insertion into the bore-holes.

Flameless Explosives. — The terrible significance of accidents in coal mines, resulting from fire-damp explosions, is too well known to require any comment here. According to the *Colliery Guardian* (15th April, 1887), official statistics show that "during 50 years, ending 1885, there have occurred 503 *fatal explosions*, in which about 5000 *miners have lost their lives.* This gives an average of ten such explosions a year, and an average of ten deaths to each explosion."

It is needless to say that these disasters in collieries have drawn the attention of scientists to the importance of producing a compound which should not produce any flame when exploded in the bore-hole in fiery mines. The first step in this direction was the introduction of the so-called "water cartridge," invented by Mr. Settle, of Bolton. In this invention, the explosive charge was disposed in such a manner that it was entirely surrounded by water, and the flame was therefore quenched by this water at the instant of its explosion.†

The economic value of the water cartridge led to further advances, and amongst the substitution for water of solid materials which possess fire-quenching properties, and ulti-

* See 'Dictionary of Explosives,' by the late Colonel Cundill, R.A.

† See *post*, Chap. XVII., on the 'Use of Explosives in Fiery Mines.'

Digitized by Google

mately to the invention of a series of so-called *Flameless Explosives*, the properties of which, chemical as well as physical, are discussed in the following pages. The subject is one of great importance, as by the production of a *truly flameless explosive* a great boon would be conferred on the coal-mining fraternity, to whom I would seriously recommend an impartial trial of these new compositions. They should thoroughly experiment with these explosives before pronouncing a judgment *pro* or *contra* any of them, as only by continued practical use in the mines over an extended period can the value of an explosive be determined.

Roburite belongs to the variety of explosives the resolution of which into gases is not accompanied by a flame when detonated under confinement; and it is claimed that, as the resulting explosion gases will not ignite fire-damp or coal dust in coal mines, the name "flameless," therefore, is an appropriate term.

This explosive is the invention of Dr. Carl Roth, a German chemist, and he contends that by his peculiar process of chlorinating and nitrating certain coal-tar products and then mixing them with some inorganic oxygen-yielding substance, he obtains a compound which evolves gases which will instantaneously quench any flame that may be produced by the explosion. In fact, the practical effect is somewhat similar to that produced by Settle's water cartridge, with the distinction that the quenching element is chemically combined with the explosive, whereas in the water cartridge the explosive is surrounded with water.

The chemical compound, as I am informed, consists of chlorinated dinitro-benzol mixed with certain proportions of ammonium nitrate, calculated to oxidise it completely, and in the result Dr. Roth claims to produce a practically flameless detonation.

Dr. Carl Roth gives the chemical equation for the decomposition of roburite as follows :—

$$\underbrace{C_6 H_3 Cl (N O_2)_2}_{\text{(Organic.)}} + \underbrace{9 N H_4 N O_3}_{\text{(Inorganic.)}} = 6 C O_2 + 19 H_2 O + 20 N + H Cl$$

Digitized by Google

Putting the molecular weights in place of the above symbols—

$$[202{\cdot}5 + 720] \left\{ \begin{array}{l} 264 + 342 + 280 + 36{\cdot}5 \\ \text{Carbonic Acid.} \quad \text{Water.} \quad \text{Nitrogen.} \quad \text{Hydrochloric Acid.} \end{array} \right.$$

$$922{\cdot}5 \qquad 922{\cdot}5$$

Roburite has theoretically, by the dynamometer of Trauzl, nine times the force of gunpowder. The product of its gas volume and calories (units of heat) is given as 1,150,000, that of dynamite being about 950,000.

From what has been said, it will be seen that roburite belongs to the Sprengel type of explosive, being a mixture of two substances, neither of which separately possesses explosive properties; in this case both components are solid, and the resulting mixture has a sandy granular appearance, somewhat resembling the commonest yellow sugar.

As is shown in the following pages, two other explosives, called *Securite* and *Bellite*, possess similar properties to roburite, and do not differ materially as to composition; but as roburite is now being manufactured on a commercial scale in England, and is in actual use by miners, I shall give results of experiments which were conducted with a view to substantiate Dr. Roth's claims.* These were :—

"1. That the two components are perfectly harmless and inert separately, so that they can be stored and transported without any restriction whatever.

"2. That even when mixed or ground up together in an ordinary coffee, cement, or flour mill, the mixture is perfectly safe to handle and use, as neither percussion, friction, nor the application of an ignited or heated body will cause it to explode; this can only be effected by using a detonator charged with fulminate of mercury.

"3. That, when detonated, roburite produces neither spark nor flame, and will not, therefore, ignite fire-damp nor coal dust in mines. Dr. Roth states that this point was decided by

* For the particulars here given of these experiments, I am indebted to the inventor, Dr. Roth.

Digitized by Google

the trials of the Imperial German Commission upon Accidents in Mines, and that, in consequence, this explosive is now being introduced into the coal-mining regions of Germany, as affording absolute safety to the men employed.

"4. The amount of noxious gases produced by this explosion is so infinitesimal, that for this reason alone it is superior to other explosives in common use for longitudinal and deep mining work. The report from a mine in Westphalia, with shafts about 1500 ft. deep, states with reference to roburite:—'The men are not inconvenienced by the gases, and experience no difficulty whatever in breathing the moment after a shot has been fired, and they resume their labour at once.'

"5. Roburite is not subject to deterioration through climatic variations of temperature. It should be kept dry, but if it becomes damp, its strength can be safely restored by drying."

The experiments were conducted at Chatham, and the proceedings are thus described:—

"*Safety Tests.*—1. After being ground through a small hand-mill, the substance was struck direct and glancing blows with heavy hammers upon iron plates without exploding.

"2. Flame was then applied to a portion of it by means of a short length of Bickford fuse, but without igniting the mass.

"3. Thrusting a red-hot iron from a portable forge into the roburite caused only slow combustion and crepitation locally, which ceased when the iron was withdrawn. When a quantity was put on the forge fire it merely burnt away like an ordinary combustible.*

"*Test for Strength on Steel Plates.*—The plates were laid flat in shallow trenches, a hollow being left underneath the central portion of each plate; heavy timber balks were stacked around each square trench with the object of showing the comparative dispersive force of each explosive.

"1. 3 lbs. each of dynamite and roburite were placed on the

* I would not recommend miners to repeat such experiments. It is well known that dynamite will also burn away without exploding, but I know of cases where it exploded when set on fire, especially when in bulk. —M. E.

Digitized by Google

centre of plates 2 ins. thick, some sandy loam being piled loosely on top. The results of detonation were that the dynamite produced a dent in centre of plate 1¾ in. deep; the indentation produced by the roburite was about 1½ in. deep, but the bulge appeared to have a wider area than in the former case.

"2. 5 lbs. each of roburite and gun-cotton were then exploded upon the same plates, with the result that in the former case the plate was smashed into four tolerably equal pieces, while the gun-cotton made a breach through the centre of the plate somewhat resembling that which would be caused by the penetration of a large projectile; the diameter of the hole was roughly 12 in., with five radial fissures almost reaching the edges, the longest 15 in., the plate being at the same time bent into the shape of a pack saddle; this would seem to have been a remarkably tough piece of metal. The timber balks were scattered in all directions.*

"3. 8 lbs. each of dynamite and roburite were then detonated upon plates 3 in. thick. The dynamite caused an indentation 2¼ in. in maximum depth, while the roburite gave a bulge 3 in. deep in the centre, and of a larger area, reaching apparently almost to the corners of the plate.

"4. This series of tests was concluded by exploding 12 lbs. each of roburite and gun-cotton on plates 4 in. thick, rather more loam being heaped on top of each. The roburite caused a wide indentation of 1⅞ in. deep in centre, while the tremendous local force of the gun-cotton was exemplified in a striking manner; in addition to an indentation 3½ in. in greatest depth, a small crack appeared to extend right through the plate, this crack corresponding with one edge of the lowest slab of gun-

* From experiment No. 2, I conclude that gun-cotton by its more local action would be more adapted for offensive or defensive torpedo charges, as it would blow a hole in the bottom of a ship without destroying it. The ship after sinking could be raised and easily repaired, whereas roburite would most likely twist and disturb the ironwork, making it useless, but as a bursting charge for shells, the dispersive effects of roburite may prove an advantage in attacking large bodies of troops.—M. E.

Digitized by Google

cotton, the rectangular shape of which could be clearly seen indented on the steel plate, the depth being ¼ in. at the crack and ⅛ in. along the other edges of the slab. There is a circular hole drilled in the slab of wet gun-cotton to receive a small cylindrical disc of dry gun-cotton, as a primer, and the position of this disc was marked by a circular hollow in the steel plate ½ in. deep in centre.

"*Ground Mines.*—10 lbs. each of gun-cotton, blasting gelatine, and roburite were loaded into holes in the bottom of the ditch 4 ft. deep by 8 in. in diameter, filled up with sand, and slightly tamped; the explosion of these charges cast up tremendous fountains of loam and sand, and resulted in the following craters: gun-cotton, 10 ft. 6 in. wide by 1 ft. 8½ in. deep; gelatine, 14 ft. 6 in. wide by 3 ft. 7 in. deep; roburite, 12 ft. 3 in. wide by 2 ft. 9 in. deep. The explosion of the gun-cotton mine appeared to cause great local action, but it will be seen that the area and depth of its crater was considerably less than that caused by the roburite, which again must yield the palm, in this instance, to the blasting gelatine. It is, however, to be remarked that these mines had been placed much too close to one another, so that their craters crossed; this would give whichever charge was the last to explode a certain advantage."

From the published reports* of competitive trials made in the Wharncliffe Silkstone and Monk Bretton Collieries between roburite and other explosives, it will be seen that roburite was found to exhibit all the characteristics of a true high explosive, in respect of the amount of work done in breaking rock and coal. During these experiments it was noticed, also, that the explosion of the charges in the bore-holes produced no visible flame.

To determine the flamelessness of roburite the following series of experiments (we are told) were made:—

"1. A shot fired on the ground, exposed; this gave no perceptible flame (70 grammes of roburite was the charge in these experiments).

* *Engineering*, 28th October, 1887.

Digitized by Google

"2. A shot fired on the ground, bedded in fine coal-dust; no flame nor ignition of the coal dust was perceptible.

"3. A shot fired suspended in a case into which gas was conducted, and the atmospheric air allowed to enter so as to form an explosive mixture. The gas was not fired.

"4. A shot fired in a boiler flue 16 ft. by 2 ft. 8 in., placed horizontally, in which was a quantity of fine coal dust kept suspended in the air by the action of a fan. No flame nor ignition of the coal dust took place.

"5. A shot fired as above, except that an explosive mixture of gas and air was flowing into the boiler tube in addition to the coal dust. That this mixture was fire-damp was proved by the introduction of a safety-lamp, the flame of which was elongated, showing what miners call the 'blue cap.' There was no explosion of the gas, or sign of flames.

"6. A shot of roburite fired in the boiler tube without any gas or suspended coal dust. The report was quite as loud as in the preceding case; indeed, to several present it seemed more distinct.

"7. A shot of ½ lb. gunpowder was fired under the same condition as No. 5, *i.e.* in an explosive mixture of gas and air with coal dust. Not only was there an unmistakable explosion of the fire-damp, with very loud report, and a vivid sheet of flame, but the gas flowing into the far end of the boiler tube was ignited and remained burning until turned off."

Several shots were fired in the pits, while the lamps were covered so as to produce complete darkness, but no flame or spark was perceptible, according to the report of the witnesses present.

Mr. James Hilton, in a paper read before the Manchester Geological Society, says that after an experience gained in firing over 3500 roburite charges, he had drawn up the following conclusions and rules for the use of roburite:—

"1. It was reliable on account of the safety with which it could be transported and stored.

"2. That it took a very strong detonator to explode it.

"3. It was practically flameless under pressure, the gases

Digitized by Google

evoked in its combustion being of such a character as to quash any initial flame there might be.

"4. In fiery mines, it should be treated so as to confine the gases, and give them a chance of action on the initial flame at the moment of action, the quenching element being chlorine.

"5. With regard to the gases evolved by the decomposition of roburite, it appears from the formula of the inventor that there are no noxious nitrous fumes caused by its explosion.

"6. The drill hole should only be a trifle larger than the diameter of a cartridge, and is more suitable when machine-drilled.

"7. Open one end of the cartridge, bore a hole down the centre of it (with a wooden peg), then insert the detonator well into the middle of the cartridge, and next tie the covering of the cartridge point to the fuse.

"8. In tamping be careful to use dry material, and to ram the hole very lightly for the first three or four inches, so as not to displace the detonator or compress the roburite. Afterwards tamp finally for not less than a foot, with clay or damped borings from the drill hole. This rule is most important, as the safety of the explosive depends on the tamping.

"9. Fire the detonator with an electric fuse where fire-damp is given off or coal dust is present.

"10. Store roburite in a dry place, and if the hole is wet fire the charge as quickly as possible after it has been placed in the hole.

"11. If the charge misses fire disconnect the cable from the battery, and wait ten minutes before going to it, for although there has not been a single case of hanging fire with me in over 3500 shots, yet I have heard of an accident happening through a shot hanging fire for a few minutes. It is supposed that the paper at the end of the electric fuse inserted in the detonator smouldered for a short time and fired the fulminate of mercury."

After giving the details of a large number of experiments,

Digitized by Google

Mr. Hilton observed that in the number of roburite shots he had mentioned either sparks or a flash had been seen, on an average, once in a hundred times, but in none of these, in his opinion, would an inflammable mixture have been ignited, although the margin between danger and safety would have been very near.

Bellite.—This explosive has been invented by Mr. Carl Lamm, who introduced its manufacture in Stockholm. It is essentially a mixture of nitrate of ammonia and di- or tri-nitro-benzol. These substances are mixed together at a temperature of 176° to 194° Fahr., which melts the latter, causing it to thoroughly cover over all the particles of the nitrate ammonia, and protecting this substance from atmospheric influence; and a compound is formed of which each molecule is explosive.

In its granulated state, and in cartridges, its sp. gr. is 1 to 1·2, and in this condition it is said that it can be readily exploded by an ordinary fulminating cap even under confinement. When compressed, however, into solid cakes, it needs more powerful detonators and also strong confinement. It evaporates at about 300° Fahr., and at a higher temperature it is stated that it will not explode. Unlike nitro-glycerine, dynamite, &c., which detonate violently when suddenly heated to a like temperature, bellite is said to take fire only and to burn as fat. It is also stated that bellite is non-sensitive against blows, friction, and vibration, and that it possesses great chemical stability, permitting long storage and transportation to distant countries.

It has been placed on the list of licensed explosives in England.

Securite, like bellite and roburite, consists of a mixture of meta-dinitro-benzole with nitrate of ammonium or nitrate of potash. The proportions are about 20 parts of the former to 74 of the latter. It is a yellow powder, with the odour of nitro-benzole. Other varieties contain trinitro-benzole or

Digitized by Google

di- or trinitro-naphthaline. The following equations are given as representing the various compositions and their products of combustion, and claim to show that it is a perfectly safe explosive to use in the presence of fire-damp and coal dust:

$$C_6H_4.2\,NO_2 + 10\,(NH_4.NO_3) = 6\,CO_2 + 22\,H_2O + N_{22}$$
$$2\,(C_6H_4.3\,NO_2) + 15\,(NH_4.NO_3) = 12\,CO_2 + 33\,H_2O + N_{30}$$
$$C_{10}H_6.2\,NO_2 + 19\,(NH_4.NO_3) = 10\,CO_2 + 41\,H_2O + N_{40}$$
$$2\,(C_{10}H_5.3\,NO_2) + 33\,(NH_4.NO_3) = 20\,CO_2 + 71\,H_2O + N_{72}.$$

As is shown by the preceding chemical formulas the composition of both securite and bellite, does not vary much from roburite, although securite substitutes as an oxidising salt the nitrate of potash for the nitrate of ammonia.

Experiments have been extensively reported upon both abroad and in England by various authorities, and the results may be summarised as follows:—

Securite and bellite do not seem to explode by friction, pressure, a blow, fire, or electricity, but detonate under the influence of a powerful detonator.

It is claimed that the explosion gases are innocuous, and that the explosion is not accompanied by any amount of flame or gases. That they belong to the flameless variety has been shown by experiments, where these explosives were exploded in a gaseous mixture of a hydrocarbon and air, inside an iron tank; such a mixture is highly explosive, but securite and bellite explosions did not fire it, whereas gunpowder did.

Their action in coal and stone is more in the nature of rending than of pulverising.

Unlike nitro-glycerine preparations, they do not freeze in cold weather.

Cartridges of these explosives, when thrown into a fire, simply fizzed away without exploding.

Heavy weights, when dropped from a certain height on to the cartridges of these explosives, did not explode them.

That they may possibly be applied for military purposes is shown by the fact that cannon balls can be propelled with these explosives from guns, and a 32 lb. ball was sent flying through the air for a distance of 95 yards when fired with

Digitized by Google

¼ oz. of bellite, whereas ½ oz. of gunpowder sent it only to a distance of 40 yards; but it remains for future experiments to demonstrate if larger charges of these explosives could be used in artillery, to send balls to a distance of several miles, such as actual military operations would require.

Trench's Fire-extinguishing Compound, manufactured by the Cotton Powder Company, is the invention of Mr. G. Trench, the manager of the company at Faversham. The object of the invention is to surround the cartridges of tonite, when used in coal mines, with a composition which will extinguish the flame of the shot. It consists of sawdust impregnated with certain chemical substances, and to an inexperienced eye it has the appearance of dirty salt. If a charge of tonite, or of dynamite or gelatine-dynamite, is packed inside a few ounces of this mixture, and then fired, not the least trace of flame can be observed, and experiments appear to show that there is no flame at all. The following report* of experiments conducted in the presence of several scientific gentlemen and practical members of the mining community has been published :—

"A large wrought-iron tank, of 45 cubic feet capacity, had been sunk level with the ground in the middle of the yard; to this tank the gas had been laid on, for a purpose that will be explained later on. The charges were fired by means of electricity, a small dynamo-firing machine being placed from thirty to forty yards away from the 'mine.' Operations were commenced by the top of the tank being covered over and plastered down in order to make it air-tight; then a sufficient quantity of coal gas was placed in it to make it highly inflammable and explosive, the quantity being ascertained by a meter which had been fixed specially for the purpose. Whilst the gas was being injected, the cartridge was prepared. The first experiment was to try whether a small charge of tonite—fired without the patent extinguisher—would ignite the gas. The gas having been turned on, a miner's lamp was

* From the *Faversham News*, 22nd October, 1887.

Digitized by Google

placed in the 'tank,' but this was extinguished before the full quantity of gas had gone through the meter. However, the gas being in, the charge (1¼ oz. tonite) was placed in the 'mine,' the detonator was connected by means of long wires to the dynamo machine, and the word was given to 'fire.' With a tremendous report, and a flash of fire, the covering of the mine flew in all directions, clearly showing that the gas had been ignited and added considerably to the noise of the report and the force of the explosion. The next cartridge (a similar charge) was prepared with the patent compound. First of all a brown paper case of about two inches diameter was taken, and one of the tonite cartridges was placed in the centre of it, the intervening space between the charge and the case being packed with the 'Fire-extinguishing Compound.' The mine having had another supply of gas injected, the protected cartridge was placed inside and fired. The result was astonishing, the explosion not being nearly so loud, whilst there was not the least flash of fire. 'Protected' and 'unprotected' charges were fired at intervals, gas being turned into the tank on each occasion. Two ¾ oz. charges of tonite were fired without the compound, and on each occasion the gas was exploded, and the jet at the end of the supply pipe was, upon examination, found to be alight. Charges varying from 1 oz. to 6 oz. of tonite were fired with the compound, and on each occasion the report was trifling, whilst no flash could be seen."

In actual mining the paper case can be dispensed with, the charge being placed in the bore-hole and tamped down with the fire-extinguishing compound around it, but to ensure the explosive being entirely surrounded with compound the paper bag should be used.

The accompanying illustration (Fig. 38) shows the manner of placing the tonite cartridge in the paper bag, and surrounding it with the fire-extinguishing compound *a*, *a*. The attachment of fuze and detonator is also shown, as well as the wooden rammers.

Digitized by Google

Favier's Explosive.—This compound is prepared by coating nitrates, such as nitrate of ammonia, with a molten hydro-carbon, like paraffin, and then compressing the substance into a cartridge.

With this object in view, during manufacture the moulds in which the compression is effected are heated by means of a circulation of hot water or steam at the melting point of the hydro-carbons, or better, the material is brought to this temperature in a mixer; under the double influence of the pressure and heat the material agglomerates itself, the hydro-carbon covering the molecules of the nitrate with a protective



FIG. 38.—APPLICATION TO CARTRIDGES OF TRENCH'S FIRE-EXTINGUISHING COMPOUND.

coating which may exude slightly and so form externally a sort of protective varnish to the mass, which may be further augmented by plunging the material on its coming from the mould into a melted waterproof mixture.

For the manufacture of more feeble explosives, nitrate of soda is employed, either alone or mixed with nitrate of ammonia or with any other compound capable of readily giving off the hydrogen which it contains. Before the compression of these two compounded substances sulphur may be added to them, which will lower the temperature of their transformation into gas.

Digitized by Google

The mixture of nitrate of ammonia and of the hydro-carbon with or without sulphur, worked at the minimum density of 1·6, possesses a very great stability and does not explode, as do the nitrous bodies, under the influence of an ordinary fulminating capsule, and consequently recourse is had to an intermediate nitrous body, the points of contact whereof with this improved compound are multiplied as much as possible.

For this purpose a cylindrical opening is formed in the centre of the moulded cartridge along its longitudinal axis, these cartridges being made of nitrate of ammonia coated with the molten hydro-carbon; and in the said opening is placed a nitrated explosive body intended to communicate the initial detonation to the surrounding compound, thus increasing the initial detonation produced by the discharge of the fulminating capsule placed in contact with the nitro-compound.

In the central opening, gun-cotton, picric acid, the chlorates of ammonia or potash, may be used as a priming, the last two substances being previously incorporated or covered by an easily fusible hydro-carbon. These detonating compounds are moulded in form corresponding to the hole in the cartridge, and can be inserted either at the time when the explosive is to be used or previously.

By employing a quantity of gun-cotton or chlorate not exceeding one-tenth of the weight of the moulded compound to be detonated, the explosion will be positively ensured.

By using the hollow cartridge, Favier is enabled to utilise certain explosive acid mixtures of the Sprengel type, which are produced by dissolving certain hydro-carbons, phenols, natural alcohols, in nitric acid or in nitric peroxide, or nitrates, sulphates, carbonates, &c.

Several of these mixtures, in which the nitrated elements and hydro-carbons are simply in juxtaposition, will produce explosives, which according to theory are equally powerful as compound with nitro-glycerine preparations, for they can be made in required proportions for obtaining a complete combustion of their elements, and moreover do not need to give

Digitized by Google

cver during the detonation the heat absorbed by the fixing of the nitrous elements on the glycerine.

These explosives are brought to a state of paste by absorption in infusorial earth, or are placed in the central opening of the cylinder of the primary compound, the ends of which are covered by a plug of the same material, or by an inert body such as paraffin. They are exploded by means of strong fulminating caps.

Hellhoffite is a mixture of nitro-petroleum or nitro-tar oils with nitric acid. One form of it—proposed by Gruson—has been tried in shells, and consists of meta-dinitro-benzole C_6H_4, $2(NO_2)$ and nitric acid. The two substances are placed in separate receptacles in the shells, and are automatically mixed during the flight or on the impact of the shell, as the case may be.

Romite is a Swedish explosive, consisting of a mixture of nitrate of ammonia with naphthalene or nitro-naphthalene. When required for use, this is to be mixed with chlorate of potash. The nitrate of ammonia is also employed when coated with a jacket of molten paraffin and naphthalene; when so prepared in admixture of chlorate of potash, it forms a compound equal in strength to ordinary dynamite.

This explosive is used successfully in Sweden. It does not seem to explode accidentally, and may have a future before it. Experience has shown that a chemical action is likely to set up between the nitrate of ammonium and the chlorate of potash, which renders spontaneous combustion possible, but this tendency the persons interested in the preparation of romite are endeavouring (I am informed) to overcome.

Rack-a-rock consists of compressed cartridges of chlorate of potash impregnated before use with dead oils or other liquid hydro-carbons, or with nitro-benzol; or a mixture of dead oil with its own volume of bisulphide of carbon; or a mixture like the last with the addition of 3 per cent. of sulphur.

The chlorate of potash cartridges are enclosed in small

Digitized by Google

bags of cotton or other cloth, of suitable size and shape, and dipped into the liquid. The mixture of dead oil and bisulphide of carbon is used by preference, the object of the bisulphide of carbon being to prevent too large a proportion of dead oil from being taken up by the chlorate. The bisulphide afterwards evaporates out.

Nitro-benzol is also used as a dipping liquid, or as an ingredient thereof in combination with picric acid.

In practice, the cartridges are suspended in a wire basket from a spring balance and dipped into a pail containing the fluid. The completion of the absorption of the proper amount of fluid is shown by the spring balance. The proportions given are three to four and one-sixth parts solid to one part liquid ingredient. If the cartridges be kept, they appear to tend to increased sensibility to friction or percussion.

Rack-a-rock, as supplied by the Rendrock Powder Company of New York, consists (1) of a solid, composed mainly of potassium chlorate in fine powder, to which a reddish tint is given by some colouring matter; and (2) of an oily liquid, the liquid used for "rack-a-rock" consisting essentially of nitro-benzol, and that for "rack-a-rock special" of nitro-benzol saturated with picric acid—12 to 16 per cent., according to the quality of the solvent.

These compounds—neither of which is explosive by itself—are combined before use by immersing the solid in the liquid for a few seconds, until an increase in weight of about one-third is effected by absorption. The solid is supplied in the form of soft, loosely packed cartridges of different sizes, put up in bags closed at each end. The combination of the ingredients is effected by means of an open wire basket to receive the cartridges, which is suspended from a spring-balance and dipped in a galvanized iron pail containing the fluid. A little attention to the time of immersion renders the absorption fairly uniform. When prepared in this manner, the explosive is a compact red solid of about 1·7 sp. gr. It decrepitates with difficulty when hammered on an anvil, but hardly ignites in wood. A fuze of 24 grains of fulminate

Digitized by Google

of mercury fails to explode a cartridge unconfined, or explosion is only partial. Even if compacted in an auger-hole in a log, and tamped with mud, the explosion is only partial. A cartridge struck by a bullet from a Springfield rifle flashes, but does not detonate.

Ordinary friction seems to have little tendency to cause explosion. The explosive is quite safe to handle even when ready for use, and it has given excellent results in rock-blasting. It possesses the merits of high intensity of action, unusual density, absolute safety in handling and storage (components unmixed), and little cost. On the other hand, in Abbot's tests, an exceedingly strong detonating primer was found essential to develop the full power.

The inventor of rack-a-rock has improved the compound by sensitising it by means of the addition to the chlorate of potash of some sulphur in a finely powdered state, the quantity ranging from 1 to 3 per cent.; but the sulphur should be mixed, after the chlorate is melted down, with the nitro-benzol, otherwise there is danger of explosion in mixing the two ingredients dry.

In practice, the chlorate of potash is shipped in cartridges made of fine linen, the liquid ingredients of the explosive—such as dead oil—and the volatile fluid and sulphur in solution being put up in a separate tin can suitable for transportation. When the explosive is required for use, the workman simply soaks the solid ingredient in this mixture until saturation is effected, and then lays the saturated mass in the open air or other convenient place for a short time, when the volatile fluid evaporates and escapes, leaving the sulphur incorporated with the wet or moist mass of the combined chlorate of potash and dead oil, while at the same time the proper proportions in the compound of solid and liquid ingredients are secured.

General Abbot reports as follows of rack-a-rock: "This explosive, the invention of Mr. S. R. Divine, is manufactured by the Rendrock Powder Company of New Jersey, of which he is the chemist. Mr. Divine's original patent, from which

Digitized by Google

the following quotations are made, is dated June 28, 1881, the application having been filed on December 7, 1880 :—

"'My invention consists of an explosive compound composed of two ingredients—the one a solid, such as crushed or powdered chlorate of potash; and the other a liquid, such as nitrate of benzol—which are combined to form a high explosive by merely causing the mass of the solid ingredient to absorb the liquid ingredient—a combination which can be effected by the consumer at the time when and at the place where the explosive is to be used. These ingredients, being in themselves incapable of being exploded by percussion, can be with safety separately manufactured, handled, and transported to the consumer, who will have no difficulty in effecting their combination, because the operation of combining them is of so simple a character. In manufacturing my nitro-benzol I use the naphtha of commerce, and it will therefore be understood that my nitro-benzol contains some nitro-toluol and picric acid. Four and one-sixth parts of chlorate of potash to one part of nitro-benzol I consider to constitute the theoretical proportions in which the ingredients of my compound combine most effectively; but in order to somewhat diminish the sensitiveness of the compound to ignition by percussion, I prefer to use from three to not exceeding four parts of chlorate of potash to one part of nitro-benzol.'

"On December 4, 1883, Mr. Divine took out several additional patents for improvements and variations in this explosive, from which the following extracts are made :—

"'What I claim as my invention, and desire to secure by letters patent, is the described process of preparing explosive compounds composed of two ingredients—one a solid, such as crushed or powdered chlorate of potash; and the other a liquid, such as nitro-benzol—which consists in first saturating the chlorate of potash with a mixture of nitro-benzol and a volatile fluid, such as bisulphide of carbon, the proportions of the constituents of said mixture being such that the quantity of the nitro-benzol contained in the mixture absorbed by the chlorate of potash in said saturation

Digitized by Google

will be the proper proportion of said nitro-benzol relatively to the absorbing mass of the chlorate of potash in the explosive, and then allowing the said volatile fluid to evaporate and escape from the mass, substantially as and for the purpose specified.

"'(2) The object of my invention is to "sensitise" or impart increased susceptibility to explosion to an explosive compound for use chiefly in blasting, composed of chlorate of potash and nitro-benzol, so that the said compound may be readily exploded under various conditions of confinement, as in loose or "rotten rock," or shale, or in earth, or in the open air. With the wet or moist mass of these ingredients is united sulphur in a finely powdered state. The proportion in which it is desirable to use the sulphur is from about one to three per cent. thereof relatively to the mass of the combined two other ingredients named. The sulphur is united with the wet or moist mass of the combined chlorate of potash and nitro-benzol, and this may be accomplished by mixing the sulphur with said mass by hand in a suitable vessel. The danger of accidental explosion attendant upon mixing sulphur with chlorate of potash in a dry state is thus avoided.

"'(3) My invention consists of an explosive compound composed of two ingredients—the one a solid, such as chlorate of potash; and the other a liquid, such as the heavy oil of coal tar, which is commonly called "dead oil." These ingredients are combined to form the explosive by allowing the solid ingredient to absorb the liquid ingredient; and this can be done by the workman or miner at the place and when the explosive is desired for use. The theoretical proportions in which the said ingredients combine effectually to constitute my explosive compound are about seven and one-half parts of chlorate of potash to one part of dead oil. The exact theoretical proportions need not, however, be strictly adhered to, as a variation somewhat therefrom will still yield an effective explosive. With the wet or moist mass of said ingredients is united sulphur in a finely powdered state; the

Digitized by Google

proportion is from about one to three per cent. relatively to the mass of the combined two other ingredients, and the mixing with the sulphur is done by hand while the materials are wet, thus avoiding the spontaneous explosions attendant upon mixing sulphur with chlorate of potash in a dry state.

"'(4) My invention consists in a composition of matter not in itself explosive, which is a fluid mixture composed of the liquid ingredient of the explosive, such as dead oil, and a volatile fluid, such as bisulphide of carbon, and sulphur in a finely powdered state dissolved in said volatile fluid. In composing my mixture, I take the quantity of the liquid ingredient of the explosive which is the proper proportion thereof relatively to the solid ingredient, and which, in the case of dead oil, is about one part thereof to seven and one-half parts of chlorate of potash, and to this I add such a quantity of the bisulphide of carbon or other volatile fluid in which the sulphur has been dissolved as will make a fluid volume equal to the total fluid-absorbing capacity of the solid ingredient of the compound; and as the total fluid-absorbing capacity of the chlorate of potash is about double the volume of the quantity of dead oil which constitutes the proper relative proportion thereof in the explosive, I add to the dead oil, when it is used, about an equal volume of the bisulphide of carbon. Sulphur, preferably in a finely powdered state, is dissolved in the bisulphide of carbon, and the desirable proportion of sulphur is from about one to three per cent. thereof relatively to the mass of the combined solid and liquid ingredients of the explosive.'

"Experiments have been conducted at Willet's Point, with rack-a-rock in these modified forms—with some new preparations of the nitro-benzol designed by Mr. Divine to increase the intensity of action of the powder. The nitro-benzol tested in 1882 had a specific gravity of 20° Beaumé; those tested in 1884 showed 30° B. and 34° B.—the latter being experimental. The chemical modifications were communicated confidentially. At first no change was made in the potassium chlorate as supplied in 1882.

Digitized by Google

"The nitrated form of rack-a-rock, as supplied to the trade in 1884, consists of nitro-benzol (sp. gr. 30° B.) and chlorate of potash, rather coarsely pulverised and given a light-red tint by some inactive colouring matter. To test it, twenty trials were made in the usual manner in the five-foot ring.

"The following experiments were made in the belief that the strength of rack-a-rock might be further increased by using the solid in a more finely divided state—which would also make a drier powder for a high proportion of the fluid. Experience in rock-blasting had indicated that it is quite possible for the miners to overcharge the solid in the usual process of dipping. Moreover, in all detonating mixtures fineness of grain and thorough incorporation tend to promote quickness of chemical action, and hence to increase the intensity of the shock. Potassium chlorate ground to an impalpable powder by a peculiar process was used as the solid to combine (1) with dead oil and bisulphide of carbon (sp. gr. 21° B.) in the proportion of 3·54 to 1; (2) with nitro-benzol having a specific gravity of 20° B., and powdered sulphur, in the proportions of 4·5 to 1 and 0·08; (3) with the last-named fluid omitting the sulphur; (4) with the special nitro-benzol having a density of 34° B., in the proportion of 3·25 to 1; and (5) with nitro-benzol having a density of 30° B., in the proportion of 3·5 to 1. All these proportions refer to weight, not to volume.

"The following tabular statement has been computed to give an index of the absolute strength of rack-a-rock manufactured in the several proportions :—

Dynamite No. 1	100
Rack-a-rock as tested in 1882	86
Coarse base, with nitro-benzol 30° B. 4·0 to 1	86
Coarse base, with nitro-benzol 30° B. 3·5 ,, 1	89
Coarse base, with nitro-benzol 30° B. 3 0 ,, 1	77
Fine ,, ,, ,, 30° B.; 3·5 ,, 1	94
,, ,, ,, ,, 34° B.; 3·25 ,, 1	100
,, ,, ,, ,, 20° B.; 4·5 ,, 1	104
,, ,, ,, ,, 20° B.; and sulphur; 4·5 to 1, to 0·08	100
,, ,, ,, dead oil and bisulphide of carbon 20° B.; 3·54 to 1	90

Digitized by Google

"Rack-a-rock possesses one incontestable advantage over all the other powders in the market. It is absolutely safe to handle and store; until the ingredients are mixed neither can be exploded. The high specific gravity of rack-a-rock (about 1·7 in the usual cartridge form) is another great advantage, since it permits the use of small drill-holes. Lastly, the danger attending the handling of potassium chlorate when mixed with a hydro-carbon in any solid form, is quite removed by the happy device of using a liquid.

"The general conclusions warranted by these trials when rack-a-rock is exploded under the stated conditions appear to be the following: (1) With the ordinary coarse potassium chlorate and nitro-benzol 30° B., a very strong detonating primer is required to develop the full power; the proper proportions are 3·5 of the chlorate to 1 of the oil; the strength of the powder exceeds that of gun-cotton, slightly for equal weights, and vastly for equal bulks. (2) Decided increase of power is obtained by pulverising the chlorate to an impalpable powder. With this base, rack-a-rock equals dynamite No. 1 in intensity of action, when mixed in the proportion of $3\frac{1}{4}$ of the chlorate to 1 of nitro-benzol 34° B.; or in the proportion of $4\frac{1}{2}$ of the chlorate to 1 of nitro-benzol 20° B. The former explosive requires a strong detonating primer; but if $1\frac{1}{2}$ per cent. of powdered sulphur be added (with proper precautions) to the latter, the service fuze of 24 grains of fulminating mercury develops the full power. (3) With very fine potassium chlorate, a grade of rack-a-rock having 90 per cent. of the strength of dynamite No. 1, and which is fully detonated by the service fuze, may be made, *without any use of nitric acid*, by employing as the fluid the heavy oil of tar sensitised by sulphur in the manner stated in Mr. Divine's patent. In fine, it would appear that this new explosive should have a practical trial by officers of the corps engaged in blasting operations. Its use in shells is worthy of study."

Panclastite is a name given to various mixtures proposed by M. Eugène Turpin, of Paris.

Digitized by Google

In some of these mixtures he proposes to mix liquid nitrogen tetroxide or nitric peroxide (N_2O_4)[1] with bisulphide of carbon, benzol, petroleum, ether, mineral volatile oils, or other liquid or solid hydro-carbons. He recommends especially a mixture of $2\ CS_2 + 3\ N_2O_4$; but the use of two such ingredients, both giving off highly deleterious vapours, is a very serious objection to a mixture to be used in a mine or other confined space, and the vapour given off by the liquid N_2O_4 is especially dangerous. He also proposes a mixture of about eighty parts chlorate of potash to twenty parts coal tar, with the addition, if necessary, of some porous absorbent for the liquid tar. Two of his powders are as follows:—

	No. 1.	No. 2.
Chlorate of potash	80 per cent.	40 per cent.
Coal tar	14 to 16 „ „	15 „ „
Wood charcoal	4 „ 6 „ „	40 „ „
Nitrate of potash	—	40 „ „

These powders are granulated like ordinary powder, or mealed, or used in form of compressed cartridges.

Melinite—an explosive which is simply an adaptation of picric acid—is also the invention of M. Turpin. Picric acid by itself had always been considered as an imperfect body, not capable of explosion without an admixture of an oxidising substance, like chlorates, nitrates, chromates, nitric acid, &c. But in practice these mixtures proved too dangerous, as the picric acid displaced the nitric and chloric acids from their salts, and thus caused spontaneous explosion; and such compounds have caused some terrible disasters.

Turpin discovered that, contrary to all the theories adopted, picric acid alone—that is to say, neither mixed nor combined with any active substance and such as it is found in commerce—is one of the most powerful and valuable explosives that can be conceived. Its explosive force is greater than that of compressed gun-cotton and the different forms of dynamite. Its insensibility to shock, as well as its stability, is also very remarkable. Turpin also demonstrated that the maximum force of explosives of this kind, contrary to what has been

Digitized by Google

believed, does not coincide with the chemical formulæ, which correspond to complete combustion, but on the contrary with the combustion which yields carbonic oxide. On this novel theory, therefore, the maximum of power may be obtained with nothing near the maximum sensibility, which admits of obtaining results hitherto unlooked for. It is generally admitted that the power of explosives is proportionate to the heat disengaged, which has always led chemists to employ the oxidising agent, and preferably in excess, in order to obtain complete combustion. This, however, was a grave mistake, as the oxygen necessary to form carbonic acid could produce a double volume of carbonic oxide, which would produce a much more considerable amount of work, and which is far from being compensated by the increase in value of the temperature which is produced in the case of the formation of carbonic acid. As regards the carbonic oxide this need not be considered, as its conversion into carbonic acid takes place immediately it is projected into the air, by the action of the flame of the explosion, and at the expense of the oxygen of the air. Turpin found that when picric acid alone, without any admixture, is fired by means of an initial detonator of sufficient power it is capable of producing the most violent bursting effects, for which reason it is proposed to apply it for industrial and military uses, by the novel means and processes hereinafter described.

This application is the more important, as hitherto an explosive for military uses possessing the following properties found in picric acid alone has never been obtained, viz.: 1. Absolute chemical stability, that is to say, non-susceptibility of spontaneous decomposition or of elementary change. 2. Absolute physical stability, that is to say, non-susceptibility of congelation, exudation, liquefaction or evaporation. 3. Absolute insensibility to the most extreme variations of atmospheric temperature. 4. Capability of being preserved for an indefinite period. 5. Perfectly non-hygrometric. 6. Perfect security in manufacturing, manipulation, and transport. 7. Little or no capability of ignition in the open air.

Digitized by Google

8. Greater power of dispersing earth than either gun-cotton or dynamite. 9. Shattering properties equal, if not superior, to those possessed by other violent explosives. 10. Insensibility, or at least inexplosibility, on the ball striking. 11. Insensibility (when used in shells) to the shock of the discharge of the cannon.

The insensibility of picric acid by itself is due to the excess of carbon which it contains, and for this reason it is absolutely necessary to avoid the admixture of any oxidising substance, as it considerably increases its sensitiveness, as well as greatly reduces its power. Picric acid, unmixed, attains its maximum sensitiveness to priming, this property being very slight when it is in the form of fine powder; although but slightly sensitive to shock, its sensitiveness may be still further reduced by different means, which admirably adapt it for, and, in fact, are indispensable to, its use if it is desired to obtain satisfactory results.

These processes consist (1) in compressing the picric acid, in order to increase its density, and, at same time, lessen its sensitiveness, contrary to what is the case with gun-cotton, it being well known that gun-cotton in a flocculent form is not exploded by a priming, whereas it explodes readily when compressed. (2) By agglomerating it (and at the same time moulding it to various forms) with an aqueous solution of gum arabic, or some fatty body, such as heavy oils, fats, etc., which have the property of rendering picric acid insoluble, and then allowing it to dry if necessary. (3) Collodion jelly diluted in the proportion of from three to five per cent. in a mixture of alcohol and ordinary ether, may also be used to agglomerate the picric acid to lessen its sensitiveness, and adapt it for being moulded into any form. Blocks thus obtained will explode in a closed chamber, with primings of from one to three grams of fulminate. The maximum of insensibility is obtained when in the cast state, which is one of the best modes of employment. In this case it will resist, in the open air, the explosion of a priming composed of three grams of fulminate inserted in the cast mass, but it explodes perfectly in a closed chamber, such

Digitized by Google

as a shell, for example, as will be hereinafter explained. Cast picric acid behaves much like wet gun-cotton, that is to say, it may be exploded even under water with a priming of picric acid in dry powder, which is itself primed with 1·5 grams of fulminate. Very powerful explosions may, in this manner, be obtained. Cast picric acid perfectly resists the shock produced by the firing of a cannon, when contained in a projectile, having an initial velocity of six hundred metres, and produces destructive effects of a kind hitherto unknown.

The following is the process of casting the picric acid: The acid is fused in a vessel provided with a false bottom heated to 130° to 145° C. by a current of steam under pressure, or simply by the circulation of a liquid heated to the desired temperature, such as oil, chloride of zinc, glycerine, etc. The melted picric acid is run into moulds of a form corresponding to that of the blocks required, or it may be run into the projectiles themselves, which should be heated to a constant temperature of about 100° in order to prevent too rapid solidification. The importance of the application of this method is considerable. It has been observed that in large projectiles at a high velocity, ordinary powder, if in small grains, sometimes ignites through the friction which results from its settling down, in consequence of the initial shock, whereas if it is in the form of compressed blocks it resists ignition. For this reason, it is preferred to employ for hollow projectiles picric acid, in compressed powder, agglomerated after pressure, or preferably cast; it thus attains a density of 1·6 to 1·7. This latter mode of use is also more convenient, as it enables the explosive to be cast in receptacles of any form having small orifices, such as shells, torpedoes, tubes, moulds, etc. When required for producing explosions in the open air, for blowing up rails, walls, etc., for military purposes, it is preferable to employ the picric acid in dry powder. In this form it is firmly packed into the cartridge case of tin, copper, or pasteboard, and a priming tube, inserted well into the material, is used, as in the case of gun-cotton or dynamite.

The priming of the picric acid may be effected by the three

Digitized by Google

following means :—(*a*) By the direct employment of a priming of 1·5 gram of fulminate of mercury, which answers well for picric acid in dry powder. (*b*) By employing an intermediate priming of picric acid in powder, primed by the fulminate, which is very suitable when using cast or agglomerated picric acid. (*c*) By dispensing with the fulminate, and employing a sufficiently large charge of ordinary quick-burning powder enclosed in a strong tube, and made to burst inside the charge of picric acid. This last method is of essential importance in connection with artillery.

Picric acid (which is sometimes called carbazotic acid, or trinitro-phenal) is produced by the action of strong nitric acid on carbolic acid, otherwise known as phenic acid, or phenol. Its chemical formula is $C_6H_3(NO_2)_3O$, and it is a true nitro-substitution product, in which three atoms of hydrogen are replaced by three atoms of nitric peroxide. The substance was discovered by Hausmann in 1788, and for many years has had an extensive application for dyeing silk and woollen fabrics yellow. Its intensely bitter taste has also led to its employment for the adulteration of beer, to simulate the bitter of the hop. It has also been used to some extent in medicine. It melts, according to Körner, at 122·5 C. = 252·5° F. when pure; the commercial acid, according to Watts, melts between 114° and 115° C. = 237° and 239° F.

Some of its properties are thus described by Watts : "Picric acid crystallises in light yellow, strongly shining laminæ; in yellowish octahedrons, often very much truncated on two of their summits; yellowish-white needles and granules. . . . Picric acid dissolves in 160 parts of water at 5° C., in 86 parts at 15°, in 81 parts at 20°, in 77 parts at 22·5°, in 73 parts at 26°, in 26 parts at 77° (Marchand). The solution has a deeper colour than the solid acid, and imparts a strong yellow stain to the skin and other animal tissues. Picric acid is likewise easily soluble in alcohol or in ether. It dissolves in warm concentrated sulphuric acid, and is precipitated therefrom by water unchanged. Strong nitric acid dissolves picric acid in large quantities. The acid, when strongly heated, gives off acrid and

Digitized by Google

very bitter vapours, which condense as a sublimate on cold bodies; when quickly heated in a retort it decomposes with explosion, giving off nitrogen, nitric oxide, water, carbonic anhydride, hydrocyanic acid, and a combustible gas, and leaving a carbonaceous residue."

Turpin's Shell.—Fig. 39 illustrates the invention as applied to the charging of shells, with cast (fused) or powdered picric acid, and with or without a priming of fulminate. The drawing represents a longitudinal vertical section of the shell. A is the body, and B the plug containing the priming, in the chamber D of which plug may be placed a charge of quick-burning powder, or picric acid in powder. In this latter case, a priming containing from 0·8 to 1 gram of fulminate should be



FIG. 39.—TURPIN'S SHELL.

attached to the fuze C. E, copper ring surrounding the base of the shell. The chamber D is coned, and also the core which is used to form a cavity for its reception in the fused or cast acid, to enable the said core to be easily drawn out. It will thus be seen that, in order to produce the detonating explosion of the picric acid, or, on the same conditions, that of the compressed gun-cotton or dynamite without the use of fulminate, a cavity is moulded in the charge of compressed, agglomerated, or cast picric acid, to receive the screw-plug, which terminates at its inner end, in a very strong, but brittle, chamber of cast steel or iron, which is filled with very violent gunpowder, or, preferably, with 25 grams of a powder composed of chlorate of potash, tar, and charcoal. The plug is closed by means of the fuze. It will thus be seen that a strong priming of gun-

Digitized by Google

powder is used instead of a priming of fulminate, the only fulminate employed being that contained in the artillery fuze. If it is desired to obtain, either in mines or elsewhere, an explosion without detonation of the picric acid, a small charge of powder should be employed, either wrapped in paper or contained in a waterproof bag, to be ignited by the miner's fuze, the latter having no action upon the picric acid when unenclosed. Under these conditions the picric acid may be employed in mining and excavating generally in the same manner as dynamite and gun-cotton. If the mine is dry, it is sufficient to introduce the picric acid into the hole, either in powder, or in small crystals, or agglomerated, or cast, and to prime it in the ordinary way.

If the mine is wet, or under water, the picric acid must be enclosed in a waterproof envelope of metal, indiarubber, cloth, gummed taffetas, waterproof paper, &c., and primed with a strong priming of dry picric acid in powder which is itself primed by means of a fulminate. The picric acid is almost completely insoluble in cold water, and detonates freely with a priming of 1·5 gram, if it is moistened with three per cent. of water.

Digitized by Google

CHAPTER XII.

DETERMINATION OF THE RELATIVE STRENGTH OF EXPLOSIVES.

ELEMENTS of Comparison of Explosives—Methods of Comparison—Experiments of Captain Noble, Sir F. Abel, MM. Roux and Sarrau, and M. Berthelot—Nobel's Ballistic Test—Calculating the Effect of Dynamite—Apparatus of Kostersitz and Hess for Measuring Shattering Power of High Explosives—Iron-plate Test for Surface Charges of Dynamite—Pressure Gauge—Measurement of Strength of Explosives—Foot-pounds Machine—Quinan's Diagram for Measurement of Pressure—Initial Detonation.

THE most vital question which concerns explosives is the evolution, or rather concentration, of their power, absolute and relative. This is a subject to which serious attention has long been given, without leading as yet to satisfactory results.

It is not only from a theoretical point of view that such knowledge is of importance. The manufacturers of explosives are frequently themselves unable to estimate the relative value of other explosives and their own. The pressure gauges devised give only an approximate idea of their relative power. The strength of a dynamite, or its explosive effect, is made up of three factors. It may be considered as equal to the product of the three :—

1. The amount of the gases formed (that is, their volume reduced to a standard temperature).

2. The temperature of the gases.

3. The reciprocal of the time consumed during their evolution.

In practice, be it in mining or quarrying operations, it is really difficult to make comparative tests. Rock which appears to the eye uniform and quite alike, in blasting often brings to

Digitized by Google

light veins, shakes, or fissures which render a comparison of work done in two contiguous portions impossible—in fact, there is no such thing in reality as to make two bore-holes of equal depth and diameter, where conditions of the material to be blasted are identical.

Methods of Comparison of Explosives. — Explosive power may be estimated in two ways, viz. indirectly by theoretical induction, and directly by measuring the maximal tension of the gas at the moment of explosion, or the mechanical work which it is capable of performing, or what means the same, that at the moment of the dissolution of the solid into gases a certain amount of mechanical work is being done by the pressure of the gases evolved and the heat generated. For gunpowder both methods have been applied, without showing much discrepancy in the final result.

Captain Noble's and *Sir Frederick Abel's* experiments show that the maximal pressure exercised by gunpowder, when the density of the products of explosion is equal to 100, or, in other words, when 1 kilo. of exploded powder occupies the volume of 1 litre, is equal to 6400 atmospheres, or about 42 tons per square inch; that its explosion produces about 705 units of heat, which, multiplied by its mechanical equivalent, represent a theoretic work of 486 foot-tons per lb. of powder.

But highly satisfactory as are those figures, derived from actual measurements, they give no clue to find the absolute or relative power of gun-cotton, nitro-glycerine, and other violent explosives of modern application. These have been considered too powerful and too quick of explosion for even the strongest steel receptacle to resist their action, and hence, as far as we know, no attempt has hitherto been made to measure their explosive pressure by an instrument similar to those employed by Captain Noble and others to estimate the tension produced by exploding gunpowder.

By aid of repeated calorimetric tests made at the Depôt Central des Poudres, Paris, *MM. Roux and Sarrau* have sought

Digitized by Google

to determine how much heat the explosion, or rather detonation, of various explosives produces. They have thus found for

Nitro-glycerine	1784 units of heat
Gun-cotton	1123 ,, ,,
Picrate of potash	840 ,, ,,

which, multiplied by the mechanical equivalent per unit, gives

778	metre-tons per kilo. of nitro-glycerine,
489	,, ,, ,, gun-cotton,
366	,, ,, ,, picrate of potash,

as against

378	,, ,, ,, for the best sporting powder,
and 267	,, ,, ,, ,, ,, ordinary mining powder,

which is of a very inferior quality.

Comparing those figures with the heat produced by the combustion of gunpowder, as found by Sir Frederick Abel (704 units), and taking it as 1·00, the mechanical power which

Nitro-glycerine is capable of performing would rank as .	2·53
Gun-cotton ,, ,, ,, ,, ,, .	1·59
Picrate of potash ,, ,, ,, ,, ,, .	1·19

Berthelot, following a different method, purely theoretical, arrives at much lower figures for the heat produced by the combustion of the same substances, and consequently also for the amount of work it represents. He admits that at the very high temperature, which is a very general feature of explosive combustion, no complex chemical combination can exist, and that only elementary compounds, such as water vapour, carbonic oxide, and carbonic acid will be formed; so that when the chemical composition of such explosive substances is known, which are entirely converted into gas, it is easy to determine, without recourse to experiments, the nature of the gaseous products formed at the moment of their explosion. Hence, for instance, nitrate of ammonium, of which the formula is $NH_4\,NO_3$, would split up into

$$N_2 + O_2 + (H_2\,O)_2.$$

Starting from this point of view, the correctness of which cer-

Digitized by Google

tainly does not appear to admit of the slightest doubt, Berthelot computes, from well-known tables, the heat produced by the formation of the gaseous products from their elements. He further eliminates the units of caloric developed in the formation of the explosive substance to be dealt with from its elements, and takes it for granted, of course, that as much heat must be absorbed in disuniting the chemical tie as was freed in forming it. The heat lost in that operation he deducts from the sum of heat produced by the reunion of the disconnected elements, the balance representing the heat really developed by the explosive combustion. Thus, for each 227 grams of nitro-glycerine, which the explosion transforms entirely into carbonic acid, water, nitrogen, and oxygen, Berthelot calculates the heat produced by the formation of the carbonic acid and water from the elements of 430,500 units, and the heat produced by the formation of the nitro-glycerine itself from its prime elements at 130,500 units, which, deducted from the total of 430,500, leaves 300,000 units of caloric freed, or 1320 units per gram of nitro-glycerine exploded.

Nobel's Ballistic Test.—Various devices have been employed for testing the power of explosives, and to measure their relative strength, and the first in use was that adopted by Nobel. He made use for several years of a method based on measurement of the ballistic power of explosives; and though certainly open to some objections, it has the advantage of being extremely handy and sufficiently accurate for the object in view.

A mortar test is indeed more reliable for comparing detonating explosions than for slower compounds; for in the latter case, the projectile may have left the mortar before the combustion is completed, while, in the case of fulminates, their explosive conversion is so rapid that in all probability it is completed before the projectile has begun to move at all, thus acting upon it with the whole force of its initial tension. This is further confirmed by the fact, that the bore of the mortar can be made far shorter than for testing gunpowder, without any considerable falling off of the range of projection. The con-

Digitized by Google

clusions which he drew from a series of experiments were that if the ballistic power of detonating

Nitro-glycerine is expressed by	100·0
Compressed gun-cotton, weight for weight, ranks as . .	71·0
Dynamite of 28% guhr and 75% nitro-glycerine ,, . .	72·0
Ammonia powder . . . . . ,, . .	83·0
Gunpowder mixed with 20% nitro-glycerine ,, . .	50·0
Gun-cotton ,, ,, its own weight of nitro-glycerine . . . . . ,, . .	83·0
Curtis and Harvey's strongest blasting powder detonated with a cap . . . . ,, . .	28·0
Fulminate of mercury . . . . . ,, . .	30·0
Lithofracteur of the strongest kind . . . ,, . .	50·5

In this estimate no deduction has been made for the power exercised by the fulminate of the detonator caps, it being the same for all preparations except gun-cotton, for which 0·16 additional weight of fulminate was used.

Interesting as it may be to compare the relative power of explosive substances, weight for weight, the power which they are capable of exercising, bulk for bulk, is of far greater importance in their application to blasting.

It is easily computed when their specific gravity is known, which has been found

For nitro-glycerine	1·60
,, gun-cotton	1·00
,, dynamite No. 1	1·65
,, ammonia powder	1·55
,, gunpowder	1·00
,, lithofracteur	1·20
,, dynamite No. 2	1·20

When their power is compared, bulk for bulk, the various explosives range as follows :—

Nitro-glycerine	100·0
Ammonia powder	80·0
Dynamite No. 1	74·0
Lithofracteur	53·0
Gun-cotton	60·0
Curtis and Harvey's blasting powder fired by detonator	17·5

Digitized by Google

Calculating the Effect of Dynamite.—To calculate the pressure developed by the explosion of a charge of dynamite in a bore-hole, let us suppose a bore-hole three centimetres in diameter, charged with one kilogram of dynamite No. 1, containing 75 per cent. of nitro-glycerine.

The pressure in kilograms developed in the bottom of the bore-hole by the explosion gases is determined according to the formula, Vieille and Sarrau :—

$$P = \frac{V_0 \left(1 + \frac{Q}{273.\,c.}\right)}{V - v}$$

in which the letters have the following meaning :—

V_0 the volume, reduced to 0° and a pressure of 760 mm. of the gases produced by a unity of weight of the explosive.

Q the number of calorics disengaged by the explosion of a unity of weight of the explosive.

c the specific heat, at constant volume of the gases.

V the capacity in cubic centimetres of the unity of weight of the explosive.

v the volume occupied by the inert materials of the explosive.

The volume of gases produced by 1 kilo. of nitro-glycerine at 0° and under a pressure of 760 mm., is, according to the experiments of Vieille and Sarrau, 467 litres.

We can therefore take for V_0 :—

$$V_0 = 0{\cdot}75 \times 467$$

equal to

$$V_0 = 350.$$

According to Bunsen and Schiskoff, 1 kilo. of dynamite No. 1 disengages 1290 calorics.

The specific heat c is 0·220 according to Sarrau's calculations.

At last, the density of the dynamite being equal to 1·500, we deduct therefrom :

$$V = \frac{1}{1{\cdot}500} = 0{\cdot}666.$$

Digitized by Google

If we estimate at 0·100 the volume of the kieselguhr, we find from the preceding formula that the following values will represent the letters :—

$$P = \frac{350\left(1 + \frac{1290}{273 \times 0{\cdot}220}\right)}{0{\cdot}666 - 0{\cdot}100} = 13{,}900 \text{ atmospheres.}$$

To transfer this quantity into kilograms pressure per square centimetre, it is only necessary to multiply the same by the weight of a column of quicksilver $0^{m}{\cdot}760$ high and 1 centimetre square section, which is equal to augmenting it by $\frac{1}{30}$.

$$Pk = Pa\left(1 + \frac{1}{30}\right) = 14{,}317 \text{ kilograms.}$$

In applying the formula to the explosion of gun-cotton, and taking :

$$Q = 1075 \text{ (Berthelot)}$$
$$C = 0{\cdot}2314$$
$$V = \frac{1}{1{\cdot}50} \text{ (absolute density } 1{\cdot}50)$$
$$V_0 = 671 \text{ litres (Vieille and Sarrau)}$$
$$v = O$$

we find :

$$P'a = 18{,}135 \text{ atmospheres}$$
$$P'k = 18{,}740 \text{ kilograms.}$$

The explosion of 1 kilogram pure nitro-glycerine gives :

$$P''a = 18{,}533 \text{ atmospheres}$$
$$P''k = 19{,}151 \text{ kilograms.}$$

Apparatus of Kostersitz and Hess for Measuring Shattering Power of High Explosives.—The usefulness of an explosive is determined not only by its special properties and by the form in which it is used, but also and largely by the medium in which it is to be detonated. When an opinion is required regarding the efficiency of an explosive, the trials should be made under conditions similar to those

Digitized by Google

which will obtain in practice, and therefore the quarryman should try it in his quarry, the miner in his mine, and the engineer in his tunnel, before deciding upon using it. For practical purposes this method is the best, but it often happens that we are called upon for an opinion on the efficiency of an explosive when there are no opportunities available for the test by actual blasting, and hence some other method of testing must be resorted to.

FIG. 40.—APPARATUS FOR MEASURING SHATTERING POWER OF EXPLOSIVE.

The iron-plate test is one of the best known of the methods proposed for use under these circumstances, but the explosion of surface charges of an explosive upon an iron plate gives us a very imperfect idea of the probable effect of the same explosive if exploded when confined in a bore-hole. For this reason the following device, invented by Lieut.-Colonel Kostersitz and Captain Philip Hess of the Austrian Army, is used by the Technical Commission of Explosives in Vienna for determining the relative efficiency of the explosive substances intended for use in blasting.

The arrangement consists of a piece of gas-pipe 33 millimetres in the interior diameter, and 0·5 metre long, as shown in Fig. 40. Seventeen grams of the explosive are enclosed in a tin cartridge-case which has an exterior diameter of 31 millimetres, and this is inserted in the gas-pipe to the point *a*. Below the tin case and in contact with it is a plate of Bessemer steel, *b*, 3·3 millimetres thick and 31 millimetres in diameter. Next to this is the lead cylinder *c*, which is 20 millimetres thick. Next comes the steel cylinder *d*, terminated at each end in a truncated cone. And finally another lead cylinder *c'*, similar in every respect to *c*, is placed below *d*. The remaining space in the pipe is tamped with sand, and the ends of the pipe are plugged with clay stoppers. In order to adjust the parts

Digitized by Google

with precision, they are first exactly arranged within a paste-board cartridge-case, which has an interior diameter of 31·5 millimetres, and an exterior diameter of 32 millimetres, and this is then placed within the pipe. As the explosive is fired by an electric fuze, the wires are led through the sand-tamping and plug. When the filling is completed, the pipe is embedded vertically in the ground for two-thirds of its length, and then fired.

After the explosion, the pipe is found to be swollen and broken at the point where the charge was located, so that the steel plate and the lead and steel cylinders may be easily removed. The lead cylinders will exhibit regular conical indentations on the faces which were in contact with the conical terminations of the cylinder, and as the dimensions of these indentations may be easily determined by measurement, we can ascertain from them the relative amount of work which different explosives would perform when exploded in a confined space. From a comparison of similar dimensions of the upper and lower lead cylinders, we are enabled also to determine the relative shattering power of the explosives; for if the upper one, or that nearest the charge, shows the deeper indentation, the explosive exerts a shattering effect, while, if the indentation in the lower one is the deeper, the explosive exerts a pushing or propelling effect.

Of course, this method gives only approximate results as to the actual amount of work which different explosives would do when put to practical use in rocks of different degrees of hardness.

Iron-plate Test for Surface Charges of Dynamite.—This consists in estimating the strength of an explosive by its effect in smashing an iron plate of standard thickness and tenacity, when exploded in certain charges on its surface. The test is very delusive, though of value in determining certain other important qualities. *Sir Frederick Abel* has shown that weaker explosives sometimes show better results by these tests than stronger ones; in fact, the experiment is rather a test of the completeness of detonation, and of the rapidity of explosion, than of the force which becomes available in rending rock.

Digitized by Google

An easily managed apparatus for measuring the intensity of explosives which is now extensively utilized by many manufacturers both in Europe and America, may be described here. It consists of an iron ring or collar, which is chamfered out on the upper surface, so as to form a seat wherein a circular iron disc can be placed. These discs should be only supported on their outer edges, and the blow of the explosion should not meet with any resistance except that of the disc itself, and therefore these discs cannot be laid on any solid substance.



FIG. 41.—COLLAR ON WHICH DISCS ARE EXPLODED.



FIG. 42.—STEEL DISC, ¼ INCH THICK, BEFORE EXPLOSION.

Fig. 41 shows the collar on which the discs are exploded. Fig. 42 is a steel disc, a quarter of an inch thick—*before* the explosion.



FIG. 43.—STEEL DISC, ¼ INCH THICK, AFTER EXPLOSION OF 20 GRAMS DYNAMITE.

FIG. 44.—FUZE AND CARTRIDGE (¼ OZ. OF DYNAMITE).

Fig. 43 is a steel disc of the same thickness—*after* explosion of 20 grams of dynamite. Fig. 44 shows a fuze and cartridge of a quarter of an ounce of dynamite.

Digitized by Google

By exploding small charges of uniform weight on plates of the same thickness, the experimenter very soon becomes accustomed to judging of the intensity of the explosive by the manner in which the iron discs are pierced, and by the radius of the fractures which are formed.

Fig. 45 shows a steel plate five-eighths of an inch thick —after explosion of 7 ozs. of dynamite; and Fig. 46 a steel plate



Front.

Back.

FIG. 45.—STEEL PLATE, $\frac{5}{8}$ INCH THICK, AFTER EXPLOSION OF 7 OZS. OF DYNAMITE.

Scale, less than one-third.



Front.



Back.

FIG. 46.—STEEL PLATE, $\frac{15}{16}$ INCH THICK, AFTER EXPLOSION OF 14 OZS. OF DYNAMITE.

Scale, less than one-third.

fifteen-sixteenths of an inch thick—after explosion of 14 ozs. of dynamite.

The Pressure Gauge is mostly adopted by manufacturers to estimate the force of their explosives. As shown in Fig. 47, it consists of a heavy block of wood, A, upon which is bolted a cast-iron block or base, B, B, B. In this base are inserted four

Digitized by Google

wrought-iron guides or standards, C, C, set around the circumference of a 4-inch circle. The lead plug D rests upon a steel plate (not apparent in the drawing), which is let into the iron block flush with its upper surface. A ring, E, holds the guides C in place at the top, passing through the ring, which is held down by nuts, F.

The piston H (also Fig. 48), which is the piece resting on the plug of lead, is a cylinder of tempered steel, 4 inches in diameter and 5 inches in length. It is turned away at the sides to lighten it as much as possible. It moves freely between the guides. In



FIG. 47.—PRESSURE GAUGE.

FIG. 48.—PISTON OF PRESSURE GAUGE.

FIG. 49.—SHOT OF PRESSURE GAUGE.

the top is a parabolic-shaped cavity to hold the charge of explosive, N (Fig. 48). The weight of the piston is $12\frac{1}{4}$ lbs.

The shot I (also Fig. 49), made of tempered steel, is 4 inches in diameter, and 10 inches in length, weighing $34\frac{1}{2}$ lbs. It is bored through its axis to receive a capped fuze.

To put the instrument in operation a plug of lead is placed upon the steel plate within the guides. The piston is put down gently upon it, and the charge of explosive placed in the

Digitized by Google

cavity N. The shot is next lowered gently upon the piston, and the capped fuze pushed down through the hole in the shot. The fuze being lighted, when the fire reaches the cap the charge is exploded, throwing out the shot and compressing the lead plug. The accuracy of the test is based upon the assumption that the lead plugs shall be of uniform density and homogeneous structure.

The form of plug used is a cylinder, an inch in diameter and an inch in length (Fig. 50).

FIG. 50.—LEAD PLUG.

The lead cylinders used for these experiments are cut out from lead bars which are manufactured from large masses of metal melted at a high temperature; it is dense and uniform, and can be obtained in lengths of 50 feet. These plugs are more uniform than those cast separately in moulds from small masses of metal.

In making these tests it must be considered that the lead plug, while being compressed by the explosion in the pressure gauge, the density of the plug as well as the lead surface opposed to the piston continually increases. It is self-evident from this that the amount of compression shown by the plug is not a direct measure of the strength of the explosive. For illustration: if one explosive exploded in the pressure gauge compresses a plug $\frac{250}{1000}$ inch, and another explosive compresses a plug $\frac{500}{1000}$ inch, the latter explosive would be twice as strong as the former if the compressions were direct measures of relative strengths. But in fact, the latter explosive is more than twice as strong. The problem was—how much? The strength of the explosive is proportional to the *work* performed in reducing the height of the lead plug. To get an expression for the work, it was only necessary to find the number of foot-pounds required to produce the different amounts of compression.

Measurement of Strength of Explosives.—Mr. J. Trautzl, general manager of the Nobel Dynamite Works in Austria, tests the powder by firing it in a cavity in a cylinder

Digitized by Google

of lead, and measuring the size of the cavity produced by the explosion by water poured into it from a graduated tube. The apparatus is shown in Fig. 51.

It consists of a lead cylinder, B, B, 8 inches high and 8 inches in diameter, in the centre of which is a hole 1 inch in diameter, and drilled to such a depth that the centre of the test-charge coincides with the centre of the test-cylinder, that is, 4·75 inches deep. The charge, ½ oz., is wrapped in parchment paper or put in a tin box, and provided with cap and fuze. The hole is then tamped with a closely fitting lead



FIG. 51.—TRAUTZL'S APPARATUS FOR TESTING STRENGTH OF EXPLOSIVES.

stopper, *p*, *p*, through the centre of which a hole is drilled to permit the passage of the fuze. Latterly this lead stopper has been abandoned, and plastic clay, not too wet, substituted. The cylinder is laid between two steel plates, 1 inch in thickness, S, S, and the whole apparatus is then wedged in a wrought-iron frame, Z, Z, by means of the steel wedges *k*, *k*.

The explosion is hardly audible, and it is entirely safe for the observer to stand in close proximity to the apparatus. The lead cylinder is the only part of the apparatus which is changed in form by the explosion; the central cylindrical hole being widened to a bottle-shaped cavity. The cubic measurement of this cavity will differ with the different kinds of

Digitized by Google

explosives used, and is ascertained by pouring in water from a glass tube graduated in cubic centimetres.



Example 1. Example 2.

FIGS. 52, 53.—DIAGRAMS ILLUSTRATING RESULTS WITH TRAUTZL'S APPARATUS. Two explosions, Dynamite No. 4.



Example 1. Example 2.

FIGS. 54, 55.—DIAGRAMS ILLUSTRATING RESULTS WITH TRAUTZL'S APPARATUS. Two explosions, Reime Gelatine.

Figs. 52, 53 and Figs. 54, 55 show the effect of explosives

Digitized by Google

on the lead in cases where dynamite and reime gelatine respectively were the subjects of test; and the subjoined table shows the results arrived at in a series of experiments—

Number.	Name of explosive.	Composition of the explosive.	Cubic contents of cavity in the dead cylinder				
			Before the explosion. cubic cms.	After the explosion, in cubic centimeters.			
				Test I.	Test II.	Test III.	Average.
1	No. 1 Dynamite old	75% nitro-glycerine, 25% kieselguhr	50	980	920	960	953
2	No. 1 Dynamite new	60% nitro-gelatine, 40% explosive absorbents	50	1200	1200	1250	1217
3	No. 2 Dynamite .	75% nitro-gelatine, 25% explosive absorbent	50	930	950	970	950
4	No. 3 Dynamite, with primer . .	25% nitro-glycerine, 75% explosive absorbent	50	700	740	720	720
5	No. 3 Dynamite .	15% nitro-glycerine, 85% explosive absorbent	50	590	550	590	577
6	Nitro-gelatine . .	— — —	50	1500	1550	1500	1517
7	Nitro-glycerine . .	— — —	50	1790	1750	1790	1777

Foot-pounds Machine.—Lieutenant Quinan, of the U.S. Army, has devised an apparatus which is shown in Fig. 56. It consisted of three boards, forming a slide 16 feet high, in which a weight (the shot of the pressure guage) could fall freely. One of the boards was graduated into feet and half-feet. The horizontal board at the bottom, upon which the others were nailed, rested on a heavy post set deep in the ground. A round tenon formed on the top of the post projected through a hole in the board. On the top of this tenon, turned bottom upwards, was placed the piston of the pressure gauge. This served as the anvil, and on it the plugs were placed. The fuze-hole of the shot was plugged with a large wire, which projected through the top and gave a hold for a simple form of clutch, by means of which and a light rope passing over a pulley at the top of the structure, the shot was hoisted to any desired height. The clutch was released by hand from a ladder.

With this apparatus the uniformity of the plugs is tested. It was found that plugs cast separately in mould were of no value for these tests, and had to be rejected. The plugs cut

Digitized by Google

from drawn lead gave satisfactory results. These plugs were carefully measured before compression and again after compression, by taking the average of several measurements. The difference between the original length and the reduced length gave the compression caused by the blow of the shot in falling. The instrument used in

FIG. 57.—MICROMETER CALIPERS.

measuring the plugs is the micrometer calipers shown in Fig. 57 (manufactured by Messrs. Brown and Sharp, of New York).

This instrument is exceedingly accurate and convenient: it reads to the thousandth part of an inch, and even this space can be readily divided.

The more uniform structure of the drawn plugs, as compared with the cast, is apparent



FIG. 58.—DRAWN LEAD PLUG AFTER COMPRESSION.



FIG. 59.—CAST LEAD PLUG AFTER COMPRESSION.

FIG. 56.—FOOT-POUNDS MACHINE.

in the different appearances of the two after reduction in the pressure gauge, or in the foot-pounds machine. The drawings (Figs. 58 and 59) show this better than description. Having adopted the drawn plugs, Lieutenant Quinan constructed a table for

Digitized by Google

converting the compressions of the drawn plugs into foot-pounds, or actual measures of the strength of explosives. This was simply and expeditiously done by making several series of experiments in dropping the shot from various heights, beginning with a half-foot and going up a half-foot at a time to about 16 feet. An average of all the compressions at a given height was assumed as correct. The height multiplied by the weight of the shot gave the foot-pounds corresponding to that particular compression.

Diagram for Measurement of Pressure.— To more graphically represent the relations between the plug compressions and foot-pounds, as well as for convenience in work, Lieutenant Quinan constructed a diagram, using the compressions as the ordinates, and the foot-pounds as the abscissæ of a curve. This diagram is shown on a much reduced scale, and without detail, in Fig. 61.

The extreme co-ordinates are fixed by nitro-glycerine.

The original diagram, 21 × 14 inches, has been relied upon for converting plug compressions into foot-pounds, or units of strength.



FIG. 60.—SECTION OF PLUG SHOWING REDUCTION IN PRESSURE GAUGE.

In using the diagram, the figures in the "scale of plug compressions" represent thousandths of an inch. The amount of compression received by the plug is ascertained by deducting its measurement after coming out of the pressure gauge from the measurement made before explosion. The difference is, of course, the compression received, in thousandths of an inch. Find the point in the "scale of plug compressions" corresponding with the amount of compression ascertained. From this point follow the perpendicular lines until the curved line is reached. Then from the point in the curved line so reached follow the horizontal lines to the "scale of foot-pounds." The figure there reached is the equivalent in foot-pounds of the compression.

Digitized by Google

The standard charge for this pressure gauge is 24 grains.

This system gives a comparative measure for high explosives. This pressure gauge is not, however, an accurate test for lower explosives. A triple charge of good black blasting powder fired with a fuze will produce a scarcely perceptible effect on the plug, and yet we know that this powder is capable of great work in certain kinds of rock. We may suppose, without an



FIG. 61.—QUINAN'S DIAGRAM FOR MEASUREMENT OF PRESSURE.

error affecting our principle, that, in firing 24 grains of high explosive, the product of the amount of gas multiplied by the temperature of the gases gives a number equal to the product of the corresponding elements in the explosion of triple the charge of black powder. But in one experiment we get a compression which is almost infinitely greater than in the other; for in the last we get a result too small to be measured. It is because the third factor in our formula for explosive effect—time—bears a similar but inverse ratio in the two cases; in the first being inconceivably short, and in the second case a sensible interval.

In the explosion of the black powder, the force, though great, is developed so gradually, that at no one instant is enough inertia developed in the shot to produce a sensible compression of the lead.

Digitized by Google

Initial Detonation.—I have already referred to the relative value of quick and slow explosives. Given a particular piece of work to be accomplished, it may well be that, of two explosives available, the more powerful one may, for want of quickness of combustion, be the less efficacious for the purpose in view. This drawback of the slow action of the more powerful explosive may be overcome by adopting the method of firing explosives which is known as the *detonating ignition*. It consists in applying a *strong local explosion* instead of a spark or flame.

It is especially in connection with nitro-glycerine that this mode of ignition has led to remarkable results, and it was to suit the peculiar nature of that substance that it was invented. Nitro-glycerine, indeed, without that special firing, though it is an explosive, is not a blasting agent, as it cannot be applied with any degree of certainty that it will go off. Not so when fired by a local explosive. It not only detonates without any confinement, but it affords an extraordinary facility for setting off substances which, without its aid, are absolutely inexplosive. If, for instance, charcoal and nitrate of potassium are mixed without sulphur, they form no explosive compound within the ordinary meaning of that term; but if from 10 to 15 per cent. of nitro-glycerine is added, a local explosion, produced by a strong detonator or fulminate cap, will cause the almost inert mixture to detonate with nearly the same rapidity as the nitro-glycerine itself. Nitrate of ammonium and charcoal, with or without sulphur, form a mixture so sluggish at the ordinary temperature, that when tried in a shell along with 6 ozs. of gunpowder, the explosion of the latter failed to set it off, or even to inflame it; yet mixed with 15 per cent. of nitro-glycerine, it detonates with an extraordinary violence. Saw-dust, bark, resin, starch, sugar, glucose, flour, dextrine, gum, &c., mixed with any nitrate, become, if a small portion of nitro-glycerine is added, most violent detonating fulminates. Nor is that all. Substances considered as absolutely incombustible will form explosives; for instance, chloride of ammonium, mixed with nitrate of potash and nitro-glycerine, will decom-

Digitized by Google

pose explosively with the formation of chloride of potassium, and the freed hydrogen unites with oxygen of the nitrate. Sulphates are very much more sluggish; but if very finely divided and mixed with charcoal, they also indicate a decided reaction, although too slow to be completed in the extremely short time which an explosion occupies. Chlorate of potash mixed with nitro-glycerine detonates even without the presence of charcoal or any other combustible. The number of organic compounds, soluble or even insoluble in nitro-glycerine, which can thus be brought to detonate is almost unlimited.

In practice it will be found of great advantage, when blasting large charges of ordinary mining powder, to fire them with a primer of dynamite or gun-cotton. The initial detonation will cause a more rapid combustion of the gunpowder, and tear the rocks asunder with more certainty than when the powder is fired with an ordinary fuze. This causes a more gradual development of gases, which in some cases are not capable of overcoming the resistance of the rocks, and the charge becomes smothered without performing its work.

This extraordinary influence which the presence of nitro-glycerine exercises on slow explosives, and even seemingly inert substances, is easily accounted for. Being a liquid, it comes in very close contact with the mixtures, and when the detonation ensues, the fine layer of nitro-glycerine which adheres to every grain is instantaneously converted into an extremely dense atmosphere of gas, having a temperature of at least 3000° to 4000° C. Such a bath must quicken even the slowest combustion. This explains the great success of Judson powder, where the dope is mixed with only 5 per cent. of nitro-glycerine, forming quite a formidable explosive.

It is exactly the same cause which makes gunpowder burn with extreme quickness in a gun, while its combustion in the open air is comparatively slow. When confined, the hot gas accumulates in proportion as it is being generated, and the denser it grows the more heat it brings to bear on the reaction, which thus becomes almost instantaneous.

The action of the detonator cap in setting off nitro-glycerine

Digitized by Google

and other explosives is far more complicated, and not so easily explained. Some attribute it only to the heat produced by compression, some only to the heat of the gas given off by the fulminate of the cap, and others, again, to the dissociating power of a strong vibration. It is not unlikely, at least in some instances, that all those influences are brought to bear on the explosion, but it would be very difficult indeed to compute the part contributed by each. There can be no doubt as to the dislocation of certain unstable compounds by vibration alone, since the slight shock which sets off chloride and iodide of nitrogen, perchlorate of ethyl, &c., cannot possibly raise their temperature, even locally, to the degree at which they explode. Even in the case of nitro-glycerine, which exhibits no such extreme sensitiveness, direct experiments have shown that very violent vibration can cause it to explode. But if vibration alone suffices to set off nitro-glycerine, it is still less doubtful that heat alone will do it. Not only does it detonate by being raised to the temperature at which its constituent elements associate, but a minute charge of gunpowder, so slightly confined that the gas which it produces has a very feeble tension, never fails to make it detonate. It suffices, indeed, to apply heat in any shape, so that it acts upon a very large surface of nitro-glycerine, for then the gas evolved can no longer escape as quickly as it is produced, and the pressure, accumulating with immense rapidity, brings on the explosion.

Nitro-glycerine preparations and gun-cotton go off easily under the influence of a sharp local explosion, such as is produced by a fulminate. Two opposite tendencies are here at work, with one to set off the explosive, acting on it by heat, vibration, or whatever cause it may be, and the other to throw it away by the propelling impulse due to the expanding gas. Both must be extremely quick in operating, and it is therefore easy to see how a slight, apparently insignificant, difference may turn the scale and cause an explosion or a miss-fire. For instance, in grinding chlorate of potassium and sulphur with care in a mortar, a series of small detonations take place,

Digitized by Google

which do not spread, but a somewhat stronger blow or friction will set off the whole. Evidently in one case the propelling power is preponderant over the igniting tendency, in the other it is not. Even the quickest substance requires time to get heated, and unless the velocity implanted allows that time, combustion cannot take place.

Sir Frederick Abel found by repeated experiments that a charge of fulminate amply sufficient to set off compressed gun-cotton failed to explode the same material in a loose form; but by twisting loose uncompressed gun-cotton round the cap, and securing it well with a string, so as to increase its density and resistance to projection, it is brought to detonate with great facility without increased charge of fulminate. It has also been found that loose gun-cotton detonates more readily if impregnated with quite inert substances than in its isolated state, evidently because the additional weight opposes additional resistance to motion, thus allowing time.

The reasoning which led to firing slow explosives by local detonation was this: When a hammer strikes a very thin layer of nitro-glycerine on an anvil, the blow produces a strong compression of the liquid, which liberates heat, and raises its temperature to the point at which it detonates. But only that part which actually receives the blow explodes. If, however, the hammer is very heavy, and the blow strong, the explosion is not confined to the part which receives the direct shock, and the whole goes off. A local detonation, owing to the immense tension of its gas, must be very similar in action to a strong blow, and it will thus compress the explosive liquid which surrounds it, causing it to detonate at will, and to propagate the explosion throughout the whole mass by the same means. When firing large masses of ordinary mining powder or Judson powder, it is always best to use a dynamite primer, as better results are obtained, owing to the more rapid and complete combustion of the powders.

Digitized by Google

CHAPTER XIII.

CONDITIONS TO WHICH MODERN EXPLOSIVES SHOULD RESPOND.

CONDITIONS of Strength—Quick Explosion desirable for Blasting—Internal Resistance to Detonation — Conditions of Safety—Immunity against Fire—Decomposition—Leakage—Deliquescence—Unstable Character of Deliquescent Explosives—Resistance to High Temperature—Insensitiveness to Friction, Shocks, and Jars—Percussion — Concussion—Transmission of Explosion—Tamping—Purity of Explosion Gases—Detection of Nitro-glycerine in the Human Body—Precautions during Manufacture of Explosives — Explosions due to External Causes—Action of Explosives Department of Home Office.

Conditions of Strength. — The strength of a nitro-glycerine explosive is influenced by several things :—

1. By the amount of nitro-glycerine present.
2. By the amount of gas in proportion to the solid matter appearing in the explosion.
3. By the kind and character of the gases.

With the dynamites the strength is not proportionately dependent upon the amount of nitro-glycerine. It will be found that within certain limits an increase or decrease of the nitro-glycerine will affect the strength of the dynamite but little. Any inert substances used in the explosive will appear as such in the explosion; but this is not the case where the absorbent is an explosive base or dope, as in such dynamites a large amount of the power developed is contributed by that explosive base. An approximate estimation of this power can be computed by the mortar test, and for that purpose it suffices to make out the quantity of nitro-glycerine contained in a

Digitized by Google

compound, and compute the distance of projection to which it would carry the projectile of the testing mortar. Then fire a shot with the compound containing the explosive base: the balance of projection is due to the other ingredients, and permits of a tolerably near estimation of their relative power. It is true that the gaseous products of the exploded nitroglycerine and those of its explosive partner may react on each other, and cause a slight loss or gain of power, but it cannot materially alter the relative value of the two components.

Quick Explosion desirable for Blasting. — Under certain conditions, otherwise similar, a quick explosion is preferable to a slow one for blasting. The same amount of expansion is produced in either case, but the maximal tension of the gas developed may be vastly different, and on that tension depends the blasting power. For instance, mealed gunpowder under certain conditions burns with a tension scarcely sufficient to burst a straw, yet the same substance, under other conditions, becomes capable of tearing the hardest rock. The difference in action is due only to a difference in the rapidity of combustion.

It is therefore clear that, of two explosives, the more powerful one may, for want of quickness of combustion, be the less efficacious for blasting. It becomes then a matter of considerable importance to possess a ready means of overcoming the drawback of this slow action, and as already explained (page 182), the difficulty is met by means of *strong local explosions*, either with *strong detonators* or with *primers*.

Internal Resistance to Detonation.—An explosive which is carefully compounded with reference to the chemical relations of its elements, and which gives in theory a nearly perfect resolution into gas, sometimes fails to show the strength naturally expected. This leads to the theory of internal resistance to detonation offered by different substances. *Lieut. Quinan*, in a discussion on this very interesting phenomenon, remarks: "In being converted into gas, the cohesion of the particles, as well as the chemical attraction which unites the atoms, must be overcome. Work expended in this direction is lost in

Digitized by Google

overcoming external resistance, or in strength, as shown by the pressure gauge. The work done in the drug-mill in reducing the ingredients to dust is saved to the explosive, and reappears in its greater efficiency in breaking rock."

Conditions of Safety. — *Immunity against fire* exists only to a certain extent. The statement that dynamite can be set on fire, and that it will burn away without exploding, is not quite correct, and is a very broad assertion. There have been instances where large quantities have taken fire and burned away without exploding, but unfortunately there have been instances also where large quantities of dynamite have been accidentally set on fire, with most disastrous results. Small quantities, and sometimes even large ones, may possibly burn away with immunity, but there is always the danger that the burning explosive will heat the portion not ignited to its exploding temperature, especially when in large masses. One of the peculiarities of dynamite is that it burns or takes fire at a lower temperature than its explosion temperature, and this accounts for its property of burning some time away without exploding.

Decomposition.—In order that the explosive may be kept and stored with safety, it must be free from any tendency to decompose. It will not decompose if it has been properly made and purified. The effect of a high temperature is to mature the seeds of decomposition, if they exist. Chemical decomposition is productive of heat, which sometimes leads to ignition and explosion.

Decomposition, in all classes of nitrated organic compounds, may be thus accounted for: After their nitration a certain portion of acid—sulphuric, nitric, and hyponitric —always adheres to those compounds, more or less, according to their form and structure. From a liquid explosive substance the acids are easily washed out, by churning it with water first and then with alkaline solution. It is quite clear that if the last traces of acids are not perfectly washed out, and that if especially hyponitric acid is present, which is a

Digitized by Google

highly corrosive material that attacks almost every organic compound, even at the ordinary temperature, it has to be removed; if not, it will slowly, but surely, lead to incipient decomposition, which, acting on a nitrated substance, sets free portions of dioxide of nitrogen or hyponitric acid.

From nitro-glycerine the corrosive acid is washed out with the utmost facility, and from the moment when the importance of that operation became fully appreciated it has never been neglected. Hence the chemical stability exhibited by dynamite under all conditions of climate. It sometimes indicates an acid reaction; but that is due to the absorbent, and not to the slightest trace of hyponitric acid present.

Leakage.—The most important quality for safety is that the nitro-glycerine shall not leak out of the powder. This is a practical return of the nitro-glycerine to the liquid condition, and if it leaks it is a failure as a safe explosive. Besides being a direct loss of strength, leakage is the source of a great many accidents. The exuding nitro-glycerine saturates the paper cartridges, the sawdust surrounding them, oozes through the crevices of the boxes, gets into the holds of vessels, the floors of cars, the walls of magazines, and a hundred other improper places, where it may cause an unexplained accident. The effect of high temperature is to make the nitro-glycerine more fluid, and nitro-glycerine explosives are more liable to exudation in warm than in cold weather.

Deliquescence.—If deliquescent salts, or other substances which attract moisture, are present, the explosive becomes sensitive to hygrometric and thermometric changes. The effect of a deliquescent salt like nitrate of soda in absorbing moisture in damp atmospheres is, however, not the only argument against it and similar salts.

The theory of deliquescence involves other and more important considerations. The great aim of any manufacturer of explosives should be to give a stable, reliable and uniform character to the powder or explosive he brings before the mining public. If we could know beforehand the conditions to which each case of explosive and each individual cartridge

Digitized by Google

in it shipped from the factory would be subjected, the problem would be easier. If we could know that the explosive would not be subjected to atmospheric changes, the temptation to use a cheap and powerful agent would be irresistible. But we have no right to assume this. Explosives are frequently exposed to the weather, sometimes frozen, sometimes heated rapidly by thawing; now rained upon, now warmed by the sun's rays, now they are transported in ships over oceans where the air is charged with a constant, penetrating dampness, and during transit they undergo changes of temperatures, leaving a temperate climate to cross the torrid zones of the tropics, to be carried into a temperate zone again: then to be used in damp mines, and also in atmospheres heated by chemical action in the rocks. Under these varying conditions, an injurious action accompanies the use of deliquescent ingredients. First, when the air is damp the explosive rapidly absorbs water, to the injury of its strength.

Constant atmospheric changes will act so injuriously on such explosives as to spoil them entirely. A deliquescent salt, by absorbing moisture, overloads the absorbents with moisture, and drives out the nitro-glycerine, if such is present in the explosive, a loss which cannot be restored, as well as a source of danger.

In some cases the explosive compound becomes so spoiled that it will not explode at all, and what does the miner think of an explosive which will miss fire, when after many hours of hard labour he has drilled his hole and it fails to do its work? We all know that repeated miss-fires will destroy confidence in an explosive.

But this is not all. There is an additional objection, the theory of which is best illustrated by a very simple experiment. Take a glass of water and place a thermometer in it. We will suppose it indicates 65° F. Drop into the water about half its weight of nitrate of soda. The temperature is rapidly reduced to about 32° F. While the salt is uniting with the water, a large amount of heat is rendered latent, causing a reduction of temperature. Supposing the quantity of water

Digitized by Google

used to be one pound, this reduction of temperature represents work expended to the amount of about twenty-five thousand foot-pounds.

Now let us reverse the conditions. Take a quantity of the salt saturated with moisture, and expose it to a drying atmosphere, so that it loses its moisture rapidly. The temperature of the salt is now curiously elevated, for the heat rendered latent before, becomes sensible now.

The progress of deliquescence is thus explained. The air confined in the cartridge contains a slight quantity of moisture, which, in uniting with the salt, causes a depression in temperature, which condenses fresh moisture from the surrounding air, as a pitcher of ice-water condenses moisture on its outside. This being taken up, reduces the temperature still more, and brings a fresh supply, and so on. The process continues till arrested by an outside or atmospheric elevation of temperature, when the action is reversed. In losing moisture, the heat rendered latent is given out, raising the temperature, which causes a fresh loss of moisture, and further elevation of temperature, and so on, till a change in atmospheric conditions arrests this process, and induces the contrary.

Unstable Character of Deliquescent Explosives.—Deliquescence (it is found) gives two different and incompatible characters to an explosive in which deliquescent salts are used, depending upon the particular state in which it is taken: when absorbing moisture it is comparatively weak, and insensitive to blows or compression; when losing moisture it is comparatively strong, and very sensitive to both. The temperature being already elevated, a slight blow will raise it to the exploding point. The compression given by the tamping-rod in compacting it in the bore-hole may be sufficient to cause a premature explosion. These qualities render it unfit to bear climatic changes, and especially dangerous in warm or drying weather. Its constant subjection to chemical action gives it a character of instability conducive to disasters in handling it. An explosive which is safe to-day and dangerous to-morrow is the most dangerous of all explosives.

Digitized by Google

From what has been said, it will be seen to be not only essential that all explosives should respond to the conditions enumerated, as to

Safety against *fire and high temperatures;*
Safety against *friction, jars, and shocks;*
Safety against *percussion, concussion, and tamping;*
Safety against *leakage or liquefaction;*

but that they stand also the *heat test* of Sir Frederick Abel: and last, although not least, all explosives should stand the *test of time.*

Temperature.—The effect of heat on all explosives is to bring

FIG. 62.—FRICTION TEST.

them nearer their exploding-points, and thus to increase their sensitiveness. This heat makes a slight saving of work in explosion—so that all explosives are a little stronger in warm weather. The exploding-point of nitro-glycerine is given by Hill at 356° F. Gunpowder is 560° F. The danger of deliquescent ingredients is not in lowering the firing-point of nitro-glycerine, but of elevating the temperature of the explosive to a dangerous approximation to this point.

Insensitiveness to Friction is so general with nitro-glycerine explosives, that it might be classed with their general properties,

Digitized by Google

and this quality is doubtless due to the action of the nitroglycerine, which has all the attributes of an oil as a lubricant.

The test for friction is to rub the powder between two sandpaper surfaces. One piece is tacked to a board lying on the ground, the other to a block of wood with a long handle. Fig. 62 will show the test better than with any description.

Shocks and Jars.—Safety against shocks and jars implies several different qualities, which, though allied, are not identical.

Percussion.—By percussion is understood the blow received by the explosive when it is struck between hard surfaces, or by a body moving with very high velocity. To test the sensitiveness of an explosive as to its resistance against percussion, Lieut. Quinan has proposed the apparatus shown in Fig. 63, which may be called a percussion gauge.

FIG. 63.—PERCUSSION GAUGE.

It consists of a hammer of dense wood, with a steel rod inserted in its lower end. This hammer slides freely up and down in guides set in a heavy block of wood. The anvil consists of a second steel rod, which is set vertically in the block, directly under the hammer. The slide is graduated to tenths of a foot. The weight of the hammer being known, the blow is easily estimated in foot-pounds.

To get a measure for any particular explosive, a pinch is placed on the anvil, and the hammer dropped from increasing heights until a complete explosion is obtained—the anvil being cleaned and a new pinch used for each blow. For perfect accuracy, the quantity used should always be the same.

In reporting upon an accident which had occurred at a factory in England, Colonel Majendie, H.M. Chief Inspector of Explosives, cites a series of experiments which were made to test the question of percussion, as it was thought not unlikely

Digitized by Google

that the accident referred to was caused by something striking or falling upon the dynamite with force sufficient to explode it. He says, "Under certain conditions dynamite is exceedingly sensitive to explosion by a blow. A large number of experiments have been carried out to illustrate this point. Thus in 1873–4 the War Office Committee on Gun-cotton carried out a series of experiments with falling weights, from which it appeared that a weight of 20 lbs. falling from two to three feet, and in some cases with a fall of only two feet, on a small quantity (50 grains, half an inch in diameter) of dynamite placed between two gun-metal plates, generally sufficed to secure the explosion of the dynamite. With 30-grain samples, under the same conditions, the same results were accomplished with a 5 lbs. weight.

"Further experiments made by the committee showed that when the quantity of dynamite was still further reduced, viz. to 3 grains spread on the surface of the lower gun-metal disc, the fall of the 5 lbs. weight sufficed to produce explosion at 18½ inches, and in one instance even at 15½ inches; and it is worthy of notice, and is perhaps not generally known, that this degree of sensitiveness is at least equal or even slightly superior to that of cap composition under similar conditions.

"Again, from some experiments carried out for me by Dr. Dupré, in 1879, in connection with the Cymmer explosion, it appeared that ordinary dynamite may be exploded by a 1 lb. steel weight falling on a small portion from a height of 8 inches. In 1879 I carried out a number of experiments on this subject, operating upon samples of 30 grains, and half an inch in diameter, between gun-metal discs, when it appeared that a 5 lbs. weight falling 36 inches, and even in one instance 30 inches only, sufficed to produce explosion—a result which compares very closely with that obtained by the committee with a similar weight, as above recorded. When there was a little exuded nitro-glycerine present, a somewhat higher degree of sensitiveness was exhibited.

"The immediate object of these experiments was to establish the relative sensitiveness of the unfrozen and frozen

Digitized by Google

dynamite; and it may be useful to state here, as bearing upon a question which arises in connection with this accident, that the result of these experiments was to show decisively that, contrary to the commonly received idea, frozen dynamite is considerably less sensitive to explosion by a blow than unfrozen dynamite.

"Dr. Dupré has, at my request, carried out some experiments with dynamite brought from Pembrey to illustrate the subject of the liability of dynamite to explosion by percussion, and he has so framed his experiments as to establish a comparison between the sensitiveness of dynamite when warmed and the same dynamite when cold (but unfrozen). He took twelve portions of dynamite of 1 grain each, and wrapped each portion in a small piece of tinfoil so as to occupy a circular space of about $\frac{1}{3}$ inch diameter. Six of these portions were heated to a temperature of 200° F., and placed one by one on a steel anvil heated to the same temperature, and a 1 lb. weight, also heated to 200° F., was allowed to fall on them from different heights. The anvil and weight were then cooled, and the same experiment was repeated with cold (unfrozen) dynamite (temperature about 52° F.). The results were as follows:—

Dynamite at a temperature of 200° F.			Dynamite at a temperature of 52° F.		
No. of experiment.	Height. Inches.	Result.	No. of experiment.	Height. Inches.	Result.
1	10	Explosion.	1	12	No explosion.
2	10	Explosion.	2	14	No explosion.
3	8	No explosion.	3	16	Very feeble explosion.
4	9	Explosion.			
5	8	No explosion	4	15	No explosion.
6	9	Explosion.	5	16	No explosion.
			6	18	Explosion.

"It thus appears that there is a very markedly superior sensitiveness in the warm dynamite, which can be exploded by a 1 lb. weight falling 9 inches, while the cold dynamite

Digitized by Google

required the same weight to fall something like about 18 inches to produce an explosion."

It should be mentioned that accidents which have occurred from the incautious handling of dynamite would appear to show that it may be exploded by wooden implements applied with incautious energy.

Concussion.—By concussion is understood the shock delivered by transmission through air or other medium intervening between the powder and the source of disturbance. Nitro-glycerine, as a liquid, can readily be exploded by a shock so transmitted. There is danger in producing an explosive sensitive to concussion, and this sensitiveness increases in proportion to the amount of nitro-glycerine present, or the relative approach of an explosive to the liquid condition. This quality can be easily tested by placing cartridges on the ground at certain distances one from the other, and exploding one by means of a cap, and if the cartridge lying at a certain distance from it should explode, this second explosion is the result of concussion, and the explosion is called a *sympathetic explosion*, or explosion by sympathy.

Transmission of Explosion.—Under the direction of the Military Committee of the Austrian Army, sitting at Vienna, experiments were instituted by Captain Emanuel Wavra to test the propositions made by Captain Peyerle regarding the application of intermediate charges to transmit explosion through the sympathetic vibration of iron or other materials by the use of an initial charge. Captain Peyerle's proposal was that his method should be utilised for the destruction of iron bridges in time of war.

In carrying out the experiments, the idea was to insert the fulminating cap in such a way that the closed end should fall plumb with the end of the cartridge, and to place the charge on the iron, the cap in direct contact with the iron. Railroad rails were used about 6 to 7 metres long, supported on three beams, and the charges were always so placed as to rest

Digitized by Google

on the part of the rail which was free or did not rest on the beam. The dynamite used came from the factory at Pressburg, and was taken from three different parcels. The dynamite from one lot showed the peculiar and often-observed property of not freezing even when exposed for several days to a temperature of $-8°$ to $-50°$ C. In placing the charges, the precaution had to be taken to have the cap and cartridge in intimate contact with the rail. The primers were all frozen. The firing was done with fuzes. The freezing of the cartridges and primers was accomplished artificially in a freezing apparatus, where they were exposed for several days to a temperature of $-20°$ C.

The experiments were carried out between the 7th and 17th of January, 1878, on the Simmeringer heath, the temperature during that time varying between 0° to $-6°$ C. The soft dynamite was kept for several days at a temperature of 30° C. The cartridges were fastened to the rails with twine, and great care was taken, in the adjustment of the charge, to have the cap in contact with the rail.

In Fig. 64 one of the experiments with charges of soft dynamite is illustrated. The diagram shows the size and



FIG. 64.—DIAGRAM ILLUSTRATING TEST OF TRANSMISSION OF EXPLOSION.

distance apart of the charges, a cap with 0·6 gram of fulminate being employed: *u u* are the supporting beams; *s s*, iron rails; *z*, the initial charge; *r*, the charge to be influenced; *i*, the fuze and cap.

In the result of the experiments, the following were the conclusions of the committee:—

"(1) The method proposed by Captain Peyerle cannot be recommended, for the reason that the transmission of explosion with frozen dynamite does not even take place at the short

Digitized by Google

distance of 0·6 metre, and with an initial charge of 1 kilogram, as seen in experiments Nos. 5, 6, 13, and 14.

"(2) The experiments Nos. 4, 5, 6, 11, 12, 13, and 14, where the primer was surrounded with dynamite in the charges to be influenced, in connection with the experiments Nos. 7, 8, 9, and 15, which were executed under similar conditions, but where the primers of the charges to be influenced were free, have shown that transmission of the explosion does not take place on account of the vibration of the iron rail, but by the direct percussion blow of the explosion gases, or, what is the same, the transmission takes place through the air.

"(3) The results of these experiments with soft dynamite, in comparison with those executed by Captain Peyerle, have also demonstrated that this transmission with soft dynamite cannot be depended upon even at the short distance of 0·7 metre and the heavy initial charge of 1 kilogram, and is therefore too uncertain to be recommended."

In accordance with these conclusions, it was decided by the Army Committee not to adopt Captain Peyerle's method for the destruction of bridges in time of war.

Tamping.—Sensitiveness to compression is not identical with the properties already considered. The difference can be illustrated in this way: With a resilient explosive, a thin layer placed on an anvil will yield an explosion under a blow which will not affect a thicker layer. A pasty explosive, on the contrary, shows nearly as much sensitiveness in mass as in small quantity. Safety against compression is one of the most valuable properties an explosive can possess, since it enables the miner, without risk, to properly fill his bore-hole, and to get the requisite concentration of power. An explosive which can be tamped freely will be found much more economical in use than one which is too sensitive to be tamped at all.

The apparatus (Fig. 65) used to test this quality is simple, and at the same time unequivocal as to results. A slide similar to the one used in the foot-pounds machine was prepared for the shot of the pressure guage. A piece of iron gas-pipe,

Digitized by Google

about 2½ feet long, its lower end stopped with an iron plug, was fixed vertically in the slide, and supported on a block of iron.



FIG. 65.—TAMPING.

To make the test, cartridges of the explosive are slipped into the pipe, and a short wooden tamping-rod placed on them.

The shot is then dropped from increasing heights upon the

Digitized by Google

end of the rod, giving more or less compression, depending upon the heights and number of blows. The weight of the shot being 34½ lbs., the energy of the blow in foot-pounds is easily calculated.

Purity of Explosion Gases.—Theory tells, and practice proves, that at very high temperatures no complex chemical combination can exist. Hence nitro-glycerine, when it detonates, must split up into carbonic acid, carbonic oxide, water, and nitrogen. It is difficult to explain the reason of complaints arising from the use of modern explosives in mines on account of bad fumes, though of their existence there can no longer be any doubt, and the poisonous element consists of hyponitric acid. But such fumes are never the products of a rational use of the explosive substance, and it is quite evident that hyponitric acid can never escape decomposition in an atmosphere of 3000° C. or more with combustible elements in presence.

It does not. But when a dynamite cartridge burns instead of exploding, the combustion takes place at a much lower temperature, and the nitric acid contained in the nitro-glycerine gives off only part of its oxygen, forming dioxide of nitrogen, which escapes, and in contact with the atmosphere gets converted into hyponitric fumes. It is easy to become convinced by actual experiment of the different atmosphere produced by a cartridge when burning or exploding. In the worst-ventilated tunnel twenty cartridges may be detonated without as much molestation as is caused by the burning of one.

An excess of explosives in bore-holes should also be avoided, owing to the quantity of gases produced, as it will be found in practice, that if the quantity of explosive is proportionate to the amount of work it has to do, the gases produced are not so obnoxious as if an excess of explosive is employed.

I have known of cases of asphyxiation from imperfect explosions, and it is imperative, therefore, that proper attention should be paid to ventilation in workings where large quantities of explosives are fired.

Digitized by Google

Perfect Detonation.—The frequent occurrence of bad fumes in mines proceeds from the general mistake of not securing the detonator cap to the fuze, and the fuze to the cartridge. In charging, the miner under such circumstances easily draws fuze and cap out of the cartridge, leaving them separated, so that the cap cannot possibly exercise its detonating influence. What then takes place is this. Part of the dynamite burns, emitting hyponitric fumes, and part generally explodes under the influence of accumulating heat and pressure. Thus the charge goes off, but with a far inferior effect to that of a proper detonation, and with emission of a great deal of red fumes of hyponitric acid. A perfect detonation is requisite, and strong exploders ought to be used in preference. In practice it will be found best to use the triple-force caps, even if single force insure a good explosion.

Detection of Nitro-glycerine in the Human Body.—The poisonous character of nitro-glycerine has already been referred to. If in any case the death of a person should be suspected to be due to this substance, the following method will serve to ascertain the existence of nitro-glycerine in the body. Parts of the body, liver, intestines, &c., are extracted with ether or chloroform; a few drops of the extract are placed in a watch-glass, mixed with two or three drops of aniline, evaporated until ether (or chloroform) and water have gone off, and to the residue a drop of concentrated sulphuric acid is added. If nitro-glycerine is present the contents of the watch-glass will assume a crimson colour, due to the reaction between aniline sulphate and nitric acid, the latter having been liberated from the nitro-glycerine.

Precautions during Manufacture of Explosives.—That the manufacture of explosives is dangerous is obvious, for many reasons. The frequency of accidents shows the danger which exists in their manipulations, and even with the greatest care and most proper supervision they cannot be wholly avoided. *Dr. F. H. Jenssen*, in an able paper on the

Digitized by Google

subject, says that accidental explosions can be traced either to—

1. Improper construction and faulty arrangement of the works and machines;
2. Carelessness on the part of the workmen;
3. Maliciousness.

In making nitro-glycerine there is a danger of firing in the converter or nitrating apparatus, and after that comes the danger from overheating when the nitro-glycerine is precipitated. As the acid nitro-glycerine is very sensitive, and decomposes at 100° F., it is essential that the charge in the converter should be run into a very large body of water, and that this water should be changed as soon as possible. Under no circumstances should acid nitro-glycerine be stored over-night. Care should be taken that the pipe lines between the tanks do not cross or approach near steam or hot-water pipes. Accidents arise from the wash waters, since they carry nitro-glycerine partly in suspension and partly attached to the solid impurities in the water. For economy's sake, as well as to avoid accidents, arrangements should be made to catch as much of this as possible before discharging the water; but where the water is run off, it should be led through earthenware or lead pipe by the shortest line to the river, bay or well. If wooden conduits are used, they become saturated with nitro-glycerine and acids. Hence they should be well covered to protect them from the sun, which causes decomposition.

The effect of the sun's rays was seen at one factory where no provision had been made to catch the traces of nitro-glycerine, and where the wash waters ran a short distance over a sandy beach before entering the river. The result was that on a hot summer's day red fumes were observed rising from the ground, and a heavy explosion soon occurred.

Even where wells are used, there is danger from these wash waters. For instance, at a factory where these waters were led through a ditch in rocky ground, it was found that considerable quantities of the explosive had accumulated in the fissures in the rock. Numerous unsuccessful efforts were made to remove

Digitized by Google

this, and finally the ditch was dammed, so as to keep the explosive covered with water. Several years after, the ditch was struck by lightning, and an explosion ensued which damaged the buildings in the vicinity severely, and hurled large masses of the rock to considerable distances. From the sensitive nature of acid nitro-glycerine, it naturally follows that the recovery of the spent acids is attended with great danger.

During a visit to the Pembrey works in Wales a few years ago, I saw that the precaution was taken to lead the wash waters to a pond which was "torpedoed" once a week—that is, a charge of dynamite was lowered to the bottom of the pond and fired, thereby exploding any nitro-glycerine which had been carried there by the wash waters. This (in the light of previous experience just cited) was a very wise measure.

In the making of the dynamite, there is little danger if the absorbent is itself a safe one, and is not too warm, and the proper precautions regarding the use of metal tools are taken. The buildings should be heated by hot water or steam, and the pipes so covered as to prevent the dust from settling upon them, or, if it does settle, they should be frequently cleaned. This dust is a constant source of danger, especially in the making of explosive gelatine, where nitro-cellulose is used in the dry state and finely pulverised. In all the rooms, the windows should be shaded, to prevent the direct sunlight from falling on the explosive. Similar precautions are to be taken in the packing department.

Among instances of maliciousness, a case in point occurred where a quantity of tips from phosphorus matches had been placed in a bag of infusorial earth, and were not discovered until the earth had been made up into dynamite.

Explosions due to External Causes.—*Mr. L. J. Le Conte* holds that dynamite catastrophes are intimately associated with electric phenomena. He has for the past ten years noted the circumstances attending the accidental explosions which so frequently occur on the Pacific Coast of North America, and he has found that, with the exception of such as occur during

Digitized by Google

thunderstorms, the explosions take place during the violent, desiccating, north-wind storms peculiar to the winter and spring months in California, but occasionally happening in midsummer.

These winds (it must be remembered) have a velocity of 50 miles per hour, and a relative humidity of about 20 per cent., but frequently as low as 15 per cent., though seldom as low as 5 per cent. During the prevalence of the winds a prodigious amount of electricity is developed by the friction of clothing, especially when walking against the wind. One can thus easily generate a spark *half an inch long*. The phenomenon is also strongly marked in horses at work, the electricity causing their manes and tails to bristle to a remarkable extent. Mr. Le Conte finds in this electricity the exciting cause of these explosions, and in the *dust* that prevails in the works, the medium through which explosion is propagated, a dust explosion always preceding the explosion of the mass of powder. The explosions occur on the third or fourth day of the storm.

To test his theory, he made four predictions in 1882 and 1883, and in each case an explosion of considerable magnitude occurred. To guard against these accidents, he suggests the use of steam jets, such as have been so successfully applied in cotton and flour mills, and in coal mines.

As explosions during thunderstorms are caused by the return shock, it should be a fundamental precaution that all good conductors of electricity be prohibited from entering any building where explosives are stored or manufactured; and it would be a wholesome rule not to allow such conductors to be anywhere near the premises.

Too much stress cannot be laid on the great services rendered by the Explosives Department of the Home Office in elucidating the causes of accidental explosions, and the reports of Col. Majendie, H.M. Chief Inspector of Explosives, and the other members of the Department, clearly demonstrate that through the searching investigations of these officials a degree

Digitized by Google

of knowledge has now been gained in the art of manufacturing explosives, by which, if absolute safety is not guaranteed, at least the best precautions which human ingenuity can suggest have been introduced ; and the decrease of accidents in this country proves, that the efforts of the Explosives Department have not been without beneficial results, in lessening the dangers incident to the manufacture of explosives and their use in the arts and otherwise.

Digitized by Google

CHAPTER XIV.

GENERAL DIRECTIONS FOR USING DYNAMITE.

GRADES of Dynamite—General Rule for its Use—Materials for use in Blasting—Drill Holes, Charges, etc.—Charging with Cartridges—Priming—Tamping—Explosion of Blast—Miss-shots—Imperfect Explosions—Explosion by Sympathy—Frozen Dynamite—Safe Mode of Thawing—Frozen Nitro-glycerine Compounds—Precautions.

DYNAMITE is the article among modern explosives which is now best known and mostly in use. The American name for it is *Giant Powder*.

There are, or ought to be manufactured at each factory, two grades of dynamite, No. 1 and No. 2, also a No. 3.

No. 1 is more powerful than No. 2, and, when gelatinised is not affected by water. It is also much more expensive.

No. 2 is about three-fourths as strong as No. 1, but is weakened by water if kept in contact with it too long.

For the very hardest work, and for cases requiring long exposure to water, I recommend No. 1; for all other cases, No. 2.*

As a key to a clear understanding of the peculiar nature of dynamite and success in its use, I give the following general rule and explanation:—

Rule.—*Let it be put into close quarters, and held there by the most unyielding barricades or confinement at command. Let there be no vacancies about the charge, and let all its surroundings be as compact, heavy, and incompressible as possible.*

The explosion of gunpowder (it may be explained) proceeds progressively by combustion, and its gases gradually accumu-

* See 'Modern High Explosives,' "Dynamite No. 2," page 67.

Digitized by Google

late until the resistance to them gives way. This yielding, in almost every case, takes place before all the powder is burned, so that any vacancies are filled with gas at the maximum pressure or density, and no effect is lost. But dynamite does not thus explode. Explosion does not take place by combustion, or progressively; it takes place instantaneously, and all parts of the charge decompose simultaneously, thus making the initial pressure the maximum one. Hence every vacancy withdraws gas sufficient to fill it, and thereby weakens the effect accordingly.

Therefore leave no vacancy about the charge.

Nobel discovered that nitro-glycerine and its compounds could not be exploded by the ordinary means used with gunpowder, as with a common fuze there would be no explosion; but if the material was exposed to a sudden blow, detonation occurred. This led to the application of detonators, or caps. The detonation of a cap in a cartridge of dynamite acts like a violent blow, producing heat and concussion, which act on the particles of dynamite immediately surrounding it, and these, exploding, set off the rest of the charge in the bore-hole. It is essential that the first blow given by the explosion of the cap or detonator should be sufficiently strong to ensure a perfect detonation of the entire charge; and the stronger the detonator, the more certain this result. The importance of this has been fully recognised, as we find that in practice usually triple- and quadruple-force caps are used. With a weak cap, an explosion may be obtained, and the surrounding particles of dynamite will take fire and burn, and the generation of heat, flame, and gases will set off the remainder of the unexploded charge, but in many cases this explosion is imperfect and of a lower order. Such a result not only lessens the amount of work done by the explosive, but also produces gases which (owing to the incompleteness of the detonation) are of a different nature from the gases resulting from a complete detonation. Miners often complain that some well-known explosive gives off bad or sickening fumes, which, when attention is paid to proper detonation of the explosive, will entirely disappear. Too

Digitized by Google

much attention cannot be given to the proper application of the cap, which, as just pointed out, should in all cases be strong enough to ensure the complete detonation of the entire charge. In very deep holes, where the charge of dynamite is several feet in length, it will be found advantageous to place one cap at the bottom, one in the centre, and one at the top of the charge, and to use in preference electric fuzes, which may be fired simultaneously. The modern varieties of nitro-gelatine compounds are not as sensitive to detonation as dynamite, and therefore require extra strong caps or detonators.

Materials for use in Blasting. — *Cartridges.* — In all cases where dynamite is used I recommend cartridges. They are easy to handle, and ready for use, in form shown in Fig. 66. The regular sizes are from 4 to 8 inches long, and from ¾ to 2 inches in diameter. Cartridges of the proper size to suit the diameter of the bore-holes are preferable, but the miner can load the largest hole with the smallest cartridge by slitting them on the side, as shown in Fig. 67, and pressing them down in the drill-hole with a wooden tamping-rod.

FIG. 66. FIG. 67. DYNAMITE CARTRIDGES.

Caution.—*In tamping powder or explosives, always use a wooden rammer. Never use an iron or steel bar with any explosive.*

From the nature of the substance, dynamite cartridges may be readily cut into such lengths as may be required.

Caps.—The regular cap or exploder, from a triple to a sextuple force cap, is employed to effect the explosion of the dynamite.

Caution.—*If you value your fingers and do not want to lose them, do not go "fooling with the cap" because you want to see "what is in it," or "what it is made of."*

Digitized by Google

Fuze.—Use the better quality of fuzes, the best is always the cheapest, and as dynamite is often used under water, or water employed for tamping, I recommend the best double tape fuze for regular use. Single tape may be used where you know your ground is only a little wet.

Nippers and Pinchers.—A very convenient little tool for cutting fuze and pinching the cap to the fuze is shown in Fig. 68. By means of the notch S_2, the fuze is cut, and when the same is inserted in the cap, as shown in Fig. 69, with the



FIG. 68.—FUZE CUTTER AND NIPPER.

FIG. 69.—FUZE AND CAP.

notch S, the upper part of the cap is squeezed tightly on to the fuze 2.

This is a necessary precaution, as caps which are not tightly squeezed on to the fuze often fail to explode.

Funnel.—A tube with a funnel mouth will be useful in charging with loose powder.

Drill-holes, Charges, &c.—As to the diameter and depth of holes, where they should be made, the direction they should take, the quantity of powder or explosive to be used, and many other matters, no precise rules can be laid down for blasting with any explosive. In these things there must be variation

Digitized by Google

according to the location, character of the material to be blasted, the purpose of the blast, and other circumstances too numerous and complicated to anticipate. Much must, therefore, be left to the good sense and experience of the blaster.

The following observations and examples will afford some assistance :—

As a general rule, the drill-holes and charges for dynamite can be and should be comparatively small.

In heavy work the holes should be large in size and less in number, and the amount of dynamite should be in proportion to the work to be done.

A small quantity in a deep hole, whether the hole is large or small; also a small quantity in a large hole, whether the hole be deep or shallow; also a large quantity in a small but deep hole; also a large quantity in a large but shallow hole, are all examples of misapplication. They are all violations of the general rule applicable to all explosives—*that the quantity of explosive should not only be proportionate to the resistance, but the hole should be proportionate to the explosive, or the explosive to the hole.*

Owing to the great difference in the capacity between the old powder and the new explosives, the tendency will be to overcharge; it is, therefore, recommended that each blaster experiment on this point, so far, at least, as to ascertain the minimum quantity of explosives which will answer his particular purpose.

Charging with Cartridges.—*The charge must fit and fill the bottom of the bore, and be packed solid.* This is an essential pre-requisite to an effective blast. The best way to secure it is this: Take a cartridge as nearly as possible of the same size as the bore, and cut it into sections of about twice or three times their diameter. With a hard wood rammer, as large as will run freely in the hole, press these sections into the bore-hole one by one with sufficient force, until each section is driven to the bottom and expanded laterally, so as to fill the hole solidly in every direction. If the cartridge is

Digitized by Google

smaller than the hole, slit it lengthwise. Any size cartridge may be used, provided it is thus put in (see Fig. 70).

Caution.—*Metallic rammers must not be used.*

Priming.—The primer consists of the cap with the fuze in it imbedded in a cartridge of the explosive. The cap may be inserted directly into the charge, only it is liable to get out of place. A convenient way to prepare a primer is this:—Cut off squarely the end of the fuze and thrust it into the cap up to the fulminate. If the fuze is too large, scrape it down, and



FIG. 70.—CHARGING.

FIG. 71.—FASTENING CAP.

if too small, wind it with paper. Then clamp the cap to the fuze with the nippers, being careful not to disturb the fulminate in the cap (see Fig. 71).

If for a wet hole, smear the junction of the fuze and cap with bar soap or the like, to make it water-tight.

Now open the end of a cartridge, and with a pointed stick make a hole in the explosive and insert the cap (with the fuze attached) the full length of the cap, and press the explosive firmly about the cap. Next gather the cartridge paper about the fuze and tie it there strongly with a string, so that the cap cannot be withdrawn from the explosive (see Fig. 72). Cut off so much of the cartridge as is not needed, and the primer is complete.

Thus prepared, place it in the drill-hole, and press it with a wooden rod into contact with the charge.

Digitized by Google

In cases where whole cartridges are required they may be attached, as in Fig. 73.

Tamping.—This is of great importance. The idea prevails to some extent that dynamite "strikes downward" more than upward, and that tamping is useless. This is mere idle talk. *Always tamp if you can*, and with the best materials at hand and in the strongest manner.

By reason of its quickness, dynamite will do a good deal without tamping when gunpowder would do nothing, but this is no reason for rejecting tamping.

In deep and down holes water makes an excellent tamp. A shallow tamp of water amounts to but little. A shallow tamp of sand, brick-dust, or clay is much better.

FIG. 72.—PRIMER.

In driving and packing the tamp next to the primer, be careful not to explode the cap; the first handful of tamping should always be pressed down gently.

In fissures and artificial cracks, surround the charge with mud, clay, sand, or water if possible.

Explosion of Blast.—In most cases it is better not to cut off the required length of fuze until the hole is charged and tamped. Then cut it off at a safe length, and fire. Set fire to the fuze with a match or fusee: the burning of the fuze explodes the cap; the explosion of the cap explodes the primer or charge in which the cap may be. All the other cartridges or charges in the same hole are exploded by the first explosion of the primer (see Fig. 74).

Miss-Shots.—In case the blast misses, remember that the

Digitized by Google

cap is charged with fulminate, and must not be trifled with. Therefore, take out the tamping to within two or three inches of the charge, put in another cartridge, fire it, and its explosion will set off the main charge, unless the explosive had become frozen in the bore-hole.

Imperfect Explosions.—One of the essential points in blasting is that the charge in the bore-hole should explode completely. An explosive which is insensitive enough to resist the impact of the initial detonation, and only explodes partially and incompletely, is a very dangerous compound, and may become a source of danger under many circumstances, some of which it will be well to consider here.

It frequently happens, especially during the winter months, that an incautious miner will not allow sufficient time for his dynamite cartridges to be completely thawed. He knows that frozen dynamite is hard to explode, and also that frozen dynamite may explode with a strong primer of soft dynamite or gun-cotton, but this result cannot be relied upon. Should the dynamite which remains frozen not be exploded, there is the danger that the portion of the charge which is exploded may drive the frozen dynamite into fissures and crevices of the rock, and it may afterwards happen that the unsuspecting miner, when drilling in the neighbourhood of such fissures, will bore into some of this hidden material, with disastrous results.

Other cases will happen where the partial explosion will do enough work to "bottom the hole," and the boulders of rock or coal will hold hidden the unexploded charge. There are cases on record where lumps of coal thus unwittingly charged with an explosive, have been thrown into a cooking-stove, with the result that cook, stove, and house have disappeared into the air. In my own experience, I have known disasters in quarries where blocks of rock held pieces of dynamite, and these blocks being broken by the sledge-hammer, explosions have resulted which seemed inexplicable, but which, on investigation, proved to result from incomplete explosions of the bore-hole charges.

Digitized by Google

Manufacturers are prone to claim safety for their explosives by showing how insensitive they are. There must be a limit, however, to insensitiveness to concussion, inasmuch as, the explosion of modern explosives being the result of a blow or impact, it becomes a very material point to determine where the line of insensitiveness should be drawn, or the result may be that the charge will refuse to explode at all, and miners well know the serious and dangerous task before them when an unexploded charge has to be withdrawn from the bore-hole.

Cases have also come under my observation where, several cartridges being in a bore-hole, the cartridges at the top will explode, and one or two remain sticking in the bottom of the hole. Such a result can be avoided by inserting some caps in the intermediate cartridges. It is very difficult, however, to explain the many "freaks" in the action of explosives which one must be prepared to encounter in blasting operations, in which at times results appear entirely at variance with previous results, especially as regards the transmission of detonation by sympathy. (Some observations on "explosion by sympathy" will be found later on in the present chapter.)

Working miners, through sheer recklessness begotten of familiarity with explosives, often regard them as perfectly harmless substances, and frequently have I seen them preparing their charges while quietly smoking their pipes. If a miner, on inserting his charge, finds, it may be through the unevenness of the bore-hole, that the cartridge will not slip in easily—a not infrequent occurrence with rigid cartridges—he will often take his drill in hand and "go at it" with all his might to get the charge home. No need to say that frequent accidents are the result of such practices. No amount of preaching, however, will remedy the evil, although it is a sorry reflection that a little precaution would have saved many valuable lives.

Caution.—*Never pick out a shot of powder or dynamite, as it is always attended with more or less danger.*

Digitized by Google

I have always followed the practice, after inserting the primer, to take a piece of old newspaper, make a ball of it and push it on top of the primer and then put in the tamping. If the shot misses fire and the tamping has to be

FIG. 73.—PRIMER.



FIG. 74.—FIRING THE CHARGE.

scraped out, as soon as the scraper reaches the paper I know I am near the explosive; and simple as this precautionary measure is, it prevents the scraper from coming in contact with the fulminating cap.

To ensure explosion, the dynamite must not be frozen. The fuze must be good, and be kept in the cap; the cap must be kept dry, and not be withdrawn from the explosive. Therefore, if there is a miss-blast, find out the cause if you can, so as to avoid it afterwards, and look for the cause in one of the five things named.

A space of several inches, either vacant or filled, between several charges or cartridges in the same hole, will not prevent the simultaneous explosion of all.

In case the blast is not effective, it will be because the directions have not been followed, or because the blaster has erred in some matter left to his discretion. The most common causes of failure are deficiency of the explosive and defective tamping. Never spare the explosive because it is dear; put in enough to make good blasts, and then, if dynamite proves too expensive, leave it and use common gunpowder again.

I will repeat here again, that the great advantage claimed for the modern explosives consists, not so much in diminishing

Digitized by Google

the cost of the explosives as an item of expense, as an increasing the amount of work accomplished. The difference in the cost of high explosives and of powder, respectively, is trifling in comparison with the difference in the cost of drilling, charging, tamping, convenience in wet work, and effectiveness of blasts.

Dynamite, as a general rule, throws rock less and breaks it more, and extends its effects much deeper, than ordinary blasting powder; and those who use it soon learn not to judge of a blast by first appearances. It frequently happens that a blast which seems to have had no effect proves to have done remarkable execution in cracking and loosening the rock, and preparing the way for subsequent blasts. This is especially the case in tunnels and shafts.

Explosion by Sympathy.—It is well known that the detonation of a certain quantity of an explosive will cause the propagation of this explosion to another quantity of an explosive some distance away. There is no doubt that the air surrounding an explosive which detonates is violently repulsed and undergoes compression, striking in its course everything in its vicinity with great force. How great such force is all those who have been near the scene of an explosion of a powder factory or magazine can testify. It is a common experience that houses are demolished, trees are uprooted, and everything within a certain radius is wrecked.

It may appear a singular phenomenon that dynamite explosions effect more local damage than the widespread destruction resulting from gunpowder explosions; but this is explained by the fact that, the explosion of dynamite being more rapid, the gases are so rapidly projected into the surrounding atmosphere that no time is given for the gradual compression of the air-space which would otherwise reach to greater distances. If there is another quantity of dynamite or powder within the radius of compression, the blow it receives is sufficient to set it off. This is known as "explosion by sympathy."

Digitized by Google

The air-space through which detonation is transmitted varies with each explosive. It also depends on the initial charge which transmits the explosion, and on the sensitiveness of the explosive which is to be detonated. In some cases a distance of a few inches will be sufficient to prevent these sympathetic explosions. It is a point which has been closely studied by military engineers, as being important to them in the application of surface charges when demolishing bridges and other structures. When in the field, the military engineer has no time to bore holes, &c., and for this reason he places his charges on the top of the object to be destroyed. If the object is of great length, these charges are multiplied, and should, if practicable, be so arranged as to explode by sympathy, but as this cannot be safely relied upon, a connection is usually made by long cartridges between one mass of explosive to the next, thereby having a continuous train which will explode almost simultaneously.

Frozen Dynamite.—Dynamite freezes more easily than water. When frozen it is hard and cannot be loaded properly into bore-holes, and is difficult of explosion. It must be thawed.

In doing this we encounter one of the peculiarities of the powder, and almost its only practical danger.

You can set dynamite on fire or burn it up without causing an explosion, but you must **never roast, toast, bake,** or **fry it.** That is, you must not bury it in embers or hot ashes, nor put it in an oven or kettle or other heated vessel, or on boilers or other heated metals, nor set it up before a fire, or expose it to any strong radiation of heat. It must not be thawed or heated rapidly.

There is **but one safe mode of thawing it,** which is to keep it in a kitchen or other room at summer heat, and away from the fire, until it is soft. It is then ready for use.

It is better to keep it, during cold weather, where it will not freeze at all. A dry, warm cellar or deep mine will protect it.

Digitized by Google

If these directions are disregarded, an explosion of more or less intensity is liable to follow.

Dynamite manufacturers generally supply a special thawing apparatus, consisting of portable tin or metal pots surrounded with a water-jacket to hold warm water.

Frozen Nitro-glycerine Compounds.—When dynamite and other nitro-glycerine compounds are frozen, they are difficult to explode, except by means of strong primers, when the effect is more violent and sharp than with the like compounds in a soft condition. Frozen nitro-gelatine, especially, is more effective when properly detonated, and this substance, when frozen, is capable of complete detonation with a strong cap, and shows a decided superiority in the explosive force developed. Soft, unconfined nitro-gelatine is difficult to explode even with very strong detonators, owing to its plastic nature, with the result that in the open air the portion of the cartridge which explodes will disperse the unexploded portion, and it is therefore advisable to well tamp bore-holes which are charged with nitro-gelatine.

The non-sensitiveness of nitro-gelatine has been reduced by incorporating it with finely pulped explosive gun-cotton, which imparts more rigidity to the cartridges, thereby reducing the yielding character of this substance.

More sensitiveness is also imparted to nitro-gelatine by incorporating with it oxidising salts and carbonaceous substances, which absorb the nitro-glycerine, especially in a thin blasting gelatine; and the resulting cartridges, although still plastic, are more compact, and will resist the blow of initial detonation of the cap, instead of yielding like the soft, gummy substance of the nitro-glycerine.

Sir F. Abel has pointed out that when frozen nitro-glycerine preparations are subjected to the rapid application of great heat (as, for example, by the burning of portions of a mass of the explosive substance itself), a detonation is much more readily brought about with the frozen material than if it be in its normal condition. The following is offered as the most

Digitized by Google

probable explanation of this result: When a mass of dynamite, as in these cartridges, is exposed to sufficient cold to cause the nitro-glycerine to freeze, it does not become uniformly hardened throughout, partly because of slight variations in the proportion of nitro-glycerine in different portions of the mixture composing the cartridge, and partly because, unless the exposure to cold be very prolonged, the external portions of the cartridges will be more thoroughly frozen than the internal. It may thus happen that portions of only partially frozen or still unfrozen dynamite may be more or less completely enclosed in hard crusts or strong envelopes of perfectly frozen and comparatively very cold dynamite. On exposure of such cartridges to a fierce heat very rapidly applied, as would result from the burning of a considerable quantity of the material, some portion of one or other of the cartridges would be likely to be much more readily raised to the igniting or exploding point than the remaining more perfectly frozen part in which it is partly or completely embedded. If the ignition of this portion be brought about (which it will be with a rapidity proportionate to the intensity of heat to which the cartridge is exposed), the envelope of hard, frozen dynamite, by which it is still more or less completely surrounded and strongly confined, will operate like the metal envelope of a detonator, in developing the initial pressure essential for the sudden raising of the more readily inflammable portion of the dynamite to the temperature necessary for the sudden transformation of the nitro-glycerine into gas, and will thus bring about the detonation of a portion of the cartridge, which will act as the initiative detonator to the remainder of the dynamite.

These explanations point to the danger of assuming that, because dynamite in the frozen state is less sensitive to the effects of a blow or initiative detonation than the thawed material, it may therefore be submitted without special care to the action of heat, for the purpose of thawing it.*

The necessity for imparting injunctions to working miners

* Sir F. Abel, "Recent Contributions to the History of Detonating Agents" (1879).

Digitized by Google

to use the warm-water apparatus for thawing out the cartridges, will be apparent, and it is gratifying to know that the number of accidents from this source is diminishing with the extension of knowledge on the subject.

Precautions.—Never attempt to thaw frozen dynamite by *roasting*, *toasting*, or *baking it.* Never put it in heated vessels or on boilers, or before fires or heated metals.

Never put a cap into a charge or primer until you are ready to use it. After it is made, never let a primer leave your hands until it is in the hole.

Keep the caps away from the dynamite. Never let them come near each other, except when they are to be used.

Never allow smoking or other fire near the powder or explosive, as it burns rapidly, and especially when loose, and may fire caps incautiously left near by, and thus bring on an explosion.

Never use a metallic rammer.

Do not get nitro-glycerine on your fingers. It will be absorbed by the skin, and give you a headache.

Invariably prepare your primer at a distance from your explosive.

As premature explosions may also take place by incautious handling of the electric apparatus, it is well to follow the directions given below.

Mobray, in his account of the Hoosac tunnel, refers to two fatal accidents which occurred through handling the wires under certain conditions. Premature explosion was caused in each case by the victims, who wore rubber boots, becoming charged with electricity due to the use of highly compressed air employed for the ventilation. The following are the cautions he recommends: "Let a blaster, before he handles these wires, invariably grasp some metal in moistened contact with the earth, or place both hands against the moist walls of the tunnel. Before taking the leading wires to the electric fuze wires, let the bare ends of the leading and return wires be brought first in contact with themselves, and then in contact

Digitized by Google

with the moist surface of the tunnel; and before inserting the armed cartridge, let him unite both of the uncovered naked wires, and touch with them a metal surface having good ground-connection. Above all, do not ventilate, by allowing a free blast of air through a rubber connecting-pipe, until after the electric connections have been made and the blast fired."

An accident is on record where a blaster had laid a packet of dynamite on the top of a frictional exploder, and on firing the blast, this dynamite exploded, resulting in the death of three men standing near.

Although dynamite is not exploded by an electric spark, but simply burns away when a current of electricity is passed through it, it ought to be adopted as a general rule to keep explosives at a distance from any electrical machine capable of generating strong currents. When tamping charges having electric fuzes embedded in them, press gently with the tamping-rod, and do not give forced blows. Never attempt to pull out a primer holding an electric fuze by trying to drag it out by the wires—an explosion may happen.

In tamping a charge, grains of powder or explosive lying upon the sides of the hole, and sometimes forming a train to the charge at the bottom, undergo a great amount of friction through the coarse tamping material, which may cause ignition and premature explosion of the charge; therefore tamp with care, use only slight pressure, and do not resort to any violent motion of the wooden ram-rod.

Miners are very fond of carrying dynamite cartridges in their pockets, especially in winter, when the warmth of the body keeps the compound in a soft condition. I caution miners not to have matches at the same time in their pockets, and not to smoke their pipes and forgetfully stick the still-burning pipe in the same pocket. Laughable as this caution may appear, experience has shown that it is not out of place. The miner has generally an idea that dynamite is harmless, and accordingly he too often treats it with the utmost recklessness.

Digitized by Google

CHAPTER XV.

EXPLOSIVES IN PRACTICAL APPLICATION.

EFFICIENCY of Dynamite in removing Tree Stumps and Boulders—Blasting Tree Stumps—Blasting Boulders—Sinking Wells—Breaking Ice—Breaking Boulders—Removing Piles under Water—Pile-driving with Dynamite—Rock-blasting—Tunnelling and Blasting in Headings—Musconetcong Tunnel—Tunnelling with Hand Labour—Königshütte Tunnel—Pfaffensprung Tunnel—Blasting Large Mines—Underground Drilling with Compressed Air—Mining with Power Drills—Quantity of Explosives used in Blane Valley Contract.

IF properly used, dynamite will take out stumps of large trees and break up masses of rock more economically than can be done by any other means.

Blasting Tree Stumps.—Find with a crowbar the best place between the roots to get under the body of the stump. Do not be afraid of the uphill side: this may require a little more digging, but will afford a better tamp.

If the stump is not too large, a single cartridge, 1½ by 8 inches, well situated and carefully tamped, will take it out.

If the stump is large and deep in the ground, the hole must be larger than will be made by the crowbar.

Dig down by the side of the stump, then make a horizontal hole under the bottom of the stump as near the centre as possible, and just large enough to receive the explosive, disturbing the natural earth as little as possible. Place the explosive close to the wood; then put in the primer and tamp.

The tamp in stump and boulder blasting is of the utmost consequence, much more so than in bore-hole work. The following directions can be varied according to circumstances:

Digitized by Google

After putting the charge and primer in place at the bottom of the hole and in contact with the stump, ram in a little clay or compact dirt, and then wet it, or use mud for packing. Thus fill up the entire opening. If the charge is well under the stump, this will do; but if it is not—if, as is frequently the case, the charge is only partially under, and especially if it is on the lower side of the stump—make a dam (the larger the better) about the mouth of the hole, and fill it with mud or water.

Remember that the barricade should be as compact and as heavy as practicable. Therefore loose gravel, sand dirt,



FIG. 75.—A STUMP BEFORE BLASTING.



FIG. 76.—SAME STUMP AFTER BLASTING.

loam, stones, etc., etc., are of little service. Water or mud, or dampened clay, and plenty of it, is the best.

If the stump has a tap or peg root, put the charge well down and close to this root.

Fig. 75 shows a stump which was removed by blasting; it was a green white-oak stump, 30 inches in diameter, with roots deeply bedded in the ground. To have cut out and dug out this stump, with axe and spades, would have been a hard day's work for two or more good men. A hole was punched beneath the stump, as shown in the figure, with an iron bar, so as to reach the centre of it. Two of the cartridges were placed beneath the stump, and were tamped with some earth; a pail of water was then poured into the hole, which had the

Digitized by Google

effect of consolidating the earth around the charge. The fuze was then fired. The result was to split the stump into numerous fragments, and to throw it entirely out of the ground, leaving only a few shreds of roots loose in the soil. The result is shown in Fig. 76. The fragments of the stump were thrown to a distance of 30 to 50 feet, and many smaller ones were carried over 100 feet. The quantity of explosive consumed was not less than two pounds.

One useful effect of the explosion consisted in the breaking up of the stump into such pieces as could be easily sawed into firewood; by which much after-labour in breaking it up, when taking it out in the usual manner, was saved. This test was perfectly successful, and proved not only the thorough effectiveness of the new method, but its economy in cost and in time. Several other stumps were taken out in the same manner, the time occupied with each being from five to ten minutes. Smaller stumps were thrown out with single cartridges, but in not one case was anything left in the ground that might not be turned out with the plough, or that would interfere with the ploughing of the ground.*

Blasting Boulders.—If you can get the charge under the rock in the manner directed for stumps, do so. If it cannot be placed directly under the boulder, place it as nearly so as you can. Also try to get your charge against the flat or hollow side of the rock, and not against the swell side. Wherever the charge may be, see that it is well supported and surrounded and burdened with water, mud, damp clay, or some other compact and weighty material.

Where there is a crack or cleft, unless it is either too wide or too narrow, it may be made serviceable. The cleft should be packed with damp clay or mud up to the point where the charge is to be. Lay the charge and primer in their place, and fill and pack the balance of the crack with clay or mud in like manner.

* For further information on the subject see 'Modern High Explosives,' chapter vi., "The Application of High Explosives in Agriculture."

Digitized by Google

Sinking Wells, &c.—Make a hole with the crowbar to the depth desired, put the charge at the bottom, tamp well, and fire. The effect is perfection: the harder the ground, the better.

Breaking Ice.—If the ice rests on water, place the charge in the water under the ice, and in contact with it. If the ice is apart from water, it must be dealt with according to practice for either a drill-hole or a boulder.

Breaking Boulders.—In a case where a rock of about 150 cubic feet, and weighing about 10 tons, was experimented upon,



FIG. 77.—THE ROCK AS IT WAS.



FIG. 78.—THE ROCK AFTER BLASTING.

the shape of the rock before explosion was as shown in Fig. 77. A hole was made with the bar in the ground beneath the rock, and three cartridges were inserted and exploded. The result is shown in Fig. 78. To have produced this by the ordinary method, such as was here done in a few minutes by one man, would have occupied at least two men with drills, sledge, etc., two or three days.

The application of this method is seen to be of great value where the saving of time is an object. An acre of stumps or rocks may be cleared in one day by one or two men, and the material left ready for use as firewood, or as stone for fences or buildings. The cost in money is also reduced in some cases very considerably, and almost absolute safety to the careful operator is ensured. It would be generally advisable

Digitized by Google

to secure the services of an expert, and that the parties who have work of this character to be performed should jointly engage such a man who could either do the whole work, or do it in part, and instruct a foreman or skilful workman sufficiently in a day to perform the remainder. The most favourable



FIG. 79.



FIG. 80.
PILES WITH CHARGES ELECTRICALLY CONNECTED.

FIG. 81.—PILE CONTAINING CHARGE.

seasons for operating upon stumps and rocks are spring and autumn, when the ground is saturated with water. It should be explained that this explosive is not injured by water, although a long-continued exposure to it would affect some qualities of it.

Removing Piles under Water.—A method of procedure in this case, which has been devised by M. Trautzl, the Austrian military engineer,* is represented in Figs. 79, 80, and 81.

* See 'Die Dynamite,' Trautzl, Vienna.

Digitized by Google

Twenty-four wooden piles, which had to be removed, were fixed (see Fig. 79) in the river-bed of the Danube, near Vienna. The piles were cut off with the saw just above the level of the water, bored to a depth of 12 feet with an auger $1\frac{1}{8}$ inch in diameter, and each hole charged with one pound of dynamite. The dynamite charges were in tin cylinders, and provided with detonators having electric fuzes (Fig. 81). The



FIG. 82.—STUMP WITH THREE HOLES CHARGED.



FIG. 83.—EXTERNAL APPLICATION OF CHARGE.

bore-holes were tamped with water, and the charges were fired by electricity. The explosion brought all the twenty-four stakes simultaneously to the surface, and each stake was completely torn to about 18 inches in height from the bottom of the charge.

The expense was about one-fifth of what the usual mode of extricating would have cost.

A very interesting example of applying dynamite to a wooden

Digitized by Google

stump under water is represented in Fig. 82. It was removed from an arm of the Danube near Vienna. It measured about 3 feet in diameter at the top, which reached about 20 inches above the water, and was very rotten. Three holes were bored vertically downward to depths of 4½ feet, 8 feet, and 8½ feet respectively, and about 1½ inch in diameter. The boring of each of the deeper holes lasted four and a half hours, and the third three hours. Each hole received a charge of one pound of dynamite, packed in water-tight tin cases. The result of the explosion was a complete loosening of the ground in which the stump was imbedded, so that its removal by mechanical means was perfectly easy.

Where there is no necessity for removing a stake from below the ground, and it is sufficient to get rid only of such portions as stand in the water, no bore-hole is required; the external application of a dynamite cartridge is enough to effect the removal. The method represented in Fig. 83 was applied in a case where the current of the water was so powerful as to prevent the simple laying on of the cartridge. The latter, *c*, was fastened to a wooden hoop *b*, of somewhat larger dimensions than the stake *a*; the hoop was then attached to two strong wooden poles, *d*, *d*, and then pushed over the stake down to the bottom of the river. A cartridge containing one pound of dynamite employed in this manner broke off stakes of an average diameter of 1 foot.*

Pile-driving with Dynamite.—An interesting series of operations with this object was carried out at Buda-Pesth, in July and August, 1881, under the direction of Lieutenant St. von Prodanović, of the Austrian Engineers.

Owing to the great shattering power of dynamite, it could not be placed immediately on the piles and there exploded, and accordingly, to protect them, iron plates, either of cast or wrought iron, had to be interposed between the head of the piles and the charge. The shape of these plates or hoods will be fully explained.

* See 'Modern High Explosives:' "Subaqueous Blasting," pp. 323-357.

Digitized by Google

At the outset, the fact had to be established whether a pile could be driven in at all with dynamite, and also in what shape the charge should be employed. Two piles were chosen for this purpose; their heads were levelled off horizontally, very perfectly, and iron hoods of the shape shown in Fig. 84 placed on top. These hoods were of cast iron and weighed 254 kilogs. Laterally were four holes, *a*, 60 mms. deep and 25 mms. in diameter, in which were inserted wrought-iron bars 1·0 metre in length, permitting an easy manipulation of the hood. On one of the piles a charge of 1·5 kilog. of Nobel's dynamite No. 2 was placed (No. 1 being excluded, as it was considered too strong). The charge was spread out inside of a hoop 30 cms. in diameter, like a disc (Fig. 85),



FIG. 84.



FIG. 85.

PILE-DRIVING WITH DYNAMITE.

and was condensed to 1·4 sp. gr. and provided with an ordinary fuze. The charge was properly adjusted and covered with clay, as shown in Fig. 86, this being done to bring the charge in close contact with the pile, and also to diminish the force of the explosion, as in the vicinity of the work were a number of buildings. The other pile was provided with a hood of similar construction. The charge in this case also consisted of 1·5 kilog. of No. 2 dynamite, but was compacted in a cylindrical form of 15 cms. diameter and covered with clay as shown in Fig. 87. Both charges were fired simultaneously, and gave the following results :—

The first pile was driven in 34 millimetres = l_1
The second ,, ,, 24 ,, = l'_1

Digitized by Google

Both hoods broke in the direction of the bores, *a*. It will be seen that the two piles, which offered the same resistance to the blow, did not penetrate to the same depth, but the flat



FIG. 86.



FIG. 87.

PILE-DRIVING WITH DYNAMITE.

charge gave a greater effect than the concentrated charge, and future experiments gave like results. A flat charge does not injure the hood as much as a concentrated charge, the latter pressing it down like a dish (see Fig. 88)



FIG. 88.



FIG. 89.

PILE-DRIVING WITH DYNAMITE.

The detonation and air-pressure resulting from the explosion was very violent, with the result that at a distance of 130 yards all the windows in the building were broken.

Digitized by Google

The results of the first day's experiment may be summarised as follows: (1) Pile-driving with dynamite was shown to be practicable; (2) the construction of the iron hood employed in the test was defective; (3) flat charges, coinciding with the cross-section of the piles, were found more effective than concentrated charges; and (4) the charges, owing to local conditions, ought to be reduced.

A second experiment was subsequently made. One of the hoods being left over from the previous experiment, it was used with one of the piles. Three charges, each 15 cms. in diameter, and weighing 0·5 kilog., were fired in succession, giving a total penetration of 21 mms., or 7 mms. per shot of 0·5 kilog. The plate burst at the third shot in the same way as in the previous experiment. For the next trial a hood was used of the construction shown in Fig. 89, where the holes are



FIG. 90.

FIG. 91.

PILE-DRIVING WITH DYNAMITE.

bored on the lower edge, so as not to weaken the main body. Two charges of 30 cms. diameter, and weighing 0·75 kilog., were successively exploded on this hood, resulting in a total penetration of 49 mms., or about 24 mms. per shot. The plate broke in this case also in the direction of the holes. This experience was sufficient to determine that cast iron was not the material to be used.

A third experiment followed. As three cast-iron hoods were left over from the previous experiment, three piles were provided with them. The first pile was not driven down hard, and stuck only 3 metres in the ground, whereas 3 metres protruded above ground (see Fig. 90). Two unlike charges were exploded, weighing 0·5 kilog., and 30 cms. in diameter, giving a penetration of 18 mms. at the first shot and 8 mms. at

Digitized by Google

the second—a very unsatisfactory result, the explanation of which was that the long portion of the pile above ground was set in vibration, which caused a loss of power. The top of piles Nos. 2 and 3 were not cut off horizontally, but were levelled off on an incline to the horizon, in such a way that the resulting gas-pressure acting downward formed an angle with the axis of the piles. Pile No. 2 gave only a penetration of 1 mm.; pile No. 3 of 20 mms.; and with another charge, of 0·75 kilog., of 3 cms.

On the same day the experiments were continued with the wrought-iron hood (Fig. 91), which proved much better than the cast-iron ones, as it withstood fourteen shots of 0·75 kilog.

FIG. 92.



FIG. 93.



FIG. 94.

PILE-DRIVING WITH DYNAMITE.

This hood was placed on a pile which had been weighted down with 35,000 kilogs. of iron, and gave no penetration. Four charges of 0·75 kilog. were exploded, giving a penetration of 16 mms., 5 mms., 4 mms., and 2 mms. respectively.

On the fourth and fifth days the experiments were continued, when results corroborating the previous experiences were obtained.

In all the experiments made during the first five days it was ascertained that with all the hoods the iron ring which lapped over the pile would show splits and fissures first, which would enlarge after each shot until it burst (Fig. 92), and it was decided on the sixth day to try cast-iron dies (Fig. 93).

Digitized by Google

These, however, proved entirely unsuited to the purpose, and the experiments were continued with wrought-iron plates of the dimensions shown in Fig. 94.

Further experiments were instituted to determine the carrying capacity of the piles. For this purpose piles were chosen which were entirely reliable, and these were driven down carefully. Piles Nos. 1, 2, and 3, of the group 2104, were picked out, which had been driven down by a steam pile-driver having a rammer weighing 750 kilogs. No. 1 had been driven down till a tally of ten strokes did not show a penetration of more than 5 mms.; pile No. 2 was driven down till a similar tally only showed a penetration of 10 mms., and pile No. 3 of 13 mms. The two piles 2714 and 2731, which had been thoroughly tested, were included in the experiment. A tally of ten blows gave a penetration of 20 mms. with pile 2714, and 20 mms. with pile 2731, the rammer weighing 550 kilogs. To equalise the results, the penetration of these two piles was reduced to the weight of rammer of 750 kilogs., after the formula—

$$P = \frac{n}{m \cdot e} \cdot \frac{G^2 \cdot g \cdot h}{(G + g)^2}$$

G = weight of rammer = 550 kilogs.; g = weight of pile = 200 kilogs.; h = lift of rammer = 3000 mms.; n = 10 = number of blows per tally; m = 4 = the coefficient of safety. According to this, P_{2714} = 30,066 kilogs., and P_{2731} = 37,582 kilogs., the carrying capacity of the piles.

Supposing these two piles were driven down by a pile-driver whose rammer-weight was 750 kilogs., the penetration of the two piles can be figured out (after their carrying capacity is established) from the formula—

$$l = \frac{1}{P} \cdot \frac{n}{m} \cdot \frac{G^2 \cdot g \cdot h}{(G + g)^2}$$

by P representing its carrying capacity and G being = to 750; therefore l_{2714} = 34·9 mms., and l_{2731} = 27·9 mms. These five piles were levelled on their tops horizontally and provided with pilot-rings; on them were placed wrought-iron plates, and

Digitized by Google

charges of 0·5 kilog. and 24 cms. diameter were exploded by electricity simultaneously. The levelling gave the following result:—

For pile No. 2714	17 millimetres	penetration	= 0·486	Tally of the rammer weighing 750 kilogs.
,, ,, ,, 2731	13 ,,	,,	= 0·464	
,, ,, ,, 2104 I.	3 ,,	,,	= 0·600	
,, ,, ,, 2104 II.	5 ,,	,,	= 0·500	
,, ,, ,, 2104 III.	7 ,,	,,	= 0 538	

On an average, the effect of a 0·5 kilog. charge was found equal to 0·517 tally of a rammer weighing 750 kilogs. having a drop of 3 metres.

As is seen by the above figures, the effect did not vary in the five cases much from 0·5 of a tally; so that one charge of 0·5 kilog. is equal to five blows of the rammer weighing 750 kilogs. having a drop of 3 metres. In this manner a relation is established between the effect of dynamite and the pile-driver.

Some information may be added as to the examination of the piles for their carrying capacity. A pile having a weight g = 200 kilogs. must—by means of a rammer G weighing 750 kilogs., with a constant drop h = 3 metres, to carry a weight P = 40,000 kilogs., with m = four times the security—be driven in to a penetration point l = 23·4 mms. per tally, = to ten blows. It has to be determined how great the penetration of a pile will be under the influence of the explosion of 0·5 kilog. of dynamite, and according as the same is greater or smaller than, or even to, 11·7 mms. = $\frac{23{\cdot}4 \text{ mms.}}{2}$, the pile will have a carrying capacity which is greater than, even with, or smaller than, the one required, which is 40,000 kilogs. In the last case the pile has to be driven deeper, and is continued till the penetration is 11·7 mms.

The wrought-iron discs of the construction, shown in Fig. 93, stood twenty to twenty-four explosions. The top of the piles did not show the least deformation, even when no pilot-rings were employed.

It should be mentioned that pile-testing with dynamite can

Digitized by Google

only be employed with piles which are at a considerable depth in the ground, as a long protruding end would cause vibrations. Piles which protrude one-fourth of their length out of the ground can be used for this purpose.

Rock Blasting.—Rock blasting has to be resorted to in almost all mining operations, such as quarrying, tunnelling, shaft-sinking, railway cuttings. In all such work the bore-holes have to be applied in such a manner that the explosive may act towards the line of least resistance, or the shortest distance from the bottom of the hole to the nearest open face.

If we have an open face *e f*, Fig. 95, as a rule the bore-hole *a b* should not form an angle with the face exceeding 45°. Where ordinary gunpowder is used, if the angle is too great the result

FIG. 95. — APPLICATION OF BORE-HOLES IN ROCK.



FIG. 96.—BORE-HOLE NOT BOTTOMED.



FIG. 97. — BORE-HOLE PARALLEL WITH FACE.

will be that the hole will not be bottomed, as shown in Fig. 96, at *f*.

In a rock formation, as shown in Fig. 97, the bore-hole *a b* ought to be parallel with the face *e d f*; and in this case the whole block *e a b f* ought to be thrown out by the explosion of the charge.

The effect of a shot may be influenced, among other considerations, by—

1. The shape in which the rock is presented, the size and number of the open faces, the shape of the piece it is desired

Digitized by Google

to take out (if that is an object), and, of course, primarily, the size of the cross-section of the face, if it is heading work.

2. The texture of the rock, whether it is hard or easy, firm or loose, whether it is brittle or tough. Thus experience gained in blasting close-grained, hard granite, trap, gneiss, etc., would not apply to limestone, sandstone, slate, etc.

3. The structure of the rock, as to whether it is laminated, stratified, or fissured, upon its cleavage, etc., and upon whether it is massive or broken, etc.

In tunnelling when the strata dip downward toward the face, hence toward the miner, the breaking-in is started at the roof.

If the strata dip from the face; the breaking-in must be started at the bottom.

4. The elasticity of the rock.



FIG. 98.—BLASTING OUT CUTS.



FIG. 99.—BLASTING ON AN INCLINE.

5. The explosive used.

6. Whether the hole is to act alone, or simultaneously with or following others. In the case of simultaneous firing, the question arises as to how the waves of oscillation will best act in concert.

7. The character of fuze and tamping.*

These rules do not apply to blasting with gunpowder only, but may be safely utilised also for high explosives.

* See 'Modern High Explosives:' "The Principles of Blasting," pp. 229–263.

Digitized by Google

In blasting out cuts, work has (in most cases) to be begun on a horizontal plane, or on a slightly inclined surface. For this purpose a series of shallow holes are bored—as at *a*, *a*, *a*, Fig. 98—whose crater faces are enlarged by the application of another series of holes, *b*, *b*, *b*, and then by *c*, *c*, *c*. When this enlargement has reached the depth *d f* and the plane *f h*, we proceed in a similar manner till we have obtained the depth *g j* and the plane *j k*, and so on to *j l* and *l m*.

In this way we produce the step-like face *d*, *f*, *j*, *l*, *m*, and the number of miners can now be increased, taking care always to fire shots first on the lower benches, as otherwise the debris from the upper benches would bury the lower ones.

If working on an inclined plane, like Fig. 99, the work is commenced by blasting out with short bore-holes, *f g*. *h i*, the sections *b c a*, *d e b*, and opening up proper faces like *b c*, *d e*, which permits of a systematic attack with deep holes afterwards. Another advantage gained by this method is, that several benches can be worked simultaneously, offering great economy in time and money.

Tunnelling and Blasting in Headings.—The system adopted by American railway contractors, in driving railway tunnels, is to advance first with the heading, the full width of the top arch, and then to follow up with the bench work, in such a way that the heading work does not interfere with the bench work. It consists in first blasting out an entire wedge or core the entire height of the heading, and about 10 feet deep at the centre, and subsequently squaring up the sides by several rounds.

Musconetcong Tunnel.—This work—which is being cut through syenitic rock, on the Lehigh Valley Railway at Easton, in the state of New Jersey—may be described in some detail as an instance of American practice.* Twelve holes are first drilled, by means of rock-drills run with compressed air, six on each side, in pairs of two and two, as shown in Fig. 100 at

* See Drinker on 'Tunnelling.' J. Wiley and Sons, New York.

Digitized by Google

C, A being the floor of the heading. These twelve holes are drilled with from $1\frac{1}{2}$ to $2\frac{3}{4}$ in. "bits," the holes being on the face 9 feet apart, but are drilled convergingly one towards the other, and at such an angle as to meet or cross at the bottom, the largest bits being put in first. This permits the concentration of the powder charges near the vertical centre line of the tunnel within the line of least resistance.

Fig. 101 shows the heading in plan, with the rock-drill H



FIG. 100.—HEADING OF MUSCONETCONG TUNNEL.



FIG. 101.—PLAN OF THE HEADING.

mounted on a carriage boring drill-hole C to meet at an angle the drill-hole C'.

When the twelve holes are bored, they are then charged with about 25 lbs. of No. 1 dynamite, and 50 lbs. of No. 2, and are fired simultaneously by electricity. No. 1 dynamite is only used for the centre cuts, inasmuch as in them a quick, strong explosive is required, comprised in a small bulk at the bottom of the holes, where the greatest resistance will be found, while the No. 2 added serves for filling the holes, so starting the sides of the cut as the apex moves. The centre cut being out, a second round of holes is started for the first squaring up, as shown by the numbers, 1, 1, 1, 1, and eight holes are bored nearly in a parallel direction with the centre holes C; these are loaded with No. 2 dynamite and fired. In the subsequent rounds, 2, 2, 2, 2, and 3, 3, 3, 3, the resistance is pretty equally distributed along the whole length of the holes, and is also, of course, not so great as in the cut; therefore No. 2 dynamite is used.

Digitized by Google

In the first and second squaring-up rounds, from 50 to 60 lbs. of No. 2 dynamite are charged, and in the third from 80 to 90, the holes getting stronger as the arch falls at the sides; there are generally also one or two additional roof-holes in the third round that are not shown in the figure, their position being variable, according to the lay of the rock. The top holes in the first round are also designed to bring down any roof not shaken by the centre cut blasts, and are, therefore, given a strong angle toward the centre, and always drilled from 12 to 14 ft. deep.

The horizontal projection of the above holes is shown in Fig. 101, and as stated before, C, C′ are the centre cut holes; 1, 2, and 3, the square-up holes. As to their relative depth, the holes of the first squaring round are always drilled a foot or more deeper than the cut holes, and when blasted they generally bring out a foot additional of shaken rock at the apex of the cut. The following calculations will approximately show the number and depth of holes required, and the dynamite used for a lineal advance of 10 ft. in heading work :—

12 centre holes at 10 ft. 6 in. each,				giving	126 ft.	(*a*)
8 1st sq. up holes at 12 ft.				,,	96 ,,	(*b*)
8 2nd ,, ,,	,, 12 ,,			,,	96 ,,	(*c*)
6 3rd ,, ,,	,, 12 ,,			,,	72 ,,	(*d*)
2 roof holes	,, 9 ,,			,,	18 ,,	(*e*)
36 holes				giving	408 ,,	(*f*)

(*a*) total depth of holes, charged with 25 lbs. No. 1 and 50 lbs. No. 2 dyn.
(*b*) ,, ,, ,, ,, 55 ,, No. 2 dynamite.
(*c*) ,, ,, ,, ,, 55 ,, ,, ,, ,,
(*d*) ,, ,, ,, ,, 85 ,, ,, ,, ,,
(*e*) ,, ,, ,, ,, 14 ,, ,, ,, ,,
(*f*) total depth, charged with 25 lbs. No. 1 and 259 lbs. No. 2 dynamite.

Now, allowing the cut holes to be 10½ ft. deep, the cut will generally blast out about 9 full ft. linear, which, as explained above, is raised to 10 in the subsequent rounds.

Assuming the average cross section in an 8-ft. heading to be about 175 ft. for a lineal advance of 10 ft., 65 cubic yards of rock would be broken, which would give an average of, say, $\frac{4}{10}$ lb. No. 1, and 4 lbs. No. 2 dynamite burnt, and a little over 6 ft. of holes drilled, per cubic yard broken.

Digitized by Google

This, however, it should be noted, would often be increased by occasional block or side holes, and is assumed for a case in which no holes are supposed to have missed, and in which no secondary drilling and blasting are required.

The above estimates are based on ordinary 10 ft. cuts; there were, however, many instances of 12 and 13 and sometimes 14 ft. cuts taken out by ambitious foremen; but even dynamite has its limit of strength, and working cuts too deep is not advisable, as they will often only blow out partially, leaving the rock in an awkward shape.

The "bench work," as the rock enlargement is termed, is kept from 400 to 600 ft. back of the heading, so avoiding any interruptions at the bench from heading blasts, and allowing



FIG. 102.—SECTION OF BENCH-WORK AT MUSCONETCONG TUNNEL.



FIG. 103.—PLAN OF BENCH.

plenty of room for handling and switching trucks, also for backing the machines to a safe distance from the face when blasting.

Figs. 102 and 103 show the method of blasting adopted in enlarging the rock. First six top holes, from 12 to 13 ft. deep,

Digitized by Google

are drilled and blasted; their relative position is shown in Fig. 104, which is a horizontal projection of the heading: A being a centre line, B the sides of the enlargement, B' sides of the headings, C face of bench; 1, 2, 3, 4, 5, and 6, the drill holes. These six lift most of the rock; what is left is broken by several horizontal lines shown by B in Fig. 102, in which A is the top carriage with the drill mounted, and B the bottom carriage with drill.

These two sets of holes, top and bottom, will average a linear advance for the bench of 9 ft., the following being a fair estimate of the number of feet drilled and powder burnt for 9 ft. advance:

6 top holes at	12 ft.	depth, or	72 ft.	total depth, charged with	62 lbs. No. 2 dynamite.
4 bottom ,,	10 ,,	,, ,,	40 ,,	,, ,, ,,	45 ,, ,, ,,
10 holes			112 ,,	,, ,, ,,	107 ,, ,, ,,

The total height of the cross section adopted for the tunnel through rock, from lower sub-grade (1·75 ft. below base of rail) to roof, was 20·15 ft.; with an 8 ft. heading-off, this leaves about 12 ft. of a bench, with an area of 306 sq. ft., which gives about 102 cubic yards to a lineal advance of 9 ft., or 1·05 lbs. No. 2 dynamite, and 1·1 ft. of holes drilled to 1 cubic yard of rock broken, holes being drilled with from $1\frac{1}{2}$ to $2\frac{3}{4}$ in. bits, the largest bits being put in first.

Tunnelling with Hand Labour.—When similar work

FIG. 104.—FACE OF TUNNEL.



FIG. 105.—FACE OF TUNNEL.

is done by hand labour, the system generally adopted is the following:—

Digitized by Google

In the centre of the face, Figs. 104 and 105, three holes are drilled inclining one to the other; same miners bore one central hole, but the result is not so satisfactory. These holes are each $2\frac{1}{2}$ feet deep, and should be fired simultaneously by electricity, which tears out a cone in the centre, shown by the dotted lines in the figure, and around this cone another series of holes is drilled, concentric with the opening in the centre. These shots (2) are fired again simultaneously, then we proceed with series 3, and at last the bottom shots of series 4.

In driving a tunnel having a small cross-section, such as is shown in Fig. 106, eight holes are bored 1 foot to $1\frac{1}{2}$ foot in depth, and they are all fired simultaneously by electricity.

Another example is given in Fig. 106, representing a small tunnel, say 6 feet high. Three holes are drilled around the centre as shown in the figure, and inclined one to the other at such angles that the bottoms of the two lower ones nearly meet, the third upper hole inclines downward. These three central holes are fired simultaneously by electricity. The central breaking-in hole being produced, the enlargement-holes are placed as shown in the figure.

In driving tunnels of larger section, the methods employed vary according to circumstances, and the following examples exhibit some of the best works which have been executed during the last twenty years.

Tunnel at Königshütte, Prussia.—This tunnel was driven through very hard sandstone, and the engineer, Hugo Münch, gives an account of the system there employed.

The rectangular section measured 2·1 metres in height, and 3 metres in width. Nine holes were drilled, as shown in Fig. 108; they had a depth of 0·9 metre, and had a very slight inclination.

The holes numbered 1 to 6 were each charged with 150 grams of nitro-gelatine, and the other three on top with 140 grams each. The ordinary Bickford fuzes and fulminate caps were used for firing.

Digitized by Google

Shots 1, 2, and 3 were first exploded, which produced a breaking-in 0·75 metre in depth, and 0·6 metre in height; then 4, 5, and 6 were fired, causing an enlargement from 0·9 to 1·4 metre. At last the shots 7, 8, and 9 brought down the rock up to the roof.



FIG. 106.—FACE OF TUNNEL.



FIG. 107.—FACE OF TUNNEL.

1500 kilograms of gelatine were consumed in executing the work. If dynamite No. 1 had been used, each bore-hole would have required 280 grams per load, making a consumption of 2520 kilograms, against 1500 kilograms of gelatine. The



FIGS. 108, 109.—SECTIONS OF KÖNIGSHÜTTE TUNNEL.

economy in the explosive was in the proportion of 3 to 5, and there was a real economy of 10 per cent., taking the price in German marks at $4\frac{1}{2}$ and 3 for the two qualities.

Pfaffensprung Tunnel.—This was in hard granite, 2·2

Digitized by Google

metres high and 2·5 metres wide. Six holes were drilled as shown in Figs. 110 and 111. The holes measured 0·073 metre in diameter, and 1·5 metre in depth; and were drilled parallel with the axis of the tunnel. The charges consisted of nitro-gelatine cartridges 0·07 metre in diameter, and 0·1 metre in length, and weighed 500 grams each.



FIGS. 110, 111.—SECTIONS OF PFAFFENSPRUNG TUNNEL.

Blasting in Large Mines.—For engineering works of great magnitude, where large masses of rocks are to be moved at low cost, the most economical method is to make excavations into the quarries and there accumulate a large quantity of explosive, which is fired simultaneously.

In such cases a chamber is generally excavated at the end of a gallery, the length of which depends on the effect which it is desired to produce. The gallery is driven in zigzag, to avoid the charge blowing out the tamping. The dimensions of the gallery should be as small as possible, and only sufficiently large for one man to work in them.

The explosives are piled up in an excavation made at the end of the gallery, several primers of dynamite are introduced into the charge, and the whole well covered over with bags of earth or sand up to the roof of the tunnel, so as to ensure a good tamping. The excavation is now walled up in masonry and well packed in with débris, so as to ensure that the explosives are under close confinement.

Digitized by Google

Blast of Rock at Genoa.—In 1884 the Italian Dynamite Company fired on this principle a large blast in the port of Genoa, and particulars of the operation have been published.*

It was a question of blowing up a rocky hillock, *a*, *D*, *f*, *C*, Fig. 112, situated in the port of Genoa, and located between the lighthouse and the inner basin of the harbour. There had previously been excavated from the slope of the hill quite a cut, leaving exposed a steep face 20 to 26 metres in depth, and the bluff above was supported only by eight pillars. The pillars, 1, 2, 3, 4, to the left, were so weak that they were hardly able to bear the weight of the superincumbent rock mass. That portion of the hill which is shown in section in Fig. 113, rested to the right on the middle pillar 5. In the bend of the hill to the right of the quarry, the pillars 6, 7 and 8 supported the hill.



FIG. 112.—PLAN OF BLAST OF ROCK IN PORT OF GENOA.

At a height of about 28 metres (see Fig. 114) a tunnel was driven horizontally, but in a zigzag course. Its dimensions were 1·5 metre high by 0·9 metre wide, and at each turn the bends which made the zigzag were cut at right angles. At the end of the gallery a well was sunk, 8 metres deep and 1 metre

* In a report issued in Italy by the Societa del Dynamiti di Avigliana.

Digitized by Google

in diameter, which at the bottom was so enlarged as to form a mine chamber of 5 cubic metres contents.

To make the charge, sacks coated with paraffin were employed, and they held each 42 kilograms of dynamite. A



FIG. 113.—SECTION OF BANK OF ROCK.

line of workmen was ranged along the tunnel, and they passed the sacks one to the other, to the underground mining overseer, who placed the sacks in the mine chamber, pressing them



FIG. 114.—SECTION OF BANK OF ROCK.

tightly one against the other. After he had placed one layer at the bottom, a box with gelatine dynamite was placed in the centre, containing two primers, one provided with an electric fuze, and the other with an ordinary Bickford fuze. The

Digitized by Google

mine was now filled with a total weight of 5000 kilograms of dynamite, and sacks filled with sand were placed on top of it to fill the chamber, then loose sand was poured in till the shaft was completely filled for its total depth of 8 metres. At the tunnel end pieces of timber were piled up, and on it a coating of cement. At every turn of the zigzag a barricade of timber was built up, which was walled up with masonry, so as to ensure the complete confinement of the explosive.

The result on firing the mine was the complete breaking up of the hill-side up to the contour lines *a*, *b*, *c*, *d*, *e*, *f*, shown in Fig. 112, and the cubage of rock loosened by the blast was estimated at 120,000 cubic metres. There was no projection.*

Underground Drilling with Compressed Air.—In most mines where a large output of mineral is obtained, the drilling is done by machine drills.

In tunnels and shafts these drills are clamped to iron columns which are easily mounted and dismounted, but when stoping either "overhead" or "underhead," the drill is mounted on a tripod, which also can be shifted easily from one place to another. Fig. 115 shows a cross-section of an iron-mine in the state of New York.

Galleries are driven on various levels along the foot and hanging walls of the ore body, connecting with one main central working shaft, and parallel with one another. At about every 200 feet they are connected by means of cross-cuts driven transversely through the ore body, which varies from 40 to 60 feet in width; this ensures thorough ventilation and communication through the mine. A′, A′ show the longitudinal galleries along the second level; B′, B′ along the first level; D, D are the cross-cuts. After the cross-cuts are completed, breaking down the ore from overhead is commenced, and the accumulated ore remains on the mine floor, except such surplus as can be well spared, the broken ore occupying more space

* For further information on the subject of big blasts, the reader is referred to the author's 'Modern High Explosives.'

Digitized by Google

than the solid vein stone. The drill goes upwards as the ore heap accumulates in the mine.

To support the mine, occasional pillars are left standing



FIG. 115.—STOPING ORE IN AN IRON-MINE.

There are also shoots built up of timber carried along the foot and hanging walls through which the mineral is dropped into

Digitized by Google

the galleries below, and from where it is carried on cars to the central hoisting shaft.

Mining with Power-drills and High Explosives.—The introduction of power-drills in conjunction with modern high explosives has completely revolutionised the old system of mining and excavating. Mines which would never have paid have been rendered profitable through the great economy effected by these modern appliances.

There are instances on record of very unexpected profitable workings due to this cause, such as a copper-mine in the United States, which contains only three-fourths of one per cent. of copper per ton of stone (equivalent to 14 lbs. of copper per ton of rock), which nevertheless has been made to pay by reducing the cost of mining to a minimum. It would evidently not pay to work such a mine by the old method of hand-drilling, as the quantity of ore raised per man would be too small; but by the use of power-drills, a daily output of several hundred tons becomes feasible, which, although leaving a small profit on each ton raised, will in the aggregate show a handsome bonus.

The holes are generally bored to an average depth of 6 feet with power-drills, and two men on a ten-hour shift will drill about 36 feet in moderately hard ground, whereas in hand-drilling it is considered a good day's work for three men (one drill-holder and two strikers) to drill 8 or 9 feet. This would give an advantage of power-drilling over hand-drilling as of 4 to 1. When driving on a mineral lode, it is customary, when the face of the drift has been properly squared up, to commence breaking in at the bottom corner of the face near the foot wall. A hole is drilled perpendicular to the face, say 3 or 4 feet deep, and heavily charged with dynamite and fired. This produces a cavity around which two or three other holes are bored and fired; this will prepare the way for the next round of three or four holes, and so on. When the holes are fired by ordinary fuzes, they are cut of different lengths, so that the holes shall explode in rotation, and not simultaneously.

Digitized by Google

The quantity of explosive to be used in any particular instance can only be ascertained by experience, and no rule on the subject can be laid down. In deep bore-holes miners generally add from ½ to 1 lb. of ordinary black powder on top of the dynamite charge, as it helps to throw the rock around the mouth of the bore-hole, and will not leave a "bull-ring," as the miners call this imperfect explosive effect.

In starting a hole with a power-drill, the drill should be run slowly at first, for bits of rock get detached and obstruct the action of the drill by slipping under the bit of the drill. It is well to start a small cavity by hand-drilling first, so as to form a seat for the bit of the machine drill. Small pieces of rock may also fall from the sides into the hole, and the drill get stuck. In such a case the drill may be released by striking it a few blows with a sledge-hammer; the pieces of rock thus get broken, and the drill will resume its course. It is important to keep all rubbish away from the mouth of the bore-hole, so as to give the drill fair play-room. When the hole is once down 6 or 7 inches, the drill may be allowed to run at full speed.

Quantity of Explosives required for Excavation.—In the subjoined table will be found particulars of the quantity of explosives actually used in excavation in the course of tunnelling operations on a portion of the work recently executed in carrying out the scheme of the Glasgow Corporation Water Works. The table was compiled by Mr. R. Adam, A.M.Inst.C.E., the engineer-in-charge:—

Digitized by Google

GLASGOW CORPORATION WATERWORKS.—BLANE VALLEY CONTRACT (TUNNELS).

AVERAGE QUANTITY OF EXPLOSIVES, &C., USED PER CUBIC YARD OF EXCAVATION, REDUCED FROM AMOUNT CONSUMED ON 1400 LINEAL YARDS TUNNEL.

Name of Tunnel.	Dynamite.	Powder.	Fuse.	Detonators.	Candles.	Naphtha.	Remarks.
	lbs.	lbs.	hanks.	boxes.	packets.	galls.	
Ballewan, S. .	1·370	—	0·200	0·034	0·120	0·310	Very hard rock. Hand-drilling. Day work.
Ballewan, N. .	0·900	—	0·130	0·022	0·120	—	Good rock. Hand-drilling. Sub-contract.
Dumgoyn, S. .	1·270	—	0·200	0·027	0·210	—	Wet moderate rock. Hand-drilling. Day work.
Dumgoyn, N.	1·970	—	0·210	0·025	0·100	0·200	Soft rock. Machines. Sub-contract.
Dumgoyn, N.	1·600	—	0·150	0·020	0·070	0·150	Hard rock. Machines. Sub-contract.
Sauchie . .	0·370	2·240	0·400	0·011	0·110	0·050	Dry Red Sandstone. Hand-drilling. Sub-contract.
Lettre . . .	1·163	0·308	0·180	0·029	0·150	0·120	Partly wet sandstone. Hand-drilling. Day work.

Fuse, Hank = 48 feet. Detonator, Box = 100. Candles, Packet = 3 lbs.

Digitized by Google

CHAPTER XVI.

NITRO-GELATINE AND GELATINE DYNAMITE IN PRACTICAL APPLICATION.

NITRO-GELATINE and Gelatine Dynamite as used in Mining and in Tunnelling—Removal by Gelatine Dynamite of Obstruction in a Blast Furnace—Iron-plate Tests with Nitro-gelatine—Experiments with Military Explosive Gelatine.

Nitro-gelatine and Gelatine Dynamite as used in Mining and in Tunnelling.—Nitro-gelatine and gelatine dynamite are both excellent explosives for use under water, since, owing to their imperviousness to water, no nitro-glycerine exudes from them when submerged. No. 1 gelatine dynamite contains 60 per cent. of gelatinised nitro-glycerine, which is intimately incorporated with 40 per cent. of a mixture of finely powdered potassium nitrate and wood pulp. In addition to its excellent water-resisting qualities, it is equal in explosive efficiency to the 75 per cent. kieselguhr dynamite.

Engineer Hugo Mrünch has furnished the following results from the competitive trials of nitro-gelatine, gelatine dynamite, and kieselguhr dynamite, which have been made in various parts of Europe. To explode the nitro-gelatine a special primer was used.

1. *Experiments made in the Coal-mines of Königshütte, Prussia.*—These were made in a tunnel driven in very hard sandstone, the tunnel being 3 metres (10 feet) wide, and 2·10 metres (7 feet) high. Nine holes were bored (see Fig. 116), 0·9 metre each in depth, and leaving lines of resistance varying from 0·9 to 0·85 metre. Holes Nos. 1 to 6 were

Digitized by Google

charged with 150 grams of nitro-gelatine per hole, while a charge of 140 grams was used in each of the holes Nos. 7 to 9. A 20-gram primer was used with each charge, and they were fired with Bickford fuzes and extra strong blasting caps.



FIG. 116.—EXPERIMENT IN COAL-MINES OF KÖNIGSHÜTTE, PRUSSIA.

The three lowest holes were fired first, and a breaking-in hole 0·75 metre deep and 0·6 metre in diameter was produced. Through the explosion of the second series of holes, 4 to 6, the breaking hole was enlarged to 0·9 metre in depth and 1·4 metre in diameter. The explosion of the third series broke the rock down quite to the roof of the tunnel. The total amount of nitro-gelatine used in this work was 1·5 kilog. As it had been customary in this mine to charge the holes with 280 grams when kieselguhr dynamite (75 per cent.) was used, the total weight for the nine holes would be 2·52 kilogs.; therefore the efficiency of the nitro-gelatine compared with the kieselguhr dynamite is as 5 to 3. But the price of the nitro-gelatine is to that of the kieselguhr dynamite as 4·5 to 3, hence there is a saving in price of 10 per cent. in the use of the nitro-gelatine.

2. *Experiments in a Mine at Lugen, Saxony.*—Two holes, each 2·05 metres deep, were bored in the face of a cross-cut, 2·15 metres high and 1·7 metre wide, which had been made in a very hard sandstone (Fig. 117). Each hole was charged

Digitized by Google

with 926 grams of nitro-gelatine, and fired by electricity. The explosion produced a funnel 1·75 metre deep.

3. *Experiments in the Silver-Lead Mines, Friedrichssegen, near Oberlahustein.*—Ten holes, each 0·9 metre deep, were



FIG. 117.—EXPERIMENT IN A MINE AT LUGEN, SAXONY.

bored in one of the drifts which was 2·1 metres high and 1·75 metre wide. The rock is a hard, massive graywacke, and the holes were nearly all located horizontally. It was customary



FIG. 118.—EXPERIMENT IN THE SILVER-LEAD MINES, FRIEDRICHSSEGEN.

to charge the breaking-in holes 1 to 4 (Fig. 118) with 362 grams each of No. 1 kieselguhr dynamite, and to fire by electricity. In order to produce a funnel of about 0·75 metre in depth, the holes had to be loaded and fired three times in

Digitized by Google

succession with a charge of this weight. The enlargement-holes 5 to 10, which were also fired by electricity, contained charges of 274, 206, 104, 232, 154, and 232 grams respectively.

The results obtained with nitro-gelatine were as follows: The breaking-in holes 1 to 4 contained 181 grams each, and the first firing produced a funnel 0·48 metre deep, which was increased to a depth of 0·7 metre by a second firing of similar charges. The enlargement-holes 5 to 10 contained 37, 103, 52, 116, 77, and 116 grams respectively. Therefore the weight of nitro-gelatine used was to that of the kieselguhr dynamite as 2 to 5·5. Later reports state that a saving of 20 per cent. per metre of advance has been effected through the use of nitro-gelatine.

4. *Experiments at the Pfaffensprung Tunnel.*—The holes were bored in the bottom header, which was 2·2 metres high



FIG. 119.—EXPERIMENT AT THE PFAFFENSPRUNG TUNNEL.

and 2·5 metres wide. The holes were 0·073 metre in diameter and 1·5 metre deep, and, owing to the peculiar construction of the boring-machines, which prevented any angular deflection of the drills, the holes were all parallel with the axis of the drift. The cartridges of nitro-gelatine were 70 mms. in diameter, 100 mms. long, and weighed 0·6 kilog. The firing was done by caps and fuzes, and the fuzes were so cut as to explode the charges successively, in the numerical order shown in Fig. 119.

Digitized by Google

The charges were 1·25 kilog. per bore-hole. It was believed that 0·7 kilog. would have been sufficient to do the work of breaking down, but the engineer-in-charge held that the saving in the labour of removing the fissured rock (a very hard granite) when the larger charges were used more than counterbalanced the increased cost of the explosives.

When kieselguhr dynamite was used in this work, the charges were 2·08 kilogs. in weight, but, nevertheless, the holes would not bottom to within 0·25 to 0·3 metre.

5. *Experiments in the Spiral Tunnel near Faido.*—Four breaking-in holes (Fig. 120) were bored in the middle of the face, to a depth of 1·5 metre. These holes were parallel to one



FIG. 120.—EXPERIMENT IN THE SPIRAL TUNNEL NEAR FAIDO.

another, and were 0·5 metre apart. Grouped about them were eight enlargement-holes, which diverged from a common centre in the face of the drift, and whose lines of resistance were 1·5 metre. The holes had a diameter of 35 mms. at the bottom. The breaking-in holes were charged with 1·05 kilog. of nitro-gelatine each, and the fuzes were so cut as to explode simultaneously. Each of the enlargement-holes contained from 0·45 to 1·0 kilog.

The formation at this tunnel was a very hard gneiss, while in one place mica slate appeared in the bottom of the tunnel in parallel layers. In this slate it was found impossible to bottom the holes at the first firing, even with the heaviest

Digitized by Google

charge, and so they had to be loaded twice. To facilitate the work, the breaking-in holes were bored in an inclined position, and then blasted with 125 grams of the nitro-gelatine. This produced a pocket at the bottom of the holes, and enlarged them so that they could hold 1·025 kilog. each. The second firing generally made a clean sweep to the bottom. The efficiency of the nitro-gelatine to kieselguhr dynamite in this work was found to be in the ratio of 5 to 3. Not only was the result more satisfactory as regards efficiency, but the gases from the explosion of nitro-gelatine were thought to be less obnoxious than those from the other nitro-glycerine preparations. It was found, however, that good primers and strong caps were essential to success.

6. *Experiments in a Coal-mine near Tankerode, Saxony.*— The tunnel was 3·25 metres high and 1·6 metre wide, and the bore-holes were located as shown in Fig. 121. The holes 1, 2,



FIG. 121.—EXPERIMENT IN A COAL-MINE NEAR TANKERODE, SAXONY.

and 3 were 0·9, 0·8, and 0·7 metre deep. Their lines of resistance were 0·6 metre, and they were charged with 160 grams of nitro-gelatine, and through their explosion a funnel 1·45 metre wide and 0·7 metre deep was formed. Holes 4 and 5 were 0·95 and 1·0 metre deep, and were charged with

Digitized by Google

190 grams. Holes 6 and 7 were 0·7 metre deep, and were charged with 160 grams. All these holes had lines of resistance of 0·6 metre, and, when fired successively as numbered, they bottomed the holes. Holes 8 and 9 were bored from inside the funnel to a depth of 0·8 metre. Their lines of resistance were 0·85 metre, their distance apart 1·2 metre, and their charges 200 grams of nitro-gelatine per hole. Both holes were tamped with water, and their explosion brought away a block measuring over 1·0 cubic metre, and gave an average advance of 0·8 metre.

The superintendent determined to increase the depths of the holes in the future to 1·2 metre, with lines of resistance of 1·0 metre. Such a method of work could not be carried out with kieselguhr dynamite.

Since the introduction of nitro-gelatine in Europe, the holes have been bored somewhat deeper than had before been customary. *The depth of the breaking-in holes should be equal to from one-half to two-thirds of the width of the drift or adit.*

Removal by Gelatine Dynamite of Obstruction in a Blast Furnace.—A stoppage in one of the blast furnaces of the Innerberger Iron Company, at Schwechat, Austria, having necessitated its going out of blast, it was found that an enormous "sow," 0·65 metre thick and 4·0 metres in diameter, had been formed from iron, of great toughness and equalling Bessemer steel in hardness. Above this was a mass composed of iron, slag, rock, and graphite cemented together, which averaged 2·15 metres in height and 2·45 metres in thickness (see Fig. 122). As this upper portion was worthless, it had to be separated from the lower part.

To do this the horizontal holes 1 to 6 (Fig. 123) were drilled about 0·82 metre in depth. The holes 2, 3, and 4 were loaded and fired four times, and 1, 5, and 6 were fired five times. The charges varied from 55 to 187 grams per hole until the fifth round, when the charges in these three holes were increased to 198 grams. By the fourth and fifth rounds pieces of iron were thrown out, as shown in Fig. 123.

Digitized by Google

To cut up the lower part, or the "culot," nineteen holes, averaging 0·25 metre in depth, were bored, and they were fired



FIG. 122.—REMOVAL BY GELATINE DYNAMITE OF OBSTRUCTION IN A BLAST FURNACE.

in groups. Portions of the iron became detached from the



FIG. 123.—DRILL-HOLES MADE IN REMOVING OBSTRUCTION FROM BLAST FURNACE.

top as the firing progressed, thus diminishing the depths of some of the bore-holes so much that they were again deepened.

Digitized by Google

These holes were repeatedly fired, some of them five times, both singly and in groups, with charges ranging from 187 to 300 grams, until the iron was broken into pieces of such size that they could be easily handled.

Thirty-two and a half kilogs. of gelatine dynamite were consumed in the entire work, and the total cost amounted to 300 Austrian florins (£32 10*s.*), while the sound iron which was recovered weighed 1350 centners (135,000 lbs.). Owing to the vicinity of buildings, and on account of the furnace itself, only small charges could be used, and this necessitated repeated firing.

Iron-plate Tests with Nitro-gelatine.—A series of experiments with this object were carried out by Captain Ph. Hess, of the Austrian Army. Wrought-iron plates of good quality, 16 cms. wide, 32 cms. long, and from 13 to 40 mms. thick, were usually employed, though in some of the experiments the plates were 16 cms. square. To prevent any error due to the direct action of the primer on the plate, the charges—which were laid across the width of the plates—had a length of 21 cms. The cartridges were all formed with parchment paper, the dynamite having the form of a right cylinder, and the nitro-gelatine (with 4 per cent. of camphor) that of a prism with a square section. The special primer, of 20 grams weight, was employed.

The iron plates were supported on two square timbers as shown in Fig. 124, thus leaving the central portion, 250 mms. in length, unsupported. The cartridge was laid across the plate at right angles with the longer axis (Fig. 125), and bound to it with a cord in such a way that one end of the cartridge coincided with one edge of the plate, while the opposite end of the cartridge projected 5 cms. over the other edge of the plate. The primer was attached to this projecting end, and it was so adjusted as to ensure a close contact with the explosive.

As the nitro-gelatine cartridges were square in form, the superficial contact between the explosive and the plate would

Digitized by Google

not have been the same, when these were placed flat upon the plate, as that which obtained when the cylindrical dynamite cartridges were placed upon the plate; and hence, in order to secure this equality, it was decided to place the square prisms with their diagonals perpendicular to the plate-surface, as shown in Figs. 126 and 127.



FIG. 124.

FIG. 125.

FIG. 126.

FIG. 127.

DIAGRAMS ILLUSTRATING IRON-PLATE TESTS WITH NITRO-GELATINE.

In discussing the weights of the charges, that portion of the charge which projects beyond the plate will be left out of consideration, since numerous trials have demonstrated that only that portion of the explosive which is in direct contact with the plate exerts any material effect, and that the influence of the projecting portion is very slight. Hence it will be understood that the weights given in the following experiments are the weights of the 16 cms. of the cartridge which is in direct contact with the plate. In order, then, to find the full weight of explosive used, it will be necessary to multiply the weight

Digitized by Google

given by $\frac{4}{3}$, and to add to this product the weight of the primer.

The detonation was determined by means of caps containing 1 gram of fulminate and an ordinary fuze. Both soft and frozen nitro-gelatine were tested, the ordinary kieselguhr dynamite being used as a standard for comparison.

Subjoined is a *résumé* of the experiments.

(*a*) *Tests on Iron Plates* 13 *mms.* (*half-inch*) *thick.*

Soft Preparations.—Nos. 1, 2, 3, 4.—The charge each time consisted of 100 grams of the military explosive gelatine. The explosions broke holes completely through the plates.

Nos. 5, 6, 7, 8.—The charge each time consisted of 100 grams of dynamite No. 1. Explosions 5 and 8 blew holes through the plates, while 6 and 7 caused indentations with fissures on the convex side of the plate.

Nos. 9, 10, 11, 12.—The charge each time consisted of 80 grams of military explosive gelatine. Nos. 9, 10, and 12 blew holes completely through the plates, and in No. 12 a piece of iron lying underneath was partially broken, but in No. 11 only a concavity resulted, which was about equal in extent to that obtained in No. 7, where 100 grams of dynamite No. 1 were used.

From these experiments it is concluded that 100 grams of military explosive gelatine are sufficient to pierce iron plates 13 mms. thick with certainty; 80 grams of this explosive could not be relied upon with certainty to pierce plates of this thickness, and the same is true with 100 grams of dynamite. We may also conclude that 80 grams of military explosive gelatine are equal in breaking effect to 100 grams, and consequently the gelatine is, for equal weights, 25 per cent. more powerful than kieselguhr dynamite No. 1, and ought to do that amount more work.

Frozen Nitro-gelatine.—These experiments were made for the purpose of determining whether the breaking efficiency of the frozen military explosive gelatine was equal to that of the soft

Digitized by Google

or unfrozen gelatine. As it had been demonstrated that 100 grams of the soft gelatine was the smallest quantity of the explosive which would pierce plates of 13 mms. in thickness with certainty, it was decided to use the same weight of the frozen gelatine, as any difference in efficiency would be apparent at once. The explosive was kept for eight days in a mixture of salt and snow, in order to ensure complete freezing.

Nos. 13, 14.—The charge was 100 grams of frozen military explosive gelatine. Both explosions pierced the plates completely, and the plates presented the same appearance as was seen in Nos. 1 and 4; hence there does not appear to be any difference in breaking efficiency between soft and frozen military explosive gelatine. It is to be regretted that these experiments were not extended to the 80-gram charges, since, in the previous trials with this weight, the plates were pierced in three of them. It is safe to say that frozen military explosive gelatine is certainly equal in strength to the best kieselguhr dynamite.

(*b*) *Trials on Plates* 26 *mms.* (1 *inch*) *in Thickness.*

Nos. 15, 16, 17.—The charges consisted of 130 grams of soft military explosive gelatine. Nos. 15 and 16 produced an indentation in the plates with some deep (?) fissures on the reverse side. No. 17 pierced the plate completely.

Nos. 18, 19, 20.—The charges were 160 grams of soft dynamite. No. 18 pierced the plate completely; Nos. 19 and 20 produced an indentation with fissures on the reverse side.

Nos. 21, 22.—The charges were 160 grams of soft military explosive gelatine. The plates were pierced in both cases. The effects of the shots with 130 grams of gelatine were nearly equivalent to those of the shots with 160 grams of dynamite, and the relation between the gelatine and dynamite is therefore as 160 to 130, or nearly as 125 to 100. At the same time, it is shown that 160 grams of gelatine are required to pierce 1-inch plates with certainty.

Digitized by Google

(*c*) *Trials on Plates* 40 *mms.* (1½ *inch*) *thick.*

It should be noted here that these plates were more crystalline in structure than the previous ones, and that their resistance was relatively not much greater than that of the thinner plates.

Soft Explosives.—Nos. 23 and 24.—The charges were 160 grams of nitro-gelatine. In both cases the plates were completely pierced.

Nos. 25 and 26.—The charges were 190 grams of dynamite. No. 25 pierced the plate completely; No. 26 only partially.

The efficiency of the 160 grams of nitro-gelatine was superior to that of the 190 grams of dynamite; hence the relative efficiency of 125 to 100 still holds good.

Frozen Explosives.—In these experiments it was sought not



FIG. 128.



FIG. 129.

IRON-PLATE TESTS WITH FROZEN EXLOSIVES.

only to determine the relative efficiency of soft and frozen explosives, but also to ascertain if, in cartridges of considerable length, the whole of the mass was exploded by means of the special primer used. The cartridges of nitro-gelatine were 0·63 metre long, wrapped in parchment paper, and they were placed in a mixture of snow and salt and stored in a refrigerator for eight weeks before using. Figs. 128 and 129 show the manner of arranging the cartridges for firing. As the supply of plates 32 cms. long had been exhausted, plates 16 cms. in length were employed, and therefore they offered a

Digitized by Google

greater resistance than those used in Nos. 23 to 26. Hence it was decided to increase the weight of explosive used.

Nos. 27, 28.—The charges were 190 grams of nitro-gelatine. In both cases the plates were completely pierced. This proves conclusively that frozen nitro-gelatine is completely detonated even when in quite long cartridges, and that it equals the soft explosive gelatine in efficiency.

No. 29.—The charge was 250 grams of soft dynamite in a cartridge 16 cms. in length. The result was equal to those obtained in the cases of Nos. 27 and 28.

Here again the ratio of 125 to 100 is obtained, and it agrees with that existing between the soft explosive gelatine and the soft dynamite, so that we may fairly claim that the frozen gelatine is equal in efficiency to the soft gelatine.

The explosive gelatine used in these experiments contained 4 per cent. of camphor, which was used to diminish its sensitiveness. Some of this camphor may escape during storage, owing to its volatility, but while this would increase the sensitiveness of the explosive, it would also increase its disruptive efficiency.

The following conclusions are to be deduced from these experiments: (1) Normal military explosive gelatine is, weight for weight, 25 per cent. more efficient than kieselguhr dynamite No. 1. (2) The normal charges of this gelatine required for breaking plates are: for 13-mm. plates, 100 grams; for 26-mm. plates, 160 grams; and for 40-mm. plates, 190 grams. (3) The primer and charge may be frozen without diminishing either their explosive efficiency or the readiness with which they may be exploded, and this even when the cartridges are as much as 63 cms. in length.

Behaviour of Explosive Gelatine under Water.—Two cartridges of nitro-gelatine (containing 4 per cent. of camphor) were placed in a tub of water. The cartridges were 21 cms. long and 133 grams in weight, and they were freely exposed without any paper case or other protecting envelope. Two similar cartridges were placed in a linen bag and hung in the stream

Digitized by Google

(the Moldau river), where they were exposed to the action of the current for forty-eight hours. When these samples were taken out on the third day, they were found to be coated with a thin whitish film, but there was no evidence of oily exudation, and the weights were unchanged. After being exposed to the air for a short time, all the samples regained their natural transparent appearance.

Nos. 30, 31.—The charges were 100 grams each of the nitro-gelatine which had been submerged in the river during forty-eight hours. Dry primers were used, and the charges were exploded on plates 16 cms. square and 13 mms. thick. In both cases the plates were completely pierced. Hence there was no diminution in the bursting efficiency owing to the action of the running water.

Tests of the Special Primer designed for use with Military Explosive Gelatine.—The primer which had been used with the high explosives was made with gun-cotton dynamite (75 per cent. nitro-glycerine and 25 per cent. Lenk's gun-cotton). These having been found incompetent to induce the complete detonation of the explosive gelatine, and thus develop its full strength, a new primer composition was devised which consisted of 60 per cent. of nitro-glycerine and 40 per cent. of nitro-hydro-cellulose. While the tin capsules used held only from 15 to 17 grams of the old composition, they held from 19 to 20 grams of the new, since the latter was more dense.

Some experiments were made in order to determine the relative strength of the old and new primers, by exploding them on iron plates. The plates varied in thickness from 5 to 9 mms., and were supported on square blocks of wood, as shown in Fig. 130.

The primers were placed upright on the plates, and were exploded by caps containing 1 gram of fulminate. The results of these experiments were found useful in fixing upon a standard of strength for the new primer.

No. 1. *New Primer.*—Plate 5 mms. thick. The explosion produced a clean round hole in the plate, the diameter of the hole being equal to that of the cylinder.

Digitized by Google

No. 2. *Old Primer.*—Plate 5 mms. thick. The result was an elliptical opening in the plate, which was then sharply bent and broken in two pieces. These effects show that, although the iron is poorer than in No. 1, still the old primer is not so efficient as the new.

No. 3. *Old Primer.*—Plate 5 mms. thick. Results, one fissure and the plate bent without breaking.



FIG. 130.—EXPERIMENTS TO DETERMINE STRENGTH OF PRIMERS.

No. 4. *New Primer.*—Plate 6 mms. thick. A clean round hole.

No. 5. *New Primer.*—Plate 9 mms. thick. Elliptical hole in plate.

These experiments show that the new primer produces the same deformation in the 9-mm. plate that the old one does in the 5-mm. plate.

Test of Frozen Primers.—Some of the new primers were frozen in a mixture of ice and salt.

Nos. 6 and 7. *Frozen Primers.*—Plates 9 mms. thick. Marked indentation in the plate in both cases.

Nos. 8 and 9. *Unfrozen Primers.*—Plates 9 mms. thick. Clean-cut holes were blown through the plates in both cases.

Digitized by Google

Hence the primers are weaker when frozen than when soft.

Experiments with Military Explosive Gelatine.—In some experiments with this substance which were made by Captain Emmanuel Wawra, of the Austrian Engineers, on the Simmeringer Haide, between January 29 and February 10, 1878, the nitro-gelatine came either in the form of cubes 4 cms. wide and 100 grams in weight, or of parallelopipedons 20 cms. long, 4 cms. in cross-section, and weighing 500 grams. It contained 1, 4, and 10 per cent. of camphor. For the experiments in the laboratory, samples were prepared of various shapes, and containing from 0, 1, and 2, up to 10 per cent. of camphor. The primers contained about 30 grams of the mixture.

The manufacturer who furnished the nitro-gelatine was required to conform to the following specifications: (1) The explosive to be of uniform composition (90 parts nitro-glycerine, and 10 parts soluble nitro-cellulose.) (2) The nominal and actual camphor contents to be identical. (This deserves special attention, on account of the volatilization of the camphor during the gelatinizing.) (3) The constituents to be entirely free from acid, and the percentage of moisture must be noted. (4) The primers to be composed of 60 per cent. of nitro-glycerine, and 40 per cent. of nitro-hydro-cellulose. (5) The cartridges to be wrapped in double layers of tin-foil.

The results of the analysis of the nitro-gelatine were as follows:—

NITRO-GELATINE WITH 1 PER CENT. OF CAMPHOR.

	Analysis.	Synthesis.
Nitro-glycerine	86·30	89·1
Collodion-cotton	12 59	9 9
Camphor	0·98	1·0
Water	0·66	0·0
	100 53	100 0

Digitized by Google

NITRO-GLYCERINE WITH 4 PER CENT. OF CAMPHOR.

	Analysis.	Synthesis.
Nitro-glycerine	84·82	86·40
Collodion-cotton	10·04	9·60
Camphor	4·74	4·00
Water	0·68	0·00
	100·28	100 00

The freezing of the nitro-gelatine was effected by exposing it in a freezing apparatus to a temperature of −15° C. for six or seven days. It was observed that, in spite of this low temperature, some portions of the gelatine failed to freeze.

On the days on which the experiments were made, the thermometer ranged between 0° and 3° C. The soft gelatine required was obtained by exposing a portion for three days in the thawing apparatus, at a temperature of 40° C. The gelatine was exposed to the firing in small wooden boxes, which contained 4½ kilogs. each. The boxes were laid on a horizontal square beam, and a second beam was placed vertically behind it. Both beams were embedded in the slope of the earth-wall, which served as a proof-butt.

Experiments with Frozen Gelatine.—At each volley four guns were fired simultaneously, at a distance of 150 paces, into the box. *First volley:* Box contained gelatine with 1 per cent. of camphor. Complete explosion. The beams were shattered into splinters. *Second volley:* The guns did not fire simultaneously, and did not hit. *Third volley:* Complete explosion. Results similar to first volley.

Trials were now made with one gun only. *First round:* Fired in gelatine with 4 per cent. of camphor. Distance, 150 paces. Complete explosion of the box. *Second round:* Fired into gelatine with 10 per cent. of camphor. Distance, 150 paces. Complete explosion.

Experiments with Soft Gelatine.—First round: Gelatine with 4 per cent. of camphor. Distance, 150 paces. No explosion. *Second and third rounds:* Fired into the same box, with the same result. First volley with four guns, of which two hit, but

Digitized by Google

no explosion. Second volley with four guns, of which one hit, but no explosion. Third volley with four guns, of which three hit, but no explosion. Fourth volley with four guns, one hit, no explosion. Fifth volley with four guns, two hit, no explosion.

Digitized by Google

CHAPTER XVII.

APPLICATION OF ELECTRICITY IN FIRING MINES.

ECONOMICAL Value of Blasting by Electricity—Sir Frederick Abel's Test —Electric Blasting Apparatus—Magneto Machine No. 3—Directions for Blasting—Influence of Heat on the Conductivity of Gutta-percha-covered Wire—High-tension Fuzes.

THOSE who have most carefully studied the question of blasting by electricity are most earnest in praise of the method and of its economical value.

A very little thought will make apparent the greater effect which can be produced by firing simultaneously a number of blasts, instead of firing them singly, while a little experience will teach that even in firing single blasts by this apparatus much can be gained. One advantage gained in firing single holes is, that in case of miss-fire (which happens rarely by this method) no time is lost in waiting, as in the case of firing by safety fuze there would be before approaching the work. There is no "hanging" fire.

A second advantage is, that the explosion of the electrical fuze at the bottom of the charge, where the priming cartridge can be placed, throws the fire through the whole body of the powder, igniting it all at once, and by *detonation*, giving the same charge by far greater explosive effect, as has been fully demonstrated by experiment.

Another advantage is, the explosion of an electric fuze at the bottom of charge produces the first rupture in the rock at bottom of the hole, leaving the tamping perfectly tight, and confining all the explosive gas until the dynamite is completely consumed and its force expended in loosening rock.

Digitized by Google

When firing is done with a common fuze, the first point of rupture in the rock is often near top of charge, which often leaves a large part of the hole unruptured, the drilling of which and the powder it contained was a total loss, for if it had exploded it would have burst everything around the hole.

The following test, devised by *Sir Frederick Abel*, illustrates very well the different behaviour of gunpowder with the detonating mode of firing :—

"Three small iron cylinders of inch steam pipes, each being 5 in. in length and having a cap screwed on one end, are bedded in the earth, with the open ends level with the surface.

"In the first is placed a charge of fine-grain gunpowder, which is fired by an electric fuze, primed with mealed powder. The powder explodes with a dull report, leaving the cylinder in its place and uninjured.

"The second tube contains an electric fulminate fuze, the remainder of the space being filled with sand. On firing this tube is bulged and cracked a little, but not moved.

"The third tube contains the same quantity of powder as was used in the first one, but it is fired by a fulminate fuze similar to that which was used in the second tube.

"In this case the report is sharp, the cylinder is torn to pieces which are scattered about, and the earth in which it was imbedded is thrown out so as to leave a considerable cavity."

When the charge is very large, it is best, indeed, to place several fuzes at different points, as it is obvious that, whether using fulminate fuzes or others, a great advantage is obtained by a simultaneous firing of the powder at different points instead of firing at one end.

The now well-known effect of the ignition of gunpowder in a confined space is to suddenly convert its solid substance into a great volume of fiery gases of a powerfully expansive nature, which will either speedily find release by rupturing the walls which confine them, or almost as speedily be again resolved, in great part, into a liquid having no expansive tendency.

It is known, too, that a certain though very small interval of

Digitized by Google

time is taken in the passage of the fire through the whole mass of a charge of powder, proportioned, of course, to the size of the charge, its density or compactness, and also, in some degree, to other qualities.

It is also well known that the speed of electricity is many thousand times greater than that of fire passing through any substance whatever, being by comparison instantaneous.

It will readily be seen, therefore, that a great advantage is had, when a charge is fired at many points, and the whole converted into these violent gases simultaneously, over firing at one point, with a comparatively gradual production of the rupturing force.

Electric Blasting Apparatus.—The machine for blasting by means of an electric current which finds the greatest favour at the present time is a magneto-electric instrument of small size, weighing only about 16 lbs., occupying considerably less than half a cubic foot of space, and sold in America at 25 dols.

It is constructed on the Wheatstone and Siemens principle, having a magnet of the horseshoe character, of iron, wound about with coils of insulated copper wire; between the poles of the magnet there is fitted to revolve an armature of cylindrical construction, carrying in its body other insulated wire coiled longitudinally, as to the cylinder.

The rapid revolution of the armature, by suitable means, generates and sustains in the machine an accumulative current of voltaic electricity of great power, which at the moment of its maximum intensity is, practically, switched off to the outside circuit in which are the fuzes, and in the interior of each fuze the ignition is accomplished instantly.

In magnetic iron mines the "frictional" machine fails through diversion or dissipation of the electricity, but the "magneto" there works perfectly well; and in submarine or very wet work is also superior, as imperfect insulation is not always an obstacle to its successful working.

The *Magneto Machine No.* 3 here described has fired fifteen

Digitized by Google

fuzes—the current of electricity having been conveyed through one-quarter of a mile of bare iron telegraph wire in the water at the bottom of a canal, the fuzes also being immersed.

The capacity of the machine is for about 12 or 15 holes, though under wholly favourable circumstances many more can be fired. The interior arrangement is shown in Figs. 131 and 132 A is the principal magnet; B, the armature revolving between the poles of the principal magnet; C, the loose pinion, its teeth engaging with the rack bar, and by clutching also engaging with the spindle of the armature on the downward stroke (only) of the rack bar; D, the spring, which when



FIGS. 131, 132, 133.—MAGNETO MACHINE FOR ELECTRIC FIRING OF BLASTS.

struck by the foot of the descending rack bar, breaks the contact between two small platinum bearings, and this causes the whole current of electricity to pass through the outside circuit,—the leading wire and fuzes; E, the two platinum bearings, one on the upper face of the spring, the other on the under side of the yoke over the spring; F, the commutator.

The "commutator" is a thin ring of copper like a section of a tube, or would be so were it not divided by a saw cut on each side into two equal parts, which are fastened upon a hard rubber hub. The commutator has pressing upon it (on the outer surface of the ring) two copper springs. These should

Digitized by Google

press firmly upon it, and its surface must be kept bright and clean.

In the course of time, particularly if the machine should not have been used, this surface may become tarnished, then it will be necessary to make it bright. Rubbing with dry emery paper will serve the purpose. Also, small particles of the copper, the result of the wear of the ring or the springs, may fall into the crevices between the two parts of the ring. If these crevices become filled with dust of copper, the result will be to weaken the effectiveness of the machine, as it is necessary that the two parts of the ring should be insulated, and this is the reason of the hard rubber hub.

In order to cleanse this ring or commutator, the rack must be taken out of the case, which can be done by removing the small pin near the lower end of the same. Then the interior works of the machine, with the shelf on which they rest, can be moved partly out of the case—far enough for the purpose. Having done this, remove the springs which press upon the commutator, and then remove the yoke which holds in place the spindle upon which the commutator runs, when the latter can readily be cleaned and replaced.

In very few of the machines has there been any necessity found for this cleaning process, and these minute directions are given, not because they are very likely to be needed, but to save to the person using a machine the trouble and delay caused by having to return it to the makers, from perhaps a great distance. The spindle bearings front and rear will need oiling occasionally.

Fuzes.—The platinum fuze, which is used with the magneto machine, is shown in section in Fig. 134, nearly of the actual size.

A is the shell, of copper, having a raised rim, thrown out from the inside, which holds the sulphur cement more firmly in place; B, the chamber containing the charge of explosive, composed mainly of fulminate of mercury—very powerful; C, the fuze wires, of copper, entering the shell, having a covering which is a partial insulator sufficient for all ordinary purposes; D, the bare ends of the copper fuze wires, projecting

Digitized by Google

above the sulphur cement and into the charge; E, the small platinum wire, or bridge, soldered to and connecting the two ends of the fuze wires: this is heated to redness or combustion by the passage of the electric current; F, the sulphur cement holding the fuze wires firmly in place.

The fuzes commonly in use have wires of 4, 6, and 8 feet in length; any required of greater length of wire are specially made. Those in general use are all of cotton-covered wires, but gutta-percha covering is sometimes required. This nicety of insulation by gutta-percha covering, however, is not needed for general work, but only where blasting is to be done in deep water—probably, indeed, not then, unless several fuzes are to be fired simultaneously through a great length of submerged wire.

FIG. 134.—PLATINUM ELECTRIC FUZE.

Leading Wire.—Enough wire is needed with each machine to make two leaders, of sufficient length to reach from the blast to a safe distance for the person to stand who is to set the machine in operation. Five hundred feet is the quantity usually adopted, but in some cases a thousand have been used.

Connecting Wire.—This is sold in coils of one or two pounds weight, and is used in connecting the fuzes with each other where several charges are to be fired simultaneously.

Wire Reels.—As after use the leading wires may become entangled, and to facilitate the playing out of the wires when preparing them for use and in shifting them from blast to blast, a little apparatus is used called the blasting wire reel. It consists of a strong hard wood box, with a double reel inside, so adjusted that, by means of a connecting rod on the flange of each wheel, easy and speedy connections can be made with the battery in use. To this rod the leading wire is permanently connected, and is always ready for use. It is

Digitized by Google

but the work of a moment to run out as much leading wire as is wanted to connect the battery, and fire; and then as quickly wind up again. The reel by means of a strap is carried around the neck of the man.

Directions for Blasting.—A fuze should be used with the wires attached, of such length that the ends may protrude from the surface after the hole is charged, the fuze head being in the centre of the charge.

Tamp with dry sand, or in such a manner that the wires may not be cut or the insulated covering upon them be injured. When all the holes to be fired at one time are tamped, separate the ends of the two wires in each hole, joining one wire of the first hole with one of the second, the other or



FIG. 135.—CONNECTING WIRE.



FIG. 136.—MINES ELECTRICALLY CONNECTED.

free wire of the second with one of the third, so proceeding to the end or last hole.

If the wires attached to the fuzes should not be long enough, use connecting wire for joining. All connections of wires should be by hooking and twisting together the bare and *clean* ends, and it will be better if the parts joining be bright. (Fig. 135).

The charges having all been connected as directed above, the free wire of the first hole should be joined to one of the "leading" wires, and the free wire of the last hole with the other of the two leading wires. The leading wires should be long enough to reach a point at a safe distance from the blast—say two hundred and fifty feet at least. (Fig. 136).

All being ready, but *not until the men are at a safe distance*, connect the leading wires, one to each of the projecting screws

Digitized by Google

on the front side of the machine, through each of which a hole is bored for the purpose, and bring the nuts down firmly upon the wires.

Now, to fire, taking hold of the handle for the purpose, lift the rack (or square rod toothed upon one side) to its full length and press it down, for the first inch of its stroke with moderate speed, but finishing the stroke with all force, bringing



FIG. 137.—FIRING BY ELECTRICITY AT BOTTOM OF SHAFT.

the rack to the bottom of the box with a solid *thud*, and the blast will be made.

Holes which are fired simultaneously should not be more than their own depth apart from each other; thus, if the holes are 6 feet deep, they should only be 6 feet apart.

It is advisable to place the priming cartridge with the electric fuze in it at the bottom of the hole, and leave several

Digitized by Google

inches of the wires protruding out of the hole. In tamping take care not to rub the wires.

Fig. 137 represents a blast of three holes, each 6 feet deep, ready to fire in the bottom of a shaft that may be many hundreds of feet deep. As soon as the operator in the house



FIG. 138.—THE BLAST FIRED.

pushes down the operating rod, all the holes will fire simultaneously, and the result will be as shown in Fig. 138.

Influence of Heat on the Conductivity of Gutta-Percha-covered Wire. — The subjoined remarks on this subject by *J. M. Kostersitz*, Lieutenant-Colonel of Engineers in the Austrian Army, will be found of practical value :—

"It will be well to mention (he says) in advance, that the influence of heat is deleterious to the igniting effect, and the

Digitized by Google

reason of this is in the diminution of the insulating power of the gutta-percha.

"Schellen, in the year 1870, in his book 'On the Electro-Magnetic Telegraph,' says that when gutta-percha is cleansed of its impurities it possesses great insulating power, which decreases with an increase of temperature. Its conductivity at 20° C. is twelve times greater, and therefore its resistance to electricity is twelve times less than at 0° C. At that time no experiments had been made to determine this phenomenon exactly, and its influence on its application to explosive purposes. The impression prevailed at that period that the igniting power was not influenced in any way.

"Water was considered as an element against which the greatest precautions were to be taken, but subsequent experiments disproved this supposition, even if the copper wire was deprived of its insulation in some places. Not alone was it proven that the conducting power of the copper wires is unimpaired by water, but that during very hot weather water affords the greatest protection for the wires. That the igniting effect during hot weather is considerably diminished is beyond doubt, as this fact made itself felt during every experiment carried out during the hot weather.

"At first the supposition existed that the deleterious effect of heat acted only on the electric apparatus, in consequence of the rarification of the air, and this was partially correct.

"Later experiments have proved that the fault is with the wires. The experiments which finally solved this question were finished in the year 1875, and publications of that year recommended as precautionary measures the prevention of the crossing and touching of the leading and return wires, whether they are insulated or not insulated. There was also another danger to be feared, which was if the connecting wires between the different mines should touch one another.

"These connecting wires should not be viewed as a part of the main conducting line, but they should be considered as a part of the arrangement where the equalisation of the electricity takes place. In case these connecting wires should touch one

Digitized by Google

another, and if in consequence of a high temperature the insulating power of the gutta-percha should be diminished, at the point of contact an adjustment of the two electricities takes place which greatly influences the igniting effect, which under certain conditions may result in a miss-fire of all the mines.

"If, for example, we have such an arrangement as in Fig. 139, in which A is the leading and B the return wire, while the dots 1 to 7 indicate as many mines, and if the connecting wire 2 and 3 should cross 6, 7 in *a b*, then it may happen that the equalisation of electricity on the road 1, 2 and 7 may take place, and the mines 3, 4, 5, 6, be excluded from the passage of the electric fluid and miss fire. Therefore the greatest precaution is necessary to avoid contact of the connecting wires, as well as of the leading and return wires.



FIG. 139.—CONDUCTING WIRES.

"A case in point took place during the experiments with a new electric apparatus, in which a complete miss-fire of the fuzes occurred. This led to a detailed investigation of its causes. The experiment took place on the 7th of August, 1874; temperature, 20° C.; humidity, 90 per cent.; barometer, 753 mm. Owing to a rainstorm the atmosphere was charged with moisture, and was sultry; the temperature of the air was high. The uncertainty of the weather necessitated making the connections of the fuzes in a hut. The number of fuses was 114. The space was limited, and a contact between a number of the connecting wires could not be avoided. On closing the circuit only two fuzes exploded, nearest to the leading wire. A repitition of the firing met with a similar result, to the great surprise of those present. An examination of the electric apparatus proved its complete efficiency, and

Digitized by Google

the leading and return wires showed no interruption in their continuity, but it was decidedly proved that the hut for the fuze arrangement was too small, and it was impossible, owing to want of space, to completely insulate the connecting wires, so that their contact was unavoidable.

"The fuzes were now taken into the open air, and the trial made immediately on the spot caused the explosion of all the connected fuzes, 114 in number. Further experiments, which were carried on in the open air, always caused the explosion of all fuzes.

"It may be mentioned here that the wooden hut was saturated by the rain, and that some of the connecting wires touched on some large nails, and in this way, by means of the wet boards, a dispersion of the electricity into the ground may have also taken place. This supposition was likewise strengthened by the fact, that in the experiments carried on in the open air some connecting wires were purposely placed in contact with others, and a complete explosion still ensued. Of course the temperature had cooled down somewhat, the grass was wet in which the wires were placed, which cooled the wires, and in consequence the conditions for the passage of the electricity in the open air were more favourable.

"The following experiments were carried out by the military committee in Vienna in the summer of 1875, during the hot days on the 1st, 2nd, and 3rd of July, when the temperature stood at 29° to 35° C.; the moisture varied between 70 and 62 per cent.; the barometer showed only 720 mm.

"The apparatus, contrary to the usual precaution taken with them, were left exposed during the whole day to the influence of the extraordinary heat, as well as the fuzes and connecting wires, whereby the insulating power of the gutta-percha was considerably diminished. Whereas, during the forenoon, the apparatus had a power of firing from 50 to 100 fuzes, on the afternoon of the first day the number was reduced to 30, and on the afternoon of the second and third days only 20 fuzes would explode.

Digitized by Google

"To find out the cause of this diminution of effect, the fuzes were put down again in the hut, and the effect raised at once from 40 to 60. The same effect was obtained on putting the connecting wires into troughs of water, and they were connected with an apparatus which had been exposed for a whole day to the rays of the hot sun. This experience has again demonstrated the weakening effect which heat exercises both on the apparatus and wires, and has also shown that in placing the wires on the ground or on water, or even by simply covering them with a bad conductor of heat, a good protection is offered, and the precaution must also be taken not to expose the apparatus unnecessarily to the influence of heat.

"The experiments subsequently made on the 10th of August led to the adoption of certain precautionary measures for preventing the defects caused by heat on the igniting power of apparatus and wires. Attention has to be drawn more to the connecting wires than to the leading and return wires, and that especially in those connecting wires which are very close together, an equalisation of electricity may take place, whereby the firing effect is diminished or partly destroyed. By avoiding all contact of the connecting wires, the results obtained were entirely satisfactory, as from 100 to 150 fuzes were exploded.

"Heretofore the cause of imperfect firing was assigned to defects in the apparatus, but these experiments show that it was also the improper application of the connecting wires."

Low and High Tension Fuzes.—"High-tension" fuzes differ from the "low-tension" fuze already described (p. 273), in that their ignition is effected by the passage of electricity through an inflammable semi-conducting material used as priming, and interposed between the terminals. The low-tension fuze is ignited by the incandescence of a thin wire bridge over the interval between the terminals. In regard to the action of this bridge, it should be remembered that when

Digitized by Google

any circuit is closed, the whole is heated to a definite amount. The greater the resistance in any portion of this circuit, the more is the heat localised in that portion. The resistance varies according to the area of the cross-section of a wire, and the material of which the wire is composed. It also varies with the length of the circuit, but that does not immediately affect the part in question. The finer the wire, and the less its conducting power, the greater is the resistance. Hence the wire bridge should be as fine and have as little conductivity as possible consistent with other considerations. Platinum is a very suitable metal for bridges, as its conductivity and its specific heat are low compared with other metals. It can be drawn into a very fine wire; it is not brittle; and it is not liable to rust or corrode. An alloy of platinum and silver is more fusible than pure platinum, and iridio-platinum wire gives a higher resistance than a platinum wire of the same dimensions.

High-tension fuzes can be fired by any kind of electricity, but they offer a variable resistance, and the same fuze may vary in resistance on being kept in store for any length of time, or exposed to climatic changes. The testing of such fuzes is difficult and dangerous, and they also require high insulation.

Low-tension fuzes, when they are fired in series, ought to have as nearly as possible the same resistance, as in case a series of mines is to be fired simultaneously, one or two fuzes may be accidentally more sensitive than the others in circuit, and these sensitive fuzes would explode first, break the circuit, and the other mines would remain unexploded.

The term "high-tension" for these fuzes seems to be the proper one, because, if an electric current of low tension attempts to traverse a high-tension fuze, it is practically stopped altogether in its flow, while a strong current has power to traverse the resisting medium. In the low-tension fuze the fine platinum wire offers but slight resistance, which is overcome by a comparatively feeble current.

High-tension fuzes are divided into two classes—

Digitized by Google

(1) Those in which the priming composition possesses sufficient conductivity for the electric current to pass through it without exploding it, but being sufficiently resistant to cause the electricity to raise it to its point of inflammability.

(2) Those in which the priming is very resistant, and opposes itself to the passage of the current, which therefore discharges itself as an electric spark between the extremities of the con-



FIG. 140. — ABEL'S ELECTRICAL FUZE.



FIG. 141.—ABEL'S ELECTRICAL FUZE, IN SECTION.

ductors. The second class is now usually found in practical use.

The priming for high-tension fuzes is generally a mixture of sulphide of antimony, chlorate of potash, and plumbago; or of sulphide of antimony, chlorate of potash, nitrate of potash, and carbon; or of sulphide of antimony, chlorate of potash, and sub-phosphide of copper.

Digitized by Google

The high-tension fuze in general use is known as Abel's electrical fuze, and has the following construction :* The ends of two fine copper wires (Fig. 140) are embedded in a thin solid gutta-percha rod, parallel to each other, but at a distance of about 1·5 mm. At one end of the gutta-percha a small cap of paper, *c c*, is fastened, in which is placed a small quantity of the priming composition. The paper is fastened down, so that the exposed ends of the wires are in close contact with the powder. This is the actual fuze. For service, the capped end of the fuze is placed in a perforation in the rounded head of a wooden cylinder, so as to project slightly into the cavity, *g*, of the cylinder. This cavity is filled with meal powder, which is well rammed down, so that the fuze is firmly embedded. It is afterwards closed by a plug of gutta-percha, and the whole is finally coated with black varnish.

The free ends of the wire *a a* are pressed into small grooves in the head of the cylinder (Fig. 141), and each end is bent into one of the small channels with which the cylinder is provided, and which are at right angles to the central perforation. They are wedged in here by driving in small copper tubes, the ends of which are then filed flush with the surface of the cylinder. The bared ends of the two insulated conducting wires are then pressed into one of the small copper tubes or eyes, and fixed there by bending the wire round on to the wood, as shown at *e*.

The conducting wire used in firing may be thin, but it must be well insulated. One end, which is bared, having been pressed into the hole *d* of the fuze (Fig. 140), the other is placed near the exploder. In the other hole, *d'*, of the fuze a wire is placed, which serves as earth-wire, care being taken that there is no connection between the two wires. The fuze having been introduced into the charge, the earth-wire is placed in good connection with the ground. The knob *f* of

* Ganot's 'Elementary Treatise on Physics,' by E. Atkinson, Ph.D., 14th edit., 1893 (Longmans, Green, and Co.), from which the illustrations here given are taken, by permission of the publishers.

Digitized by Google

the exploder is also connected with the earth by leading the bare wire into water or moist earth, and the end of the insulated wire connected with the instrument used for generating the spark required for ignition.*

* A simple machine used for this purpose, designed by Baron von Ebner, for generating frictional electricity—which is at once powerful, portable, and capable of working in any weather—is constructed by Messrs. Elliott.

Digitized by Google

CHAPTER XVIII.

USE OF EXPLOSIVES IN FIERY MINES.

SIR F. ABEL on the Prevention of Fire-Damp Explosions during Blasting —A New Method of Exploding Charges in Fiery Mines—Compressed Lime Cartridges for bringing down Coal.

THE use of explosives in coal mines, particularly in those having fiery seams, is a matter of special interest to all who are concerned in the manufacture and utilisation of explosives. It is a recognised fact, that ordinary explosives cannot be employed with safety for blasting purposes in coal mines, where there is more or less fire-damp distributed throughout the workings. Fire-damp necessitates the exclusion of flame, and we know that every explosion is accompanied by an outburst of flame. Coal-dust, also, greatly adds to the dangers arising from the existence of fire-damp in a coal mine, and may even cause explosions, which would not take place but for its presence. This question of fire-damp and coal-dust explosions was felt to be of such paramount importance, that new regulations on the subject were incorporated in the Coal Mines Regulation Act of 1887, which no doubt will prove a great benefit to the workers in coal mines.

The Prevention of Fire-Damp Explosions during Blasting.—The whole subject of prevention of such explosions has been admirably dealt with in some lecturcs delivered by *Sir Frederick Abel* before the Institution of Civil Engineers. For lack of space I can only repeat some of the most prominent points which have a direct bearing on the subject of safety blasting, as expressed by this eminent scientist. He says :—

Digitized by Google

"Formidable danger frequently attends the employment of blasting-powder in coal mines, on account of the flame which generally attends, though to a variable extent, the firing of a shot tamped in the usual manner; and especially on account of the large volume of flame which is projected to a considerable distance, either when a blast-hole is overcharged, or when the preponderating strength of the material operated upon gives rise to what is termed a 'blown-out shot,' the tamping being projected from the hole like a shot from a gun.

"The Royal Commissioners recognised the dangers frequently attending the use of powder in coal mines, and the extreme difficulty of effecting any important diminution of those dangers; and they devoted much attention to the question whether it might be possible to discover any powder substitute, or any method of using such substitute, which would secure immunity from danger due to the presence of coal-dust and fire-damp in the localities where blasting had to be carried on.

"Even if undiluted nitro-glycerine is exploded in a shot-hole, the high temperature has the effect of raising to incandescence particles of the tamping employed, or of the stone or coal exposed to the highly heated gases and vapours developed, so that, under any circumstances, sparks would be liable to be projected on the firing of a nitro-glycerine charge. The same holds good with any of the nitro-glycerine preparations known in commerce, such as lithofracteur, blasting gelatine, or gelatine-dynamite; moreover, flame in more or less abundance may be produced by the explosion of some nitro-glycerine preparations, the composition of which includes proportions of inflammable materials.

"That the heat to which very finely divided solid particles may be raised, by exposure to the highly heated products of detonation of nitro-glycerine preparations, is sufficient to determine the ignition of an explosive fire-damp mixture, has been amply demonstrated by experiment, and it is even possible that sparks sufficiently hot to produce that result may be carried to some distance by the blast of heated gases projected by a shot,

Digitized by Google

and thus reach places at some distance from the shot-hole where gas may have lodged.

"In the early part of the labours of the Commission in 1880, I applied the principle of most complete explosion, or detonation, of one or other of the so-called 'high explosives' in conjunction with the method devised by me in 1873, of distributing the operation of the force, developed by small charges of the explosive, over a considerable area, through the agency of a comparatively large volume of water, by which the charge is enveloped.

"The principle of suddenly transmitting the force of detonation of a charge of explosive uniformly in all directions, *by completely surrounding with water* the charge to be detonated, had already been successfully applied by me to the conversion of an ordinary shell into a projectile operating with the destructive effects of a shrapnel-shell, and to several other purposes, and it occurred to me that, by applying the same principle to the charging of a shot-hole, the effect might be not only to modify the destructive action of a high explosive, and thus to attain a comparatively moderate splitting or rending action instead of powerful disintegrating effects, but also to accomplish the extinction, through the agency of the water envelope, of any incandescent particles or sparks, and perhaps flame, projected by the exploding charge, the water being thrown forward together with them, in a finely divided condition. It soon afterwards came to my knowledge that Dr. McNab had previously put into practical execution the idea of extinguishing the flame of a *powder* charge, projected from a shot-hole, by inserting a cylinder filled with water over the charge, and confining it by a small amount of tamping. A series of experiments conducted for the late Commission indicated, however, that water tamping, as first suggested by Dr. McNab, and applied by Settle, used in conjunction with a *high explosive*, such as dynamite, afforded very considerable, if not absolute, security against accidental explosions, under the conditions just now specified.

"The charge of explosive should be placed in a water-tight

Digitized by Google

cartridge, enclosed on all sides by water, with or without the additional use of superposed tamping. The results obtained after a series of exhaustive trials justified the conclusion, that the so-called water cartridge, employed in conjunction with a high explosive, could be relied upon to afford security against accidental explosions during shot firing in the presence of explosive gas mixtures, or of very inflammable coal-dust thickly suspended in air containing some small proportion of fire-damp.

"In constructing a water cartridge there is not the least necessity for employing any device for keeping the explosive in such a position that its circumference is surrounded equally on all sides by the water; it suffices simply to insert the charge, with its waterproofed fuze or wires, attached, into the blast-hole direct (if the latter is in perfectly solid stone or coal, and in a suitable position), or into the cylinder of thin sheet metal, varnished paper or membrane, which is filled with the water; it is best, however, to insert the charge nearly to the bottom of the water, so as to utilise the tamping effect of the greater part of the column. The liquid is retained by a wooden or cork plug, through which the fuze or conducting wires pass, and tamping is applied over this after insertion of a tuft of hay or other suitable padding material.

"Gelatine-dynamite* is especially suitable for employment in conjunction with water, as nitro-glycerine is not displaced therefrom even after long immersion in water.

"The work done in coal by a high explosive, through the agency of a column of water which encases it (or 'water cartridge'), is different in character to that accomplished by the same charge used in the ordinary manner. Instead of exerting a crushing action immediately round the charge, whereby much small coal is produced and no large amount of displacing work performed, the force being distributed over the whole area of the water column, its action is thereby greatly moderated, and the coal is brought down in large masses—the work done extending over at least as large an area as that of the best powder-shots.

* In my opinion, forcite also.—M. E.

Digitized by Google

"In applying this system as a safeguard against accidental ignition of coal-dust or fire-damp mixtures, the quantity of water used should at least amount to four times the volume of the charge employed. If less is employed, the flame will not be quenched.

"The experiments carried out for the Royal Commission with water cartridges led to the observation, that a considerable proportion of the water was driven forward in a body instead of being dispersed in a very fine state of division, by the force of a *blown-out shot*, and a suggestion was consequently made for the employment of the water in a different manner, which was worked out by Mr. Galloway with most successful results, so far as related to the extinction of flame and spark from a blown-out shot. By distributing the water through a porous body, such as sponge or moss, and thus effecting an initial interruption of continuity of the mass of liquid placed over the shot, its thorough dispersion in a very finely divided condition is ensured, and its extinguishing power is greatly increased. Comparative experiments have shown that the water cartridge did not afford that absolute security against the ignition of an explosive gas mixture by a blown-out dynamite shot which was attained by the comparatively simple moss and water tamping, which can be applied without difficulty even in holes having an upward inclination.

"It may be well again to emphasise the fact, that neither the water cartridge, nor water tamping applied in the manner in which it has been found so thoroughly efficient in conjunction with high explosives, affords any safeguard against explosions arising from the presence of fire-damp or of coal-dust associated with fire-damp, in mine workings where blasting is carried on, if *powder*, or any explosive agent analogous in its composition and mode of explosion to powder, be employed in conjunction with them.

"Suggestions have been made to use, in conjunction with *powder*, or as tamping over the charge, certain solid preparations which will evolve gases or vapours when exposed for a sufficient period to heat capable of extinguishing flame, the

Digitized by Google

idea being that the heat developed by the explosion of the charge would accomplish the desired results, and that the dangers arising from blown-out shot might thus be guarded against."*

Exploding Charges in Fiery Mines. — *Lieutenant-Colonel T. Lauer*, of the Austrian Imperial Engineers, has invented a very ingenious as well as simple method of firing powder, dynamite, or other explosives, which is specially adapted for use in fiery mines. He lays down five rules relating to blasting in coal-mines which miners would do well to bear in mind, as they refer to the prevention of fire-damp explosions by the charge, often a fruitful cause of explosion.

The rules in question are:—(1) No charge should be exploded before it has been ascertained by means of the safety lamp that within a radius of 30 ft. the quantity of fire-damp is less than 3 per cent. (2) The firing of the charges by ordinary fuzes or squibs should be absolutely forbidden, as the combustion of these causes an inflammation of the fire-damp. Only electric or other similar methods of firing should, in fact, be permitted at all. By the use of these methods sparks are produced only in the interior of the bore-hole charge. (3) Simultaneous firing of the bore-hole charges should be brought into use, for if the charges are fired in rotation those first exploded will not only produce coal-dust, but will sometimes open seams from which fire-damp escapes, and is fired by explosions following after. (4) The use of ordinary gunpowder and its derivatives should be forbidden, and only strong high explosives should be used. (5) A sufficient amount only of explosive should be taken in order to make a charge to cause dislocation and rending of the surrounding coal and rock, in which case a

* In a previous chapter (p. 144) I have described a solid tamping mixture which has been invented by Mr. Trench, and which is now being introduced in lieu of the water cartridge. From the testimony of several colliery proprietors it would appear that this tamping mixture possesses the property of rendering tonite flameless when exploded in cartridges surrounded by the mixture.—M. E.

Digitized by Google

consumption of the explosive takes place inside the medium in which it is employed and no flame escapes.

In the use of the detonating friction tube, which has been invented by Col. Lauer, the spark (as with the electric exploders) is caused inside the body of the explosive in the bore-hole, and, as several charges can be fired simultaneously, the system appears to commend itself by its cheapness and simplicity.



FIGS. 142, 143, 144.—LAUER'S SYSTEM OF FIRING CHARGES.

The friction tube in this apparatus consists of a small cylinder, A, Fig. 142, which encloses the friction apparatus, and this is connected with an iron wire, C. The iron wire as well as its protecting tube, B, are long enough to extend a few inches beyond the mouth of the bore-hole (see Fig. 143), and the wire terminates there in a loop, C, which for safety is bent over and fastened to the tube by a string. The fulminating cap and primer are set in the bottom part of the small cylinder, A. The

Digitized by Google

bore-hole is charged in the usual way. To fire the mine, the loop, C, is untied from the tube, B, straightened out and tied to a strong string of a certain length, which ought to enable the miner to get beyond the radius of projection from any flying *débris*. By giving a smart pull to the end of the cord, the iron wire, C, becomes disconnected from the friction apparatus and causes the inflammation of the composition contained in the small cylinder, A, and the detonation of the exploder and charge.

For the simultaneous firing of several charges, all that is required to be done is to connect together the strings E and F from the several bore-holes to one main cord. Each string, E, ends in a kind of hook, D, which is tied to the loop C. The main cord, G (Fig. 144), can be laid on pulleys fastened to the sides of the tunnel or drift, so as to keep the same in line. All the mines being connected, the small winch, H, is first put gently in motion so as to give a certain amount of tension to all the strings, then a strong pull is given to the cord, G, which will cause the simultaneous explosion of all the charges.

It is claimed that eight charges can be fired in this manner. This system of firing has been tried in several Austrian coal-mines, and seems to have given satisfactory results.

Compressed Lime Cartridges.—The considerable increase in volume which caustic or quick-lime rapidly undergoes during the slaking process, or its conversion into hydrate of lime by union with water, was many years ago regarded as a source of power which might be made available in lieu of powder for the bringing down of hard coal.

Messrs. Smith & Moore prepare the lime for this purpose by reducing freshly burned fat lime of high slaking power to powder, and converting this into cylinders by applying powerful pressure, which produces a very compact cartridge, rendering the material less liable to deterioration from air slaking than if kept in lumps. In the next place, they apply the heat which will have been rapidly developed in the loaded hole by the

Digitized by Google

slaking of the lime charge simultaneously throughout its entire length, to the generation and superheating of steam on a somewhat considerable scale, whereby the force exerted by the expanding charge of lime is supplemented in an important manner. This is effected by ensuring the application of water to the compressed lime almost simultaneously throughout the entire length of the charge.

Sir Frederick Abel, in commenting on the use of lime cartridges, states that, during a series of operations in the Shipley collieries, Derby, the preparation and charging of a number of holes at one time was expeditiously carried out, and the joint action of the holes in bringing the coal down in large masses was very satisfactory, the charges generally performing their work up to the back of the holes. The time occupied by the action of the lime ranged from ten to forty minutes from the time of wetting the charge, but the men were able to return to their work directly the coal had fallen; the latter was brought down almost entirely in large masses, and the work in such coal appeared to be carried on with advantage in point of economy over blasting. The results obtained with lime cartridges in other collieries seem to be satisfactory on the whole. That its application should not be attended with the same success in soft and in very hard coal as in massive coal of medium hardness is to be expected, and seams in which many fissures occur are not likely to be worked successfully by the system, as the force due to the generation of steam by the slaking of the lime must be lost in many instances.

In damp mines, the cartridges should be kept in tightly closed cases until just before they are required to charge a hole with.

A so-called blown-out shot with lime causes the latter to be more or less violently scattered about in the vicinity of the shot-hole, and should men be in the immediate neighbourhood it is very possible that their eyes may suffer from such an accident, but there is no possibility of an explosion being brought about by the blowing out of the lime, or by any other circumstance which may attend the use of the lime-cartridge.

Digitized by Google

The maximum heat developed in the interior of a lime-cartridge as applied in coal getting does not exceed 600° F., and is therefore insufficient to inflame a mixture of gas and air, or to ignite any inflammable material with which the lime-cartridge might possibly come into contact in actual practice.

The conclusion of the Royal Commissioners for inquiring into accidents in coal mines, that "in some coal-seams the lime-cartridge will perform work quite equal to that accomplished with powder, at no greater cost, and with absolute immunity from risk of explosions," was arrived at after very careful inquiry, and is well worthy of the attention of colliery managers.

Digitized by Google

CHAPTER XIX.

APPLICATION OF EXPLOSIVES IN SUBMARINE ENGINEERING.

REMOVAL of Obstacles in Rivers and Harbours — Methods of Submarine Blasting—Pontoon Drilling—Machine Drills—Drilling and Blasting—Blowing up Sunken Wrecks.

IT becomes very often the duty of an engineer, in making river or harbour improvements, to remove loose rocks, boulders, logs, sunken ships, which form obstacles to navigation, and in such cases the application of surface charges of dynamite, properly located against the object, will effect the purpose. In such blasts it is usual when not using nitro-gelatine, to enclose the ordinary dynamite in tin tubes, which are fastened to long sticks and lowered from a boat against the object to be removed.

The firing in such cases is performed advantageously by electricity. In deep water divers have to descend to the river bottoms to apply the charges properly. The effect is usually very satisfactory, as the superincumbent weight of the water forms an excellent tamping.

When the rock-masses are large, holes have to be bored, which heretofore was accomplished by dropping heavy steel drills on to the rock and boring the holes by simple gravitation, but since the introduction of compressed air drills the drilling is accomplished by mounting these drills on platforms erected in the water or by mooring scows over the rock to be removed, and drilling from a platform projecting from the boat. These drills need the constant attention of divers, who also have to do the charging of the holes.

Digitized by Google

Submarine excavation is always costly and laborious work, and particularly so when submerged reefs are covered with strata of sand, gravel, and silt. Many ingenious inventions have been made to overcome these difficulties, and full information on this subject will be found in my work on 'Modern High Explosives.' As examples of modern engineering, detailed accounts of the removal of the obstruction in New York Harbour known as Hell Gate, and of the removal of obstructions in rivers and harbours in different parts of the globe, are given in that volume.

Methods of Submarine Blasting.— Before the invention of nitro-glycerine, the removal of rocks under water was considered one of the most difficult branches in engineering. The method first used was to place ordinary gunpowder in strong wooden cases, which were lowered on to the rock and exploded by ordinary fuzes. The application of these surface charges did not result in much work, and a French engineer, about thirty years ago, executed some work in Boston harbour, U. S. A., by drilling holes into Tower and Carwin Rocks,* by means of heavy bars of iron, weighing several hundred pounds, which worked in guides resting on tripods under water. The drill by means of a long rope is attached to a crank pin, and by means of an engine is hoisted several feet and then dropped; as many as sixty blows per minute are given in this way, and the gravitation of the drill bores the hole slowly. When this reached a certain depth, it was loaded by divers with a chlorate of potash compound and exploded.

At the present time such work is executed by machine drills, which are worked either from floating pontoons or stationary stagings erected in the water over the rock which is to be blasted.

The drill can also be mounted on a tripod stand, lowered on to the rock under water, and attended by a diver; drilling operations are carried on by leading compressed air to the drills by means of indiarubber tubing, and the exhaust dis-

* See 'Modern High Explosives,' p. 330.

Digitized by Google

charged through another tube above water. Then there are also instances where subaqueous drilling has been carried out in diving bells; but these are tedious and expensive methods. Of late also, at Port Natal, some important work was carried out by working from a tripod direct at the rocky bottom of the bay.

Pontoon Drilling is in favour with some engineers, by working long drills from the deck of a pontoon stage, so as to admit of the machinery being all above water and easy of access. It is usual to build a floating stage composed of two pontoon punts, secured parallel to each other several feet apart, thus leaving sufficient space for the working of the drills. On each side of the drills rails are laid, bearing two light travelling derricks, in each of which a guide-pole, 6 inches square, works freely, carrying on it a rock drill, and fitted with a rack and pinion gear for adjustment of the drill to the various depths required. The guide-poles are shod with iron, and, when in use, rest on the river bottom, the stage rising and falling freely according to the state of the tide or the swell caused by waves, without in any way affecting the steadiness of the guide-poles. The stage is secured against lateral movement by strong mooring-chains from each of the four corners, and worked by crab-winches.

One of the pontoons carries the machinery, such as the boiler, air-compressor, and air-receiver. The other pontoon is generally fitted as a workshop, forge, and a small air-compressor to furnish air to the diver, as it is advisable to supply the divers with air from a separate compressor or receiver.

I have had occasion to visit works of this description in the United States, and the plan usually adopted there is to erect over the rock to be blasted a stationary framing 20 to 30 ft. square, which is built of timber, and is easily dismounted, and the drills are mounted on this staging; they are worked by steam. The boiler is on a scow, which at the same time carries the dredger, and as the drills are worked by steam which is led to them in tubing, no air-compressor is required, except a small one to supply the divers.

Digitized by Google

I have also seen a small stage from which two drills are worked, consisting of a large box made of 1½ in. planks, 12 ft. square and 3 ft. high, air and water tight; this box was mounted within four posts, and when the holes were to be fired, by turning a crank, working a rack and pinion gear, the box was lowered on to the surface of the water and the four posts lifted out of position, so that the same became a floating stage, and could be moored back again after the firing of the blasts.

Where the stationary stagings are large, 20 ft. square or more, the blasting can be carried out safely, without damaging the supports, and they are only shifted whenever the bore-holes become located too near the supporting posts.

Machine Drills.—The drills are generally of a heavy pattern, at least 5 in. diameter by 8 in. stroke, and the drill steel ranges from 2 to 3 in. diameter, as long bars have to be used when there is any depth of water.

Each drill works in a sliding frame, so that several feet in depth can be drilled without adding on fresh length of steel to the drill, or changing to longer bars. Sometimes the depth of water over the rock may be 20 ft., and as the drill platform is several feet above the water surface, and holes have to be bored 6 to 7 ft. in depth, it is not unusual to have drill steel 35 ft. in length.

In case the rocks which have to be removed are covered with mud, silt, gravel, the boring becomes very difficult, as the silt will work in between the drill and the sides of the bore-hole, and jam the drill. To avoid this inconvenience it is a usual practice first to drive down iron tubes through the silt 4 to 5 in. in diameter till they rest on the rocks, and then the drills are worked within them. These tubes reach above the surface of the water and prevent the sand getting into the bore-holes, and also enable the workmen to let the cartridges into them from above, by tying them to a string, and thus dispense with the services of the diver.

General Newton constructed a scow in New York, for carrying out blasting work in East River, which had a central

Digitized by Google

opening like a well, into which he lowered a dome built of boiler iron, and there were several tubes inside these wells, in which he worked the drills.

Drilling and Blasting.—The bore-holes are drilled in rows located in a line across the river, or at right angles to the axis of the river. The depth of the holes depends on the depth of rock to be removed. When a hole is drilled, it is cleaned out by the diver, who inserts a nozzle into the hole and injects compressed air, to clean out the sand, and then plugs up the hole till the time comes to insert the charge.

If it is required to remove 6 ft. in depth of rock, it will be necessary to drill the holes 8 ft. deep, so as to get the explosive below the level from where the rock has to be removed, as otherwise there would be danger that if the holes were not bottomed the required depth would not be attained. To make sure of a successful removal, the holes ought never to be drilled too far apart.

When a row of holes are drilled, they are charged with the highest grade explosives, and powerful high-tension fuzes must be employed, and the holes being electrically connected among themselves, the leading and return wires are attached to the end holes; when the diver gets to the surface, connection is made with the battery and the charges exploded. Of course no tamping is required. When using dynamite, tin canisters are necessary to hold the charges, but with nitro-gelatine this is not necessary.

The explosion of the charges causes only a dull muffled sound and a slight upheaval, as the work is mostly expended in rending the rock and overcoming the resistance of the superincumbent weight of water, and very seldom rocks are projected above the water surface. The big pieces of rocks are afterwards removed by means of a derrick placed on the scow or the pontoons.

When a new hole is started it is very difficult to steady the lower end of the drill and make it enter the rock, and for this reason cast-iron shells weighing 100 lb. are used to steady

Digitized by Google

them. This shell is about 1 ft. in height, 15 in. in diameter at the base, standing on three pivots or legs, about 3 in. long, convex on top, through the centre of which a hole passes vertically admitting the free working of the drill.

It is considered good work when 1 ft. can be drilled in half an hour, but the drilling of course depends on the nature of the rock.

Mr. Saunders,* of New York, has invented an arrangement which facilitates the working of drills on rocks covered with silt.

Works of magnitude, like the blowing up of Hallett's Points and Flood Rock at Hell Gate, New York, involved operations of a different nature. There the rocks were undermined by tunnels and galleries miles in length, the pillars which were left standing to support the roofs were drilled with holes, as well as the roofs, and when charged were all exploded simultaneously.

General Newton, the chief of engineers of the United States Army, has accomplished, in the laying out and prosecution of this memorable work, an amount of ingenuity which has no parallel in the history of explosive engineering undertakings.

Blowing up Sunken Wrecks.—Very often explosives are employed to remove ships which have got wrecked in the pathway of navigation. Divers who make this a special business then examine the position of the vessel, and by the application of long charges of dynamite or gun-cotton will break up the vessel. The charges are either placed on deck, or hung against the sides, or posts are driven into the sand and the charges tied to them. Care must be taken in all cases to have the explosive in immediate contact with the object to be destroyed, so as to obtain the maximum effect.

No special rules can be laid down how to proceed in such work, as each individual case presents features of its own, and has to be dealt with accordingly.

* See 'Modern High Explosives.'

Digitized by Google

CHAPTER XX.

APPLICATION OF EXPLOSIVES FOR MILITARY PURPOSES.

MODERN Explosives as applied in Warfare—Zalinsky's Pneumatic Gun—Essential Conditions of Dynamite Firing—How Zalinsky's Gun was Invented—Official Report upon the Gun—The German and the Maxim Pneumatic Guns—The Graydon Dynamite Shell—Gun-cotton Shells—Blasting Gelatine as a Military Explosive.

THAT modern explosives should have an extensive application for military purposes as a destructive agent is a development of their utility which one would expect to find. Our knowledge of these numerous compounds has received large contributions through the searching inquiries and experiments instituted by various Governments as to the qualities, both chemical and physical, of modern explosives, and the results may be thus summarised: The navy departments of most nations have adopted compressed gun-cotton for torpedo charges, and other submarine ground mines; whereas the military engineers of the land forces lean towards the use of the plastic nitro-gelatine and its derivatives as demolition charges, owing to their enormous shattering power (*brisance*) when bridges, stockades, railway embankments, walls, forts, and similar obstacles have to be removed. Such explosives as nitro-gelatine, gelatine-dynamite, and forcite, being far more powerful and exerting a greater local action than gun-cotton, should be able to rival the latter in its application to submarine mining; but so far as safety is concerned, wet gun-cotton, no doubt, offers an advantage which nitro-glycerine preparations do not possess. As bursting charges for shells and hollow projectiles, modern explosives will doubtless be extensively applied in the near future, and in that shape will form a terribly destructive engine

Digitized by Google

of war. Their efficiency for that purpose has indeed been proved in the firing of projectiles from the weapon I am about to describe.

Zalinsky's Pneumatic Gun.—Lieutenant Zalinsky, of the United States Army, has practically demonstrated that large quantities of explosives, like dynamite, nitro-gelatine, or gun-cotton, even in charges of several hundred pounds, when enclosed in metallic shells, can be safely fired by means of compressed air.

I was present in New York Harbour in 1884, when the Lieutenant fired his first experimental shots from his four-inch gun at Fort Lafayette, and was greatly impressed with this modern weapon, although in military, naval, and scientific circles many authorities did not believe in the ultimate success of the young and energetic Lieutenant's so-called "Dynamite Gun." That his perseverance had some reward is proved by the fact that the United States Government constructed a cruiser equipped with these guns. I also understand that the Italian Government ordered one from New York; and I may be allowed to mention that I brought this gun to their notice in 1886 by submitting the specifications and drawings to Admiral Martinez at La Spezia, and explaining to him the *modus operandi* of the apparatus.

Essential Conditions of Dynamite Firing.—Before entering into a description of the latest form of gun and projectile, it will be well to state the conditions which must be fulfilled to make dynamite firing successful.

The great requisite is, to discharge the dynamite shell from the gun without shock. Compressed air is eminently adapted to effect this in a perfect manner, as the pressure admitted to the gun can be regulated to any degree. Therefore, when firing the projectile, a gentle pressure is admitted, at first just sufficient to overcome its friction and inertia; but, once in motion, the pressure can be rapidly increased up to the full limit, without in any way subjecting the projectile to an undue shock.

Compressed air, also, permits the use of a detonator

Digitized by Google

to explode the charge, and a strong exploder is embedded in the body of the charge, the explosion of which is caused by a specially designed electrical arrangement, which ensures the perfect explosion of the dynamite in the shell. The detonator consists of a substance which is even more sensitive to shock than the explosive itself, and which by its sudden and violent action influences the latter so that it explodes with its maximum power.

Heating of the gun never takes place, as it is well known that compressed air when expanded absorbs heat and cools the surrounding atmosphere; hence this gun, instead of becoming heated by successive discharges, is actually cooled.

How Zalinsky's Gun was Invented.—The idea of firing dynamite by means of compressed air originated with a schoolmaster, named Meford, whom one of his pupils hit in the eye with a paper ball from his pop-gun. Being of an inventive turn, Meford concluded that compressed air could be used as a motive power for firing something else besides paper. He devised a tube of brass 2 ins. in diameter and $\frac{1}{4}$ in. thick, 28 ft. long, mounted on a T rail and stiffened with tie-rods; this was erected on a tripod, and arranged as a breech-loader. The slide block was attached to a flexible hose and connected to an air reservoir, from which the air was admitted by a hand-cock. This was very uncertain, the air being cut off too soon or else wasted by too long a delivery. The pressure was but 300 lbs. The projectiles used were cylindrical brass tubes 1 in. to $1\frac{1}{2}$ in. in diameter, and 12 ins. to 18 ins. long; they had attached to them a wooden frustum of a cone, of which the larger end was the size of the bore. The point of the shell was of wood, and was loaded with lead so as to keep the centre of gravity well forward. Two discs of pasteboard, with a thickness of Canton flannel between them, acted as a gas check, the flannel being 1 in. larger in diameter than the pasteboard; this was placed against the under tail of the projectile.

The great difficulty was the short range attainable by these

Digitized by Google

means; but, Lieutenant Zalinsky's attention having been called to this gun, he had it brought to his station and commenced experiments. He found an increased accuracy of aim over the ordinary smooth bores. The length in calibres of the 28-ft. gun was 168, and to this proportion is due the property of imparting great energy to a shell, and at the same time of avoiding a shock liable to produce premature explosion. With the 2-in. gun and a less pressure than 500 lbs., he had thrown a projectile across the Narrows of New York Harbour, a distance of 2100 yards.

In testing the safety of throwing dynamite in such thin shells, various experiments were tried. The dynamite in small quantities was placed at the base of the shell, and the balance was filled with dry sand; in this way it was exposed first to the shock from the air pressure, and next to that of the inertia pressure of the sand, which was much greater than that of an equal amount of dynamite. The pressure was gradually increased from 100 lbs. to 500 lbs., and the shell was placed at 5 ft., 3 ft., 2 ft., and 1 ft. respectively from the breech, and finally a shell with the full charge of dynamite was thrown; placed at the breech, in this case, there was an air cushion of 8 ft. between the valve and the projectile. This 500 lbs. pressure being the limit of the endurance of the hose, a greater one was not tried.

The next series of experiments started with the construction of a gun 4 ins. in diameter and 40 ft. in length. The barrel was a seamless tube of $\frac{3}{16}$ in. in thickness, and in three sections, mounted on an iron truss supported by a tripod. The valve was automatic, opening rapidly and permitting a certain uniform volume of air to escape, and closing at the time the projectile reached the muzzle. Its general character may be described as that of a balanced valve. The air was admitted by this until the projectile was just outside the muzzle, and, to have the final pressure as great as possible, the reservoir was nine times the volume of the bore. The velocity attained with the 4-in. gun was found to be 72 per cent. of the theoretical velocity.

Digitized by Google

In early experiments with the projectile, the tails were found to be too long and heavy, and the best results were attained by making the centre of gravity as near to the point as possible. The projectile being assumed to fall the instant it left the gun, it was decided to have the rear of the tail taper slightly to afford freedom of exit, and such projectiles had regular flights. The pressures being uniform, the fall of shells having the same centres of gravity struck nearly in the same places. In fact, accuracy of range with a pneumatic gun is one of its strongest features.

The shells were next fired with 17 lbs. of dynamite and with success. The fuzes then met the attention of this investigator. The ordinary percussion fuzes of fulminate proved unsatisfactory, as did the copper capsules. It was also noticed that 17 lbs. shells with percussion capsules did not produce the desired effect when they exploded, and Lieutenant Zalinsky naturally looked to a possible effect from exploding these shells from the rear, assuming that a small interval of time was required even to fully explode dynamite, and that the layers of gases exploded near the target tended to retard the effect of those developed at the rear of the shell.

This resulted in the devising of an electric fuze depending on the action of a small battery enclosed within the shell. The best battery was found to be the chloride of silver one, on account of its small size and its reliability. After remaining idle a month, these little batteries were found equal to the requirements. The diagram, Fig. 145, is a section of the fuze and connections, in which A is the fuze case, B a metallic plunger, inside the vulcanite cylinder *a*; the contact springs *b b* are attached to the wire *c*, joining the electrical primer C. The second wire *d* goes from the primer to the metallic fuze case. The primer is thus in contact with one pole of the battery placed within the upper part of the fuze case. As will be seen, this battery is suspended to the fuze case A A by thin projections *e e*, which are sheared off by the shock of firing the gun, and the other pole falls into such a position that the metallic plunger B can come into contact with it and complete

Digitized by Google

the circuit. When the shell strikes, the plunger B moves forward to the pole *f*, the circuit is closed and the charge is exploded.

By examining the diagram, Fig. 146, it will be seen that in the fuze just mentioned the battery was attached to a projecting steel plunger held in place by a stiff steel wire pin, and when the end of the plunger is within $\frac{1}{8}$ in. of the target the circuit was closed. In this diagram, A is the steel plunger and B the battery attached to it; C is a low-tension electrical primer, one wire from which, *c*, goes to a contact *b* in the



FIG. 145.—EXPLODER FOR PNEUMATIC DYNAMITE GUN.



FIG. 146.—SHELL WITH EXPLODER.

bottom of the fuze; the other, *c'*, connects the primer and the fuse case. On striking the target the plunger is forced in, shearing off the light steel safety pin, and when the front of the shell is at the desired distance from the target the pole *a* of the battery comes in contact with *b*, and the circuit is closed through the primer, which explodes the charge from the rear. The actual time required to produce explosion before the full impact of the shell took place, is $\frac{1}{70000}$ of a second. Plungers arranged to close up to $\frac{1}{4}$ in. from the target were successful, but beyond that the effects were weakened. Ex-

Digitized by Google



FIG. 147.—ZALINSKY'S 8-INCH DYNAMITE GUN.

periments showed that it was important to bring the charge as intimately in contact with the target as was possible with as large an area of contact as possible.

The next step in this investigation was the construction of an 8 in. gun, designed to throw 100 lb. of dynamite with an initial velocity of 1400 ft. per second, and with a range of two miles, and to have it so arranged that the gunner could aim, elevate, and fire it without removing his eye from the sight. A view of this gun is given in Fig. 147. The pressure to be used was 2000 lbs., and the length of the gun was 60 ft. The 8 in. gun when worked with 1000 lb. pressure, and at an elevation of 35 deg., a shell with 60 lbs. of explosive material has been thrown $2\frac{1}{4}$ miles, and one with 100 lbs., at an elevation of 33 deg., was thrown 3000 yards.

Official Report upon the Gun.—Under the direction of the authorities of the United States Navy, an official inquiry into the merits of Lieutenant Zalinsky's weapon has been held, and the Board to whom the inquiry was entrusted, having witnessed experiments to test the rapidity of fire, accuracy, and extreme range of the new gun, have reported as follows:—

"1. That the dynamite gun is a new instrument which has its own functions in time of war; that it cannot replace any existing weapon; and that its place cannot be wholly taken by any other.

"2. That the value of compressed air as a means of throwing projectiles from a gun is chiefly apparent in the ability which it

Digitized by Google

gives to the gunner of exactly reproducing any shot, and of accurately increasing or decreasing range, at will.

"3. That the machinery employed in connection with the control of air under great pressure is very effective.

"4. That the gun is remarkably accurate.

"5. That the extreme range is probably about two miles, the effective range from 1400 to 1800 yards.

"6. That the power of the projectile has not yet been thoroughly tested.

"7. That the gun appears to be trustworthy in its action.

"8. That the system is a simple and inexpensive one, and that the gun might be made in any large town where there are foundries and machine-shops.

"9. That the weapon is valuable for harbour defence.

"10. That it is adapted to naval warfare whenever mortar fire can be advantageously used.

"11. That a modification of it might be adapted to the projection of torpedoes from ships.

"12. That, until after the gun has been properly tested on board the dynamite cruiser now under construction, it will be inexpedient to adopt it as part of the battery of ships of war."

The dynamite cruiser which is referred to in the report was built by Messrs. Cramp, of Philadelphia, and has now been successfully launched. Instead of the 10·5-in. pneumatic guns for which she was originally designed, she is to have three 15-in. tubes, which will be able to throw shells loaded with 600 lbs. of explosive gelatine. The length of her guns, which was excessive, has also been shortened to 55 ft. The gun which has been constructed for the Italian Government has a calibre of 15 ins., and a length of only 40 ft.

The German and the Maxim Pneumatic Guns.—Another pneumatic gun has, according to the *Temps*, been tried in Germany, under the supervision of the German Admiralty. The instrument is said to be of 11·7 ins. calibre, and is 73·8 ft. long. The shell was 81·5 ins. long, and contained 66 lbs. of nitro-glycerine. The target was a wooden vessel

Digitized by Google

moored 2080 yards away from the firing-point. Two rounds of shell completely destroyed the craft.

Of Mr. Hiram Maxim's dynamite gun little of a practical nature is yet known. It is a pneumatic tube; but the tube is comparatively short, and, according to the specification of the patent, a very high muzzle velocity is attained. The peculiarity of the invention seems to consist chiefly in the substitution of a mixture of air and some volatile hydrocarbon for air alone. This mixture is so regulated that there shall be just sufficient oxygen to convert the hydrogen of the hydro-carbon into water, and the carbon into carbonic acid gas.

After the projectile has been driven by the expansive force of the gas through a certain portion of the length of the bore, the mixture of air and hydrocarbon is caused to explode, and the pressure is thereby at once increased about eight-fold. The explosive charge in the shell is to be some form of dynamite, detonated by means of a capsule and firing-pin. It does not, however, appear that Mr. Maxim has yet built a gun in accordance with his designs.

The Graydon Dynamite Shell.—*Graydonite* is the name which has been given to an invention of Lieutenant James Weir Graydon, late of the United States Navy, who in 1886–87 conducted, first in California and afterwards in Russia, a series of experiments with the Graydon dynamite shell. This he succeeded in firing, with some degree of success, from a 6 in. rifled gun that was loaded with a mixture of 1 lb. of dynamite to 37 lbs. of powder. Mr. Graydon claims for graydonite absolute freedom from danger in handling and transportation, a destructive power from 400 to 700 per cent. greater than that of No. 1 dynamite, and suitability for military and naval uses. Particulars of its composition have not been made public. Since the conclusion of the experiments in Russia, the Ordnance Board of the United States Army has assisted at further experiments with the Graydon dynamite shell at Sandy Hook.

The Graydon method of charging the shell consists in subdividing the bursting charge of dynamite into small pellets,

Digitized by Google

each of which is enclosed in a separate envelope and treated with paraffin. The interior of the shell is previously lined with asbestos. Explosion is secured by means of a detonator, which acts upon impact. The great advantage of the shell is alleged to be that it can be fired from any service gun with the ordinary service charge of powder.

At the Sandy Hook experiments a 7 in. Ames wrought-iron muzzle-loading rifled gun was used, with a powder charge of 23 lbs., and with a steel service shell that weighed, with its charge of 2·3 lbs. of No. 2 dynamite, about 122 lbs. The target was a section of wrought-iron turret, made up of two 7 in. plates, so as to give a total thickness of 14 in. The target was, however, not a new one. It had been indented by previous practice, and several cracks in its surface were noticeable. Three shells were fired at, and burst on, the surface of this target. The third round penetrated the first plate, seriously bulged and cracked the second, and had a generally disruptive effect upon the turret.

The next day four rounds were fired, two at a wooden target a mile away and two seaward. All the shells were fused. The first shell burst prematurely 300 yards from the gun, the second burst at or beyond the object, the third did not burst, the fourth burst prematurely at 1000 yards. These results were not satisfactory. Later in the day the liability or otherwise of the dynamite to explode on being fired into with small-arm projectiles was tested. This experiment was also unsatisfactory. The compound exploded on being struck at 50 yards by a Springfield rifle bullet. Yet it was something to have shown that the dynamite shells could be successfully fired from an ordinary gun, and were capable of inflicting serious damage upon a somewhat heavily-armoured target.

Gun-cotton Shells.—The following extracts from an article upon this subject—translated from a German publication*—will be read with interest :—

* *Schweizerische Zeitschrift für Artillerie und Genie*, December, 1887. For the translation I am indebted to *Engineering* of 15th June, 1888.

Digitized by Google

"The German artillery, in opposition to the French, decided against melinite in favour of gun-cotton as a burster for shells, a substance already adopted by the German Navy for projectiles of large calibre and torpedoes. These shells fulfil the object of perforating in the shortest time and with absolute certainty the projection given in the opposing forts, of acting as mines in the cavities formed, and of rendering the occupation of the structure assailed absolutely impossible. It is no longer a secret that during last autumn and winter the 15-cm. and the short 21-cm. German guns, fired at Kummersdorf with high bursting charges of gun-cotton, succeeded in perforating the defence of forts which were specially constructed so as to represent one of the French frontier forts, and in reaching the parts best covered, such as the magazines, &c., with overwhelming effect—a notable and important triumph for the German artillery.

"Artillerists have studied the properties of gun-cotton for a long time. Ten years ago it was experimented with at the Government gun-cotton factory at Hanau, under the direction of an officer of the German staff, and in the end the disadvantages in its use were overcome, and it was produced in a form which places it in the first rank as an explosive for shells, damp cotton specially prepared being now used for that purpose. It is carried on service in a moist state, and to explode it a primer of dry cotton with a special detonating composition is employed. The construction of this primer is kept secret. The damp state of the cotton gives security against premature or spontaneous explosion, tendencies which were rightly considered defects in the use of the earlier forms of gun-cotton.

"The great safety in transport and use of gun-cotton now obtained is due not only to the experiments at Hanau, but also to others made by the firm of Von Förster and Wolff at Walsrode, in Hanover, who, in 1883, took out two patents, one for a mode of preserving gun-cotton, the other for the construction of a shell fitted with that substance.

"Von Förster's method of preserving gun-cotton consists in dipping the cotton, either in a dry or moist state, into ether for

Digitized by Google

15 to 20 seconds, whereby a very thin, hard, yellowish-brown film is formed on the surface of the cotton, rendering it waterproof, and giving it the semblance of a piece of wood. Instead of ether, nitro-benzol, or any fluid which dissolves the cotton, can be used. This film in no way decreases the explosive qualities of the gun-cotton, but it prevents its losing its consistency and decomposing. It preserves the requisite degree of moisture, and prevents paraffin soaking in. As, however, the skin is not absolutely impermeable, water finds a passage and the cotton is modified by keeping. Von Förster, however, states that under favourable conditions this disadvantage can be neglected, as experience has shown that gun-cotton unprovided with a protecting film loses its moisture in a few days if exposed to a current of dry air, whereas the protected cotton retains its moisture for many weeks under the same conditions. On the other hand, the skin is so slight that it does not interfere with the rapidity of ignition.

"In case dry-cotton charges should be preferred, Von Förster recommends dipping them in ether, closing the channel for ignition by means of a paper washer, and giving the charge a bath of paraffin, which adds a second impervious lacquer.

"Von Förster, it should be added, disapproves of the use of gun-cotton impregnated with paraffin, as prepared in the Kruppamühle factory in Schleswich. This, he states, is secure against neither decomposition nor accidental ignition; it is as liable to explosion as dry cotton; and is more sensitive to concussion than the wet cotton, being exploded by three successive rifle-bullets, which would have no effect on gun-cotton containing 15 per cent. of moisture.

"The projectile, which forms the subject of the second patent, is a cast-iron shell in two parts screwed together and filled with discs of compressed gun-cotton. Towards the base of the shell a detonator is placed, connected by a channel with the gun-cotton placed above it. The shell is fitted with a common percussion fuze, which communicates with the detonator by a primer, either of granular gun-cotton or the same substance mixed with meal powder. The patent does not specify how

Digitized by Google

the detonator is fixed in position. This arrangement was chosen after experiments made with gun-cotton exploding in the open air, and the following results were also determined. The force of gun-cotton varies with its density. It is more powerful in a moist state than when dry. It is best to ignite the charge as far as possible from the point of attack, and an axial channel through the charge increases the effect of explosion.

"It does not appear that these shell as described have been tried, and the most recent experiments with shell exploding in the open do not seem to confirm the conclusions as to the position of the detonator and the value of the axial channel. The endeavour was made to improve the shell by charging it through the fuse hole, leading to a further patent in May, 1885, for another mode of charging shell and of securing the explosive contents.

"The gun-cotton in this is used in the form of prismatic grains, made by cutting up the compressed discs, and to the charge of wet cotton 200 grms. of dry cotton are added. When the charge is placed in position the neck of the shell is closed by a plug, leaving space for the fuse and detonator, which is pierced by a curved channel through which paraffin at a temperature of 75° to 80° is poured. The paraffin fills all the interstices between the grains, and as it hardens forms the whole into a compact mass.

"The fuse is the same as the German percussion fuse, model 1873. The cupped part of this is lengthened and is open at the base, enclosing a capsule which contains 1 grm. of fulminate, surrounded by an india-rubber ring and washer. The whole is fixed by a screw. By slightly modifying the arrangement a delayed action fuse is obtained. To secure the immediate action of the capsule on the charge the former is surrounded with a primer of 10 grms. of dry gun-cotton, protected against concussion by an india-rubber ring. The shells are kept in store loaded, but the fulminate and fuse are only inserted when required for use.

"The German Government delivered in the spring of 1885 to the Walsrode works a cast-iron 15 cm. gun for trial of this

Digitized by Google

mode of charging shell. Shells 2 and 2½ calibre were used, weighing with lead coat 27 kg. empty and with an internal capacity of about 2 dm.³ Each shell had a charge of 1·35 kg. gun-cotton, 20 per cent. moisture, in rectangular grains 10 mm. by 20 mm., with 200 grms. dry cotton in cubical grains of 6 mm. The powder charge was 1·5 kg., distance of butt 70 m., velocity of shot at 30 m. being 245 m. Of five rounds none burst prematurely, two were set for delayed action and formed larger cavities than the other three. The shell were shattered into very small pieces, none of which exceeded a few millimetres in size. A hail of small pieces was thrown back more than 70 m. A loaded shell was then embedded in the butt and exploded, producing a crater about 2 m. diameter, 70 cm. deep, and 1·25 m.³ in capacity.

"Von Förster thereupon adopted a new position for the capsule—of which he gives no information—but which seems to have given good results, and the trials were continued to test all the points in his system.

"For this purpose blind shell were fired with primers of wet cotton. The detonators were found unexploded. This was followed by loaded shell without primers or detonators. The charge of gun-cotton was found to be neither consolidated nor altered. Filled shell with primers were then fired against the butt strengthened with wood baulks and iron rails, but the shell failed to explode; the butt was still further strengthened sufficient to break up a blind shell on impact. Under these conditions the charged shell for the most part burst. In some cases, however, they rebounded uninjured.

"Finally, fully charged and fitted shells were used, more than 200 rounds of 8·8 cm. shell being fired with a velocity of 450 m., common shell filled with gun-cotton were fired with a velocity of 200 m. from the rifled 15 cm. mortar and from the 15 cm. gun with a velocity of 400 m. These guns fired also steel shell 6 calibres long fitted on the same system. No premature burst occurred, and the bursts were in all cases satisfactory.

"On exploding an 8·8 cm. 7 kg. cast-iron shell at rest, 200

Digitized by Google

pieces over 10 grams and 600 under 10 grams were counted. An 8·8-cm. steel shell, 6·64 kgs. in weight, gave 23 large pieces weighing together 2·26 kgs., and 127 weighing 2·865 kgs. A cast-iron 15-cm. shell, weight 27 kgs., gave 376 pieces over 10 grams, and 828 pieces under 10 grams in weight were found to pass through wood baulks 25 cms. thick. A 15-cm. shell 6 calibres long, with a charge of 9·935 kgs. gun-cotton, sunk vertically in the ground, the base 25 cms. beneath the surface, gave a crater 4 metres broad, 1·3 metre deep, and 7 cub. metres in capacity. With a burster of 16 kgs. the following dimensions were obtained: 5·1 metres diameter, 1·56 metre depth, 12 cub. metres contents.

"In November, 1885, it was announced that the German Government had adopted the Walsrode gun-cotton for shell-bursters.

"In 1882 the German artillery commenced experiments with shells filled with gun-cotton on its own account, the original experiments being to determine the possibility of using high bursting charges with the 21-cm. mortar. Steel was used for the shell instead of iron, so as to increase the strength of the walls and permit the employment of larger charges, and the length of the shell was carried to 5 calibres.

"The following is a description of the 21-cm. mine shell: The shell is formed in two parts screwed together. The gun-cotton is contained in a zinc case and consists of small discs of compressed cotton 5 mms. thick, with 20 per cent. moisture. A primer of dry cotton is placed in the upper half of the shell, which is pierced by a central channel for the quicksilver detonator. When the burster is placed in its case, a wooden tube is inserted in the channel for the detonator, and paraffin is poured in to fill the interstices. A metal plug then closes the case, in which an opening is left for communication with the detonator. When the burster is in place, the head of the shell is put on and a metal cylinder inserted which fixes the burster and receives the fuze and detonator.

"The use of compressed gun-cotton discs permits of the use of a charge about one-third heavier than when the gun-cotton

Digitized by Google

is inserted in grains, but in the latter case making the shell in two parts can be avoided.

"General Brialmont states that in 1883 experiments were made with the 21-cm. mortar against casemates of strong brickwork 1 metre thick covered with 80 cms. of concrete and 1 to 1·5 metre of earth. Shells 6 calibres long with 19 kilogs. of gun-cotton as a burster perforated the structure and burst inside. It was further observed that the 21-cm. shell, with a burster of 26 kilogs., fitted with delayed-action fuze, penetrated 4 metres into sand. A casemate 1 metre thick, with 3 metres sand, would be perforated by such a projectile, which 5 metres of protection are required to keep out. The craters in the sand measured 4·8 metres in diameter, 2·4 metres deep, and were about 15·5 cub. metres in capacity.

"The trials were extended to shells for other natures of guns, especially the 15-cm. and 28-cm. mortars. The burster of the last is given as 50 kilogs."

Blasting Gelatine as a Military Explosive.—In order that an explosive substance may be suitable for military purposes, it must conform to the following conditions: (1) The substance must possess the greatest breaking efficiency for the smallest unit of weight and unit of volume. (2) It must possess great insensitiveness to sympathetic explosions and to mechanical shocks, especially those due to small projectiles, while it yet retains the property of exploding completely through the influence of an initial detonation. (3) It should be quite insensitive to fire, or at least so much so that there would be no chance of an *immediate* explosion when a considerable mass of it becomes ignited. (4) It should possess great stability, and not only should its efficiency remain unimpaired, but it should remain so under very extreme conditions. (5) It should remain unaffected by water.

There are only three substances thus far known which may be considered as approaching these requirements. They are kieselguhr dynamite, compressed wet gun-cotton (containing 15

Digitized by Google

per cent. of water), and military explosive gelatine; and these we will compare according to the requisites above mentioned.

(1) *Breaking Efficiency.*—Different experiments have shown that, weight for weight, gelatine with 4 per cent. of camphor is 25 per cent. more efficient than the best kieselguhr dynamite. As the density of the gelatine is 1·6, while that of the dynamite is 1·4, if their efficiency for equal weights is in the ratio of 5 : 4, for equal volumes it will be $5 \times 1{\cdot}6 : 4 \times 1{\cdot}4 = 10 : 7$. Hence for equal volumes the gelatine possesses 40 per cent. greater efficiency than the dynamite.

The efficiency of compressed gun-cotton with 15 per cent. of water, has been found to be practically the same as that of an equal weight of kieselguhr dynamite. The density of dry compressed gun-cotton is 1; and as the experiments of the Austrian Military Committee have shown that a prism of this substance does not change in volume where it has absorbed 15 per cent. of moisture (or when 240 grams have increased by absorption to 280 grams), we may conclude that the density of this wet gun-cotton is about 1·16. Accepting this, we find that the relative efficiency by volume of military explosive gelatine and wet compressed gun-cotton (15 per cent. moisture) stands in the ratio of 174 : 100. Hence for equal weights the explosive gelatine is 25 per cent., and for equal volumes 75 per cent., more efficient than the gun-cotton.

The advantages of this concentration of energy will be seen when we consider the question of transportation and storage during a time of war; for we can carry 25 per cent. more energy by transporting explosive gelatine instead of kieselguhr dynamite, and we can stow 40 per cent. more energy in one magazine if we fill it with gelatine rather than with dynamite. We may, therefore, build smaller magazines, and these can be more easily protected from external dangers than larger ones.

Through the use of explosive gelatine, we may also employ smaller torpedoes than are required for the other high explosives. There is little doubt also that the time will come when shells will be loaded with this explosive.

Digitized by Google

(2) *Insensitiveness.—Insensitiveness to Great Pressures.*—A hole 60 mms. deep and 11 mms. in diameter was bored in a block of iron, and a brass piston 75 mms. long was fitted neatly into it. A mass of the military explosive gelatine was pushed to the bottom of the cavity, and it filled it completely to a height of 11 mms. The brass rod was inserted in the hole above the gelatine, and an iron lever weighing 300 kilogs. was so adjusted to the top of the rod that one of its arms measured 5 metres in length, and the other 0·5 metre (Fig. 148). A weight of 250 kilogs. was attached to the extremity of the



FIG. 148.—TEST OF INSENSIBILITY OF EXPLOSIVE GELATINE TO PRESSURE.

longer arm, and, as the area of surface of the gelatine was 0·95 square cm., the mass sustained a load of 3050 kilogs. It was exposed to this pressure for 15 minutes, and during this time the rod penetrated to a depth of 3 mms. into the gelatine. No explosion resulted; the gelatine was removed from the hole with difficulty, and no exudation of nitro-glycerine was observed. This power of retaining the nitro-glycerine even under great pressure, as well as when submerged in water, makes this substance of especial value for shaft-sinking when there is much water to contend with.

Insensitiveness to Mechanical Shocks.—Four per cent. of camphor, when added to nitro-glycerine, renders it nearly as insensitive to mechanical shocks as compressed gun-cotton which contains from 15 to 20 per cent. of water. Experiments

Digitized by Google

have demonstrated that the addition of even 1 per cent. of camphor renders it sufficiently insensitive for all practical purposes. This insensitiveness is of the utmost importance from a military standpoint, especially if the explosive be used for the coast defence; for torpedoes loaded with gun-cotton have been exploded by counter-mines situated at considerable distances from them, which have produced sympathetic explosions.

While wet gun-cotton may be completely detonated through the initial impulse of a dry gun-cotton primer, nitro-gelatine is but incompletely detonated by such an impulse (J. Trautzl), and gelatine dynamite requires a much stronger initial impulse than compressed gun-cotton to ensure its complete detonation. This should lead to the conclusion that torpedoes loaded with nitro-glycerine could not be exploded by counter-mines.

Whenever shells come to be thrown from guns with success, either by means of compressed air or of gunpowder, nitro-gelatine will be used as the filling, and the promising results obtained by Lieut. Zalinsky at Fort Lafayette, with the new dynamite air-gun, lead us to believe that this difficult problem is nearing its solution (see p. 305).

In this connection the question will arise as to whether it will be possible to produce an equally insensitive primer which shall be powerful enough to effect the complete detonation of the nitro-gelatine, so that for the torpedo service not only will the filling resist the shock of the counter-mines, but the primer also, since one without the other would be useless. One feature which strikes us very favourably is the gelatinous, elastic consistency of the gelatine, which renders it well adapted to neutralise the shock of a neighbouring counter-mine, and thus to serve as a safety-guard and protector to the primer which is embedded in its elastic mass. If, however, the nitro-gelatine is frozen, the conditions are changed, and they become analogous to the examples last cited. Hence there is yet a vast field for experiments in this direction.

(3) *Insensitiveness to Fire.*—In this respect nitro-gelatine stands below wet gun-cotton, and approaches more closely to

Digitized by Google

kieselguhr dynamite in its behaviour. Wet gun-cotton cannot be set on fire by either flame or spark, but it must first be dried before it can be ignited. If a large quantity of wet gun-cotton were to take fire, there would be danger of its exploding only when it was in contact with a quantity of inflammable material, the burning of which might dry the gun-cotton. Therefore wet gun-cotton is the safest of all explosives as regards fire.

When nitro-gelatine is compared in this particular with dry compressed gun-cotton, or with dynamite, we find this difference: the last two substances burn with great vivacity when brought in contact with a spark or flame, but no explosion results. If, however, large quantities should get on fire, or if the gaseous products of combustion cannot escape readily, or if other circumstances prevail which favour the storing up of the heat resulting from the combustion, in that portion which is not burning, then an explosion will take place, as the trials with gun-cotton in England have proved.

Nitro-gelatine takes fire as easily as the other two, and burns with a yellow flame, and although its temperature of explosion is higher than that of the dynamites, there is little doubt that, if set fire to when in large masses, it would explode under the unfavourable conditions above mentioned, but as it may be exposed for some time under wet coverings without suffering, its storage can be rendered more safe, especially on board ships, in forts, and under like circumstances, which is a very important consideration.

(4) *Stability.*—Two points must be considered in discussing the stability of nitro-gelatine: (1) the possibility of the evaporation of the camphor; (2) the possibility of a gradual decomposition of the nitro-glycerine, or the nitro-cellulose, or both of them, during long transportation or storage.

It has been proved that evaporation of the camphor does take place, but not to a sufficient degree to impair its insensitiveness. Nitro-gelatine with 1 per cent. of camphor is not absolutely insensitive to the impact of a rifle-ball, yet after exposing it for 48 hours to the atmosphere at a temperature of

Digitized by Google

30° C., its sensitiveness was not in the least increased, and several balls fired into it from a distance of 25 metres failed to explode it. Close packing has been recommended as a preventive to this evaporation. Even without camphor, nitro-gelatine is certainly less sensitive to shocks than kieselguhr dynamite.

Experiments conducted on a small scale have demonstrated that when the military explosive gelatine is prepared from perfectly pure nitro-glycerine and equally pure collodion gun-cotton, it has as good keeping qualities as the kieselguhr dynamite, and that the addition of the camphor exerts no deleterious effect on its chemical stability. It is, however, advisable to add to it a small quantity of an alkaline carbonate, at a certain stage in the manufacture, as this will not only neutralise any free acid that may be present, but it will also tend to counteract any decomposition which may afterwards arise. There is also a possibility that the high temperature at which the gelatinising process is carried on may start a slight decomposition, which might be sufficient to endanger afterwards the chemical stability of the explosive; therefore it seems essential to add the alkaline carbonate. Sir F. Abel employs ammonium carbonate for his compressed gun-cotton, and as this substance would, owing to its great volatility, distribute itself very evenly throughout the whole mass, 1 per cent. is sufficient.

Digitized by Google

APPENDICES.

APPENDIX A.—*CAPTAIN HESS ON THE ANALYSIS OF EXPLOSIVES.*

APPENDIX B.—*DETERMINATION OF STABILITY.—INSTRUCTIONS AS TO TESTS ISSUED BY THE HOME OFFICE.*

APPENDIX C.—*APPLICATIONS FOR AUTHORISATION OF EXPLOSIVES. — INSTRUCTIONS ISSUED BY THE HOME OFFICE.*

APPENDIX D.—*THE EXPLOSIVES ACT*, 1875.—*ABSTRACT OF THE PRINCIPAL PROVISIONS OF THE ACT.*

Digitized by Google

APPENDIX A.

ON THE ANALYSIS OF EXPLOSIVES.*

BY

PHILIP HESS,

Captain of Engineers in the Austrian Army.

Section I.—THE ANALYSIS OF NITRO-COMPOUNDS—Determination of Nitrogen in Gun-cotton and Glycerine—Results of Analyses by various methods—Analysis of Kieselguhr Dynamite—Of Explosive Gelatine—Of New Dynamite No. 1.

Section II.—COMPOSITION OF GUN-COTTON SAMPLES—Method of Analysis—Results of Analyses of Lenk's and Abel's Gun-cotton—Determination of Ash Residue of Gun-cotton.

Section III.—QUALITATIVE AND QUANTITATIVE CHEMICAL ANALYSIS OF NITRO-GLYCERINE COMPOUNDS—Ingredients of Nitro-glycerine Compounds—Qualitative Examination—Quantitative Examination—Notes as to Analysis of Nitro-gelatine containing Camphor.

I.—THE ANALYSIS OF NITRO-COMPOUNDS.

Determination of Nitrogen in Gun-cotton and Nitro-glycerine.—Champion and Pellet discovered a method for the determination of the nitrogen in gun-cotton,

* Translated from the German, as published in 'Mittheilungen über Gegenstände des Artillerie und Genie Wesens,' Vienna. This Appendix is reprinted here (with a few corrections) as given in the first edition of this work (1889). Careful students of the subject of explosives will, in addition, avail themselves of the published results of the work of other writers.

Digitized by Google

which was based on the reaction; that on boiling nitro-cellulose with ferrous chloride and hydrochloric acid, all of the nitrogen of the nitrates is disengaged in the form of nitrogen oxide, and can be exactly measured.

A vacuum is created in the flask in which the reaction is to be carried on, by boiling a certain weight of gun-cotton with distilled water, and the ferrous chloride mixed with hydrochloric acid is introduced into this flask by aspiration; and when on heating the flask to boiling, the nitrogen oxide is



FIG. 149.—APPARATUS FOR ANALYSING.

developed, it is conducted into a graduated tube, where it is measured.

F. M. Eder, who employed this method almost exclusively in his determination of nitrogen oxide in pyroxylin, introduced one modification, in that he substituted a solution of ferrous sulphate in hydrochloric acid for the ferrous chloride, and yet obtained equally satisfactory results.

[The apparatus used by Captain Hess is identical with the one used by Champion and Pellet, and is shown in Fig. 149.]

Twenty to twenty-five grams of crystallised ferrous sulphate are dissolved in 100 cubic centimetres of water, in a flask K hold-

Digitized by Google

ing from 150 to 200 c.c., and to the solution a few small scraps platinum are added to prevent bumping during the boiling. The flask is closed with an india-rubber stopper having two bores, through which the glass tubes r and r_2 are inserted. The tube r_1 is closed by the cock h, and r_2 is closed by means of the pinch-cock q fastened to the india-rubber connecting tube s.

Through continuous boiling all air is expelled from the flask, and the end of the tube r_2, which is bent up at nearly right angles, is introduced into the graduated tube R, which has been filled with caustic soda solution, and stands in the basin w, which also contains caustic soda solution, as shown in the figure.

An accurately weighed quantity of the nitro-compound is dissolved in about 5 to 6 c.c. of sulphuric acid, and the solution poured into the funnel of r. From 0·12 gram to 0·16 gram of the nitro-compound are generally weighed out. The funnel is washed down with 2 to 3 c.c. of sulphuric acid, which is first poured into the small beaker glass that contained the dissolved sample. By carefully opening the cock h, the acid solution flows into the flask K, whereby the introduction of any air-bubbles is avoided as much as possible. Afterward the funnel is washed down with distilled water till the flask contains about 8 c.c. of fluid.

After heating the flask, a small pressure is obtained, the pinch-cock q is carefully opened and the nitrogen oxide with some steam is driven toward R. At the commencement only that gas is collected which is produced by the contact of the concentrated acid solution with the ferrous sulphate solution. The remainder of the nitrogen oxide gas is only disengaged by the concentration of the contents in the flask, which goes on gradually as the liquid boils down; and a very small quantity even remains behind and cannot be expelled in this way. When the contents of K commence to puff up, the tube r_2 is closed by q, the flame is extinguished and a vacuum is formed in K, and thereby the nitrogen oxide is disengaged, which was still retained by the liquid in K. After a while about

Digitized by Google

20 to 25 c.c. of water are introduced in the flask and the distillation is continued, whereby the remnant of nitrogen oxide is driven off with great facility toward R. The process can be considered as finished, when no further augmentation of the gas volume is noticed. The following table clearly shows how far the results, which have been obtained by various methods employed in the determination of nitrogen, agree.

To establish the correctness of the method, the following trials were made on—

1. Chemically pure nitromannite (recrystallised twice from alcohol).

2. A nitro-glycerine, the nitrogen contents of which have been determined by Dumas' method by Captain Dittel, and found to be 18·35 per cent.

Both these samples were analysed, and the correctness of the method established.

According to Champion and Pellet the composition of gun-cotton is pentanitro-cellulose, and the commercial nitro-glycerine in the dynamites is pretty nearly trinitrin.

The nitrohydro-cellulose, of the factory at Zamky, shows an unexceptionally low percentage of nitrogen, and it can be surmised that in its employment for primers for nitro-gelatine it could be advantageously replaced by higher nitrated gun-cotton.

The nitrogen contents of the collodion-cotton examined coincide exactly with the collodion-cotton prepared after Schering's method.

The paper powder prepared by the firm of Prentice and Co. was to a certain extent insoluble in sodium sulphide solution, so that it must have been a mixture of nitrated and unnitrated gun-cotton.

Kieselguhr Dynamite.—The simplest form of dynamite is the old Kieselguhr dynamite. For the analysis, from 1·5 to 2 grams (23·2 to 30·9 grains Troy) of this powder is put in a watch-glass of known weight, and dried in an exsiccator, over

Digitized by Google

Results of Analyses made by various Methods for the Determination of Nitrogen in certain Nitro-compounds.

Preparation	Percentage of Nitrogen as found by Method of				
	Dumas.	Crum-Hempel, modified by the employment of Lunges Nitrometer		Champion and Pellet.	Champion and Pellet modified.
		and rinsing down with concentrated Sulphuric Acid.	and rinsing down with dilute Sulphuric Acid.		
Nitro-mannite, recrystallised twice from Alcohol. Theory N=18·58%	..	18·33 18·43	18·52	..	18·53
Nitro-glycerine from Nobel's Kieselguhr Dynamite. Zamky, 1879	18·35	18·20 18·24 18·19	18·42 18·34 18·45	..	18·52 18·42 18·55
Collodion-cotton from Moll in Vienna	..	10·98 11·05 11·23	..	11·27	..
English Gun-Cotton from Waltham Abbey, 1874	..	12·67 12·56	..	..	..
English Gun-Cotton from Tonite, manufactured at Faversham, England	..	12·92 12·86	..	..	13·02
Prussian Gun-Cotton from Kruppamühle, 1879	..	12·17 12·27 12·20 12·29	..	..	..
Hirtenberg Gun-Cotton, immersed for over ten years in water	..	12·11 11·88	..	..	..
The same Hirtenberg Gun-Cotton, dried and nitrated again in a mixture of 1 part concentrated NHO_3 and 3 parts concentrated H_2SO_3	..	12·92 12·80 12·89	..	..	..
Nitro-Glycerine from Guhr Dynamite. Zamky, 1880	..	18·20 18·21	..	..	..
Nitro-Glycerine from Guhr Dynamite, 1877	..	..	18·18 18·16	..	..
Nitrated Hydro-Cellulose. Zamky, 1879	..	12·05 12·31	..	12·26	..
English paper powder from Prentice and Co., Stowmarket	..	..	9·82	..	9·82

Digitized by Google

calcium chloride or sulphuric acid for at least two days. Let us assume that before drying we had the following weight—

Watch glass with powder . . .	5·7412 grams
,, ,, without powder . .	3·8534 ,,
Dynamite	1·8878 ,,

and after drying we had—

Watch glass with powder . . .	5·7176 ,,
,, ,, without powder . .	3·8534 ,,
Dynamite	1·8642 ,,
Deducting from . .	1·8878
	1·8642
There remains . . .	0·0236 grams

or 1·25 per cent. for moisture.

Then having prepared two filtering-papers of exactly equal size and weight, we take a thin beaker, 1¾ in. wide by 1½ in. high, and weigh it accurately, and put it under a glass funnel which is provided with a loose stopper of cotton placed in the neck, and introduce the weighed filter paper into the funnel. The loose stopper of cotton under the filter paper prevents the too fast passing through of the ether. The filter paper is slightly moistened with ether, the dynamite put into it, and is treated with repeated washings of ether, until this has been done six or eight times, when all the nitro-glycerine will have been dissolved and filtered into the beaker.

A very simple way of ascertaining if any nitro-glycerine is yet passing in the solution, is by dropping two or three drops on a piece of writing paper, when if there is only a trace of nitro-glycerine the paper will show a greasy spot. As soon as the filter paper is dry, it is cleaned with ether and then ignited together with its contents in a platinum dish of known weight. When a uniform colour has been obtained it is allowed to cool, and then weighed.

Digitized by Google

As a result we have :—

Weight of platinum dish and contents . . .	15·6616 grams
,, ,, alone	15·1769 ,,
Therefore Kieselguhr and ash	0·4847 ,,

Then the second filter paper, of exactly the same weight as the one used, is reduced to ashes in the platinum dish and again weighed.

Weight of platinum dish and contents . . .	15·1780 grams
,, ,, ,, alone	15·1769 ,,
,, ash	0·0011 ,,
The Kieselguhr equals 0·4847 − 0·0011 . .	0·4836 ,,

equal to 25·61 per cent.

The nitro-glycerine can be determined now by the loss, but the percentage of it is ascertained as follows: a water bath, covered with a sheet of tin and a wire netting, is heated to about 70° Centigrade, the beaker with its filtrate is put on the wire netting. The ether must not boil, but slowly evaporate; and as soon as it has nearly all evaporated, the flame is repeatedly withdrawn. The filtrate will soon assume a milky appearance, and when this takes place the beaker is lifted several times and shaken a little to stir up the contents. When all the ether has evaporated, the remainder consists of nitro-glycerine and acetic ether, which can be evaporated by continued heating over the water bath. If an air-pump is at hand, even the smallest traces of acetic ether can be extracted.

We have now :—

Weight of beaker with contents	42·9550 grams
,, ,, alone	41·5744 ,,
Nitro-glycerine . . .	1·3806 ,,

or 73.14 per cent. The explosive examined is therefore composed of—

Nitro-glycerine	73·14 per cent.
Kieselguhr	25·61 ,,
Moisture	1·25 ,,
	100·00

Digitized by Google

A detailed examination of the Kieselguhr must be made under a microscope (900) magnifying power, to ascertain whether it contains a heavy percentage of Bacillariæ and Pleurosigmata (the first-named infusoria to be largely in excess), but no grains of quartz and no wheel-shaped Dictyodaceæ. A good Kieselguhr is absolutely necessary for good guhr dynamite, bad Kieselguhr, even with the same percentage of nitro-glycerine makes a weaker dynamite.

Explosive Gelatine.—The analysis of this substance is made as follows: About 1·5 to 2 grams of gelatine is taken and weighed; assuming that we have—

Beaker with explosive	42·2103 grams
,, alone	41·5305 ,,
Then gelatine	1·6798 ,,

A few drops of alcohol are then poured upon the gelatine, and after that, an excess of ether, until the nitro-glycerine and nitro-cellulose is completely dissolved. Then an excess of chloroform is added. Two filtering-papers exactly alike are cut, and one of them laid in a glass funnel. The solution of chloroform containing the nitro-glycerine and the nitro-cellulose is then filtered into a beaker of known weight and frequently wet with chloroform. The filtrate is then nitro-glycerine dissolved in chloroform, while the remainder is nitro-cellulose.

The filtering-paper is then taken from the funnel, the chloroform remaining about the filter allowed to evaporate, and the funnel thoroughly cleaned with chloroform. Then the filter-paper with the nitro-cellulose and the other filter not used are put over a water bath for about fifteen minutes at a temperature of 100° Centigrade, and both filters then weighed. The difference in their weight gives the proportion of nitro-cellulose; say in this case the difference is 0·1243 gram or 7·4 per cent. nitro-cellulose.

The filtered fluid is then treated as in the first test, with the result:—

Digitized by Google

Weight of beaker with contents .	43·0683 grams
,, ,, alone . . .	41·5308 ,,
Hence nitro-glycerine . .	1·5555 ,,

or 92·6 per cent. The explosive gelatine consequently contains

Nitro-glycerine . . .	92·6 per cent.
Nitro-cellulose . . .	7·4 ,,

It is advisable to determine the moisture in the gelatine before its solution in ether and alcohol.

New Dynamite No. 1.—Weigh out about 2·5 to 3 grams, and dry for about three days in an exsiccator; it is then weighed again.

Say the following are the results:—

Watch glass with contents . .	8·2939 grams
,, ,, alone.	5·3538 ,,
Hence dynamite with moisture	2·9401 ,,

and after drying in the exsiccator, we have—

Watch glass with contents . . .	8·7616 grams
,, ,, alone	5·8538 ,,
Hence dynamite	2·9078 ,,

2·9401 − 2·9078 = 0·0323 gr. = 1·10 per cent. moisture.

The dynamite in the beaker is then moistened with some alcohol, then ether is added until the nitro-glycerine and the gun-cotton are completely dissolved. It is then filtered through a filtering-paper of known weight, and washed with ether. The ether and alcohol is then evaporated and the filtering-paper is dried at about 100° C. The filtered fluid is then covered with chloroform, which separates the gun-cotton from the nitro-glycerine. The process is now the same as that with explosive gelatine, described above. When the dry filter-paper is weighed, we have—

Weight of filter-paper with contents . .	1·3858 grams
,, ,, ,, alone	0·7623 ,,
Therefore absorbents alone . . .	1·0735 ,,

or 36·51 per cent.

Digitized by Google

The paper with the absorbent is then put into the funnel, and is repeatedly washed with boiling water until the saltpetre and soda are dissolved. The filtered fluid is now put in a platinum dish and carefully dried over a water bath, and, after having been left for twenty-four hours in the exsiccator, it is weighed.

Platinum dish with contents . . .	15·9322 grams
,, ,, alone	15·1769 ,,
Hence saltpetre and soda . . .	0·7553 ,,

Besides these two substances the residue contains the soluble parts of the wood pulp. For ordinary purposes this analysis is sufficient, and we have for the explosive examined :—

Moisture	0·0323	gram	or	1·10	per cent.
Saltpetre, soda and dissolved pulp	0·7553	,,	,,	25·68	,, ,,
Wood pulp	0·3182	,,	,,	10·82	,, ,,
Gun-cotton	0·0647	,,	,,	2·20	,, ,,
Nitro-glycerine	1·7693	,,	,,	60·17	,, ,,
Loss	0·0003	,,	,,	0·03	,, ,,
	2·9401			100·00	

If an exact analysis is desired, then, after the above-described proceeding we must determine the residue in the filtering paper :—

Paper with residue	1·0805 gram	
,, alone	0·7623 ,,	
Therefore dried wood pulp . . .	0·3182 ,,	or 10·82 per cent.

Then a few drops of water with one drop of nitric acid are added to the salts in the platinum dish, and after that it is dried and weighed. From the difference the percentage of soda can be calculated, as the sodium carbonate has been changed by the nitric acid into sodium nitrate. For instance, let the first weight of saltpetre, soda, and dissolved wood pulp (as above) 0·7553 gram = P; the second weight = 0·7450 gram = P', therefore difference = 0·0103 gram. The molecular weight of sodium nitrate is 85, twice the same = 170;

Digitized by Google

the molecular weight of sodium carbonate = 106. We have then the proportion :—

$$106 : (170-106) = x : 0{\cdot}0103$$
$$\text{or} \quad 106 : 64 = x : 0{\cdot}0103$$
$$\text{hence } x = \frac{106 \times 0{\cdot}0103}{64} = 0{\cdot}0171 \text{ gram of sodium carbonate.}$$

To ascertain the percentage of the dissolved wood pulp, the contents of the platinum dish are heated until the saltpetre is melted; it is then cooled, a little water and a drop of nitric acid added, and then dried over steam. The dish is then heated to 150° C., dried in an exsiccator and weighed :—If, for instance, the weight of the dish and contents is 0·7273 gram, then P′ = 0·7450, P″ = 0·7273; the difference is 0·0177 gram; equal to the weight of the dissolved constituents of the wood pulp. The above given weight of 0·7553 gram has the following composition :—

Potassium nitrate.	0·7205 gram	=	24·50 per cent.
Sodium carbonate	0·0171 ,,	=	0·58 ,, ,,
Dissolved wood pulp . . .	0·0177 ,,	=	0·60 ,, ,,
	0·7553 ,,	=	25·68 ,, ,,

These examples show that an analysis of dynamite can be made at a small expense of time and means; all that is needed is careful, intelligent work, and a good balance which is accurate to $\frac{1}{10000}$ of a gram.

II.—Composition of Gun-cotton Samples.

The gun-cotton prepared after the Lenk-Abel system shows a variable composition, as will appear from the table of results of analyses given below, which has been compiled by several observers, although the analyses were conducted on one and the same method, as follows :—

a. **Determination of Moisture.**—As in compressed gun-cotton the moisture is not evenly distributed throughout the whole mass, it becomes important to obtain an average

Digitized by Google

sample. This is best obtained by dividing several cartridges into thin discs and sampling these perfectly. The divided gun-cotton is now weighed in a glass tube, which can be hermetically closed, and the weight of which has been previously taken; it is exposed in this to the influence of a current of dry air at a temperature of 40° C., until its weight remains constant. To prevent any of the powdered gun-cotton from being carried away by the current of air, the outlet of the tube is closed by a cotton stopper. Parts of this sample are then taken for analysis, the weight of the tube being taken each time, so as to determine by the difference of weight how much of the gun-cotton has been taken out.

b. **Determination of Ash.**—A certain weight of the gun-cotton is saturated with paraffin (about 5 grams will suffice) in a platinum dish and set on fire, and the residue weighed.

c. **Extraction of Alkalies.**—A certain quantity of dried gun-cotton is leached out with water, which dissolves any alkaline carbonates present. An addition of a carbonate of an alkaline earth is found by the analysis of the ash. All of the ash that is not soluble in hydrochloric acid, can be considered as sand.

d. **Determination of the contents of Mono- and Dinitro-Cellulose.**—About 5 grams of the triturated and dried gun-cotton are saturated in a flask with absolute alcohol, and then ether is added. The flask is closed with a cork and left standing at the ordinary temperature of the room, shaking it gently occasionally till all the fibres are dissolved. Alcohol ether is now added till the solution is perfectly fluid, and it is now passed through a linen filter. Should the filtrate appear turbid, it is repeatedly passed through the filter. After carefully washing the filter with alcohol-ether it is dried in a current of air of 40° C. and again weighed. The difference between the weight of the gun-cotton sample itself and the weight of the residue on the linen filter gives the contents of mono- and dinitro-cellulose.

Digitized by Google

The residue consists of ash particles insoluble in water, of trinitro-cellulose and unnitrated cotton fibres.

e. **Separation of Trinitro-cellulose from the Unnitrated Cotton-fibres.**—A portion of the residue from *d* is weighed out in a test tube, and repeatedly boiled with an excess of concentrated sodium sulphide. The trinitro-cellulose goes into solution; whereas the unnitrated fibres are not attacked.

The solution is passed through a weighed linen filter and washed with distilled water, till the drops of filtrate do not impart a brown colour to paper saturated with lead acetate. The filter is now washed with dilute hydrochloric acid, to wash out traces of sulphide of iron, and at last is washed with distilled water to free it from hydrochloric acid, then dried at 40° C. in a current of dry air and weighed.

It is advisable to examine the residue obtained once more by repeating the whole process, so as to see if any trinitro-cellulose remains. The residue must not be considered as pure cotton, but must be incinerated, and the ashes leached out with hydrochloric acid and the residue which is insoluble must be weighed out. As an explanation of the subjoined Table, it must be first noticed that—

Samples *a* and *b* are from the gun-cotton factory at Kruppamühle in Upper Silesia.

Samples *c* and *d* are gun-cotton from some other continental factory.

Sample *e* is English gun-cotton extracted from a blasting compound named "Tonite," from the cotton-powder factory at Faversham.

Samples under *g* and *h* indicate the composition of Abel's gun-cotton according to Musprat.

Sample *i* gives the composition of a sample of English gun-cotton (which has been freed of its ash, amounting to 1 per cent.) according to Champion and Pellet. But instead of indicating the highest nitrated product of cotton by the name of trinitro-cellulose, Champion and Pellet by doubling the cellulose formulæ used the name "Pentanitro-Cellulose."

Digitized by Google

TABLE SHOWING THE COMPOSITION OF SOME GUN-COTTON SAMPLES PREPARED AFTER LENK'S AND ABEL'S METHODS.

Denomination of the sample.	Percentage of the sample in						Totals.	By whom the Analysis made.	REMARK.
	Trinitro-Cellulose.	Mono- and Dinitro-Cellulose.	Cellulose.	Extracted with water.	Sand.	Other Ash residues.			
A	88·60	5·51	3·30	1·64	0·37	0·17	99·59	Captain Hess.	
B	89·10	5·57	3·28	1·40	0·33	0·69	100·37	Second Lieutenant Dolliak.	
C	80·33	9·44	8·40	0·25	0·06	1·56	100·04	Captain Hess.	
D	80·57	9·20	8·41	0·26	0·05	1·60	100·09		
E	85·53	6·45	3·57	2·43	0·22	1·86	100·06	Second Lieutenant Dolliak.	
F	93·13	5·63	1·05	..	0·19		100·00	Captain Hess and Captain Schwab.	This sample taken from Tonite.
G	81·5	12·0	5·0	0·5			99·50		
H	82·5	12·0	4·0	0·5			99·50		
I	93·0	6·0	1·0	..	..	..	100·00	Champion and Pellet.	

Digitized by Google

Determination of the Ash Residue of Gun-cotton.—In incinerating gun-cotton, collodion-cotton, or any other nitro-cellulose, in consequence of the rapid development of gas the ashes are blown away from the vessel, and an exact determination of the ashes becomes difficult.

To avoid this the weighed quantity of gun-cotton is impregnated with paraffin. The burning now proceeds slowly, and there is no loss of ashes. The *modus operandi* is as follows:

A quantity of clear paraffin, just sufficient to impregnate the gun-cotton, is melted in a platinum dish. An excess of paraffin is not objectionable. After the gun-cotton is soaked it is set on fire. The contents of the dish do not burn now any faster than pure paraffin would. There remains a carbonaceous residue, which can be incinerated.

The results obtained in this manner by Captain Hess are very satisfactory, and a sample of gun-cotton from a German factory gave, after two trials, a percentage of ash of 2·40 and 2·41 per cent. A second assay gave 2·44 and 2·56 per cent., and a third assay gave 2·33 and 2·34 per cent.

A sample of English gun-cotton gave in three determinations an ash content of 4·24, 4·19 and 4·11 per cent.

III.—Qualitative and Quantitative Chemical Analysis of Nitro-glycerine Compounds.

Ingredients of Nitro-glycerine Compounds.—In the determination and separation of the ingredients which are contained in the various nitro-glycerine compounds, account is taken of the various parts which they play, and hence they are classified as follows:—

1. Explosive ingredients.
2. Absorbents which are non-explosive and play no part in the explosion.
3. Absorbents which are chemically active and which are subdivided into:—
   - *a.* Mineral absorbents.
   - *b.* Organic absorbents.

Digitized by Google

4. Oxidising agents, which promote the combustion of the organic absorbents during the explosion.

5. Ingredients which contribute to the stability of the explosive compounds.

6. Ingredients which are intended to impart certain advantageous technical properties to the nitro-glycerine compounds, besides the explosive effect.

1. As explosive ingredients of the nitro-glycerine compounds we have: Nitro-glycerine, gun-cotton, collodion-cotton, nitrated wood fibres.

2. As absorbents, which are non-explosive, and play no part during the explosion, we have: Kieselguhr, Randanite, Tripoli clay, and argillaceous earth.

3*a*. Mineral absorbents, which act chemically through the volatile gases which are developed by the heat generated during the explosion, such as chalk, carbonate of magnesia.

3*b*. Organic absorbents, such as sawdust, wood pulp, paper pulp, charcoal, brown coal and stone coal.

4. As mineral oxygen carriers we have: Saltpetre, nitrate of soda, nitrate of ammonia and nitrate of baryta. Sometimes chlorate of potash is used, as in Séranine and Horsley powder.

5. The ingredients which contribute to the stability of the explosive compounds are generally the carbonates of the alkalies and alkaline earths, like carbonate of soda, carbonate of ammonium, carbonate of lime, carbonate of magnesia. The two last serve also as absorbents for the nitro-glycerine.

6. Other additions are: Paraffin, sulphur, resin and other substances which are utilised to modify the absorbing capacities of the absorbents and diminish their hygroscopic properties. To diminish the sensitiveness of the nitro-glycerine to mechanical and thermal influences, camphor is added in some instances.

Qualitative Examination of Nitro-glycerine Compounds.—For the qualitative examination of the nitro-glycerine compounds, the following advice is given:

The compound is very finely divided, which is done by

Digitized by Google

cutting the gelatine into very thin sections, and when the compound is pulverulent it is treated with ether, but when gelatinous, with a mixture of two parts of ether and one of alcohol. In the first case, the nitro-glycerine is extracted, and if paraffin, sulphur, resin or camphor is present, they are also dissolved. In the second case the collodion-cotton is also dissolved.

Reactions of the Nitro-glycerine.—The ether solution is evaporated on a water bath at a temperature of about 30° C. To prove the presence of the nitro-glycerine as such, a drop of it is taken out on a piece of blotting-paper and is hammered on an anvil, which causes an explosion.

The portion dissolved in alcohol and mixed with an alcoholic solution of ammonium sulphide will cause the separation of sulphur.

A solution of ferrous sulphate, to which a few drops of muriatic acid are added, will give, when a drop of nitro-glycerine is added and on slightly warming, the nitrogen-oxide reaction.

On adding a drop of the oil to an iodide of potassium and starch solution, acidulated with dilute sulphuric acid and containing some zinc filings, a blue coloration of the liquid will be produced.

If after evaporation of the ether the oil shows a specific gravity of 1·6 and has no smell, it can be concluded that it is pure nitro-glycerine.

In making these tests pure ether must be employed, as otherwise the impurities which are less volatile will be found in the residue. This will be especially the case with acetic ether.

Reactions for Paraffin, Sulphur, and Resin. — If after the evaporation of the ether (when the solution is completed) the residue is carefully examined, and if the presence of paraffin, sulphur, and resin is suspected, then the nitro-glycerine is decanted, and the residue pressed between filtering-paper as long as it shows any fat.

By boiling the residue with soda solution the resin is first dissolved.

Digitized by Google

Another portion of the residue after drying is treated with aqua regia, by which any sulphur will be converted into sulphuric acid, which is then precipitated as barium sulphate.

Another portion of the residue is boiled with a solution of ammonium sulphide, whereby the sulphur dissolves and forms ammonium polysulphide, and the paraffin after cooling collects as a crust on the surface of the liquid, and can be washed with water, dried and subjected to a further examination.

The test for paraffin can also be made after the evaporation of the ether from the oil, by taking some of the sample and treating it with alcohol, and pressing between filter-paper till all the liquid is absorbed. Then the residue is tested as to its fusibility and its boiling-point, and the smell of its distillation products noticed.

The resin which may be present can be saponified by boiling with soda solution, from which the resin can be precipitated by hydrochloric acid.

Reactions of Collodion-cotton and Camphor. — If the ether solution contains camphor, this is recognised at once by its smell.

If the explosive is treated with a mixture of alcohol and ether, then on addition of chloroform the mono- and dinitrocellulose is separated. By now heating gradually from 30° to 80° C., the solution is freed from ether, alcohol, and chloroform.

The mono- and dinitro-cellulose which is separated is recognised by its explosibility when struck with a hammer on an anvil; and also through its deportment with sodium sulphide solution, in which it dissolves on boiling. By boiling it with hydrochloric acid and ferrous sulphate it ought to give the nitrogen oxide reaction.

Reaction of the Nitrates, Chlorates, and Carbonates soluble in Water.—The residue from the extraction of the explosive with ether or alcoholic ether is now treated with hot distilled water, whereby the nitrates, chlorates, and those carbonates which are soluble in water go into solution. The determination of these

Digitized by Google

substances in the aqueous solution offers no difficulty. The residue which remains after leaching with hot water, if the explosive in the first instance has only been treated with ether, may contain mono-, di- and trinitro-cellulose, but if the extraction has been carried on with alcoholic-ether only trinitro-cellulose, the higher nitro-products, and all the other substances which are insoluble in alcohol, ether and water.

Reaction for Trinitro-cellulose. — The presence of trinitro-cellulose in the residue is determined :—

1. By examining the residue under the microscope by means of polarised light; the trinitro-cellulose shows the original structure of the cotton fibres, but they are of a dull aspect, while the unnitrated fibres show a very vivid play of prismatic colours.

2. By boiling the residue with ferrous sulphate solution and hydrochloric acid, the nitrogen oxide reaction will set in if any trinitro-cellulose is present.

3. On boiling the residue with an alcohol solution of caustic potash, when the filtrate is slightly acidulated with sulphuric acid, free nitric or nitrous acid ought to be recognised.

4. On separating the fibres taken for trinitro-cellulose, and examining them in regard to their inflammability and explosibility. The trinitro-cellulose can be separated from the residue, by boiling it with sulphide of sodium solution, filtering and washing with distilled water, which will leave the other insoluble ingredients behind.

Reaction for Carbonate of Lime, Carbonate of Magnesia, and Argillaceous Earth.—When the residue which contains these substances is treated with hydrochloric acid, the carbonate of lime, carbonate of magnesia, and also the argillaceous earth, goes into solution, and the substances enumerated under 2 and 3*b* remain behind.

Examination of the Residue: Wood, Coal, Insoluble Mineral Substances.—The residue is examined under the microscope. Sawdust, wood pulp, and charcoal are easily recognised by their structure and colour.

The wood fibres can be dissolved with caustic potash solu-

Digitized by Google

tion, and are precipitated with a brown colour by means of acids.

Brown coal will also enter into solution with caustic potash.

The residue when incinerated will yield beside wood and stone coal ash, any mineral substances which may have been contained in the explosive substance. The microscope must have detected the kieselguhr beforehand, if any was present.

Quantitative Examination of Nitro-glycerine Compounds.—A. *Extraction with Ether.*—The extraction of the nitro-glycerine, in most cases, is best effected with ether. Ether is the best solvent for nitro-glycerine on account of its great volatility, and also because ether leaves nearly all other substances behind without acting on them as a solvent.

The sample which is submitted for analysis is first dried under the exsiccator over *chloride of calcium.* The use of sulphuric acid for drying nitro-glycerine and similar compounds, as well as fulminates, ought to be avoided in all cases, *as serious accidents might happen by spilling some of the explosive into the acid.* The sample is now treated on a filter with ether, as fully described previously.

The ether solution is collected in a small beaker, previously weighed, and evaporated on a water bath. There is a moment during the evaporation when the clear liquid, in consequence of the partial separation of the nitro-glycerine from the ether, shows a milky turbidity; and the operation is now closely watched till this turbidity disappears, when the beaker is at once taken away from the bath. The nitro-glycerine still contains small quantities of ether, or acetic ether, and to free it from these traces and also from moisture, it is put again under the vacuum of an air-pump over chloride of calcium. The nitro-glycerine can be weighed as soon as no smell of ether is noticed, and the operation is repeated until the weight is constant.

Determination of the Nitro-glycerine in the presence of Paraffin, Resin, or Sulphur. Determination of these Substances.—If the explosive contains beside nitro-glycerine other substances, like

Digitized by Google

paraffin, resin, or sulphur, which are also soluble in ether, these go into solution along with it. After evaporation of the ether, the nitro-glycerine, with the adhering substances, is weighed and then heated on a water bath with a soda solution. The resin goes into solution, and is separated by decantation from the rest, precipitated with hydrochloric acid, and collected on a weighed filter, previously dried at a temperature of 100° C., washed, and again dried as before, and weighed. The nitro-glycerine is taken up with strong alcohol, decanted, and the remaining mixture of paraffin and sulphur washed with alcohol, then dried and weighed.

To separate the sulphur from the paraffin, the mixture is heated with a solution of ammonium sulphide in water. After cooling the paraffin collects as a crust on the surface, and by pricking a small hole through it the liquid underneath is poured off, and after washing with water and drying the paraffin is weighed.

The quantity of the nitro-glycerine and that of the sulphur is determined by difference.

B. *Extraction with Ether-Alcohol. Determination of the Nitro-glycerine in Gelatinised Explosives. Determination of the other Substances which can be Extracted with Alcoholic Ether.*—In acting on gelatinised materials, it is better to use alcoholic ether and to dissolve the nitro-glycerine and collodion-cotton at once, and to precipitate the collodion-cotton by adding chloroform.

If camphor is present it is extracted with bisulphide of carbon after the compound is treated with the ether-alcohol.

In case any paraffin, sulphur, or resin is present they will go over into solution with the camphor in the sulphide of carbon, and the easily volatile camphor can be separated by evaporation from the difficultly volatile paraffin, resin, or sulphur. If the weight of the extract freed from ether-alcohol but not yet treated with bisulphate of carbon is $= a$; and if the weight of the extract after treatment with bisulphide of carbon and evaporation of the same is $= b$; and if the weight of the residue which is left after evaporating the bisulphide of carbon and the

Digitized by Google

camphor it held in solution is = *c*; we find the percentage of camphor to be: $a-b-c$.

The residue *c* may contain traces of nitro-glycerine, some paraffin, resin, or sulphur, and their separation may be effected by the method described beforehand.

C. *Separation and Determination of the Ingredients which are Insoluble in Ether and Ether-Alcohol.*—In the residue which remains after the treatment of the explosive with ether and alcoholic ether, there may be present some bodies enumerated under 2, 3*a*, 3*b*, 4 and 5.

If, according to the qualitative analysis the residue, consists of refractory substances, they can be incinerated with the filter and weighed. But it is better first to dry the filter in a current of dry air at 60° C., and to weigh, and then burn the filter and weigh again, and determine by this means whether or not the residue contained small quantities of organic substances.

If the residue contains other ingredients, it is treated in the following manner :—

Extraction with Water.—If soluble salts are present, after the weight of the residue on the filter is determined, they are leached out with hot distilled water, the filtrate evaporated, dried at 120° C., and its weight determined. If the extract contains carbonates and no chlorates, the residue is dissolved again in water, neutralised with nitric acid, evaporated on a water bath, dried at 120° C., and again weighed. By this proceeding the carbonates are converted into nitrates, and from the difference of the two weighings the quantity of carbonic acid is determined.

The separation of the different bases is carried out according to the known analytical methods.

In case any chlorates are present in the aqueous solution of the soluble salts, a portion of it is taken, and the carbonic acid is first determined as calcium carbonate through precipitation with calcium nitrate, and after separation of the precipitate the solution is evaporated and heated and the chloric acid determined as silver chloride.

Another portion of the aqueous solution is taken for the

Digitized by Google

purpose of determining the nitric acid through conversion into ammonia.

The determination of the different bases is carried on with still a separate portion of the aqueous solution. The residue which is left after the extraction with water is treated as follows :—

Separation and Determination of Trinitro-cellulose.—If trinitro-cellulose is present, then a part is taken from the filter and boiled in a concentrated solution of sodium sulphide. The nitro-cellulose goes thereby into solution, and is passed through a weighed filter, which is carefully washed with distilled water, dried and weighed. The difference of weight gives the per-centage of trinitro-cellulose.

Extraction with Hydrochloric Acid. — The residue which remained on the above filter, after separating from it the trinitro-cellulose, is treated with dilute hydrochloric acid, which dissolves out the carbonates of lime and magnesia and also the argillaceous earth, and in the solution the different bases are determined. The residue is washed with water, and after drying is weighed on a filter, and from the difference or weight the quantity or alkaline and earthy carbonates is found.

Determination of the Organic and Inorganic Absorbents.— This residue contains, besides the wood, coal or similar organic substances, the insoluble mineral absorbents also.

Through incineration the organic substances can be separated, and the insoluble mineral substances are weighed as a residue. If there are several organic absorbents, such as wood pulp and charcoal, a satisfactory separation of these two substances cannot be made here, but they must be determined by means of an elementary organic analysis, which will establish the relative proportion of these ingredients quite approximately.

Notes as to the Analysis of Nitro-gelatine containing Camphor.—To determine the camphor, the nitro-gelatine is cut into very thin slices and digested in a flask with a mixture of alcohol and ether at a temperature of 30° C. About 30 cubic centimetres of the solvent are taken for 0·3

Digitized by Google

grams of the gelatine, and the solution is effected after several hours, with the exception of some pentanitro-cellulose and unnitrated cotton.

The clear solution is poured into a beaker and the flask washed with a little ether, and this added to the solution in the beaker. The whole is now mixed with about three times its volume of chloroform, which separates the collodion-cotton as a gelatinous mass, and this is collected on a linen filter, air-dried at 70° C. and weighed. The filter is washed with a little chloroform. After drying the filter, its increase in weight determines the quantity of collodion-cotton.

The filtrate is kept at a temperature of 30° C., and after being put over chloride of lime in the vacuum of an air-pump, it is freed from the alcohol-ether, chloroform and moisture, and the nitro-glycerine and camphor remains.

A portion of this remaining solution of camphor in nitro-glycerine is now taken in a test tube and mixed with 20 c.c. of bisulphide of carbon and well shaken. The camphor and a very small portion of nitro-glycerine dissolve in the bisulphide of carbon, and this solution is now decanted from the remaining nitro-glycerine. The nitro-glycerine and the decanted liquid are exposed first to a temperature of 20° C., then to 60° C., and at last in the vacuum of an air-pump over calcium chloride till the bisulphide of carbon in both samples, with the camphor contained in one, is evaporated. The evaporation of the camphor is noticeable by the smell. The test tube which contained the bisulphide of carbon shows now a few drops of nitro-glycerine, which were dissolved with the camphor and which has separated now from it. The principle of this method therefore consists in dissolving the camphor, which is held with great tenacity by the nitro-glycerine, in bisulphide of carbon.

A very small quantity of nitro-glycerine is lost by this method through its volatilisation with the bisulphide of carbon, and it is of importance to determine this loss, so as to correct the weight of the separated nitro-glycerine. Captain Hess made several tests, to determine the loss occasioned in this

Digitized by Google

way, by shaking well together 4 to 5 grams of nitro-glycerine and 20 c.c. of bisulphide of carbon, decanting and evaporating as before stated. The nitro-glycerine weighed afterwards showed by repeated tests an average loss of 1·25 per cent.

Hence in an analysis of nitro-gelatine, containing camphor, this quantity has to be added to the weight of nitro-glycerine found. The quantity of camphor is therefore determined by difference. A small quantity of camphor is also lost during the evaporation of the ether-alcohol and chloroform solution, and this loss has to be determined. To see how exact this method is, Captain Hess prepared several samples of nitro-gelatine himself, and from the synthetic conditions and the results of the analysis he found it satisfactory. From 100 parts of dry camphor gelatine he obtained

	According to Synthesis.	According to Analysis.
Nitro-glycerine	85·25	85·33
Collodion-cotton	8·74	9·00
Camphor	6·01	5·67
	100·00	100·00

Digitized by Google

APPENDIX B.

DETERMINATION OF STABILITY.—INSTRUCTIONS AS TO TESTS ISSUED BY THE HOME OFFICE.*

Heat Test as applied to Explosives of the Nitro-compound Class (as defined by Order in Council, No. 1, of 5th August, 1875).

General Instructions.

Apparatus required.

1. A water bath, consisting of a spherical glass or copper vessel (*a*), Fig. 150, of about 8 inches diameter, and with an aperture of about 5 inches; the bath is filled with water to within a quarter of an inch of the edge. It has a loose cover of sheet copper about 6 inches in diameter (*b*), and rests on a tripod stand about 14 inches high (*c*), which is covered with coarse iron wire gauze (*e*), and is surrounded with a screen of thin sheet tin or copper (*d*). Within the latter is placed an argand burner (*f*) with glass chimney. The cover (*b*) has four holes arranged as seen in Fig. 151, No. 4 to receive the regulator, No. 3 the thermometer, Nos. 1 and 2 the test tubes containing the gun-cotton or other materials to be tested. Around holes 1 and 2 on the under side of the cover are

* I am indebted to Colonel V. D. Majendie, H.M. Chief Inspector of Explosives, for a copy of these Instructions.

Digitized by Google

soldered three pieces of brass wire with points slightly converging (Fig. 151); these act as springs and allow the test-tubes to be easily placed in position and removed.

*2. Scheibler's or Page's temperature regulator.



FIG. 150.



FIG. 151.

SIR FREDERICK ABEL'S HEAT TEST APPARATUS.

*3. Two cells of Le Clanché's battery No. 1 } if Scheibler's regulator is used.
*4. A few yards of insulated copper wire }

5. Test tubes from $5\frac{1}{4}$ to $5\frac{1}{2}$ inches long, and of such diameter that they will hold from 20 to 22 cubic centimeters of water when filled to a height of 5 inches.

* This is not absolutely required, as the temperature of the bath can be kept constant by proper attention to the heating flame.

Digitized by Google

6. India-rubber stoppers, fitting the test tubes and carrying an arrangement for holding the test paper, viz., a narrow glass tube passing through the centre of the stopper, drawn out so as to form a hook, or terminating in a platinum wire hook (Fig. 152).

7. A thermometer, with range not less than from 30° to 212° Fahrenheit.

8. A minute clock.

Materials Required.

a. *Test Paper.*—The test paper is prepared as follows:—45 grains of white maize starch (corn-flour), previously washed with cold water, are added to 8½ oz. of distilled water; the mixture is stirred, heated to boiling, and kept gently boiling for ten minutes; 15 grains of pure potassium iodide (*i.e.* which has been re-crystallised from alcohol) are dissolved in 8½ oz. of distilled water. The two solutions are thoroughly mixed and allowed to get cold. Strips, or sheets, of white English filter paper, previously washed with water and re-dried, are dipped into the solution thus prepared, and allowed to remain in it for not less than ten seconds; they are then allowed to drain and dry in a place free from laboratory fumes and dust. The upper and lower margins of the strips, or sheets, are cut off and the paper is preserved in well-stoppered or corked bottles **and in the dark.** [When the paper is freshly prepared, and as long as it remains in good condition, a drop of dilute acetic acid, put on the paper with a glass rod, produces no colouration. In process of time, however, the stronger the light to which the paper is exposed, the sooner a drop of the acid produces a brown or bluish colouration (a single hour of direct sunlight produces a marked effect), and whenever this is the case the paper should be rejected. On this account it is advisable not to prepare too much of the test-paper at one time, but to prepare it fresh every month or so.]

b. *Standard Tint Paper.*—A solution of caramel in water is made of such concentration that when diluted one hundred times (10 c.c. made up to 1 litre) the tint of this diluted solu-

Digitized by Google

tion equals the tint produced by the Nessler test in 100 c.c. water containing 0·000075 grm. of ammonia or 0·00023505 grm. of chloride of ammonium. With this caramel solution lines are drawn on strips of white filter paper [which paper must be carefully washed with distilled water in the first instance, to remove any traces of bleaching matter, and dried] by means of a clean quill pen. When the marks thus produced are dry the paper is cut into pieces of the same size as the test paper previously described, in such a way that each piece has a brown line across it near the middle of its length, and only such strips are preserved in which the brown line has a breadth varying from $\frac{1}{2}$ mm. to 1 mm. ($\frac{1}{50}$ inch to $\frac{1}{25}$ inch).

I.—Testing Dynamite, Blasting Gelatine, and other Explosives of the First Division of the Nitro-compound Class.

A.—Dynamite, &c. &c.

Nitro-glycerine preparations, from which the nitro-glycerine can be extracted in the manner described below, *must* satisfy the following test, otherwise they will not be considered as manufactured with "thoroughly purified nitro-glycerine" within the terms of the license.

This test, however, though at present looked upon as the most important, as far as testing the purity of the nitro-glycerine is concerned, is only one of several which any given sample of nitro-glycerine preparation has to satisfy in order to establish its compliance with the definition in the license.

The test, although at present accepted as regulating and defining the meaning of the terms "thoroughly purified," may nevertheless be modified or superseded if, in the opinion of the Home Office, such alteration may at any time be deemed necessary.

Digitized by Google

Apparatus Required.—A funnel 2 inches across (*d*) a cylindrical measure divided into grains (*e*), see Fig. 153.

Mode of Operation.—About 300 to 400 grains of dynamite (*b*) finely divided are placed into the funnel, which has previously been loosely plugged by some freshly ignited asbestos (*a*).

The surface is smoothed by means of a flat-headed glass



FIG. 152.



FIG. 153.

SIR FREDERICK ABEL'S HEAT TEST APPARATUS.

rod or stopper, and some clean washed and dried Kieselguhr (*c*) is spread over it to the depth of about $\frac{1}{8}$ inch.

Water is next carefully dropped from a wash bottle upon this Kieselguhr, and when the first portion has been soaked up, more is added; this is repeated until sufficient nitro-glycerine has been collected in the graduated measure (*e*) below.

If any water should have passed through with the nitro-glycerine, it should be removed with a piece of blotting-paper, and the nitro-glycerine, if necessary, filtered through a dry paper filter.

Digitized by Google

Application of the Test.—The thermometer is fixed so as to be inserted through the lid of the water bath described at p. 351, into the water (which is to be steadily maintained at a temperature of 160° Fahr.*) to a depth of $2\frac{3}{4}$ inches. Fifty grains of nitro-glycerine, to be tested, are weighed out into a test-tube in such a way as not to soil the sides of the tube. A test-paper is fixed on the hook of the glass rod so that when inserted into the tube it will be in a vertical position. A sufficient amount of a mixture of half distilled water and half glycerine to moisten the upper half of the paper is now applied to the upper edge of the test-paper, by means of a camel's-hair pencil, the cork carrying the rod and paper is fixed into the test-tube, and the position of the paper adjusted so that its lower edge is about half-way down the tube; the latter is then inserted through one of the perforations of the cover, to such a depth that the lower margin of the moistened part of the paper is about $\frac{5}{8}$ of an inch above the surface of the cover. The test is complete when the faint brown line which after a time makes its appearance at the line of boundary between the dry and moist parts of the paper equals in tint the brown line of the standard tint paper.

The nitro-glycerine under examination will not be considered as *thoroughly purified* within the terms of the licence, unless the time necessary to produce the standard tint as above described IS AT LEAST 15 MINUTES.

B.—Blasting Gelatine, Gelatine Dynamite, and Analogous Preparations (see also p. 361).

Fifty grains of blasting gelatine are to be intimately incorporated with 100 grains of French chalk. [This may be readily effected by carefully working the two materials together with a wooden pestle in a wooden mortar. The French chalk should be of good commercial quality, and, after being carefully washed with distilled water and dried in a water oven, it should be exposed under a bell jar to moist air until it has taken up about 0·5 per cent. of moisture. [It should then be

* For explosives supplied for Her Majesty's Military and Naval Services, the temperature is fixed by the War Office at 180°.

Digitized by Google

bottled for use; and with ordinary care the limits of 0·5 per cent. can be maintained in keeping.] The mixture is to be gradually introduced into a test-tube of the dimensions recommended above for the dynamite heat test, with the aid of gentle tapping upon the table, between the introduction of successive portions of the mixture into the tube, so that when the tube contains all the mixture it shall be filled to the extent of $1\frac{3}{4}$ inch of its height. The test-paper is then to be inserted, and the heat is to be applied in the manner prescribed above for the dynamite heat test, and the sample tested is to withstand exposure to 160° Fahr. for a period of ten minutes, before producing a discolouration of the test-papers corresponding in tint to the standard colour test which is employed for governing the results of the dynamite heat test.

N.B.—Non-gelatinised nitro-glycerine preparations, from which the nitro-glycerine cannot be expelled by water, are tested without any previous separation of the ingredients, the temperature being as above (160° *Fahr.*), *and the time being seven minutes.*

C.—Cordite and Ballistite.

1. *Apparatus required.*—The apparatus necessary for the application of the heat test to cordite is identical with that described above (see p. 351) for explosives of the nitro-compound class generally,* with the addition of a mill and a nest of sieves similar to those used at Waltham Abbey for preparing the cordite for testing (see instructions below).

2. *Preparation of the sample to be tested.*—Pieces half an inch long are cut from one end of every stick selected for the test; in the case of the thicker cordites, each piece so cut is further subdivided into about four portions. These cut pieces are then passed two or three times through the mill, the first portion of material which passes through being rejected on account of the possible presence of foreign matter from the mill. The ground material is put on the top sieve of the nest of sieves, and sifted. That portion which has passed through

* In the Waltham Abbey apparatus the cover (Fig. 151) has all the holes around the circumference instead of having one in the centre and three around the circumference.

Digitized by Google

the top sieve and been stopped by the second is taken for the test. After each sample has been ground, the mill must be taken to pieces and carefully cleaned.

3. *Application of the Test.*—The thermometer is fixed so as to be inserted through the lid of the water bath, described under 1, p. 351, so as to be immersed in the water to a depth of $2\frac{3}{4}$ inches. The water is maintained at a constant temperature of 180° Fahr. When this temperature is reached, 25 grains of the sifted cordite are put into one of the test-tubes, and collected at the bottom by gentle tapping. A test-paper is fixed on to the hook of the glass rod, so that when inserted into the tube it will be in a vertical position. A mixture of equal parts of distilled water and pure glycerine (Price's) is now applied to the upper edge of the test-paper by means of a camel's-hair pencil, in sufficient amount to moisten the upper half; the stopper carrying the rod and paper is fixed into the test-tube and the position of the paper adjusted so that its lower edge is about half-way down the tube; the latter is then inserted through one of the perforations of the cover to the same depth as the thermometer. The lower margin of the moistened part of the paper should then be about five-eighths of an inch above the surface of the cover. The test is completed when the faint brown line, which after a time makes its appearance at the margin between the wet and dry portions of the test-paper, equals in depth of tint the brown line drawn on the standard tint paper.

4. The time which elapses between the insertion of the test-tube and the completion of the test must not be less than fifteen minutes.

N.B.—In the case of ballistite the treatment is the same, except that when it is in a very finely granulated condition it need not be cut up.

II.—Testing Gun-cotton, Schultze Gunpowder, E.C. Powder, and other Explosives of the 2nd Division of the Nitro-compound Class.

A.—Gun-cotton, Tonite, &c. &c.

Sufficient material to serve for two or more tests is removed

Digitized by Google

from the centre of the cartridge by gentle scraping, and, if necessary, further reduced by rubbing between the fingers.

The fine powder thus produced is spread out in a thin layer upon a paper tray 6 inches by $4\frac{1}{2}$ inches, which is then placed inside a water oven, kept, as nearly as possible, at 120° Fahr.

The wire gauze shelves in the oven should be about 3 inches apart. The sample is allowed to remain at rest for fifteen minutes in the oven, the door of which is left wide open.

After the lapse of fifteen minutes the tray is removed and exposed to the air of the room for two hours, the sample being at some point within that time rubbed upon the tray with the hand, in order to reduce it to a fine and uniform state of division.

Application of the Test.—The cover of the water bath is fitted with the gas regulator which is inserted through the centre hole (No. 4). The thermometer is fixed into hole No. 3. The water in the bath is then heated to 170° Fahr., and the regulator set to maintain that temperature.

Twenty grains of the sample to be tested are weighed out, placed in the test-tube, and gently pressed down until the specimen occupies a space of as nearly as possible $1\frac{5}{16}$ inch in a test-tube of the dimensions specified.

A test-paper is affixed to the hook of the glass rod or tube, and moistened by touching the upper edge with a drop of distilled water containing 50 per cent. of Price's glycerine. The quantity of liquid used must be only sufficient to moisten about half of the paper.

The cork carrying the rod and test-paper is then fixed into the test-tube, and the latter inserted into the bath to a depth of $2\frac{1}{2}$ inches, measured from the cover, the regulator and thermometer being inserted to the same depth. The test-paper is to be kept near the top of the test-tube, but clear of the cork, until the tube has been immersed for about five minutes.

A ring of moisture will about this time be deposited upon the sides of the test-tube a little above the cover of the bath; the glass rod must then be lowered until the lower margin of the moistened part of the paper is on a level with the

Digitized by Google

bottom of the ring of moisture in the tube; the paper is now closely watched.

The test is complete when a very faint brown colouration makes its appearance at the line of boundary between the dry and moist parts of the paper.

The interval of time between the first insertion of the tube containing the sample of gun-cotton in the water at 170° and the first appearance of discolouration on the paper constitutes the test, and this interval of time must be *not less* than ten minutes, or the sample will not be accepted as properly purified.

B.—Gelatinised Gun-cotton Preparations.*

Twenty-five grains introduced into test-tube * of the dimensions prescribed for the dynamite heat test; then proceed as for blasting gelatine, &c., taking the temperature at 180° Fahr., and the time as fifteen minutes.

C.—Schultze Powder, E.C. Powder, Collodion Cotton, &c. &c.

Sufficient of the sample, without further mechanical division, is dried in the oven as above, and then exposed for two hours to the air. The test as directed above for compressed gun-cotton, &c., is then applied, the minimum duration of test being the same, viz. ten minutes.

D.—Picric Acid.

(1) The material shall contain not more than 0·3 part of mineral or non-combustible matter in 100 parts by weight of the material dried at 160° Fahr.

(2) One hundred parts of the dry material shall not contain more than 0·3 part of *total* (free and combined) sulphuric acid, of which not more than 0·1 part shall be *free* sulphuric acid.

(3) Twenty grains of the material shall stand the heat test as laid down for dynamite (see *ante*, p. 354) for not less than fifteen minutes.

* If in a compressed form, it should be broken up in the same manner as cordite and ballistite.

Digitized by Google

E.—Ammonite, Bellite, Roburite, and Explosives of Similar Composition.

These are required to stand the same heat test as gun-cotton (see *ante*, p. 358).

III.—Testing Chlorate Mixtures.

No tests have yet been laid down, as at present there are no authorised explosives of this class, but in the event of any being authorised, it would be necessary to require that they should satisfy the heat tests laid down for gun-cotton, and from time to time the degree of sensitiveness to percussion or friction (especially a glancing blow) should be observed.

V. D. MAJENDIE, Colonel,
H.M. Chief Inspector of Explosives.

Home Office, Whitehall, S.W. 1st July, 1895.

APPENDIX.

Exudation and Liquefaction Test for Blasting Gelatine, Gelatine Dynamite, and Analogous Preparations.

Test for Liquefaction.—A cylinder of blasting gelatine is to be cut from the cartridge to be tested, the length of the cylinder to be about equal to its diameter and the ends being cut flat.

The cylinder is to be placed on end on a flat surface without any wrapper, and secured by a pin passing vertically through its centre.

In this condition the cylinder is to be exposed for 144 consecutive hours (six days and nights) to a temperature ranging from 85° to 90° Fahr. (inclusive), and during such exposure the cylinder shall not diminish in height by more than one-fourth of its original height, and the upper cut surface shall retain its flatness and the sharpness of its edge.

Note.—If the blasting gelatine and the gelatine dynamite to be tested be not made up in a cylindrical form, the above test is to be applied with the necessary modifications.

Test for Liability to Exudation.—There shall be no separation from the general mass of the blasting gelatine or gelatine dynamite of a substance of less consistency than the bulk of the remaining portion of the materials under any conditions of storage, transport, or use, or when the material is subjected three times in succession to alternate freezing and thawing, or when subjected to the liquefaction test hereinbefore described.

Digitized by Google

APPENDIX C.

APPLICATIONS FOR AUTHORISATION OF EXPLOSIVES.—INSTRUCTIONS ISSUED BY THE HOME OFFICE.

HOME OFFICE,
WHITEHALL, S.W.

Memo.

EXPLOSIVES ACT, 1875.

(38 Vict. cap. 17.)

When an inventor desires a new explosive to be placed on the list of "Authorised Explosives," with a view to its being ultimately licensed for manufacture or importation, the steps to be taken are as follows:—

(*a*) The inventor (or his agent) must write stating (confidentially if preferred) the exact composition of the explosive he proposes to submit,* and the name by which it is to be distinguished.

This done, the applicant will be informed as to the amount of fee payable for the examination of the same under the scale of fees laid down by the Secretary of State. This fee will then have to be deposited at the Home Office, and will *not* be returned whether the result of the examination is or is not favourable to the introduction of the explosive.

(*b*) The inventor will then be asked to submit samples (the

* A copy of the Patent Specification should be sent where practicable.

Digitized by Google

required amount being stated), and when he reports them ready a special permit for their conveyance will be sent to him.*

(*c*) The general result of the examination will be communicated to the inventor. If it is found that the explosive is likely to be reasonably safe under ordinary conditions of manufacture, transport, and use, and especially that it is not too sensitive to friction or percussion, or a combination of these, an application for a license to manufacture or import the same, will be entertained.

If, however, the explosive fails to comply with the above conditions, it will not be placed on the list of Authorised Explosives.

V. D. MAJENDIE, COLONEL,
Chief Inspector of Explosives

* When the samples have to be imported from abroad, an Importation License will be required.

Digitized by Google

APPENDIX D.

THE EXPLOSIVES ACT, 1875.

(38 Vict. c. 17.)

In the following abstract of this enactment, either the substance or (in many cases) the full text is given of those portions of the Act which it will be useful for manufacturers, vendors, and users of high explosives, or importers or carriers of those substances, to have at hand for reference.

The Act—which is intituled, "An Act to amend the Law with respect to manufacturing, keeping, selling, carrying, and importing Gunpowder, Nitro-glycerine, and other explosive substances"—was passed 14th June, 1875, and came into operation on 1st January, 1876. There is no occasion to notice here those sections of the Act which made temporary provision concerning factories or stores for explosives existing when the Act was passed and authorised under previous Acts; and the provisions of the Act (Part I.) which relate to gunpowder will be set out here in those cases only in which the same provisions are subsequently applied by the Act (Part II.) to high explosives.

In many of its provisions, the requirements of the Act are not easily followed, but on this point the remarks of *Sir Frederick Abel* will commend themselves:—"It can hardly be doubted that the somewhat complicated machinery of the Act, found necessary in the first instance in order to attain an efficient control over the making, carriage, keeping, &c., of all explosive substances in their great variety of forms and applications, from barrels of powder and ship-loads and stores of dynamite, ammunition, and detonators, to drawing-room fireworks, sub-

Digitized by Google

stitutes for pigeon-shooting, and toy crackers, will in due course be much simplified. There can be no doubt that the action of manufacturers and vendors themselves will importantly contribute (and has, indeed, already to some extent contributed) to such simplification, not by their raising difficulties and entertaining or conniving at attempts of evasion, but by their ready adoption of obviously wise precautions and improvements, and by the systematic exercise of care and vigilance within their individual spheres of influence."

Definition of Explosive.

In the Act the term "explosive" is defined to mean gunpowder, nitro-glycerine, dynamite, gun-cotton, blasting powders, fulminate of mercury or of other metals, coloured fires, and "every other substance, whether similar to those above mentioned or not, used or manufactured with a view to produce a practical effect by explosion or a pyrotechnic effect"; and it also includes fog-signals, fireworks, fuzes, rockets, percussion caps, detonators, cartridges, ammunition of all descriptions, and "every adaptation or preparation of an explosive as above defined" (s. 3).

Scope of the Act.

By the Act, various powers for the control of the manufacture of explosives, and of all trafficking therein, are vested in (1) the Secretary of State (*i.e.*, in practice, the Home Secretary), who is authorised to appoint Government Inspectors of Explosives; (2) in the Local Authorities defined by the Act; and (3) in Harbour Authorities. For the effective administration of the Act, large powers of search and inquiry are given to the Government Inspectors, and (in a lesser degree) to officers of Local Authorities. Breaches of law under the Act—whether of its express provisions or of rules or bye-laws framed under it—render the offenders liable to heavy and summary penalties, and these will be found mentioned in the following pages in every case specified in the Act. Where exception may be

Digitized by Google

taken by the occupier of premises licensed under the Act to the requisitions made by a Government Inspector, provision is made by the Act for a reference of the matter in dispute to arbitration. Special provision is also made for official inquiry into accidents occurring with explosives, not only in a factory, magazine, or store licensed under the Act, but on any "carriage, ship, or boat" used for conveying explosives; and special regulations are required to be observed at coroners' inquests on deaths resulting from accidents with explosives.

Local Authorities.

The Local Authorities for the purposes of the Act are—

In England (s. 67),

(1.) In the City of London, the court of the Lord Mayor and Aldermen;

(2.) In the Metropolis outside the City of London, the Metropolitan Board of Works*; and

(3.) In any borough not assessed to the county rate by the county justices, the Mayor, Aldermen, and Burgesses acting by the Council; but

(4.) In any harbour within the jurisdiction of a harbour authority, whether situate or not within the jurisdiction of any local authority before mentioned, the Harbour Authority, to the exclusion of any other local authority; and

(5.) In any place in which there is no local authority as above the Justices in petty sessions assembled.*

By s. 68 the Secretary of State is empowered to declare the Council of a borough assessed to the county rate, and

* By the Local Government Act, 1888, the powers, duties, and liabilities of the Metropolitan Board of Works were transferred to the London County Council (51 & 52 Vict. c. 41, ss. 40–45); and by the same Act (s. 7) the business of county justices as Local Authorities under the Explosives Act was transferred to County Councils.

Digitized by Google

the Improvement Commissioners of a district, to be Local Authorities (but not for a harbour) under the Act.

In Scotland (s. 110),

(1.) In any borough the Magistrates and Town Council;
(2.) In any harbour within the jurisdiction of a harbour authority, whether situate or not within the jurisdiction of any local authority for a borough, the Harbour Authority, to the exclusion of any other local authority; and
(3.) In any place other than a borough or harbour the County Justices.

But by s. 115, the Secretary of State is empowered to declare the Police Commissioners of a burgh to be the Local Authority in certain cases.

In Ireland (s. 116),

(1.) In the City of Dublin, the Lord Mayor, Aldermen, and Burgesses acting by the Town Council; and
(2.) In an urban sanitary district, the Urban Sanitary Authority; but
(3.) In any harbour within the jurisdiction of a harbour authority, whether situate or not within the jurisdiction of any local authority above mentioned, the Harbour Authority, to the exclusion of any other local authority;
(4.) In any place in which there is no local authority as above defined, the Justices in petty sessions.

The expression Harbour Authority in the Act includes (s. 107) any person or body of persons claiming to be proprietor or proprietors of or intrusted with the duty or power of maintaining or regulating any harbour, and any port, haven, and estuary, or intrusted with the duty of conserving the navigation of any tidal water; and any such harbour, port, haven, estuary, tidal water, and any wharf, dock, pier, jetty,

Digitized by Google

and work, and other area, whether land or water, over which the Harbour Authority have control or exercise powers, are included in the Act in the expression "harbour."

PART I.—GUNPOWDER.

Part I. of the Act comprises the sections relating to gunpowder, and contains the following provisions, these being made applicable (with certain modifications and additions) to other explosives also in subsequent sections (Part II.) of the Act :—

Manufacture and Keeping of Gunpowder.

The manufacture of gunpowder shall not, nor shall any process of such manufacture, be carried on except at a factory for gunpowder either lawfully existing or licensed under the Act; and any person who carries on any such process of manufacture, except as allowed by the Act, shall be deemed to manufacture gunpowder at an unauthorised place.

Where gunpowder is manufactured at an unauthorised place, (1) all or any part of the gunpowder or ingredients of gunpowder found in or about such place may be forfeited, and the person so manufacturing shall be liable to a penalty of 100*l.* for every day during which he so manufactures (s. 4).

Gunpowder, unless kept for private use and not for sale to an amount not exceeding thirty pounds, or in the keeping of a carrier for the purpose of conveyance in accordance with the provisions of the Act, shall not be kept at any place except in the factory in which it is manufactured; or (2) in a magazine or store either lawfully existing or licensed under the Act, or (3) in premises registered under the Act. Where gunpowder is kept in an unauthorised place, all or any part of the gunpowder found in such place may be forfeited; and the occupier of such place, and also the owner of, or other person guilty of keeping the gunpowder, shall each be liable to a penalty of 2*s.* for every pound of gunpowder so kept (s. 5).

Digitized by Google

Licensing of Factories and Magazines.

A new factory or magazine for gunpowder shall not be established except on the site and in the manner specified in a license to be granted by the Secretary of State, with the assent of the Local Authority. Detailed directions are given in the Act for obtaining such license and the requisite assent of the Local Authority (ss. 6, 7, 8).

Regulation of Factories and Magazines.

In every gunpowder factory and magazine—

(1.) The factory or magazine, or any part thereof, shall not be used for any purpose not in accordance with the license; and

(2.) The terms of the license shall be duly observed, and the manufacture or keeping or any process in or work connected with the manufacture or keeping of gunpowder shall not be carried on except in accordance with those terms; and

(3.) The factory or magazine and every part thereof shall be maintained in accordance with the license; and any material alteration in the factory or magazine by enlarging or adding to the site, or by externally enlarging or adding to any building, or by altering any mound otherwise than by enlargement, or by making any new work, shall not be made except in pursuance of an amending license granted under the Act.

In the event of any breach (by any act or default) of this section, the gunpowder or ingredients thereof in respect to which, or being in any building or machine in respect to which, the offence was committed, may be forfeited; and the occupier shall be liable to a penalty not exceeding in the case of the first offence 50*l.*, and in the case of a second or any subsequent offence 100*l.*, and in addition 50*l.* for every day during which such breach continues (s. 9).

The occupier of a factory shall not be deemed guilty of a

Digitized by Google

breach of this section for using in a case of emergency, or temporarily, one building or part of a building in which any process of the manufacture is, under the terms of the license, carried on, for another process of the manufacture, if he do not carry on in such building or part more than one process at the same time, and if the quantity of gunpowder or ingredients thereof in such building or part do not exceed the quantity allowed to be therein, or any less quantity allowed to be in the building or part of a building in which such other process is usually carried on; and if upon such use being continued after the lapse of twenty-eight days from the first beginning of such use he send notice to a Government inspector, and the inspector do not require its discontinuance (s. 9).

In the event of any breach (by any act or default) in any factory or magazine of the general rules for gunpowder factories prescribed by the Act,* all or any part of the gunpowder or ingredients thereof in respect to which, or being in any building or machine in respect to which, the offence was committed, may be forfeited; and the occupier shall be liable to a penalty not exceeding 10*l.*, and in addition (on a second offence) 10*l.* for every day during which such breach continues (s. 10).

Every occupier of a gunpowder factory or magazine shall, with the sanction of the Secretary of State, make special rules for the regulation of the persons employed therein, and there may be annexed to any breach of such special rules penalties not exceeding forty shillings for each offence (s. 11).

Supplemental as to Factories and Magazines.

Where the occupier of a gunpowder factory or magazine desires that any alteration should be made in the terms of his license, or any material alteration made in the factory or magazine by enlarging or adding to the site or by externally enlarging or adding to any building, or by altering any mound

* The "general rules" of sect. 10 are omitted here, as not concerning factories for high explosives (see *post*, p. 378).

Digitized by Google

otherwise than by enlargement, or by making any new work, he may apply for an amending license. If he satisfy the Secretary of State that the alteration may be properly permitted without increased risk, the Secretary of State may grant the amending license of his own authority, but otherwise the application will be dealt with as an application for a new license (s. 12).

A gunpowder factory or magazine license shall not be avoided by any change in the occupier of the factory or magazine; but notice of the name, address, and calling of the new occupier shall be sent to the Secretary of State within three months after the change, and in default such new occupier shall be liable to a penalty not exceeding 20*s.* for every week during which such default continues (s. 13).

Stores for Gunpowder.

Any person may apply to the Local Authority for a license for a gunpowder store, and if the proposed site, construction of the store, and amount of gunpowder to be stored therein are in accordance with the Order in Council (see s. 16), the license is to be granted on payment of a fee not exceeding 5*s.* (s. 15).

Her Majesty may from time to time, by Order in Council, regulate the construction and materials and fittings of gunpowder stores, prescribe the buildings and works from which gunpowder stores are to be separated, and the distances by which they are to be separated; and prescribe the maximum amount of gunpowder, not exceeding two tons, to be kept in stores, graduated according to their construction and situation and their distance from the said buildings and works (s. 16).

In the event of any breach (by any act or default) of the general rules prescribed by the Act for gunpowder stores, all or any part of the gunpowder in respect to which or being in the store when the offence was committed may be forfeited, and the occupier shall be liable to a penalty not exceeding 10*l.*, and in addition (on a second offence) 10*l.* for every day during which such breach continues (s. 17).

Digitized by Google

A store license shall be valid only for the person named in it, and shall be annually renewed by the Local Authority, at a fee not exceeding 1*s.*, and unless so renewed shall expire (s. 18).

Every occupier of a gunpowder store may, with the sanction of the Secretary of State, make special rules for the regulation of the persons employed therein, and there may be annexed to any breach of such special rules penalties not exceeding 40*s.* for each offence (s. 19).

Registered Premises.

A person desirous of registering with the Local Authority any premises for the keeping of gunpowder shall register his name and calling, as well as the premises, in such manner and on payment of such fee, not exceeding 1*s.*, as may be directed by the Local Authority, such registration to be annually renewed at a fee not exceeding 1*s.*

In the event of any breach (by any act or default) of the general rules prescribed by the Act for registered premises, all or any part of the gunpowder in respect to which, or being in any house, building, place, safe, or receptacle in respect to which, the offence was committed may be forfeited, and the occupier shall be liable to a penalty not exceeding 2*s.* for every pound of gunpowder in respect of which or being on the premises in which the offence was committed (s. 22).

Supplemental Provisions.

The occupier of every factory, magazine, store, and registered premises for gunpowder, and every person employed in or about the same, shall take all due precaution for the prevention of accidents by fire or explosion, and for preventing unauthorised persons having access thereto or to the gunpowder therein, and shall abstain from any act whatever which tends to cause fire or explosion and is not reasonably necessary for the work therein; and any breach (by any act or default) of this section shall be deemed to be a breach of general rules (s. 23).

Digitized by Google

The Local Authority shall cause registers to be kept of all store licenses granted by and of all premises registered with them under the Act; and a ratepayer within the area of the Local Authority, or a licensee or person registered under the Act, upon payment of a fee of one shilling, and a Government inspector, or an officer appointed by any Local Authority for the purposes of the Act, or an officer of police, without payment, shall be entitled at all reasonable times to inspect and take extracts from any such registers (s. 28).

If the occupier of a store or registered premises dies or becomes bankrupt, or has his affairs liquidated by arrangement, or becomes mentally incapable or otherwise disabled, the person carrying on the business of such occupier shall not be liable to any penalty for acting under the license or registration during such reasonable time as may be necessary to allow him to obtain a fresh license or registration (s. 29).

Sale of Gunpowder.

Gunpowder shall not be hawked, sold, or exposed for sale upon any highway, street, public thoroughfare, or public place; and (1) any person hawking, selling, or exposing gunpowder for sale shall be liable to a penalty not exceeding 40*s.*, and (2) all or any part of the gunpowder so hawked or exposed for sale, or found in the possession of any person convicted hereunder may be forfeited (s. 30).

Gunpowder shall not be sold to any child apparently under the age of thirteen years; and any person selling gunpowder in contravention of this section shall be liable to a penalty not exceeding 5*l.* (s. 31).

All gunpowder exceeding one pound in weight, when publicly exposed for sale or sold, shall be in a substantial case, bag, canister, or other receptacle made and closed so as to prevent the gunpowder from escaping, and to such outermost receptacle shall be affixed the word "gunpowder" in conspicuous characters by means of a brand or label, or other mark; and if any gunpowder is sold or exposed for sale in

Digitized by Google

contravention of this section the person offending shall be liable to a penalty of 40*s.*, and all or any part of the gunpowder so exposed for sale may be forfeited (s. 32).

Conveyance of Gunpowder.

The following general rules shall be observed with respect to the packing of gunpowder for conveyance:

(1.) The gunpowder, if not exceeding five pounds in amount, shall be contained in a substantial case, bag, canister, or other receptacle, made and closed so as to prevent the gunpowder from escaping; and

(2.) The gunpowder, if exceeding five pounds in amount, shall be contained either in a single package or a double package. A single package shall be a box, barrel, or case of such strength, construction, and character as may be for the time being approved by the Government inspector as being of such strength, construction, and character that it will not be broken or accidentally opened, or become defective or insecure whilst being conveyed, and will not allow the gunpowder to escape. If the gunpowder is packed in a double package the inner package shall be a substantial case, bag, canister, or other receptacle made and closed so as to prevent the gunpowder from escaping, and the outer package shall be a box, barrel, or case of wood or metal or other solid material, and shall be of such strength, construction, and character that it will not be broken or accidentally opened, or become defective or insecure whilst being conveyed, and will not allow the gunpowder to escape; and

(3.) The interior of every package, whether single or double, shall be kept free from grit and otherwise clean; and

(4.) Every package, whether single or double, when

Digitized by Google

actually used for the package of gunpowder, shall not be used for any other purpose; and

(5.) There shall not be any iron or steel in the construction of any such single package or inner or outer package, unless the same is effectually covered with tin, zinc, or other material; and

(6.) The amount of gunpowder in any single package, or if there is a double package in any one outer package, shall not exceed one hundred pounds, except with the consent of and under conditions approved by a Government inspector; and

(7.) On the outermost package there shall be affixed the word "gunpowder" in conspicuous characters by means of a brand or securely attached label or other mark.

In the event of any breach (by any act or default) of any of the above-mentioned general rules, the gunpowder in respect of which the breach is committed may be forfeited, and the person guilty of such breach shall be liable to a penalty not exceeding 20*l.*

The general rules contained in this section may from time to time be altered by the Secretary of State (s. 33).

Bye-Laws.

Every Harbour Authority shall, with the sanction of the Board of Trade, make bye-laws for regulating the conveyance, loading, and unloading of gunpowder within its jurisdiction.

For breaches of such bye-laws, penalties are authorised by the Act, not exceeding 20*l.* for each offence, and 10*l.* for each day during which the offence continues, besides forfeiture of all or any part of the gunpowder in respect of which, or found in the ship, boat, or carriage in respect of which, the breach of bye-law has taken place (s. 34).

Any person resisting a harbour-master or officer acting under such bye-laws shall be liable to the same penalties as a

Digitized by Google

person for obstructing the harbour-master in the execution of his duty (s. 34).

On any part of the coast of the United Kingdom or in any tidal water for which there is no harbour authority, the Board of Trade are empowered by the Act to make bye-laws for that part or water as if it were a harbour and they were the harbour authority; and they may by such bye-laws define the area within which they are to be observed, and the officers by whom they are to be enforced (*ibid*).

Every railway or canal company over whose railway or canal any gunpowder is to be carried, shall, with the sanction of the Board of Trade, make bye-laws for regulating the conveyance, loading, and unloading of such gunpowder (s. 35).

Penalties for any breach of any such bye-laws may be imposed, and may be graduated according to the gravity of the offence, and according as it may be a first, second, or other subsequent offence, that is to say, pecuniary penalties not exceeding 20*l.* for each offence, and 10*l.* for each day during which the offence continues, besides forfeiture of all or any part of the gunpowder in respect of which, or being in the carriage, ship, or boat or train of carriages, ships, or boats in respect of which, the breach of bye-law has taken place (*ibid*).

The occupier of every wharf or dock on or in which gunpowder is loaded or unloaded (if such loading or unloading is not otherwise subject to any bye-laws under this Act) may, and if so required by the Secretary of State shall, from time to time, with the sanction of the Secretary of State, make bye-laws for regulating the loading and unloading of gunpowder on or in such wharf or dock, and in particular for declaring or regulating all or any of the matters which can be declared or regulated in the case of any wharf or dock within the jurisdiction of a harbour authority by bye-laws made by such authority in pursuance of this Act; and penalties may be annexed to breaches of such bye-laws, as in the case of bye-laws made under section 35 (s. 36).

The Secretary of State is empowered to make bye-laws for regulating the conveyance, loading, and unloading of gun-

Digitized by Google

powder by land or otherwise, in any case in which bye-laws made under any other provision of the Act do not apply; and penalties may be annexed to any breach of any such bye-laws as in the case of bye-laws made under the thirty-fifth section (s. 37).

Any recommendation to Her Majesty in Council, any general rules with respect to packing, and any bye-laws which is or are proposed to be made under the Act by a Secretary of State or the Board of Trade shall, before being so made, be published in such manner as the Secretary of State or the Board of Trade may direct, and the bye-laws framed by any Railway Company, Canal Company, or Harbour Authority under the Act shall, before being sanctioned by the Board of Trade, be likewise published in such manner as the Board may direct (s. 38).

PART II.—EXPLOSIVES OTHER THAN GUNPOWDER.

Part II. of the Act relates to explosives other than gunpowder, and by s. 39 it is declared that, subject to the provisions hereafter in this part of the Act contained, Part I. of the Act relating to gunpowder shall apply to every other description of explosive, in like manner as if those provisions were re-enacted with the substitution of that description of explosive for gunpowder.

Modification of Part I. as applied to Explosives other than Gunpowder.

In the case of explosives other than gunpowder, the following modifications and additions are to be made in and to Part I. of the Act:

(1.) The draft license for a factory or magazine submitted by an applicant to the Secretary of State shall specify such particulars as the Secretary of State may require;

Digitized by Google

(2.) The prescribed general rules [*i.e.*, rules prescribed by an Order in Council] shall be substituted for the general rules in Part I. of the Act relating to factories, magazines, stores, and registered premises respectively; but no such general rule shall require the removal of any building or work in use at the date of the Order in Council by which such rule is made;

(3.) The Secretary of State may from time to time alter the general rules relating to packing contained in Part I. of the Act for the purpose of adapting the same to the packing of any explosive other than gunpowder; and

(4.) For the maximum amount limited by the Act to be kept for private use and not for sale, or in a store, and for the minimum amount limited by the Act to be exposed for sale or sold otherwise than in a substantial case, box, canister, or other receptacle as therein mentioned, there shall be substituted in the case of explosives other than gunpowder the following amounts; namely, (*a*) where such explosive consists of safety cartridges made with gunpowder, an amount containing not more than five times the maximum or minimum amount of gunpowder, as the case may be, above mentioned; and (*b*) in the case of any other explosive, the prescribed amount; and

(5.) Two or more descriptions of explosives shall not be kept in the same store or registered premises, except such descriptions as may be prescribed in that behalf; and, when so kept, shall be kept subject to the prescribed conditions and restrictions; and

(6.) Where any explosive, other than gunpowder, is allowed to be kept in the same store or registered premises with gunpowder, the maximum amount of gunpowder to be kept therein shall be the prescribed amount in lieu of the amount fixed by Part I. of the Act; and

Digitized by Google

(7.) Where any explosive, other than gunpowder, is allowed to be kept in the same magazine, store, or registered premises with gunpowder, the prescribed general rules shall be observed instead of the general rules set out in the Act; and

(8.) There shall be on the outermost package containing the explosive in lieu of the word "gunpowder" the name of the explosive, with the addition of the word "explosive," and if such name is materially false the person selling or exposing for sale such explosive, and also the owner of the explosive, shall be liable to a penalty not exceeding 50*l.*

(9.) With respect to the importation from any place out of the United Kingdom of either dynamite or gun-cotton, or any explosive (other than gunpowder, cartridges made with gunpowder, percussion caps, fireworks, and any prescribed explosive), the following provisions shall have effect: (*a.*) The owner and master of any ship having on board any such explosive shall not permit the same to be unloaded and delivered to any person who does not hold an importation license from the Secretary of State, and any transhipment shall be deemed to be delivery; (*b*) the Secretary of State may grant an importation license for any such explosive, and may annex thereto such provisions and restrictions as he may think fit, for the protection of the public from danger; (*c*) the license shall be of such duration as the Secretary of State may fix, and shall be available only for the person named in the license; (*d*) in the event of any breach by any act or default of the provisions of this section with respect to the importation of an explosive, or of the provisions of any importation license, all or any part of the explosive with respect to which such breach is committed, or being in any ship or boat in connexion with which such breach is committed, may be forfeited, and the

Digitized by Google

owner and master of such ship or boat, and the licensee or person to whom the explosive is delivered, shall each be liable to a penalty not exceeding 100*l.*, and to a further penalty not exceeding 2*s.* for every pound of such explosive; and (*e*) the Commissioners of Customs and their officers shall have the same power with respect to any such explosive, and the ship containing the same, as they have for the time being with respect to any article on the importation of which restrictions are for the time being imposed by law (s. 40).

Nothing in the Act shall apply to the filling or conveying, for private use and not for sale, of any safety cartridges to the amount allowed by the Act to be kept for private use (s. 41).

Sect. 29 of the Passengers Act, 1855,* and sects. 23 to 27, both inclusive, of the Merchant Shipping Act, 1873,† shall apply to every explosive within the meaning of this Act in like manner as they apply to gunpowder (s. 42).

Specially dangerous Explosives.

Her Majesty from time to time, by Order in Council, may prohibit, either absolutely, or except in pursuance of a license of the Secretary of State under this Act, or may subject to conditions or restrictions the manufacture, keeping, importation from any place out of the United Kingdom, conveyance, and sale, or any of them, of any explosive which is of so dangerous a character that it is expedient for the public safety to make such Order; and any explosive manufactured or kept in contravention of any such Order shall be deemed to be manufactured or kept in an unauthorised place, and any explosive con-

* By which gunpowder is prohibited as cargo on a passenger ship.

† Imposing a penalty of 500*l.* on any person who sends by ship "dangerous goods" under a false description, and empowering the shipowner or master to throw such goods overboard, and declaring dangerous goods so sent liable to forfeiture.

Digitized by Google

veyed in contravention of any such Order shall be deemed to be conveyed in contravention of a bye-law under the Act.

If any explosive is imported or sold in contravention of any such Order, (1) all or any part of such explosive may be forfeited; (2) the owner or master of the ship in which it was imported shall be liable to a penalty not exceeding 10*s.* for every pound of such explosive brought in the ship; and (3) the person to whom it was delivered and the person selling the same shall be liable to a penalty not exceeding 10*s.* for every pound of such explosive delivered or sold or found in his possession.

The Commissioners of Customs and their officers shall have the same power with respect to any such explosive, and the ship containing the same, as they have for the time being with respect to any article prohibited by law to be imported (s. 43).

Provisions in favour of certain Manufacturers and Dealers.

The occupier of a factory for any explosive shall not be required to take out a factory license for making up on such factory the explosive made thereon into cartridges or charges for cannon or blasting not containing within themselves their own means of ignition; and the occupier of any magazine, store or registered premises for keeping any explosive may keep such explosive when so made up into cartridges or charges as if it were not so made up (s. 44).

The occupier of a factory for any explosive who manufactures a new form of explosive similar to the one specified in his license, shall not deemed to have manufactured the same in an unauthorised place if the manufacture be on a small scale, and exclusively for the purpose of trial and not for sale, and if he send notice thereof as soon as manufactured to the Secretary of State (s. 45).

The occupier of a magazine, store, or registered premises for any explosive shall not be required by the Act to take out a factory license by reason that in connexion with such magazine, store, or premises he fills for sale or otherwise any cartridge for

Digitized by Google

small arms with the said explosive, so that he observe the following regulations; namely,

(1.) There shall not be in the room in which such filling is being carried on more than five pounds of gunpowder, or the prescribed amount of any other explosive, except it is made up into safety cartridges; and

(2.) Any work unconnected with the making of the cartridges shall not be carried on in the room while such filling is being carried on; and

(3.) There shall not be in the room while such filling is being carried on any fire nor any artificial light, except a light of such construction, position, or character as not to cause any danger of fire or explosion; and

(4.) In the case of a magazine or store, the room in which the filling is carried on shall be detached from the magazine or store, but in the immediate neighbourhood thereof, and at such distance therefrom as may be specified in the case of a magazine by the license, and in the case of a store by an Order in Council relating to stores; and

(5.) The occupier shall give notice in the case of a magazine to the Secretary of State, and in the case of a store or registered premises to the local authority, that he intends to carry on such filling of cartridges.

In the case, however, of magazine or store for which a continuing certificate has been obtained the previous consent of the Secretary of State will be required.

The regulations in this section shall be deemed to be general rules under the Act, and the breach of them shall be punished accordingly (s. 46).

The occupier of any magazine or store for any explosive shall not be required by the Act to take out a factory license by reason that, in connexion with such magazine or store, he,

Digitized by Google

by filling cartridges, making charges, drying, sifting, fitting, or otherwise, adapts or prepares the said explosive for use exclusively in his mine or quarry, or in some excavation or work carried on by him or under his control, so that he observe the following regulations; namely,

(1.) There shall not be in the workshop in which such adaptation or preparation is carried on more than one hundred pounds of gunpowder or the prescribed amount of any other explosive; and

(2.) Any work unconnected with such adaptation or preparation shall not be carried on in the said workshop while such adaptation or preparation is being carried on; and

(3.) The said workshop shall be detached from the magazine or store, but in the immediate neighbourhood thereof, and at such distance therefrom as may be specified, in the case of a magazine by the license, and in the case of a store by an Order in Council relating to stores; and

(4.) An explosive of one description shall not be converted into an explosive of another description, and shall not be unmade or resolved into its ingredients; and

(5.) The occupier shall give notice in the case of a magazine to the Secretary of State, and in the case of a store to the local authority, that he intends to carry on such adaptation or preparation as is allowed by this section.

In the case, however, of a magazine or store for which a continuing certificate has been obtained, the previous consent of the Secretary of State will be required.

The regulations in this section shall be deemed to be general rules under the Act, and the breach of them shall be punished accordingly (s. 47).

Digitized by Google

Existing Factories, Magazines, and Stores.

In any continuing certificate for a lawfully existing factory or magazine for any explosive other than gunpowder, the following regulations are to form part of the terms of such certificate:

(1.) If the factory or magazine is for dynamite or any substance having nitro-glycerine as one of its component parts or ingredients, the conditions contained in the existing license, with such modifications (if any) as the Secretary of State may think necessary in order to bring the same into conformity with this Act, and also any limitation of time for the expiration of the license contained in the existing license, and also the existing power of the Secretary of State to revoke the license; and

(2.) In any other case, such terms as the Secretary of State may think expedient, having regard to the conditions (if any) contained in the license under which the factory or magazine is established; and such terms shall include any limitation of time contained in such license, but shall not require the removal of any lawfully existing building or work (s. 51).

PART III.—ADMINISTRATION OF LAW.

Government Inspectors of Explosives.

A Government inspector shall have power to make such examination and enquiry as may be necessary to ascertain whether the Act is complied with, and for that purpose (1) he may enter, inspect, and examine any factory, magazine, or store of any explosive, and every part thereof, at all times by day and night, but so as not to unnecessarily impede or obstruct the work in such factory, magazine, or store, and

Digitized by Google

may make inquiries as to the observance of the Act and all matters and things relating to the safety of the public or of the persons employed in or about such factory, magazine, or store; (2) he may enter, inspect, and examine any premises registered under this Act, and every part thereof, in which any explosive is kept, or is reasonably supposed by him to be kept, at all reasonable times by day; and (3) he may require the occupier of any factory, magazine, store, or premises which he is entitled, under this section, to enter, or a person employed by such occupier therein, to give him samples of any explosive or ingredients of an explosive therein, or of any substance therein, the keeping of which is restricted or regulated by the Act, or of any substance therein which the inspector believes to be an explosive, or such ingredients or substance.

The occupier of every such factory, magazine, store, and registered premises, his agents and servants, shall furnish the means required by the inspector as necessary for every such entry, inspection, examination, and inquiry.

Any person who obstructs an inspector in the execution of his duties under the Act shall be liable to a penalty of 100*l.* for each offence (s. 55).

If in any matter not expressly provided for by the Act, an inspector find any factory, magazine, or store for an explosive, or any part thereof, or any thing or practice therein or connected therewith, to be unnecessarily dangerous or defective, so as in his opinion to tend to endanger the public safety or the bodily safety of any person, such inspector may require the occupier of such factory, magazine, or store to remedy the same; and where the occupier objects to comply with the requisition he may require the matter to be referred to arbitration in manner provided by the Act (s. 56).

Accidents.

Whenever there occurs any accident by explosion or by fire in or about or in connexion with any factory, magazine, or

Digitized by Google

store, or any accident by explosion or by fire causing loss of life or personal injury in or about or in connexion with any registered premises, the occupier of such factory, magazine, store, or premises shall forthwith send or caused to be sent notice of such accident and of the loss of life or personal injury (if any) occasioned thereby to the Secretary of State. A notice of any accident of which notice is sent in pursuance of this section to a Government inspector need not be sent to any inspector or sub-inspector of factories or any inspector of mines.

Where in, about, or in connexion with any carriage, ship, or boat, either conveying an explosive, or on or from which an explosive is being loaded or unloaded, there occurs any accident by explosion or by fire causing loss of life or personal injury, or if the amount of explosive conveyed or being so loaded or unloaded exceeds in the case of gunpowder half a ton, and in the case of any other explosive the prescribed amount, any accident by explosion or by fire, the owner or master of such carriage, ship, or boat, and the owner of the explosive conveyed therein or being loaded or unloaded therefrom, or one of them, shall forthwith send or cause to be sent notice of such accident, and of the loss of life or personal injury, if any, occasioned thereby, to the Secretary of State.

Every such occupier, owner, or master as aforesaid who fails to comply with this section shall be liable to a penalty of 20*l.* (s. 63).

Where an accident by explosion or fire has occurred in, and wholly or partly destroyed a factory magazine, or any magazine or store, the factory magazine, magazine, or store shall not be reconstructed, and any further supply of an explosive shall not be put therein, except with the permission of the Secretary of State; and where an accident by explosion or fire in a factory has wholly or partly destroyed any building of such factory as to which a Government inspector has previously to the accident sent to the occupier a notice that the building is unduly near to some building or work outside the factory, such building shall be reconstructed only upon such site in the

Digitized by Google

factory and with such precautions as may seem reasonable to the Secretary of State; and where an accident by explosion or by fire in a factory has wholly or partly destroyed two or more buildings in such factory, not more than one of such buildings shall be reconstructed except with the permission of the Secretary of State; provided that this enactment shall not apply to any buildings in a lawfully existing factory, if either both or all such buildings are incorporating mills, or if as regards any other buildings a Government inspector has not previously to the accident sent to the occupier a notice that such buildings are unduly near to each other. The reconstruction of any building in contravention of this section shall be deemed to be a breach of the terms of the license, and shall be punished accordingly (s. 64).

Coroners' Inquests.

Where a coroner holds an inquest upon a body of any person whose death may have been caused by any accident of which notice is required by the Act to be given to the Secretary of State, or by the explosion of any explosive, the coroner is to adjourn such inquest unless a Government inspector, or some person on behalf of the Secretary of State, is present to watch the proceedings; but if such accident or explosion has not occasioned the death of more than one person, and the coroner has sent to the Secretary of State not less than forty-eight hours' notice of the time and place of holding the inquest, it shall not be imperative on him to adjourn such inquest if the majority of the jury think it unnecessary; and where evidence is given at an inquest at which no Government inspector or official is present, of any neglect as having caused or contributed to the explosion or accident, or of any defect in or about or in connexion with any factory, magazine, store, or registered premises, or any carriage, ship, or boat carrying an explosive, appearing to the coroner or jury to require a remedy, the coroner is to send to the Secretary of State notice in writing of such neglect or defect (s. 65).

Digitized by Google

Special Inquiries.

The Secretary of State may direct an inquiry to be made by a Government inspector into the cause of any accident which is caused by an explosion or fire either in connexion with any explosive, or of which notice is required by the Act to be given to the Secretary of State; and where it appears to the Secretary of State, either before or after the commencement of any such inquiry, that a more formal investigation of the accident, and of the causes and circumstances thereof, is expedient, the Secretary of State is empowered to direct such an investigation to be held by a court having all the powers of a court of summary jurisdiction hearing informations for offences against the Act, as well as the powers of a Government inspector under the Act, and the special powers of entry and inspection of premises, of summoning witnesses, and of calling for books, papers, and documents, which are given by the Act (s. 66).

Powers of Officer of Local Authority.

Any officer authorised by the local authority may, on producing, if demanded, either a copy of his authority purporting to be certified by the clerk or some member of the local authority, or some other sufficient evidence of his authority, require the occupier of any store (not being subject to the inspection under the Act of any Inspector of Mines) or any registered premises, or any small firework factory, to show him every or any place and all or any of the receptacles in which any explosive or ingredient of an explosive, or any substance the keeping of which is restricted or regulated by the Act, that is in his possession is kept, and to give him samples of such explosive, ingredient, or substance, or of any substance which the officer believes to be an explosive or such ingredient or substance.

Any occupier of a store or registered premises or a small firework factory who refuses to comply with any such requisition of an officer of the local authority, or to give him such assist-

Digitized by Google

ance as he may require for the purpose of this section, or who wilfully obstructs the local authority, or any officer of the local authority, in the execution of the Act, shall be liable to a penalty of 20*l.* (s. 69).

Local Authority may provide Carriages and Magazines.

Every harbour authority and canal company shall, in addition to any other powers they may have for the like purpose, have power to provide carriages, ships, and boats for the conveyance, loading, or unloading of an explosive within the jurisdiction of such authority or company, and may charge a reasonable sum fixed by a bye-law under the Act for the use of such carriage, ship or boat (s. 71).

General Power of Search.

Where any of the following officers—namely, any Government inspector, or any constable or any officer of the local authority, if such constable or officer is specially authorised either (*a*) by a warrant of a justice (which warrant such justice may grant upon reasonable ground being assigned on oath), or (*b*) (where it appears to a superintendent or other officer of police of equal or superior rank, or to a Government inspector, that the case is one of emergency and that the delay in obtaining a warrant would be likely to endanger life), by a written order from such superintendent, officer, or inspector,—has reasonable cause to believe that any offence has been or is being committed with respect to an explosive in any place (whether a building or not, or a carriage, boat, or ship), or that any explosive is in any such place in contravention of the Act, or that the provisions of the Act are not duly observed in any such place, such officer may, on producing, if demanded, in the case of a Government inspector a copy of his appointment, and in the case of any other officer his authority, enter at any time, and if needs be by force, and as well on Sunday as on other days, the said place, and every part thereof, and examine the same, and search for explosives therein, and take samples

Digitized by Google

of any explosive and ingredient of an explosive therein, and any substance reasonably supposed to be an explosive, or such ingredient which may be found therein.

Any person who, by himself or by others, fails to admit into any place occupied by or under the control of such person any officer demanding to enter in pursuance of this section, or in any way obstructs such officer in the execution of his duty under this section, shall be liable to a penalty of 50*l.*, and shall also be liable to forfeit all explosives, and ingredients thereof, which are at the time of the offence in his possession or under his control at the said place.

Where a constable or officer of the local authority specially authorised by written authority other than a warrant of a Justice of the Peace, enters and searches as above provided, a special report in writing of every act done by such constable or officer in pursuance of that authority, and of the grounds on which it is done, shall be forthwith sent by the person by whom or under whose authority it was done to the Secretary of State (s. 73).

Where any of the following officers—namely, any Government inspector, or any constable, or any officer of the local authority—has reasonable cause to believe that any explosive or ingredient of an explosive or substance found by him is liable to be forfeited under the Act, he may seize and detain the same until some Court of Summary Jurisdiction has determined whether the same is or is not so liable to be forfeited, and with respect thereto the following provisions shall have effect:

(1.) The officer seizing may either require the occupier of the place in which it was seized (whether a building or not, or a carriage, boat, or ship) to detain the same in such place or in any place under the control of such occupier, or may remove it in such manner and to such place as will in his opinion least endanger the public safety, and there detain it, and may, where the matter appears to him to be urgent

Digitized by Google

and fraught with serious public danger, and he is a Government inspector, or is authorised by an order from a Government inspector or a Justice of the Peace, or from a superintendent or other officer of police of equal or superior rank, cause the same to be destroyed or otherwise rendered harmless; but before destroying or rendering harmless the same he shall take and keep a sample thereof, and shall, if required, give a portion of the sample to the person owning the explosive, or having the same under his control at the time of the seizure; and any such occupier who, by himself or by others, fails to keep the same when he is required in pursuance of this section to detain it, and any such occupier or other person who, except with the authority of the officer seizing the same, or of a Government inspector, or in case of emergency for the purpose of preventing explosion or fire, removes, alters, or in any way tampers or deals with the same while so detained, shall be liable to a penalty not exceeding 50*l.*, and shall also be liable to forfeit all explosives, and ingredients thereof, which are at the time of the offence in his possession or under his control at the said place;

(2.) The proceedings before a Court of Summary Jurisdiction for determining whether the same is or is not liable to forfeiture shall be commenced as soon as practicable after the seizure; and

(3.) The receptacles containing the same may be seized, detained, and removed in like manner as the contents thereof; and

(4.) The officer seizing the same may use for the purposes of the removal and detention thereof any ship, boat, or carriage in which the same was seized, and any tug, tender, engine, tackle, beasts, and accoutrements belonging to or drawing or provided for drawing such

Digitized by Google

ship, boat, or carriage, and shall pay to the owner a reasonable compensation for such use, to be determined, in case of dispute, by a Court of Summary Jurisdiction, and to be recovered in like manner as penalties under the Act; and

(5.) The same shall, so far as practicable, be kept and conveyed in accordance with the Act, and with all due precaution to prevent accident, but the person seizing, removing, detaining, keeping, or conveying the same shall not be liable to any penalty, punishment, or forfeiture, or to any damages, for keeping or conveying the same, so that he use all such due precautions as aforesaid; and

(6.) The officer seizing the same, or dealing with the same in pursuance of this section, shall not be liable to damages or otherwise in respect of such seizure or dealing, or any act incidental to or consequential thereon, unless it is proved that he made such seizure without reasonable cause, or that he caused damage to the article seized by some wilful neglect or default (s. 74).

Any of the following officers—namely, any Government inspector under the Act, any chief officer of police, and any superior officer appointed for the purposes of this Act, where the justices in petty sessions are the local authority, by the court of quarter sessions to which such justices belong, and in the case of any other local authority by the local authority itself—may, for the purpose of ascertaining whether the provisions of the Act with respect to the conveyance, loading, unloading, and importation of an explosive are complied with, enter, inspect, and examine at any time, and as well on Sundays as on other days, the wharf, carriage, ship, or boat of any carrier or other person who conveys goods for hire, or of the occupier of any factory, magazine, or store, or of the importer of any explosive, on or in which wharf, carriage, ship, or boat he has reasonable cause to suppose an explosive to be for the purpose of or in course of

Digitized by Google

conveyance, but so as not to unnecessarily obstruct the work or business of any such carrier, person, occupier, or importer.

Any such officer, if he find any offence being committed under the Act in any such wharf, carriage, ship, or boat, or on any public wharf, may seize and detain or remove the said carriage, ship, or boat, or the explosive, in such manner and with such precautions as appear to him to be necessary to remove any danger to the public, and may seize and detain the said explosive, as if it were liable to forfeiture.

Any officer above mentioned in this section, and any officer of police, or officer of the local authority who has reasonable cause to suppose that any offence against the Act is being committed in respect of any carriage (not being on a railway) or any boat conveying, loading, or unloading any explosive, and that the case is one of emergency, and that the delay in obtaining a warrant will be likely to endanger life, may stop, and enter, inspect, and examine such carriage or boat, and by detention or removal thereof or otherwise take such precautions as may be reasonably necessary for removing such danger, in like manner as if such explosive were liable to forfeiture.

Every officer shall for the purpose of this section have the same powers and be in the same position as if he were authorised by a search warrant granted under the Act, and any person failing to admit or obstructing such officer shall be liable to the same penalty (s. 75).

When a Government inspector, constable, or officer of the local authority takes samples of any explosive, or ingredient, or substance, he shall pay for or tender payment for the same to such amount as he considers to be the market value thereof, and the occupier of the place in which, or the owner of the bulk from which the sample was taken, may recover from the officer taking the sample, as a debt in the county court, any excess of the real value over the amount so paid or tendered, and any amount so tendered (s. 76).

Digitized by Google

PART IV.—SUPPLEMENTAL PROVISIONS.

Trespassers and Offenders.

Any person who enters without permission or otherwise trespasses upon any factory, magazine, or store, or the land immediately adjoining thereto which is occupied by the occupier of such factory, magazine, or store, or on any wharf for which bye-laws are made by the occupier thereof under the Act, shall for every such offence, if not otherwise punishable, be liable to a penalty not exceeding 5*l.*, and may be forthwith removed from such factory, magazine, store, land, or wharf, by any constable, or by the occupier of such factory, magazine, store, or wharf, or any agent or servant of or other person authorised by such occupier.

Any person other than the occupier of or person employed in or about any factory, magazine, or store who is found committing any act which tends to cause explosion or fire in or about such factory, magazine, or store, shall be liable to a penalty not exceeding 50*l.*

The occupier of any such factory, magazine, store, or wharf shall post up in some conspicuous place or places a notice or notices warning all persons of their liability to penalties under this section; but the absence of any such notice or notices shall not exempt a person from a penalty under this section (s. 77).

Any person who is found committing any act for which he is liable to a penalty under the Act, and which tends to cause explosion or fire in or about any factory, magazine, store, railway, canal, harbour, or wharf, or any carriage, ship, or boat, may be apprehended without a warrant by a constable, or an officer of the local authority, or by the occupier of or the agent or servant of or other person authorised by the occupier of such factory, magazine, store, or wharf, or by any agent or servant of or other person authorised by the railway or canal company or harbour authority, and be removed from the place

Digitized by Google

at which he is arrested, and conveyed as soon as conveniently may be before a court of summary jurisdiction.

Where any person is guilty of any offence which under the Act is punishable by a pecuniary penalty only, and which, in the opinion of the court that tries the case, was reasonably calculated to endanger public safety or to cause serious personal injury, or to cause a dangerous accident, and was committed wilfully by the person accused, such person shall be liable to six months' imprisonment, with or without hard labour (s. 78).

Every person who forges or counterfeits any license, certificate, document, or plan granted or required in pursuance or for the purposes of the Act, or gives or signs any such document or plan which is to his knowledge false in any material particular, or wilfully makes use of any such forged, counterfeit, or false license, certificate, document, or plan, shall be liable to imprisonment, with or without hard labour, for a term not exceeding two years (s. 81).

Every person who, without due authority, pulls down, injures, or defaces any notice, copy of rules, or document, when affixed in pursuance of this Act, or of the special rules, shall be liable to a penalty not exceeding two pounds (s. 82).

Legal Proceedings.

Where any offence under the Act for which the occupier of any factory, magazine, store, or registered premises is liable to a penalty or forfeiture has in fact been committed by some other person, such other person shall be liable to a penalty not exceeding twenty pounds, and the occupier shall be exempt from any penalty and forfeiture upon proving that he had used due diligence to enforce the observance of the Act, and had taken all practicable means in his power to prosecute the actual offender to conviction; and where a Government inspector, or an officer of the local authority, or the local authority, is satisfied that such occupier would, under the foregoing provisions, be exempt, and the occupier gives all

Digitized by Google

facilities for proceeding against and convicting the actual offender, the inspector, officer, or local authority shall proceed against that person in the first instance, without first proceeding against the occupier.

Where any offence under the Act for which any warehouseman, carrier, occupier of a wharf or dock, or owner or master of any ship, boat, or carriage, is liable to a penalty or forfeiture, has in fact been committed by some other person, this section is to apply in like manner as in the case of an occupier (s. 87).

Where a carrier or owner or master of a ship or boat is prevented from complying with the Act by the wilful act, neglect, or default of the consignor or consignee of the explosive, or other person, or by the improper refusal of the consignee or other person to accept delivery of the explosive, such consignor, consignee, or other person who is guilty of such wilful act, neglect, default, or refusal shall be liable to the same penalty to which the carrier, owner, or master is liable for a breach of the Act, and his conviction shall exempt the carrier, owner, or master from any penalty or forfeiture under the Act (s. 88).

Where a court before whom a person is convicted of an offence against the Act has power to forfeit any explosive, the court may, if it think it just and expedient, in lieu of forfeiting such explosive, impose upon such person, in addition to any other penalty or punishment, a penalty not exceeding such sum as appears to the court to be the value of the explosive so liable to be forfeited.

Where any explosive, or ingredient of an explosive, is alleged to be liable under the Act to be forfeited, any indictment, information, or complaint may be laid against the owner of such explosive or ingredient, for the purpose only of enforcing such forfeiture; and where the owner is unknown, or cannot be found, a court may cause a notice to be advertised, stating that unless cause is shown to the contrary at the time and place named in the notice, such explosive will be forfeited, and at such time and place the court, after hearing the

Digitized by Google

owner or any person on his behalf, may order all or any part of such explosive or ingredient to be forfeited (s. 89).

Every offence under the Act may be prosecuted, and every penalty under the Act recovered, and all explosives and ingredients liable to forfeiture under the Act may be forfeited, either on indictment or before a court of summary jurisdiction, provided that the penalty shall not exceed 100*l.*, exclusive of costs, and of any forfeiture or penalty in lieu of forfeiture, and the term of imprisonment shall not exceed one month. All costs and penalties may be recovered before a court of summary jurisdiction.

A court of summary jurisdiction may by order prohibit a person from doing any act for doing which such person has twice been convicted under the Act, and may order any person disobeying such summary order to be imprisoned for any period not exceeding six months (s. 91).

The court of summary jurisdiction, when hearing and determining an information or complaint, in respect of any offence under the Act, shall be constituted either of two or more justices of the peace in petty sessions, or of a magistrate empowered by law to do alone any act authorised to be done by more than one justice of the peace.

Nothing in the Act shall render liable to any penalty or forfeiture the owner or master of any ship or boat, or any carrier or warehouseman, or the person having charge of any carriage, for any act done in breach of the Act, if he prove that by reason of stress of weather, inevitable accident, or other emergency, the doing of such act was, under the circumstances, necessary and proper (s. 100).

Definition and Classification of Explosives.

Her Majesty is empowered, by Order in Council, to declare that any substance which appears to Her Majesty to be specially dangerous to life or property by reason either of its explosive properties, or of any process in the manufacture thereof being liable to explosion, shall be deemed to be an

Digitized by Google

explosive within the meaning of the Act; and Her Majesty is also empowered from time to time, by Order in Council, to define, for the purposes of the Act, the composition, quality, and character of any explosive, and to classify explosives (ss. 104, 106).

Any person who carries on any of the following processes—namely, the process of dividing into its component parts or otherwise breaking up or unmaking any explosive, or making fit for use any damaged explosive, or the process of remaking, altering, or repairing any explosive, shall be subject to the provisions of this Act as if he manufactured an explosive, and the expression "manufacture" in the Act is to be construed accordingly (s. 105).

Table of Fees.

The following are to be the maximum fees for licenses and certificates granted by the Secretary of State (s. 26) :—

Factory license, original	Ten pounds.
,, ,, amending	Five pounds.
,, ,, renewal when lost ..	Five shillings.
Magazine license, original	Ten pounds.
,, ,, amending	Five pounds.
,, ,, renewal when lost ..	Five shillings.
Importation license, first grant	One pound.
,, ,, renewal	Ten shillings.
Continuing certificate	Forty shillings.

Digitized by Google

INDEX.

A

ABBOT, General, on Californian gun-cotton, 117
———————, on explosive or blasting gelatine, 43
——————— on forcite, 55
———————, on Judson powder, 65
———————, experiments with gun-cotton, 108
———————, on rack-a-rock, 150
———————, on tonite, 116
Abel, Sir Frederick, researches on gun-cotton, 77, 79
———————, on transmission of detonation in water, 81
———————, on transmission of detonation through air, 82
———————, on pressure determination, 164
———————, test in firing gunpowder, 272
———————, on detonation of gun-cotton, 185
———————, on prevention of fire-damp explosions, 288
———————, on lime cartridges for blasting coal, 296
Abel, Sir Frederick, heat test apparatus, 351
———————, on iron-plate test, 171
Accidental explosions, instances of, 201
Accidents with nitro-glycerine, 38
Acid mixtures, 15, 16
Acids, spent, concentration of, 29
American Hercules powder, 61
Ammonia powder, 52
Analysis of explosives, 326
———, Captain Hess on, 326
———, apparatus for, 327
——— of kieselguhr dynamite, 329
——— for determination of nitrogen, table of, 330
——— of explosive gelatine, 333
——— of new dynamite No. 1, 334
——— of gun-cotton, 336
——— of gun-cotton samples, table of, 339
——— of nitro-gelatine containing camphor, 348
Archer and Fry's discovery of collodion-cotton, 119
Atlas powder, 59
Attfield's experiments with tonite, 115
Authorisation of explosives, Home Office instructions as to, 362

Digitized by Google

B

BAELEN-SUR-NETHE, forcite works at, 74
Barium nitrate, 6
Belgian forcite works, 74
Bellite, 142
Bench blasting, 237
Berthelot's caloric determination, 165
Blane Valley contract, quantity of explosives used in, 251
Blast furnace, removal of obstruction in, 258
Blasting gelatine as a military explosive, 319
Blasting, materials used in, 208
——— tree stumps, 222
——— boulders, 224
——— under water, 226
——— out-cuts, 236
——— in headings, 237
——— in large mines, 244
——— by electricity, 271
Boulders, breaking up, 224, 225
Brain's powder, 54
Butter machine, 17

C

CALIFORNIA gun-cotton, 117
Carbazotic acid, 160
Carbo-dynamite, 69
Carding-machine, 90
Celluloid, 118, 122
Cellulose, proportion of, in various substances, 131
Collodion-cotton, 118
Colonia dynamite, 52
Comparison of explosives, methods of, 164
Compressed air mixing apparatus, 21
Concussion, 196
Continental dynamite factories, 15
Cundill, Colonel, on classification of explosives, 72
———, on tests for nitroglycerine, 72

D

DAVY'S powder, 6
Dawson on collodion-cotton, 119
Deliquescent explosives, 191
Detonating caps, action of, 183
——— ignition, 182
De Tret's powder, 6
Dinitro-cellulose, 122
Dope, 71
Downward force of explosives, 4
Drill-holes, 209
Drilling and blasting, 302
——— with compressed air, 247
Drills, 301
Drying machine, 91
Dualine, 52
Dynamite under the microscope, 50
——— No. 2 .. 53
———, calculating effect of, 168
———, iron-plate test for surface charges of, 171
———, explosion of, explained, 206
———, invention of, 47
———, classification of, 71
———, grades of, 206
———, when frozen, 217
———, necessary precautions with, 220
———, general directions for using, 206
———, essential conditions in firing, 305
——— gun, 305

Digitized by Google

Dynamite shell, 312
———, Captain Hess on analysis of, 329

E

E. C. powders, 111
Ehrhardt's powder, 7
Electric blasting apparatus, 273
Electricity, application of, in firing mines, 273
———, magneto machine for electric firing, 274
Excavation, quantity of explosives required for, 250
Explosion gases of gun-cotton, 104
——— of nitro-glycerine, 36
Explosion at Stowmarket, 78
Explosions during manufacture, precautions against, 201
——— due to external causes, 203
Explosives Act, 364
Exudation and liquefaction test, 361

F

FAHNEJELM of Stockholm, 53
Faversham tonite works, 113
Favier's explosive, 146
Fiery mines, firing charges in, 144, 293
———, use of explosives in, 288
Fire-damp explosions, 134
Flameless explosives, 134
Foot-pounds machine, 178
Forcite, 54
——— -gelatine, 58
Forcite powder works at Lake Hopatkong, 73
——— at Baelen-sur-Nethe, 74
Friction test, 192
Friedrichssegen, experiments in silver-lead mines at, 254
Frozen dynamite, 217
——— nitro-glycerine compounds, 218
———, handling of, 220
Fuzes, electrical, advantages of, 271
———, low- and high-tension, 283

G

GALLOWAY'S water cartridge, 292
Gelatine dynamite, 59
——— in mining and tunnelling, 252
Gelatine explosive de guerre, 42
Genoa, blasting rock at, 245
German gunpowder, 7
——— pneumatic gun, 311
Giant powder, 206
Glonoin, 10
Glukodine, 61
Glycerides, 17
Graydon's dynamite shell, 312
Gun-cotton, 75
———, early experiments with, 75
———, California, 117
——— for military purposes, 79
——— for submarine mines, 80
———, manufacture of, 84
——— distinguished from collodion-cotton, 85
———, how to explode, 101
———, properties of, 101

Digitized by Google

Gun-cotton, detonation of, when wet, 102
————, how to render insensitive, 102
————, advantages and disadvantages of, 106
————, Captain Hess on analysis of, 336
———— gases, chemical constituents of, 105
———— shells, 313
Gunpowder, action of, 3
————, substitutes for, 6

H

HAGER'S collodion-cotton process, 120
Heat test, 351
————, apparatus of Sir F. Abel, 351
Hellhoffite, 148
Hercules dynamite, 52
Hess, Captain, on analysis of explosives, 326
————, iron-plate tests of nitro-glycerine by, 170, 260
———— and Kostersitz, apparatus of, for measuring shattering force, 169
———— and Lieut. Schwab's experiments with dynamite, 48
High-tension fuzes, 283
Hilton, Mr. James, on roburite, 140
Hollander, 93
Home Office instructions as to authorisation of explosives, 360
———— as to tests of stability, 351
Hopatkong Lake forcite works, 73
Horseley's powder, 7, 52
Hydraulic press, 96, 97
Hydro-extractors, 87, 88

I

ICE, breaking up, 225
Imperfect explosions, 213
Ingredients of nitro-glycerine, test of, 23
Initial detonation, 182
Iron-plate tests, 171
———— with nitro-gelatine, 260

J

JOHNSON'S powders, 112
Judson powder, 62

K

KELLOW'S powder, 7
Kieselguhr, 47
———— dynamite, 48
Königshütte, tunnel at, 242
————, experiments in coal-mines at, 252
Kostersitz and Hess, apparatus of, for measuring shattering force, 169

L

LAMM, Carl, 142
Lannoy's white powder, 110
Lauer's system of firing charges in fiery mines, 293
Le Bouchet gun-cotton factory, 86
Lenk gun-cotton process, 86
Lewin, J. M., 54
Lime cartridges, 295

Digitized by Google

Lime cartridges, Sir Frederick Abel on, 296
———————, Royal Commissioners' conclusion as to, 297
Liquefaction, test for, 361
Lithofracteur, 52
Low explosives, 1
Low-tension fuzes, 283
Luchs' collodion-cotton process, 119
Lugen, experiments in mines at, 253
Lydite, 7

M

MACHINE drills, use of, 301
Mackie and Faure's granulated gun-cotton, 98
Magneto machine No. 3, electric blasting apparatus, 273
Manchester, explosion of picrates at, 9
Mann's collodion-cotton process, 119
Maxim's pneumatic gun, 311
McNab water cartridge, 290
Melinite, 7, 156
Micrometer calipers, 179
Military explosive gelatine, experiments with, 268
Military purposes, explosives for, 304
Mines, use of explosives in, 144, 293
Mining with power-drills, 249
——— with high explosives, 249
Mixing machine for gun-cotton, 95
Modern explosives, characteristics of, 1
———————, essential conditions of, 186
Mowbray's nitro-glycerine process, 17
Münch's experiments, 252
Musconetcong tunnel, 237

N

NISSER'S powder, 7
Nitrate of soda, use of, in blasting powders, 6
Nitrating process at forcite works, 22
Nitro-compounds, Captain Hess on analysis of, 326
Nitro-gelatine, 40
———————— as used in tunnelling, 252
———————— iron-plate tests with, 260
Nitro-glycerine, composition of, 10
———————, process of manufacture of, 11
———————, freezing temperature of, 35
———————, properties of, 35
———————— in use, 38
———————, test of ingredients of, 23
———————, Colonel Cundill's tests for, 72
———————— in the human body, detection of, 201
———————— compounds, Captain Hess on analysis of, 340
Nitro-lactus, 111
—— magnite, 61
—— mannite, 111
—— milk-sugar, 111
—— raw-sugar, 111
—— starch, 111
Nobel's apparatus for concentration of spent acids, 29

Digitized by Google

Nobel's ballistic test, 166
Noble, Captain, on pressure determination, 164

O

OXLAND'S powder, 6

P

PALEINE, 69
Panclastite, 155
Pellet and Champion on preparation of nitro-glycerine, 15
Pembrey works, torpedoing at, 203
Pentanitro-cellulose, 121
Percussion, 193
——— gauge, 193
Peyerle, Captain, on transmission of explosion, 196
Pfaffensprung tunnel, 243
———, experiments at, 255
Picrates, 8
——— explosion of, at Manchester, 9
Picric acid, 160
———, adaptations of, by M. Turpin, 156
Pile-driving with dynamite, 228
Piles under water, removal of, 226
Pneumatic gun, Zalinsky's, 305
———, the German and Maxim, 311
Poacher for washing gun-cotton, 95
Pontoon drilling, 300
Potassium chlorate, 6
Power drills, use of, 301
Pressure gauge, 173
———, measurement of, 181
Pudrolithe, 7
Pulping-engine for gun-cotton, 93
Punshon's gun-cotton, 112
Pyro-glycerine, 10
Pyrolithe, 7
Pyroxyline, 109

Q

QUINAN, Lieut., on internal resistance to detonation, 187
——— foot-pounds machine, 178
——— diagram for measurement of pressure, 181
——— percussion gauge, 193

R

RACK-A-ROCK, 148
Relative strength of explosives, 163
Rhenish dynamite, 54
Rifle gun-cotton, 111
Roburite, 135
———, experiments with, 137
———, flameless character of, 139
Rock-blasting, 225, 235
——— at Genoa, 245
Rocks in rivers, removal of, 298
Romite, 148
Roth, Dr., on roburite, 135
Roux and Sarrau's pressure determination, 164
Rudberg's nitro-glycerine apparatus, 12

Digitized by Google

S

SAFETY, conditions of, 188
San Francisco tonite factory, 113
Saxifragin powder, 6
Schultze's gunpowder, 109
Schwab, Lieut. J., and Capt. P. Hess, experiments of, with dynamite, 48
Schwartz's powder, 6
Sebastin, 53
Securite, 142
Seranine, 52
Settle's water cartridge, 134
Sharp's powder, 7
Simmeringer Haide, experiments on the, 268
Smith and Moore's lime cartridge, 295
Smolianinoff explosive, 69
Snyder explosive, 70
Sobrero, 10
Sodium nitrate, 6
Spiral tunnel, experiments at, 256
Sprengel explosives, 133
Springing or chambering holes, 4
Stability, tests of, Home Office instructions as to, 351
Stockholm dynamite works, 12
Stowmarket, explosion at, 78
Straw dynamite, 69
Strength of explosives, determining, 2, 163
———————, conditions of, 186
———————, measurement of, 175
Strong explosives, advantages of, 2
Submarine engineering, use of explosives in, 298
Sympathy, explosion by, 216

T

TAMPING test, 198
Tankerode, experiments in coal-mine near, 257
Tests for Explosives, Home Office instructions as to, 351
Tetranitro-cellulose, 121
Teutonite, 7
Tonite, 113, 117
Torpedoing at Pembrey works, 20
Totten's gunpowder, 112
Transmission of detonation in air and in water, 81, 82
Trautzl's apparatus for measuring strength of explosives, 175
——— dynamite, 69
——— method of removing piles under water, 226
Tree stumps, blasting, 222
Trench's fire-extinguishing compound, 144, 293
Trinitro-cellulose, 121
Trinitro-phenol, 160
Tunnel at Königshütte, 242
——— at Musconetcong, 237
——— at Pfaffensprung, 243
Tunnelling, American practice of blasting in, 237
——— with hand labour, 241
Turpin's shell, 161

U

UCHATIUS' white powder, 110

V

VON DAHMEN'S dynamite, 70
Von Förster and Wolff's patent for preserving gun-cotton, 314
——— gun-cotton shell, 314
Vulcan dynamite, 52

Digitized by Google

W

WALTHAM ABBEY, manufacture of gun-cotton at, 89
Water cartridges, 134, 290, 292
Wavra, Captain, experiments by, 196, 268
Wells sunk with explosives, 225
White or German gunpowder, 7
Wrecks, use of explosives for removing, 303

Z

ZALINSKY'S pneumatic dynamite gun, 305

PRINTED BY WILLIAM CLOWES AND SONS, LIMITED,
LONDON AND BECCLES.

Digitized by Google

MANLOVE, ALLIOTT, & CO. Limited,

Engineers,

NOTTINGHAM.

MANCHESTER. LONDON. GLASGOW.



MAKERS OF

HYDRO-EXTRACTORS

FOR

Explosives and other Acid Goods.

AS USED BY

The Cotton Powder Company Limited.

The New Explosives Company Limited.

The Royal Gunpowder Factory, Waltham Abbey.

Nobel's Explosives Company Limited.

AND MANY OTHERS.

Telegraphic Address—

"MANLOVES, NOTTINGHAM."



Digitized by Google

Just Published, Crown 8vo, 282 pages. Price 9s. Cloth.

NITRO-EXPLOSIVES

A PRACTICAL TREATISE

CONCERNING THE

PROPERTIES, MANUFACTURE, AND ANALYSIS OF NITRATED SUBSTANCES, INCLUDING THE FULMINATES, SMOKELESS POWDERS, AND CELLULOID

BY

P. GERALD SANFORD, F.I.C., F.C.S.

Member of the Society of Public Analysts; Consulting Chemist to the Cotton Powder Company Limited; late Resident Chemist at the Guncotton Works, Stowmarket, and the Dynamite Works, Hayle, Cornwall

LONDON

CROSBY LOCKWOOD AND SON

7, STATIONERS' HALL COURT, LUDGATE HILL

1896

Digitized by Google

NEW AND STANDARD WORKS

ON

MINING AND METALLURGY.

PUBLISHED BY

CROSBY LOCKWOOD AND SON,

7, STATIONERS' HALL COURT, LONDON, E.C.

THE COLLIERY MANAGER'S HANDBOOK. A Comprehensive Treatise on the Laying-Out and Working of Collieries, Designed as a Book of Reference for Colliery Managers, and for the use of Coal-Mining Students preparing for First-Class Certificates. By CALEB PAMELY, M.E.; Memb. North of England and South Wales Institutes of Mining Engineers. Third Edition, Enlarged, with 700 Illustrations. Medium 8vo, 900 pages, £1 5*s.* cloth.

"Mr. Pamely's work is eminently suited to its purpose, being clear, interesting, exhaustive, rich in detail, and giving descriptions of the latest machines in every department. . . . A mining engineer could scarcely go wrong who followed this work."—*Colliery Guardian.*

"Contains a great deal of information which managers and students will find of use to them. The excellent index will enable them to lay their hands at once on any part they desire to consult."—*Nature.*

"This is the most complete 'all-round' work on coal-mining published in the English language, . . . No library of coal-mining books is complete without it."—*Colliery Engineer* (Scranton, Pa., U.S.).

COLLIERY WORKING AND MANAGEMENT: Comprising the Duties of a Colliery Manager, the Oversight and Arrangement of Labour and Wages, and the different Systems of Working Coal Seams. By H. F. BULMAN and R. A. S. REDMAYNE. Medium 8vo, 350 pages, with Underground Photographs and numerous illustrations. 15*s.* cloth.

[*Just published.*

NOTES AND FORMULÆ FOR MINING STUDENTS. By JOHN HERMAN MERIVALE, M.A., Certificated Colliery Manager, and Professor of Mining in the Durham College of Science, Newcastle-upon-Tyne. Third Edition, Revised. Small crown 8vo, 2*s.* 6*d.* cloth.

"Invaluable to any one who is working up for an examination on mining subjects."—*Iron and Coal Trades Review.*

"A vast amount of technical matter of the utmost value to mining engineers."—*Schoolmaster.*

Digitized by Google

MACHINERY FOR METALLIFEROUS MINES. A Practical Treatise for Mining Engineers, Metallurgists, and Managers of Mines. By E. HENRY DAVIES, M.E., F.G.S. Crown 8vo, 580 pages, with upwards of 300 Illustrations, 12*s.* 6*d.* cloth.

"Mr. Davies, in this handsome volume, has done the advanced student and the manager of mines good service. Almost every kind of machinery in actual use is carefully described, and the woodcuts and plates are good."—*Athenæum.*

A TREATISE ON METALLIFEROUS MINERALS AND MINING. By D. C. DAVIES, M.E., F.G.S., Author of "A Treatise on Slate and Slate-Quarrying." Fifth Edition, thoroughly Revised and much Enlarged by his Son, E. HENRY DAVIES, M.E., F.G.S., with about 150 Illustrations, Crown 8vo, 12*s.* 6*d.* cloth.

"As a history of the present state of mining throughout the world, this book has a real value, and it supplies an actual want."—*Athenæum.*

A TREATISE ON EARTHY AND OTHER MINERALS AND MINING. By D. C. DAVIES, M.E., F.G.S., Author of "Metalliferous Minerals," &c. Third Edition, Revised and Enlarged by his Son, E. HENRY DAVIES, M.E., F.G.S. With about 100 Illustrations. Crown 8vo, 12*s.* 6*d.* cloth.

"We do not remember to have met with any English work on mining matters that contains the same amount of information packed in equally convenient form."—*Academy.*

THE HANDLING OF DANGEROUS GOODS. A Handbook for the use of Government and Railway Officials, Carriers, Shipowners, Insurance Companies, Manufacturers, and Users, comprising the Properties of Inflammatory, Explosive, and other Dangerous Compounds, &c., &c. By H. JOSHUA PHILLIPS, F.I.C. Crown 8vo, 370 pages, 9*s.* cloth.

A POCKET-BOOK FOR MINERS AND METALLURGISTS, Comprising Rules, Formulæ, Tables, and Notes, &c., &c. By F. DANVERS POWER, M.E., F.G.S. Fcap. 8vo, 400 pages, 9*s.* leather.

"Mr. Power has succeeded in producing a pocket-book which certainly deserves to become the *vade-mecum.*"—*Mechanical World.*

THE PROSPECTOR'S HANDBOOK. A Guide for the Prospector and Traveller in Search of Minerals. By J. W. ANDERSON, M.A. (Camb.), F.R.G.S. Sixth Edition, Enlarged. Small crown 8vo, 3*s.* 6*d.* cloth.

"Will supply a much-felt want, especially among colonists, in whose way are so often thrown many mineralogical specimens, the value of which it is difficult for any one not a specialist to determine."—*Engineer.*

THE MINER'S HANDBOOK. A Handy Book of Reference on the Subjects of Mineral Deposits, Mining Operations, Ore Dressing, &c. Compiled by JOHN MILNE, F.R.S., Professor of Mining in the Imperial University of Japan. Fcap. 8vo, 7*s.* 6*d.* leather.

THE METALLURGY OF GOLD. A Practical Treatise on the Metallurgical Treatment of Gold-bearing Ores. Including the Processes of Concentration, Chlorination, and Extraction by Cyanide, and the Assaying, Melting, and Refining of Gold. By M. EISSLER, Mining Engineer and Metallurgical Chemist, formerly Assistant Assayer of the U.S. Mint, San Francisco. Fourth Edition, Enlarged to 700 pages with 200 Text Illustrations and 25 Plates and Working Drawings. 8vo, 16*s.* cloth.

"The work is a storehouse of information and valuable data, and we strongly recommend it to all professional men engaged in the gold-mining industry."—*Mining Journal.*

Digitized by Google

THE CYANIDE PROCESS OF GOLD EXTRACTION; and its Practical Application on the Witwatersrand Gold Fields in South Africa. By M. EISSLER, M.E., Mem. Inst. Mining and Metallurgy, Author of "The Metallurgy of Gold," &c. With Diagrams and Working Drawings. Large crown 8vo, 7*s.* 6*d.* cloth.

"This book is just what was needed to acquaint mining men with the actual working of a process which is not only the most popular, but is, as a general rule, the most successful for the extraction of gold from tailings."—*Mining Journal.*

THE METALLURGY OF SILVER. A Practical Treatise on the Amalgamation, Roasting, and Lixiviation of Silver Ores. Including the Assaying, Melting, and Refining of Silver Bullion. By M. EISSLER, Author of "The Metallurgy of Gold," &c. Third Edition, with 150 Illustrations. Crown 8vo, 10*s.* 6*d.* cloth.

"A practical treatise and a technical work which we are convinced will supply a long-felt want amongst practical men, and at the same time be of value to students and others indirectly connected with the industries."—*Mining Journal.*

THE METALLURGY OF ARGENTIFEROUS LEAD. A Practical Treatise on the Smelting of Silver-Lead Ores and the Refining of Lead Bullion. Including Reports on various Smelting Establishments and Descriptions of Modern Smelting Furnaces and Plants in Europe and America. By M. EISSLER, M.E., Author of "The Metallurgy of Gold," &c. Crown 8vo, 400 pages, with 183 Illustrations, 12*s.* 6*d.* cloth.

"The present volume fully maintains the reputation of the author. Those who wish to obtain a thorough insight into the present state of this industry cannot do better than read this volume, and all mining engineers cannot fail to find many useful hints and suggestions in it."—*Industries.*

THE IRON ORES OF GREAT BRITAIN AND IRELAND: Their Mode of Occurrence, Age, and Origin, and the Methods of Searching for and Working them. With a Notice of some of the Iron Ores of Spain. By J. D. KENDALL, F.G.S., Mining Engineer. With Plates and Illustrations. Crown 8vo, 16*s.* cloth.

"Mr. Kendall's book is thoroughly well done. In it there are the outlines of the history of ore-mining in every centre; and there is everything that we want to know as to the character of the ores of each district, their commercial value, and the cost of working them."—*Iron and Steel Trades Journal.*

INFLAMMABLE GASES: Their Detection and Estimation. By Prof. FRANK CLOWES, D.Sc. With a Chapter on the Detection of Inflammable Petroleum-Vapour. By BOVERTON REDWOOD, F.I.C. Crown 8vo, 218 pages, cloth, 5*s.* net.

MINE DRAINAGE. A Practical Treatise on Direct-Acting Underground Steam-Pumping Machinery. By STEPHEN MICHELL. With numerous Wood Engravings and Folding Plates. 8vo, 15*s.* cloth.

A HANDBOOK ON MODERN EXPLOSIVES. A Practical Treatise on the Manufacture and Application of Dynamite, Gun-Cotton, Nitro-Glycerine, and other Explosive Compounds. By M. EISSLER, M.E., Author of "The Metallurgy of Gold," &c. Second Edition, Enlarged. Crown 8vo, 424 pages, with about 150 Illustrations, 12*s.* 6*d.* cloth.

Digitized by Google

GRANITE AND OUR GRANITE INDUSTRIES. By GEORGE F. HARRIS, F.G.S., Membre de la Société Belge de Géologie, Lecturer on Economic Geology at the Birkbeck Institution, &c. With Illustrations. Crown 8vo, *2s. 6d.* cloth.

A TREATISE ON SLATE AND SLATE QUARRYING, SCIENTIFIC, PRACTICAL AND COMMERCIAL. By D. C. DAVIES, F.G.S. Third Edition, Revised, with Engravings and Folding Plates, *3s. 6d.* cloth.

THE MINERAL SURVEYOR AND VALUER'S COMPLETE GUIDE, Comprising a Treatise on Improved Mining Surveying and the Valuation of Mining Properties. With new Traverse Tables. By W. LINTERN, Mining Engineer. Third Edition, with an Appendix on Magnetic and Angular Surveying, with Four Plates, *3s. 6d.* cloth.

THE RUDIMENTS OF MINERALOGY. A Concise View of the Properties of Minerals. By A. RAMSAY, F.G.S. Third Edition, Revised, with Woodcuts and Steel Plates, *4s.* cloth.

RUDIMENTARY TREATISE ON GEOLOGY: PHYSICAL AND HISTORICAL. Partly based on Major-General PORTLOCK's "Rudiments of Geology." By RALPH TATE, A.L.S., F.G.S., &c. *5s.* cloth.

SUBTERRANEOUS SURVEYING, WITH AND WITHOUT THE MAGNETIC NEEDLE. By THOMAS FENWICK, Surveyor of Mines, and THOMAS BAKER, C.E. Illustrated, *3s.* cloth.

A MANUAL OF MINING TOOLS. For the use of Mine Managers, Agents, Students, &c. By WILLIAM MORGANS. *3s.* cloth.

ATLAS OF ENGRAVINGS to illustrate the above, containing 235 Illustrations, drawn to scale. 4to, *4s. 6d.* cloth.

A FIRST BOOK OF MINING AND QUARRYING, for Primary Schools and Self-Instruction. By J. H. COLLINS, F.G.S. *1s. 6d.* cloth.

THE BLOWPIPE IN CHEMISTRY, MINERALOGY, AND GEOLOGY, Containing all known Methods of Anhydrous Analysis, Working Examples, and Instructions for Making Apparatus. By W. A. Ross, Lieut.-Col. R.A., F.G.S., &c. Illustrated. Second Edition, Revised and Enlarged. Crown 8vo, *5s.* cloth.

THE COAL AND IRON INDUSTRIES OF THE UNITED KINGDOM. By RICHARD MEADE, Assistant Keeper of Mining Records. With Maps. 8vo, *£1 8s.* cloth.

LONDON: CROSBY LOCKWOOD AND SON,
7, STATIONERS' HALL COURT, E.C.

Digitized by Google

CROSBY LOCKWOOD & SON'S

Catalogue of

Scientific, Technical and Industrial Books.

	PAGE		PAGE
MECHANICAL ENGINEERING .	1	DECORATIVE ARTS	80
CIVIL ENGINEERING	10	NATURAL SCIENCE	82
MARINE ENGINEERING, &c. .	17	CHEMICAL MANUFACTURES .	84
MINING & METALLURGY . . .	19	INDUSTRIAL ARTS	86
ELECTRICITY	28	COMMERCE, TABLES, &c. . .	41
ARCHITECTURE & BUILDING .	25	AGRICULTURE & GARDENING .	43
SANITATION & WATER SUPPLY	27	AUCTIONEERING, VALUING, &c.	46
CARPENTRY & TIMBER . . .	28	LAW & MISCELLANEOUS . . .	47

MECHANICAL ENGINEERING, &c.

THE MECHANICAL ENGINEER'S POCKET-BOOK.

Comprising Tables, Formulæ, Rules, and Data: A Handy Book of Reference for Daily Use in Engineering Practice. By D. KINNEAR CLARK, M. Inst. C.E., Fourth Edition. Small 8vo, 700 pp., bound in flexible Leather Cover, rounded corners **6/0**

SUMMARY OF CONTENTS:—MATHEMATICAL TABLES.—MEASUREMENT OF SURFACES AND SOLIDS.—ENGLISH AND FOREIGN WEIGHTS AND MEASURES.—MONEYS.—SPECIFIC GRAVITY, WEIGHT, AND VOLUME.—MANUFACTURED METALS.—STEEL PIPES—BOLTS AND NUTS.—SUNDRY ARTICLES IN WROUGHT AND CAST IRON, COPPER BRASS, LEAD, TIN, ZINC.—STRENGTH OF TIMBER.—STRENGTH OF CAST IRON.—STRENGTH OF WROUGHT IRON.—STRENGTH OF STEEL.—TENSILE STRENGTH OF COPPER, LEAD, &c.—RESISTANCE OF STONES AND OTHER BUILDING MATERIALS.—RIVETED JOINTS IN BOILER PLATES.—BOILER SHELLS.—WIRE ROPES AND HEMP ROPES.—CHAINS AND CHAIN CABLES.—FRAMING.—HARDNESS OF METALS, ALLOYS, AND STONES.—LABOUR OF ANIMALS.—MECHANICAL PRINCIPLES.—GRAVITY AND FALL OF BODIES.—ACCELERATING AND RETARDING FORCES.—MILL GEARING, SHAFTING, &c.—TRANSMISSION OF MOTIVE POWER.—HEAT.—COMBUSTION: FUELS.—WARMING, VENTILATION, COOKING STOVES.—STEAM.—STEAM ENGINES AND BOILERS.—RAILWAYS.—TRAMWAYS.—STEAM SHIPS.—PUMPING STEAM ENGINES AND PUMPS.—COAL GAS, GAS ENGINES, &c.—AIR IN MOTION.—COMPRESSED AIR.—HOT AIR ENGINES.—WATER POWER.—SPEED OF CUTTING TOOLS.—COLOURS.—ELECTRICAL ENGINEERING.

"Mr. Clark manifests what is an innate perception of what is likely to be useful in a pocket-book, and he is really unrivalled in the art of condensation. It is very difficult to hit upon any mechanical engineering subject concerning which this work supplies no information, and the excellent index at the end adds to its utility. In one word, it is an exceedingly handy and efficient tool, possessed of which the engineer will be saved many a wearisome calculation, or yet more wearisome hunt through various text-books and treatises, and, as such, we can heartily recommend it to our readers."—*The Engineer.*

"It would be found difficult to compress more matter within a similar compass, or produce a book of 650 pages which should be more compact or convenient for pocket reference. . . . W be appreciated by mechanical engineers of all classes."—*Practical Engineer.*

L. A

Digitized by Google

MR. HUTTON'S PRACTICAL HANDBOOKS.

THE WORKS' MANAGER'S HANDBOOK.

Comprising Modern Rules, Tables, and Data. For Engineers, Millwrights, and Boiler Makers; Tool Makers, Machinists, and Metal Workers; Iron and Brass Founders, &c. By W. S. HUTTON, Civil and Mechanical Engineer, Author of "The Practical Engineer's Handbook." Fifth Edition, carefully Revised, with Additions. In One handsome Volume, medium 8vo, strongly bound **15/0**

☞ *The Author having compiled Rules and Data for his own use in a great variety of modern engineering work, and having found his notes extremely useful, decided to publish them—revised to date—believing that a practical work, suited to the* DAILY REQUIREMENTS OF MODERN ENGINEERS, *would be favourably received.*

"Of this edition we may repeat the appreciative remarks we made upon the first and third. Since the appearance of the latter very considerable modifications have been made, although the total number of pages remains almost the same. It is a very useful collection of rules, tables, and workshop and drawing office data."—*The Engineer*, May 10, 1895.

"The author treats every subject from the point of view of one who has collected workshop notes for application in workshop practice, rather than from the theoretical or literary aspect. The volume contains a great deal of that kind of information which is gained only by practical experience, and is seldom written in books."—*The Engineer*, June 5, 1885.

"The volume is an exceedingly useful one, brimful with engineer's notes, memoranda, and rules, and well worthy of being on every mechanical engineer's bookshelf."—*Mechanical World.*

"The information is precisely that likely to be required in practice. . . . The work forms a desirable addition to the library not only of the works' manager, but of any one connected with general engineering."—*Mining Journal.*

"Brimful of useful information, stated in a concise form, Mr. Hutton's books have met a pressing want among engineers. The book must prove extremely useful to every practical man possessing a copy."—*Practical Engineer.*

THE PRACTICAL ENGINEER'S HANDBOOK.

Comprising a Treatise on Modern Engines and Boilers, Marine, Locomotive, and Stationary. And containing a large collection of Rules and Practical Data relating to Recent Practice in Designing and Constructing all kinds of Engines, Boilers, and other Engineering work. The whole constituting a comprehensive Key to the Board of Trade and other Examinations for Certificates of Competency in Modern Mechanical Engineering. By WALTER S. HUTTON, Civil and Mechanical Engineer, Author of "The Works' Manager's Handbook for Engineers," &c. With upwards of 370 Illustrations. Fifth Edition. Revised with Additions. Medium 8vo, nearly 500 pp., strongly bound.

[*Just Published.* **18/0**

☞ *This Work is designed as a companion to the Author's* "WORKS' MANAGER'S HANDBOOK." *It possesses many new and original features, and contains, like its predecessor, a quantity of matter not originally intended for publication, but collected by the Author for his own use in the construction of a great variety of* MODERN ENGINEERING WORK.

The information is given in a condensed and concise form, and is illustrated by upwards of 370 Woodcuts; and comprises a quantity of tabulated matter of great value to all engaged in designing, constructing, or estimating for ENGINES, BOILERS, *and* OTHER ENGINEERING WORK.

"We have kept it at hand for several weeks, referring to it as occasion arose, and we have not on a single occasion consulted its pages without finding the information of which we were in quest."—*Athenæum.*

"A thoroughly good practical handbook, which no engineer can go through without learning something that will be of service to him."—*Marine Engineer.*

"An excellent book of reference for engineers, and a valuable text-book for students of engineering."—*Scotsman.*

"This valuable manual embodies the results and experience of the leading authorities on mechanical engineering."—*Building News.*

"The author has collected together a surprising quantity of rules and practical data, and has shown much judgment in the selections he has made. . . . There is no doubt that this book is one of the most useful of its kind published, and will be a very popular compendium."—*Engineer.*

"A mass of information set down in simple language, and in such a form that it can be easily referred to at any time. The matter is uniformly good and well chosen, and is greatly elucidated by the illustrations. The book will find its way on to most engineers' shelves, where it will rank as one of the most useful books of reference."—*Practical Engineer.*

"Full of useful information, and should be found on the office shelf of all practical engineers."—*English Mechanic.*

Digitized by Google

MR. HUTTON'S PRACTICAL HANDBOOKS—*continued.*

STEAM BOILER CONSTRUCTION.

A Practical Handbook for Engineers, Boiler-Makers, and Steam Users. Containing a large Collection of Rules and Data relating to Recent Practice in the Design, Construction, and Working of all Kinds of Stationary, Locomotive, and Marine Steam-Boilers. By WALTER S. HUTTON, Civil and Mechanical Engineer, Author of "The Works' Manager's Handbook," "The Practical Engineer's Handbook," &c. With upwards of 500 Illustrations. Third Edition, Revised and much Enlarged, medium 8vo, cloth . . **18/0**

☛ THIS WORK *is issued in continuation of the Series of Handbooks written by the Author, viz.:*—"THE WORKS' MANAGER'S HANDBOOK" *and* "THE PRACTICAL ENGINEER'S HANDBOOK," *which are so highly appreciated by engineers for the practical nature of their information; and is consequently written in the same style as those works.*

The Author believes that the concentration, in a convenient form for easy reference, of such a large amount of thoroughly practical information on Steam-Boilers, will be of considerable service to those for whom it is intended, and he trusts the book may be deemed worthy of as favourable a reception as has been accorded to its predecessors.

"One of the best, if not the best, books on boilers that has ever been published. The information is of the right kind, in a simple and accessible form. So far as generation is concerned, this is, undoubtedly, the standard book on steam practice."—*Electrical Review.*

"Every detail, both in boiler design and management, is clearly laid before the reader. The volume shows that boiler construction has been reduced to the condition of one of the most exact sciences; and such a book is of the utmost value to the *fin de siècle* Engineer and Works Manager."—*Marine Engineer.*

"There has long been room for a modern handbook on steam boilers; there is not that room now, because Mr. Hutton has filled it. It is a thoroughly practical book for those who are occupied in the construction, design, selection, or use of boilers."—*Engineer.*

"The book is of so important and comprehensive a character that it must find its way into the libraries of every one interested in boiler using or boiler manufacture if they wish to be thoroughly informed. We strongly recommend the book for the intrinsic value of its contents."—*Machinery Market.*

PRACTICAL MECHANICS' WORKSHOP COMPANION.

Comprising a great variety of the most useful Rules and Formulæ in Mechanical Science, with numerous Tables of Practical Data and Calculated Results for Facilitating Mechanical Operations. By WILLIAM TEMPLETON, Author of "The Engineer's Practical Assistant," &c., &c. Seventeenth Edition, Revised, Modernised, and considerably Enlarged by WALTER S. HUTTON, C.E., Author of "The Works' Manager's Handbook," "The Practical Engineer's Handbook," &c. Fcap. 8vo, nearly 500 pp., with 8 Plates and upwards of 250 Illustrative Diagrams, strongly bound for workshop or pocket wear and tear. **6/0**

"In its modernised form Hutton's 'Templeton' should have a wide sale, fo it contains much valuable information which the mechanic will often find of use, and not a few tables and notes which he might look for in vain in other works. This modernised edition will be appreciated by all who have learned to value the original editions of 'Templeton.'"—*English Mechanic.*

"It has met with great success in the engineering workshop, as we can testify; and there are a great many men who, in a great measure, owe their rise in life to this little book."—*Building News.*

"This familiar text-book—well known to all mechanics and engineers—is of essential service to the every-day requirements of engineers, millwrights, and the various trades connected with engineering and building. The new modernised edition is worth its weight in gold."—*Building News.* (Second Notice.)

"This well-known and largely-used book contains information, brought up to date, of the sort so useful to the foreman and draughtsman. So much fresh information has been introduced as to constitute it practically a new book. It will be largely used in the office and workshop."—*Mechanical World.*

"The publishers wisely entrusted the task of revision of this popular, valuable, and usefu book to Mr. Hutton, than whom a more competent man they could not have found."—*Iron.*

ENGINEER'S AND MILLWRIGHT'S ASSISTANT.

A Collection of Useful Tables, Rules, and Data. By WILLIAM TEMPLETON. Seventh Edition, with Additions. 18mo, cloth **2/6**

"Occupies a foremost place among books of this kind. A more suitable present to an apprentice to any of the mechanical trades could not possibly be made."—*Building News.*

"A deservedly popular work. It should be in the 'drawer' of every mechanic."—*English Mechanic.*

Digitized by Google

THE MECHANICAL ENGINEER'S REFERENCE BOOK.

For Machine and Boiler Construction. In Two Parts. Part I. GENERAL ENGINEERING DATA. Part II. BOILER CONSTRUCTION. With 51 Plates and numerous Illustrations. By NELSON FOLEY, M.I.N.A. Second Edition, Revised throughout and much Enlarged. Folio, half-bound, net . **£3 3s.**

PART I.—MEASURES.—CIRCUMFERENCES AND AREAS, &c., SQUARES, CUBES FOURTH POWERS.—SQUARE AND CUBE ROOTS.—SURFACE OF TUBES.—RECIPROCALS.—LOGARITHMS. — MENSURATION. — SPECIFIC GRAVITIES AND WEIGHTS.—WORK AND POWER. — HEAT. — COMBUSTION. — EXPANSION AND CONTRACTION. — EXPANSION OF GASES.—STEAM.— STATIC FORCES.—GRAVITATION AND ATTRACTION.—MOTION AND COMPUTATION OF RESULTING FORCES.—ACCUMULATED WORK.—CENTRE AND RADIUS OF GYRATION.—MOMENT OF INERTIA.—CENTRE OF OSCILLATION.—ELECTRICITY.—STRENGTH OF MATERIALS.—ELASTICITY.—TEST SHEETS OF METALS.—FRICTION.—TRANSMISSION OF POWER.—FLOW OF LIQUIDS.—FLOW OF GASES.—AIR PUMPS, SURFACE CONDENSERS, &c.—SPEED OF STEAMSHIPS.—PROPELLERS.—CUTTING TOOLS.—FLANGES.—COPPER SHEETS AND TUBES.—SCREWS, NUTS, BOLT HEADS, &c.—VARIOUS RECIPES AND MISCELLANEOUS MATTER.—WITH DIAGRAMS FOR VALVE-GEAR, BELTING AND ROPES, DISCHARGE AND SUCTION PIPES, SCREW PROPELLERS, AND COPPER PIPES.

PART II.—TREATING OF POWER OF BOILERS.—USEFUL RATIOS.—NOTES ON CONSTRUCTION. — CYLINDRICAL BOILER SHELLS. — CIRCULAR FURNACES. — FLAT PLATES.—STAYS. — GIRDERS.—SCREWS. — HYDRAULIC TESTS. — RIVETING. — BOILER SETTING, CHIMNEYS, AND MOUNTINGS.—FUELS, &c.—EXAMPLES OF BOILERS AND SPEEDS OF STEAMSHIPS.—NOMINAL AND NORMAL HORSE POWER.—WITH DIAGRAMS FOR ALL BOILER CALCULATIONS AND DRAWINGS OF MANY VARIETIES OF BOILERS.

"The book is one which every mechanical engineer may, with advantage to himself, add to his library."—*Industries.*

"Mr. Foley is well fitted to compile such a work. . . . The diagrams are a great feature of the work. . . . Regarding the whole work, it may be very fairly stated that Mr. Foley has produced a volume which will undoubtedly fulfil the desire of the author and become indispensable to all mechanical engineers."—*Marine Engineer.*

"We have carefully examined this work, and pronounce it a most excellent reference book for the use of marine engineers."—*Journal of American Society of Naval Engineers.*

COAL AND SPEED TABLES.

A Pocket Book for Engineers and Steam Users. By NELSON FOLEY, Author of "The Mechanical Engineer's Reference Book." Pocket-size, cloth . **3/6**

"These tables are designed to meet the requirements of every-day use; are of sufficient scope for most practical purposes, and may be commended to engineers and users of steam."—*Iron.*

TEXT-BOOK ON THE STEAM ENGINE.

With a Supplement on GAS ENGINES, and PART II. on HEAT ENGINES. By T. M. GOODEVE, M.A., Barrister-at-Law, Professor of Mechanics at the Royal College of Science, London; Author of "The Principles of Mechanics," "The Elements of Mechanism," &c. Fourteenth Edition. Crown 8vo, cloth . **6/0**

"Professor Goodeve has given us a treatise on the steam engine which will bear comparison with anything written by Huxley or Maxwell, and we can award it no higher praise."—*Engineer.*

"Mr. Goodeve's text-book is a work of which every young engineer should possess himself."—*Mining Journal.*

ON GAS ENGINES.

With Appendix describing a Recent Engine with Tube Igniter. By T. M. GOODEVE, M.A. Crown 8vo, cloth **2/6**

"Like all Mr. Goodeve's writings, the present is no exception in point of general excellence. It is a valuable little volume."—*Mechanical World.*

A TREATISE ON STEAM BOILERS.

Their Strength, Construction, and Economical Working. By R. WILSON, C.E. Fifth Edition. 12mo, cloth **6/0**

"The best treatise that has ever been published on steam boilers. —*Engineer.*

"The author shows himself perfect master of his subject, and we heartily recommend all employing steam power to possess themselves of the work."—*Ryland's Iron Trade Circular.*

THE MECHANICAL ENGINEER'S COMPANION

of Areas, Circumferences, Decimal Equivalents, in inches and feet, millimetres squares, cubes, roots, &c.; Weights, Measures, and other Data. Also Practical Rules for Modern Engine Proportions. By R. EDWARDS, M.Inst.C.E Fcap. 8vo, cloth. [*Just Published.* **3/6**

"A very useful little volume. It contains many tables, classified data and memoranda, generally useful to engineers."—*Engineer.*

"This small book is what it professes to be, viz. :—'a handy office companion,' giving as it does, in a succinct form, a variety of information likely to be required by mechanical engineers in their everyday office work."—*Nature.*

Digitized by Google

A HANDBOOK ON THE STEAM ENGINE.

With especial Reference to Small and Medium-sized Engines. For the Use of Engine Makers, Mechanical Draughtsmen, Engineering Students, and users of Steam Power. By HERMAN HAEDER, C.E. Translated from the German with considerable additions and alterations, by H. H. P. POWLES, A.M.I.C.E., M.I.M.E. Second Edition, Revised. With nearly 1,100 Illustrations. Crown 8vo, cloth **9/0**

"A perfect encyclopædia of the steam engine and its details, and one which must take a permanent place in English drawing-offices and workshops."—*A Foreman Pattern-maker.*

"This is an excellent book, and should be in the hands of all who are interested in the construction and design of medium-sized stationary engines. . . . A careful study of its contents and the arrangement of the sections leads to the conclusion that there is probably no other book like it in this country. The volume aims at showing the results of practical experience, and it certainly may claim a complete achievement of this idea."—*Nature.*

"There can be no question as to its value. We cordially commend it to all concerned in the design and construction of the steam engine."—*Mechanical World.*

BOILER AND FACTORY CHIMNEYS.

Their Draught-Power and Stability. With a chapter on *Lightning Conductors.* By ROBERT WILSON, A.I.C.E., Author of "A Treatise on Steam Boilers," &c. Crown 8vo, cloth **3/6**

"A valuable contribution to the literature of scientific building."—*The Builder.*

BOILER MAKER'S READY RECKONER & ASSISTANT.

With Examples of Practical Geometry and Templating, for the Use of Platers, Smiths, and Riveters. By JOHN COURTNEY, Edited by D. K. CLARK, M.I.C.E. Third Edition, 480 pp., with 140 Illustrations. Fcap. 8vo . **7/0**

"No workman or apprentice should be without this book."—*Iron Trade Circular.*

REFRIGERATING & ICE-MAKING MACHINERY.

A Descriptive Treatise for the Use of Persons Employing Refrigerating and Ice-Making Installations, and others. By A. J. WALLIS-TAYLER, A.-M. Inst. C.E. Second Edition, Revised and Enlarged. With Illustrations. Crown 8vo, cloth. [*Just Published.* **7/6**

"Practical, explicit, and profusely illustrated."—*Glasgow Herald.*

"We recommend the book, which gives the cost of various systems and illustrations showing details of parts of machinery and general arrangements of complete installations."—*Builder.*

"May be recommended as a useful description of the machinery, the processes, and of the facts, figures, and tabulated physics of refrigerating. It is one of the best compilations on the subject."—*Engineer.*

TEA MACHINERY AND TEA FACTORIES.

A Descriptive Treatise on the Mechanical Appliances required on Tea Plantations in the Preparation of Tea for the Market. By A. J. WALLIS-TAYLER, A.-M. Inst. C.E. With over 200 Illustrations. Medium 8vo, cloth. [*Nearly Ready. Price, about* **25/0**

ENGINEERING ESTIMATES, COSTS, AND ACCOUNTS.

A Guide to Commercial Engineering. With numerous examples of Estimates and Costs of Millwright Work, Miscellaneous Productions, Steam Engines and Steam Boilers; and a Section on the Preparation of Costs Accounts. By A GENERAL MANAGER. Second Edition. 8vo, cloth. [*Just Published.* **12/0**

"This is an excellent and very useful book, covering subject-matter in constant requisition in every factory and workshop. . . . The book is invaluable, not only to the young engineer, but also to the estimate department of every works."—*Builder.*

"We accord the work unqualified praise. The information is given in a plain, straightforward manner, and bears throughout evidence of the intimate practical acquaintance of the author with every phase of commercial engineering."—*Mechanical World.*

Digitized by Google

AERIAL OR WIRE-ROPE TRAMWAYS.

Their Construction and Management. By A. J. WALLIS-TAYLER, A.M.Inst.C.E. With 81 Illustrations. Crown 8vo, cloth. [*Just Published.* **7/6**

"This is in its way an excellent volume. Without going into the minutiæ of the subject, it yet lays before its readers a very good exposition of the various systems of rope transmission in use, and gives as well not a little valuable information about their working, repair, and management. We can safely recommend it as a useful general treatise on the subject."—*The Engineer.*

"Mr. Tayler has treated the subject as concisely as thoroughness would permit. The book will rank with the best on this useful topic, and we recommend it to those whose business is the transporting of minerals and goods."—*Mining Journal.*

MOTOR CARS OR POWER-CARRIAGES FOR COMMON ROADS.

By A. J. WALLIS-TAYLER, Assoc. Memb. Inst. C.E., Author of "Modern Cycles," &c. 212 pp., with 76 Illustrations. Crown 8vo, cloth . . **4/6**

"Mr. Wallis-Tayler's book is a welcome addition to the literature of the subject, as it is the production of an Engineer, and has not been written with a view to assist in the promotion of companies. . . . The book is clearly expressed throughout, and is just the sort of work that an engineer, thinking of turning his attention to motor-carriage work, would do well to read as a preliminary to starting operations."—*Engineering.*

PLATING AND BOILER MAKING.

A Practical Handbook for Workshop Operations. By JOSEPH G. HORNER, A.M.I.M.E. 380 pp. with 338 Illustrations. Crown 8vo, cloth . . **7/6**

"The latest production from the pen of this writer is characterised by that evidence of close acquaintance with workshop methods which will render the book exceedingly acceptable to the practical hand. We have no hesitation in commending the work as a serviceable and practical handbook on a subject which has not hitherto received much attention from those qualified to deal with it in a satisfactory manner."—*Mechanical World.*

PATTERN MAKING.

A Practical Treatise, embracing the Main Types of Engineering Construction, and including Gearing, both Hand and Machine-made, Engine Work, Sheaves and Pulleys, Pipes and Columns, Screws, Machine Parts, Pumps and Cocks, the Moulding of Patterns in Loam and Greensand, &c., together with the methods of estimating the weight of Castings; with an Appendix of Tables for Workshop Reference. By JOSEPH G. HORNER, A.M.I.M.E. Second Edition, Enlarged. With 450 Illustrations. Crown 8vo, cloth **7/6**

"A well-written technical guide, evidently written by a man who understands and has practised what he has written about. . . . We cordially recommend it to engineering students, young journeymen, and others desirous of being initiated into the mysteries of pattern-making."—*Builder.*

"More than 400 illustrations help to explain the text, which is, however, always clear and explicit, thus rendering the work an excellent *vade mecum* for the apprentice who desires to become master of his trade."—*English Mechanic.*

MECHANICAL ENGINEERING TERMS

(Lockwood's Dictionary of). Embracing those current in the Drawing Office, Pattern Shop, Foundry, Fitting, Turning, Smiths', and Boiler Shops, &c., &c. Comprising upwards of 6,000 Definitions. Edited by JOSEPH G. HORNER, A.M.I.M.E. Second Edition, Revised, with Additions. Crown 8vo, cloth **7/6**

"Just the sort of handy dictionary required by the various trades engaged in mechanical engineering. The practical engineering pupil will find the book of great value in his studies, and every foreman engineer and mechanic should have a copy."—*Building News.*

"Not merely a dictionary, but, to a certain extent, also a most valuable guide. It strikes us as a happy idea to combine with a definition of the phrase useful information on the subject of which it treats."—*Machinery Market.*

TOOTHED GEARING.

A Practical Handbook for Offices and Workshops. By JOSEPH HORNER, A.M.I.M.E. With 184 Illustrations. Crown 8vo, cloth **6/0**

"We must give the book our unqualified praise for its thoroughness of treatment, and we can heartily recommend it to all interested as the most practical book on the subject yet written."—*Mechanical World.*

FIRES, FIRE-ENGINES, AND FIRE BRIGADES.

With a History of Fire-Engines, their Construction, Use, and Management; Foreign Fire Systems; Hints on Fire-Brigades, &c. By CHARLES F. T. YOUNG, C.E. 8vo, cloth . . . . . **£1 4s.**

"To such of our readers as are interested in the subject of fires and fire apparatus we can most heartily commend this book."—*Engineering.*

Digitized by Google

STONE-WORKING MACHINERY.

A Manual dealing with the Rapid and Economical Conversion of Stone. With Hints on the Arrangement and Management of Stone Works. By M. Powis Bale, M.I.M.E. Second Edition, enlarged. With Illustrations. Crown 8vo, cloth. [*Just Published.* **9/0**

"The book should be in the hands of every mason or student of stonework."—*Colliery Guardian.*

"A capital handbook for all who manipulate stone for building or ornamental purposes."—*Machinery Market.*

PUMPS AND PUMPING.

A Handbook for Pump Users. Being Notes on Selection, Construction, and Management. By M. Powis Bale, M.I.M.E. Third Edition, Revised. Crown 8vo, cloth. [*Just Published.* **2/6**

"The matter is set forth as concisely as possible. In fact, condensation rather than diffuseness has been the author's aim throughout; yet he does not seem to have omitted anything likely to be of use."—*Journal of Gas Lighting.*

"Thoroughly practical and simply and clearly written."—*Glasgow Herald.*

MILLING MACHINES AND PROCESSES.

A Practical Treatise on Shaping Metals by Rotary Cutters. Including Information on Making and Grinding the Cutters. By Paul N. Hasluck, Author of "Lathe-Work." 352 pp. With upwards of 300 Engravings. Large crown 8vo, cloth **12/6**

"A new departure in engineering literature. . . . We can recommend this work to all interested in milling machines; it is what it professes to be—a practical treatise."—*Engineer.*

"A capital and reliable book which will no doubt be of considerable service both to those who are already acquainted with the process as well as to those who contemplate its adoption."—*Industries.*

LATHE-WORK.

A Practical Treatise on the Tools, Appliances, and Processes employed in the Art of Turning. By Paul N. Hasluck. Sixth Edition. Crown 8vo, cloth **5/0**

"Written by a man who knows not only how work ought to be done, but who also knows how to do it, and how to convey his knowledge to others. To all turners this book would be valuable."—*Engineering.*

"We can safely recommend the work to young engineers. To the amateur it will simply be invaluable. To the student it will convey a great deal of useful information."—*Engineer.*

SCREW-THREADS,

And Methods of Producing Them. With numerous Tables and complete Directions for using Screw-Cutting Lathes. By Paul N. Hasluck, Author of "Lathe-Work," &c. With Seventy-four Illustrations. Fourth Edition, Re-written and Enlarged. Waistcoat-pocket size **1/6**

"Full of useful information, hints and practical criticism. Taps, dies, and screwing tools generally are illustrated and their actions described."—*Mechanical World.*

"It is a complete compendium of all the details of the screw-cutting lathe; in fact a *multum-in-parvo* on all the subjects it treats upon."—*Carpenter and Builder.*

TABLES AND MEMORANDA FOR ENGINEERS, MECHANICS, ARCHITECTS, BUILDERS, &c.

Selected and Arranged by Francis Smith. Sixth Edition, Revised, including Electrical Tables, Formulæ, and Memoranda. Waistcoat-pocket size, limp leather. [*Just Published.* **1/6**

"It would, perhaps, be as difficult to make a small pocket-book selection of notes and formulæ to suit ALL engineers as it would be to make a universal medicine; but Mr. Smith's waistcoat-pocket collection may be looked upon as a successful attempt."—*Engineer.*

"The best example we have ever seen of 270 pages of useful matter packed into the dimensions of a card-case."—*Building News.* "A veritable pocket treasury of knowledge."—*Iron.*

POCKET GLOSSARY OF TECHNICAL TERMS.

English-French, French-English; with Tables suitable for the Architectural, Engineering, Manufacturing, and Nautical Professions. By John James Fletcher, Engineer and Surveyor. Second Edition, Revised and Enlarged, 200 pp. Waistcoat-pocket size, limp leather **1/6**

"It is a very great advantage for readers and correspondents in France and England to have so large a number of the words relating to engineering and manufacturers collected in a lilliputian volume. The little book will be useful both to students and travellers."—*Architect.*

"The glossary of terms is very complete, and many of the Tables are new and well arranged. We cordially commend the book."—*Mechanical World.*

Digitized by Google

THE ENGINEER'S YEAR BOOK FOR 1900.

Comprising Formulæ, Rules, Tables, Data and Memoranda in Civil, Mechanical, Electrical, Marine and Mine Engineering. By H. R. KEMPE, A.M. Inst. C.E., M.I.E.E., Technical Officer of the Engineer-in-Chief's Office, General Post Office, London, Author of "A Handbook of Electrical Testing." "The Electrical Engineer's Pocket-Book," &c. With about 1,000 Illustrations, specially Engraved for the work. Crown 8vo, 800 pp., leather. [*Just Published.* **8/0**

"Represents an enormous quantity of work, and forms a desirable book of reference."—*The Engineer.*

"The volume is distinctly in advance of most similar publications in this country."—*Engineering.*

"This valuable and well-designed book of reference meets the demands of all descriptions of engineers."—*Saturday Review.*

"Teems with up-to-date information in every branch of engineering and construction."—*Building News.*

"The needs of the engineering profession could hardly be supplied in a more admirable, complete and convenient form. To say that it more than sustains all comparisons is praise of the highest sort, and that may justly be said of it."—*Mining Journal.*

"There is certainly room for the newcomer, which supplies explanations and directions, as well as formulæ and tables. It deserves to become one of the most successful of the technical annuals."—*Architect.*

"Brings together with great skill all the technical information which an engineer has to use day by day. It is in every way admirably equipped, and is sure to prove successful."—*Scotsman.*

"The up-to-dateness of Mr. Kempe's compilation is a quality that will not be lost on the busy people for whom the work is intended."—*Glasgow Herald.*

THE PORTABLE ENGINE.

A Practical Manual on its Construction and Management. For the use of Owners and Users of Steam Engines generally. By WILLIAM DYSON WANSBROUGH. Crown 8vo, cloth **3/6**

"This is a work of value to those who use steam machinery. . . . Should be read by every one who has a steam engine, on a farm or elsewhere."—*Mark Lane Express.*

"We cordially commend this work to buyers and owners of steam-engines, and to those who have to do with their construction or use."—*Timber Trades Journal.*

"Such a general knowledge of the steam-engine as Mr. Wansbrough furnishes to the reader should be acquired by all intelligent owners and others who use the steam-engine."—*Building News.*

"An excellent text-book of this useful form of engine. The 'Hints to Purchasers' contain a good deal of common-sense and practical wisdom."—*English Mechanic.*

IRON AND STEEL.

A Work for the Forge, Foundry, Factory, and Office. Containing ready, useful, and trustworthy Information for Ironmasters and their Stock-takers; Managers of Bar, Rail, Plate, and Sheet Rolling Mills; Iron and Metal Founders; Iron Ship and Bridge Builders; Mechanical, Mining, and Consulting Engineers; Architects, Contractors, Builders, &c. By CHARLES HOARE, Author of "The Slide Rule," &c. Ninth Edition. 32mo, leather . **6/0**

"For comprehensiveness the book has not its equal."—*Iron.*

"One of the best of the pocket books."—*English Mechanic.*

CONDENSED MECHANICS.

A Selection of Formulæ, Rules, Tables, and Data or the Use of Engineering Students, Science Classes, &c. In accordance with the Requirements of the Science and Art Department. By W. G. CRAWFORD HUGHES, A.M.I.C.E. Crown 8vo, cloth **2/6**

"The book is well fitted or those who are either confronted with practical problems in their work, or are preparing for examination and wish to refresh their knowledge by going through their formulæ again."—*Marine Engineer.*

"It is well arranged, and meets the wants of those for whom it is intended."—*Railway News.*

THE SAFE USE OF STEAM.

Containing Rules for Unprofessional Steam Users. By an ENGINEER. Seventh Edition. Sewed . . . . . **6d.**

"If steam-users would but learn this little book by heart, boiler explosions would become sensations by their rarity."—*English Mechanic.*

HEATING BY HOT WATER.

With Information and Suggestions on the best Methods of Heating Public, Private and Horticultural Buildings. By WALTER JONES. Second Edition. With 96 Illustrations, crown 8vo, cloth . . . . . *Net* **2/6**

"We confidently recommend all interested in heating by hot water to secure a copy of this valuable little treatise."—*The Plumber and Decorator.*

Digitized by Google

THE LOCOMOTIVE ENGINE.

The Autobiography of an Old Locomotive Engine. By ROBERT WEATHERBURN, M.I.M.E. With Illustrations and Portraits of GEORGE and ROBERT STEPHENSON. Crown 8vo, cloth. [*Just Published.* *Net* **2/6**

SUMMARY OF CONTENTS:—PROLOGUE.—CYLINDERS.—MOTIONS.—CONNECTING RODS.—FRAMES.—WHEELS.—PUMPS, CLACKS, &c.—INJECTORS.—BOILERS.—SMOKE BOX.—CHIMNEY.—WEATHER BOARD AND AWNING.—INTERNAL DISSENSIONS.—ENGINE DRIVERS, &c.

"It would be difficult to imagine anything more ingeniously planned, more cleverly worked out, and more charmingly written. Readers cannot fail to find the volume most enjoyable."—*Glasgow Herald.*

THE LOCOMOTIVE ENGINE AND ITS DEVELOPMENT.

A Popular Treatise on the Gradual Improvements made in Railway Engines between 1803 and 1896. By CLEMENT E. STRETTON, C.E. Fifth Edition, Enlarged. With 120 Illustrations. Crown 8vo, cloth. [*Just Published.* **3/6**

"Students of railway history and all who are interested in the evolution of the modern locomotive will find much to attract and entertain in this volume."—*The Times*

LOCOMOTIVE ENGINE DRIVING.

A Practical Manual for Engineers in Charge of Locomotive Engines. By MICHAEL REYNOLDS, Member of the Society of Engineers, formerly Locomotive Inspector, L. B. & S. C. R. Ninth Edition. Including a KEY TO THE LOCOMOTIVE ENGINE. Crown 8vo, cloth **4/6**

"Mr. Reynolds has supplied a want, and has supplied it well. We can confidently recommend the book not only to the practical driver, but to everyone who takes an interest in the performance of locomotive engines."—*The Engineer.*

"Mr. Reynolds has opened a new chapter in the literature of the day. His treatise is admirable."—*Athenæum.*

THE MODEL LOCOMOTIVE ENGINEER,

Fireman, and Engine-Boy. Comprising a Historical Notice of the Pioneer Locomotive Engines and their Inventors. By MICHAEL REYNOLDS. Second Edition, with Revised Appendix. Crown 8vo, cloth. [*Just Published.* **4/6**

"From the technical knowledge of the author, it will appeal to the railway man of to-day more forcibly than anything written by Dr. Smiles. . . . The volume contains information of a technical kind, and facts that every driver should be familiar with."—*English Mechanic.*

"We should be glad to see this book in the possession of everyone in the kingdom who has ever laid, or is to lay, hands on a locomotive engine."—*Iron.*

CONTINUOUS RAILWAY BRAKES.

A Practical Treatise on the several Systems in Use in the United Kingdom: their Construction and Performance. With copious Illustrations and numerous Tables. By MICHAEL REYNOLDS. 8vo, cloth **9/0**

"A popular explanation of the different brakes. It will be of great assistance in forming public opinion, and will be studied with benefit by those who take an interest in the brake."—*English Mechanic.*

STATIONARY ENGINE DRIVING.

A Practical Manual for Engineers in Charge of Stationary Engines. By MICHAEL REYNOLDS. Fifth Edition. Crown 8vo, cloth **4/6**

"The author is thoroughly acquainted with his subjects, and his advice on the various points treated is clear and practical. . . . He has produced a manual which is an exceedingly useful one for the class for whom it is specially intended."—*Engineering.*

"Our author leaves no stone unturned. He is determined that his readers shall not only know something about the stationary engine, but all about it."—*Engineer.*

ENGINE-DRIVING LIFE.

Stirring Adventure and Incidents in the Lives of Locomotive Engine-Drivers. By MICHAEL REYNOLDS. Third Edition. Crown 8vo, cloth . **1/6**

"Perfectly fascinating. Wilkie Collins's most thrilling conceptions are thrown into the shade by true incidents, endless in their variety, related in every page."—*North British Mail.*

THE ENGINEMAN'S POCKET COMPANION,

And Practical Educator for Enginemen, Boiler Attendants, and Mechanics. By MICHAEL REYNOLDS. With 45 Illustrations and numerous Diagrams. Third Edition, Revised. Royal 18mo, strongly bound for pocket wear . **3/6**

"This admirable work is well suited to accomplish its object, being the honest workmanship of a competent engineer."—*Glasgow Herald.*

Digitized by Google

CIVIL ENGINEERING, SURVEYING, &c.

LIGHT RAILWAYS FOR THE UNITED KINGDOM, INDIA, AND THE COLONIES.

A Practical Handbook setting forth the Principles on which Light Railways should be Constructed, Worked, and Financed; and detailing the Cost of Construction, Equipment, Revenue and Working Expenses of Local Railways already established in the above-mentioned countries, and in Belgium, France, Switzerland, &c. By J. C. MACKAY, F.G.S., A.M. Inst. C.E. Illustrated with Plates and Diagrams. Medium 8vo, cloth. [*Just Published.* **16/0**

"Mr. Mackay's volume is clearly and concisely written, admirably arranged, and freely illustrated. The book is exactly what has been long wanted. We recommend it to all interested in the subject. It is sure to have a wide sale."—*Railway News.*

"Those who desire to have within reach general information concerning almost all the light railway systems in the world will do well to buy Mr. Mackay's book."—*Engineer.*

"This work appears very opportunely, when the extension of the system on a large scale to England is at last being mooted. In its pages we find all the information that the heart of man can desire on the subject. . . . every detail in its story, founded on the experience of other countries and applied to the possibilities of England, is put before us."—*Spectator.*

PRACTICAL TUNNELLING.

Explaining in detail Setting-out the Works, Shaft-sinking, and Heading-driving, Ranging the Lines and Levelling underground, Sub-Excavating, Timbering and the Construction of the Brickwork of Tunnels, with the amount of Labour required for, and the Cost of, the various portions of the work. By FREDERICK W. SIMMS, M. Inst. C.E. Fourth Edition, Revised and Further Extended, including the most recent (1895) Examples of Sub-aqueous and other Tunnels, by D. KINNEAR CLARK, M. Inst. C.E. Imperial 8vo, with 34 Folding Plates and other Illustrations. Cloth. [*Just Published.* **£2 2s.**

"The present (1896) edition has been brought right up to date, and is thus rendered a work to which civil engineers generally should have ready access, and to which engineers who have construction work can hardly afford to be without, but which to the younger members of the profession is invaluable, as from its pages they can learn the state to which the science of tunnelling has attained."—*Railway News.*

"The estimation in which Mr. Simms's book has been held for many years cannot be more truly expressed than in the words of the late Prof. Rankine: 'The best source of information on the subject of tunnels is Mr. F. W. Simms's work on Practical Tunnelling.'"—*Architect.*

THE WATER SUPPLY OF TOWNS AND THE CONSTRUCTION OF WATER-WORKS.

A Practical Treatise for the Use of Engineers and Students of Engineering. By W. K. BURTON, A.M. Inst. C.E., Professor of Sanitary Engineering in the Imperial University, Tokyo, Japan, and Consulting Engineer to the Tokyo Water-works. Second Edition, Revised and Extended. With numerous Plates and Illustrations. Super-royal 8vo, buckram. [*Just Published.* **25/0**

I. INTRODUCTORY.—II. DIFFERENT QUALITIES OF WATER.—III. QUANTITY OF WATER TO BE PROVIDED.—IV. ON ASCERTAINING WHETHER A PROPOSED SOURCE OF SUPPLY IS SUFFICIENT.—V. ON ESTIMATING THE STORAGE CAPACITY REQUIRED TO BE PROVIDED.—VI. CLASSIFICATION OF WATER-WORKS.—VII. IMPOUNDING RESERVOIRS.—VIII. EARTHWORK DAMS.—IX. MASONRY DAMS.—X. THE PURIFICATION OF WATER.—XI. SETTLING RESERVOIRS.—XII. SAND FILTRATION.—XIII. PURIFICATION OF WATER BY ACTION OF IRON, SOFTENING OF WATER BY ACTION OF LIME, NATURAL FILTRATION.—XIV. SERVICE OR CLEAN WATER RESERVOIRS—WATER TOWERS—STAND PIPES.—XV. THE CONNECTION OF SETTLING RESERVOIRS, FILTER BEDS AND SERVICE RESERVOIRS.—XVI. PUMPING MACHINERY.—XVII. FLOW OF WATER IN CONDUITS—PIPES AND OPEN CHANNELS.—XVIII. DISTRIBUTION SYSTEMS.—XIX. SPECIAL PROVISIONS FOR THE EXTINCTION OF FIRE.—XX. PIPES FOR WATER-WORKS.—XXI. PREVENTION OF WASTE OF WATER.—XXII. VARIOUS APPLICATIONS USED IN CONNECTION WITH WATER-WORKS.

APPENDIX I. By PROF. JOHN MILNE, F.R.S.—CONSIDERATIONS CONCERNING THE PROBABLE EFFECTS OF EARTHQUAKES ON WATER-WORKS, AND THE SPECIAL PRECAUTIONS TO BE TAKEN IN EARTHQUAKE COUNTRIES.

APPENDIX II. By JOHN DE RIJKE, C.E.—ON SAND DUNES AND DUNE SAND AS A SOURCE OF WATER SUPPLY.

"The chapter upon filtration of water is very complete, and the details of construction well illustrated. . . . The work should be specially valuable to civil engineers engaged in work in Japan, but the interest is by no means confined to that locality."—*Engineer.*

"We congratulate the author upon the practical commonsense shown in the preparation of this work. . . . The plates and diagrams have evidently been prepared with great care, and cannot fail to be of great assistance to the student."—*Builder.*

"The whole art of water-works construction is dealt with in a clear and comprehensive fashion in this handsome volume. . . . Mr. Burton's practical treatise shows in all its sections the fruit of independent study and individual experience. It is largely based upon his own practice in the branch of engineering of which it treats."—*Saturday Review.*

Digitized by Google

THE WATER SUPPLY OF CITIES AND TOWNS.

By WILLIAM HUMBER, A. M. Inst. C.E., and M. Inst. M.E., Author of "Cast and Wrought Iron Bridge Construction," &c., &c. Illustrated with 50 Double Plates, 1 Single Plate, Coloured Frontispiece, and upwards of 250 Woodcuts, and containing 400 pp. of Text. Imp. 4to, elegantly and substantially half-bound in morocco . . . . . *Net* **£6 6s.**

LIST OF CONTENTS.

I. HISTORICAL SKETCH OF SOME OF THE MEANS THAT HAVE BEEN ADOPTED FOR THE SUPPLY OF WATER TO CITIES AND TOWNS.—II. WATER AND THE FOREIGN MATTER USUALLY ASSOCIATED WITH IT.—III. RAINFALL AND EVAPORATION.—IV. SPRINGS AND THE WATER-BEARING FORMATIONS OF VARIOUS DISTRICTS.—V. MEASUREMENT AND ESTIMATION OF THE FLOW OF WATER.—VI. ON THE SELECTION OF THE SOURCE OF SUPPLY.—VII. WELLS.—VIII. RESERVOIRS.—IX. THE PURIFICATION OF WATER.—X. PUMPS.—XI. PUMPING MACHINERY.—XII. CONDUITS.—XIII. DISTRIBUTION OF WATER.—XIV. METERS, SERVICE PIPES, AND HOUSE FITTINGS.—XV. THE LAW OF ECONOMY OF WATER-WORKS.—XVI. CONSTANT AND INTERMITTENT SUPPLY.—XVII. DESCRIPTION OF PLATES.—APPENDICES, GIVING TABLES OF RATES OF SUPPLY, VELOCITIES, &c., &c., TOGETHER WITH SPECIFICATIONS OF SEVERAL WORKS ILLUSTRATED, AMONG WHICH WILL BE FOUND: ABERDEEN, BIDEFORD, CANTERBURY, DUNDEE, HALIFAX, LAMBETH, ROTHERHAM, DUBLIN, AND OTHERS.

"The most systematic and valuable work upon water supply hitherto produced in English, or in any other language. . . . Mr. Humber's work is characterised almost throughout by an exhaustiveness much more distinctive of French and German than of English technical treatises."—*Engineer.*

RURAL WATER SUPPLY.

A Practical Handbook on the Supply of Water and Construction of Water-works for small Country Districts. By ALLAN GREENWELL, A.M.I.C.E., and W. T. CURRY, A.M.I.C.E., F.G.S. With Illustrations. Second Edition, Revised. Crown 8vo, cloth. [*Just Published.* **5/0**

"We conscientiously recommend it as a very useful book for those concerned in obtaining water for small districts, giving a great deal of practical information in a small compass."—*Builder.*

"The volume contains valuable information upon all matters connected with water supply. . . . It is full of details on points which are continually before water-works engineers."—*Nature.*

HYDRAULIC POWER ENGINEERING.

A Practical Manual on the Concentration and Transmission of Power by Hydraulic Machinery. By G. CROYDON MARKS, A.M. Inst. C.E. With nearly 200 Illustrations. 8vo, cloth. [*Just Published. Net* **9/0**

SUMMARY OF CONTENTS:—PRINCIPLES OF HYDRAULICS.—THE OBSERVED FLOW OF WATER.—HYDRAULIC PRESSURES, MATERIAL.—TEST LOAD PACKINGS FOR SLIDING SURFACES.—PIPE JOINTS.—CONTROLLING VALVES.—PLATFORM LIFTS.—WORKSHOP, FACTORY, AND DOCK CRANES.—HYDRAULIC ACCUMULATORS.—PRESSES.—SHEET METAL WORKING AND FORGING MACHINERY.—HYDRAULIC RIVETTERS.—HAND, POWER, AND STEAM PUMPS.—TURBINES.—IMPULSE AND RE-ACTION TURBINES.—DESIGN OF TURBINES.—WATER WHEELS.—HYDRAULIC ENGINES.—RECENT ACHIEVEMENTS.—APPENDIX OF TABLES.

HYDRAULIC TABLES, CO-EFFICIENTS, & FORMULÆ.

For Finding the Discharge of Water from Orifices, Notches, Weirs, Pipes, and Rivers. With New Formulæ, Tables, and General Information on Rain-fall, Catchment-Basins, Drainage, Sewerage, Water Supply for Towns and Mill Power. By JOHN NEVILLE, Civil Engineer, M.R.I.A. Third Edition, revised, with additions. Numerous Illustrations. Crown 8vo, cloth . **14/0**

"It is, of all English books on the subject, the one nearest to completeness."—*Architect.*

HYDRAULIC MANUAL.

Consisting of Working Tables and Explanatory Text. Intended as a Guide in Hydraulic Calculations and Field Operations. By LOWIS D'A. JACKSON, Author of "Aid to Survey Practice," "Modern Metrology," &c. Fourth Edition, Enlarged. Large crown 8vo, cloth **16/0**

"The author has constructed a manual which may be accepted as a trustworthy guide to this branch of the engineer's profession."—*Engineering.*

WATER ENGINEERING.

A Practical Treatise on the Measurement, Storage, Conveyance, and Utilisation of Water for the Supply of Towns, for Mill Power, and for other Purposes. By C. SLAGG, A. M. Inst. C.E. Second Edition. Crown 8vo, cloth . **7/6**

"As a small practical treatise on the water supply of towns, and on some applications of water-power, the work is in many respects excellent."—*Engineering.*

Digitized by Google

EMBANKMENT AND RECLAMATION OF LAND.

A Practical Handbook for the use of Engineers. By ALEX. BEAZELEY, M. Inst. C.E. Crown 8vo, cloth. [*Just Published. Net* **7/6**

MASONRY DAMS FROM INCEPTION TO COMPLETION.

Including numerous Formulæ, Forms of Specification and Tender, Pocket Diagram of Forces, &c. For the use of Civil and Mining Engineers. By C. F. COURTNEY, M. Inst. C.E. 8vo, cloth. [*Just Published.* **9/0**

"The volume contains a good deal of valuable data, and furnishes the engineer with practical advice. The author deals with his subject from the inception to the finish. Many useful suggestions will be found in the remarks on site and position, location of dam, foundations and construction."—*Building News.*

RIVER BARS.

The Causes of their Formation, and their Treatment by "Induced Tidal Scour;" with a Description of the Successful Reduction by this Method of the Bar at Dublin. By I. J. MANN, Assist. Eng. to the Dublin Port and Docks Board. Royal 8vo, cloth **7/6**

"We recommend all interested in harbour works—and, indeed, those concerned in the improvements of rivers generally—to read Mr. Mann's interesting work."—*Engineer.*

TRAMWAYS: THEIR CONSTRUCTION AND WORKING.

Embracing a Comprehensive History of the System; with an exhaustive Analysis of the Various Modes of Traction, including Horse Power, Steam, Cable Traction, Electric Traction, &c.; a Description of the Varieties of Rolling Stock; and ample Details of Cost and Working Expenses. New Edition, Thoroughly Revised, and Including the Progress recently made in Tramway Construction, &c., &c. By D. KINNEAR CLARK, M. Inst. C.E. With 400 Illustrations. 8vo, 780 pp., buckram. [*Just Published.* **28/0**

"Although described as a new edition, this book is really a new one, a large part of it, which covers historical ground, having been re-written and amplified; while the parts which relate to all that has been done since 1882 appear in this edition only. It is sixteen years since the first edition appeared, and twelve years since the supplementary volume to the first book was published. After a lapse, then, of twelve years, it is obvious that the author has at his disposal a vast quantity of descriptive and statistical information, with which he may, and has, produced a volume of great value to all interested in tramway construction and working. The new volume is one which will rank, among tramway engineers and those interested in tramway working, with his world-famed book on railway machinery."—*The Engineer.*

PRACTICAL SURVEYING.

A Text-Book for Students preparing for Examinations or for Survey-work in the Colonies. By GEORGE W. USILL, A.M.I.C.E. With 4 Plates and upwards of 330 Illustrations. Sixth Edition. Including Tables of Natural Sines, Tangents, Secants, &c. Crown 8vo, cloth **7/6**; or, on THIN PAPER, leather, gilt edges, for pocket use. [*Just Published.* **12/6**

"The best forms of instruments are described as to their construction, uses and modes of employment, and there are innumerable hints on work and equipment such as the author, in his experience as surveyor, draughtsman and teacher, has found necessary, and which the student in his inexperience will find most serviceable."—*Engineer.*

"The latest treatise in the English language on surveying, and we have no hesitation in saying that the student will find it a better guide than any of its predecessors. Deserves to be recognised as the first book which should be put in the hands of a pupil of Civil Engineering."—*Architect.*

SURVEYING WITH THE TACHEOMETER.

A practical Manual for the use of Civil and Military Engineers and Surveyors. Including two series of Tables specially computed for the Reduction of Readings from Sexagesimal and from Centesimal Degrees. By NEIL KENNEDY, M. Inst. C.E. Demy 8vo, with Diagrams and Plates.

[*In the Press. Price, about* **10/6** *Net.*

AID TO SURVEY PRACTICE.

For Reference in Surveying, Levelling, and Setting-out; and in Route Surveys of Travellers by Land and Sea. With Tables, Illustrations, and Records. By LOWIS D'A. JACKSON, A.M.I.C.E. 8vo, cloth **12/6**

"A valuable *vade-mecum* for the surveyor. We recommend this book as containing an admirable supplement to the teaching of the accomplished surveyor."—*Athenæum.*

"The author brings to his work a fortunate union of theory and practical experience which, aided by a clear and lucid style of writing, renders the book a very useful one."—*Builder.*

Digitized by Google

ENGINEER'S & MINING SURVEYOR'S FIELD BOOK.

Consisting of a Series of Tables, with Rules, Explanations of Systems, and use of Theodolite for Traverse Surveying and plotting the work with minute accuracy by means of Straight Edge and Set Square only; Levelling with the Theodolite, Casting-out and Reducing Levels to Datum, and Plotting Sections in the ordinary manner; Setting-out Curves with the Theodolite by Tangential Angles and Multiples with Right and Left-hand Readings of the Instrument; Setting-out Curves without Theodolite on the System of Tangential Angles by Sets of Tangents and Offsets; and Earthwork Tables to 80 feet deep, calculated for every 6 inches in depth. By W. DAVIS HASKOLL, C.E. With numerous Woodcuts. Fourth Edition, Enlarged. Crown 8vo, cloth . **12/0**

"The book is very handy; the separate tables of sines and tangents to every minute will make it useful for many other purposes, the genuine traverse tables existing all the same."—*Athenæum.*

"Every person engaged in engineering field operations will estimate the importance of such a work and the amount of valuable time which will be saved by reference to a set of reliable tables prepared with the accuracy and fulness of those given in this volume."—*Railway News.*

LAND AND MARINE SURVEYING.

In Reference to the Preparation of Plans for Roads and Railways; Canals, Rivers, Towns' Water Supplies; Docks and Harbours. With Description and Use of Surveying Instruments. By W. DAVIS HASKOLL, C.E. Second Edition, Revised, with Additions. Large crown 8vo, cloth . . . **9/0**

"This book must prove of great value to the student. We have no hesitation in recommending it, feeling assured that it will more than repay a careful study."—*Mechanical World.*

"A most useful book for the student. We strongly recommend it as a carefully-written and valuable text-book. It enjoys a well-deserved repute among surveyors."—*Builder.*

"This volume cannot fail to prove of the utmost practical utility. It may be safely recommended to all students who aspire to become clean and expert surveyors."—*Mining Journal.*

PRINCIPLES AND PRACTICE OF LEVELLING.

Showing its Application to Purposes of Railway and Civil Engineering in the Construction of Roads; with Mr. TELFORD'S Rules for the same. By FREDERICK W. SIMMS, F.G.S., M. Inst. C.E. Eighth Edition, with the addition of LAW'S Practical Examples for Setting-out Railway Curves, and TRAUTWINE'S Field Practice of Laying-out Circular Curves. With 7 Plates and numerous Woodcuts, 8vo, cloth **8/6**

*** TRAUTWINE on CURVES may be had separate **5/0**

"The text-book on levelling in most of our engineering schools and colleges."—*Engineer.*

"The publishers have rendered a substantial service to the profession, especially to the younger members, by bringing out the present edition of Mr. Simms's useful work."—*Engineering.*

AN OUTLINE OF THE METHOD OF CONDUCTING A TRIGONOMETRICAL SURVEY.

For the Formation of Geographical and Topographical Maps and Plans, Military Reconnaissance, LEVELLING, &c., with Useful Problems, Formulæ, and Tables. By Lieut.-General FROME, R.E. Fourth Edition, Revised and partly Re-written by Major-General Sir CHARLES WARREN, G.C.M.G., R.E. With 19 Plates and 115 Woodcuts, royal 8vo, cloth **16/0**

"No words of praise from us can strengthen the position so well and so steadily maintained by this work. Sir Charles Warren has revised the entire work, and made such additions as were necessary to bring every portion of the contents up to the present date."—*Broad Arrow.*

TABLES OF TANGENTIAL ANGLES AND MULTIPLES FOR SETTING-OUT CURVES.

From 5 to 200 Radius. By A. BEAZELEY, M. Inst. C.E. 6th Edition, Revised. With an Appendix on the use of the Tables for Measuring up Curves. Printed on 50 Cards, and sold in a cloth box, waistcoat-pocket size. [*Just Published.* **3/6**

"Each table is printed on a card, which, placed on the theodolite, leaves the hands free to manipulate the instrument—no small advantage as regards the rapidity of work."—*Engineer.*

"Very handy: a man may know that all his day's work must fall on two of these cards, which he puts into his own card-case, and leaves the rest behind."—*Athenæum.*

HANDY GENERAL EARTH-WORK TABLES.

Giving the Contents in Cubic Yards of Centre and Slopes of Cuttings and Embankments from 3 inches to 80 feet in Depth or Height, for use with either 66 feet Chain or 100 feet Chain. By J. H. WATSON BUCK, M. Inst. C.E. On a Sheet mounted in cloth case. [*Just Published.* **3/6**

Digitized by Google

EARTHWORK TABLES.

Showing the Contents in Cubic Yards of Embankments, Cuttings, &c., of Heights or Depths up to an average of 80 feet. By JOSEPH BROADBENT, C.E., and FRANCIS CAMPIN, C.E. Crown 8vo, cloth **5/0**

"The way in which accuracy is attained, by a simple division of each cross section into three elements, two in which are constant and one variable, is ingenious."—*Athenæum.*

A MANUAL ON EARTHWORK.

By ALEX. J. S. GRAHAM, C.E. With numerous Diagrams. Second Edition. 18mo, cloth **2/6**

THE CONSTRUCTION OF LARGE TUNNEL SHAFTS.

A Practical and Theoretical Essay. By J. H. WATSON BUCK, M. Inst. C.E., Resident Engineer, L. and N. W. R. With Folding Plates, 8vo, cloth **12/0**

"Many of the methods given are of extreme practical value to the mason, and the observations on the form of arch, the rules for ordering the stone, and the construction of the templates, will be found of considerable use. We commend the book to the engineering profession."—*Building News.*

"Will be regarded by civil engineers as of the utmost value, and calculated to save much time and obviate many mistakes."—*Colliery Guardian.*

CAST & WROUGHT IRON BRIDGE CONSTRUCTION

(A Complete and Practical Treatise on), including Iron Foundations. In Three Parts.—Theoretical, Practical, and Descriptive. By WILLIAM HUMBER, A. M. Inst. C.E., and M. Inst. M.E. Third Edition, revised and much improved, with 115 Double Plates (20 of which now first appear in this edition), and numerous Additions to the Text. In 2 vols., imp. 4to, half-bound in morocco . . . . . **£6 16s. 6d.**

"A very valuable contribution to the standard literature of civil engineering. In addition to elevations, plans, and sections, large scale details are given, which very much enhance the instructive worth of those illustrations."—*Civil Engineer and Architect's Journal.*

"Mr. Humber's stately volumes, lately issued—in which the most important bridges erected during the last five years, under the direction of the late Mr. Brunel, Sir W. Cubitt, Mr. Hawkshaw, Mr. Page, Mr. Fowler, Mr. Hemans, and others among our most eminent engineers, are drawn and specified in great detail."—*Engineer.*

ESSAY ON OBLIQUE BRIDGES

(Practical and Theoretical). With 13 large Plates. By the late GEORGE WATSON BUCK, M.I.C.E. Fourth Edition, revised by his Son, J. H. WATSON BUCK, M.I.C.E.; and with the addition of Description to Diagrams for Facilitating the Construction of Oblique Bridges, by W. H. BARLOW, M.I.C.E. Royal 8vo, cloth **12/0**

"The standard text-book for all engineers regarding skew arches is Mr. Buck's treatise, and it would be impossible to consult a better."—*Engineer.*

"Mr. Buck's treatise is recognised as a standard text-book, and his treatment has divested the subject of many of the intricacies supposed to belong to it. As a guide to the engineer and architect, on a confessedly difficult subject, Mr. Buck's work is unsurpassed."—*Building News.*

THE CONSTRUCTION OF OBLIQUE ARCHES

(A Practical Treatise on). By JOHN HART. Third Edition, with Plates. Imperial 8vo, cloth **8/0**

GRAPHIC AND ANALYTIC STATICS.

In their Practical Application to the Treatment of Stresses in Roofs, Solid Girders, Lattice, Bowstring, and Suspension Bridges, Braced Iron Arches and Piers, and other Frameworks. By R. HUDSON GRAHAM, C.E. Containing Diagrams and Plates to Scale. With numerous Examples, many taken from existing Structures. Specially arranged for Class-work in Colleges and Universities. Second Edition, Revised and Enlarged. 8vo, cloth . **16/0**

"Mr. Graham's book will find a place wherever graphic and analytic statics are used or studied."—*Engineer.*

"The work is excellent from a practical point of view, and has evidently been prepared with much care. The directions for working are simple, and are illustrated by an abundance of well-selected examples. It is an excellent text-book for the practical draughtsman."—*Athenæum.*

WEIGHTS OF WROUGHT IRON & STEEL GIRDERS.

A Graphic Table for Facilitating the Computation of the Weights of Wrought Iron and Steel Girders, &c., for Parliamentary and other Estimates. By J. H. WATSON BUCK, M. Inst. C.E. On a Sheet **2/6**

Digitized by Google

PRACTICAL GEOMETRY.

For the Architect, Engineer, and Mechanic. Giving Rules for the Delineation and Application of various Geometrical Lines, Figures, and Curves. By E. W. TARN, M.A., Architect. 8vo, cloth **9/0**

"No book with the same objects in view has ever been published in which the clearness of the rules laid down and the illustrative diagrams have been so satisfactory."—*Scotsman.*

THE GEOMETRY OF COMPASSES.

Or, Problems Resolved by the mere Description of Circles and the Use of Coloured Diagrams and Symbols. By OLIVER BYRNE. Coloured Plates. Crown 8vo, cloth **3/6**

HANDY BOOK FOR THE CALCULATION OF STRAINS

In Girders and Similar Structures and their Strength. Consisting of Formulæ and Corresponding Diagrams, with numerous details for Practical Application, &c. By WILLIAM HUMBER, A. M. Inst. C.E., &c. Fifth Edition. Crown 8vo, with nearly 100 Woodcuts and 3 Plates, cloth . . . **7/6**

"The formulæ are neatly expressed, and the diagrams good."—*Athenæum.*

"We heartily commend this really *handy* book to our engineer and architect readers."—*English Mechanic.*

TRUSSES OF WOOD AND IRON.

Practical Applications of Science in Determining the Stresses, Breaking Weights, Safe Loads, Scantlings, and Details of Construction. With Complete Working Drawings. By WILLIAM GRIFFITHS, Surveyor. 8vo, cloth. **4/6**

"This handy little book enters so minutely into every detail connected with the construction of roof trusses that no student need be ignorant of these matters."—*Practical Engineer.*

THE STRAINS ON STRUCTURES OF IRONWORK.

With Practical Remarks on Iron Construction. By F. W. SHEILDS, M.I.C.E. 8vo, cloth **5/0**

A TREATISE ON THE STRENGTH OF MATERIALS.

With Rules for Application in Architecture, the Construction of Suspension Bridges, Railways, &c. By PETER BARLOW, F.R.S. A new Edition, revised by his Sons, P. W. BARLOW, F.R.S., and W. H. BARLOW, F.R.S.; to which are added, Experiments by HODGKINSON, FAIRBAIRN, and KIRKALDY; and Formulæ for calculating Girders, &c. Arranged and Edited by WM. HUMBER, A. M. Inst. C.E. 8vo, cloth **18/0**

"Valuable alike to the student, tyro, and the experienced practitioner, it will always rank in future as it has hitherto done, as the standard treatise on that particular subject."—*Engineer.*

"As a scientific work of the first class, it deserves a foremost place on the bookshelves of every civil engineer and practical mechanic."—*English Mechanic.*

STRENGTH OF CAST IRON AND OTHER METALS.

By THOMAS TREDGOLD, C.E. Fifth Edition, including HODGKINSON'S Experimental Researches. 8vo, cloth **12/0**

SAFE RAILWAY WORKING.

A Treatise on Railway Accidents, their Cause and Prevention; with a Description of Modern Appliances and Systems. By CLEMENT E. STRETTON, C.E., Vice-President and Consulting Engineer, Amalgamated Society of Railway Servants. With Illustrations and Coloured Plates. Third Edition, Enlarged. Crown 8vo, cloth **3/6**

"A book for the engineer, the directors, the managers; and, in short, all who wish for information on railway matters will find a perfect encyclopædia in 'Safe Railway Working.'"—*Railway Review.*

"We commend the remarks on railway signalling to all railway managers, especially where a uniform code and practice is advocated."—*Herepath's Railway Journal.*

EXPANSION OF STRUCTURES BY HEAT.

By JOHN KEILY, C.E., late of the Indian Public Works Department. Crown 8vo, cloth **3/6**

"The aim the author has set before him, viz., to show the effects of heat upon metallic and other structures, is a laudable one, for this is a branch of physics upon which the engineer or architect can find but little reliable and comprehensive data in books."—*Builder.*

Digitized by Google

THE PROGRESS OF MODERN ENGINEERING.

Complete in Four Volumes, imperial 4to, half-morocco, price **£12 12s.**
Each volume sold separately, as follows:—

FIRST SERIES, Comprising Civil, Mechanical, Marine, Hydraulic, Railway, Bridge, and other Engineering Works, &c. By WILLIAM HUMBER, A. M. Inst. C.E., &c. Imp. 4to, with 36 Double Plates, drawn to a large scale, Photographic Portrait of John Hawkshaw, C.E., F.R.S., &c., and copious descriptive Letterpress, Specifications, &c. Half-morocco . . **£3 3s.**

LIST OF THE PLATES AND DIAGRAMS.

VICTORIA STATION AND ROOF, L. B. & S. C. R. (8 PLATES); SOUTHPORT PIER (2 PLATES); VICTORIA STATION AND ROOF, L. C. & D. AND G. W. R. (6 PLATES); ROOF OF CREMORNE MUSIC HALL; BRIDGE OVER G. N. RAILWAY; ROOF OF STATION, DUTCH RHENISH RAIL. (2 PLATES); BRIDGE OVER THE THAMES, WEST LONDON EXTENSION RAILWAY (5 PLATES); ARMOUR PLATES: SUSPENSION BRIDGE, THAMES (4 PLATES); THE ALLEN ENGINE; SUSPENSION BRIDGE, AVON (3 PLATES); UNDERGROUND RAILWAY (3 PLATES).

HUMBER'S MODERN ENGINEERING.

SECOND SERIES. Imp. 4to, with 3 Double Plates, Photographic Portrait of Robert Stephenson, C.E., M.P., F.R.S., &c., and copious descriptive Letterpress, Specifications, &c. Half-morocco . . . . . **£3 3s.**

LIST OF THE PLATES AND DIAGRAMS.

BIRKENHEAD DOCKS, LOW WATER BASIN (15 PLATES); CHARING CROSS STATION ROOF, C. C. RAILWAY (3 PLATES); DIGSWELL VIADUCT, GREAT NORTHERN RAILWAY; ROBBERY WOOD VIADUCT, GREAT NORTHERN RAILWAY; IRON PERMANENT WAY CLYDACH VIADUCT, MERTHYR, TREDEGAR, AND ABERGAVENNY RAILWAY; EBBW VIADUCT, MERTHYR, TREDEGAR, AND ABERGAVENNY RAILWAY; COLLEGE WOOD VIADUCT, CORNWALL RAILWAY; DUBLIN WINTER PALACE ROOF (3 PLATES); BRIDGE OVER THE THAMES, L. C. & D. RAILWAY (6 PLATES); ALBERT HARBOUR, GREENOCK (4 PLATES).

HUMBER'S MODERN ENGINEERING.

THIRD SERIES. Imp. 4to, with 40 Double Plates, Photographic Portrait of J. R. M'Clean, late Pres. Inst. C.E., and copious descriptive Letterpress, Specifications, &c. Half-morocco . . . . . **£3 3s.**

LIST OF THE PLATES AND DIAGRAMS.

MAIN DRAINAGE, METROPOLIS.—*North Side.*—MAP SHOWING INTERCEPTION OF SEWERS; MIDDLE LEVEL SEWER (2 PLATES); OUTFALL SEWER, BRIDGE OVER RIVER LEA (3 PLATES); OUTFALL SEWER, BRIDGE OVER MARSH LANE, NORTH WOOLWICH RAILWAY, AND BOW AND BARKING RAILWAY JUNCTION; OUTFALL SEWER, BRIDGE OVER BOW AND BARKING RAILWAY (3 PLATES); OUTFALL SEWER, BRIDGE OVER EAST LONDON WATER-WORKS' FEEDER (2 PLATES); OUTFALL SEWER RESERVOIR (2 PLATES); OUTFALL SEWER, TUMBLING BAY AND OUTLET; OUTFALL SEWER, PENSTOCKS. *South Side.*—OUTFALL SEWER, BERMONDSEY BRANCH (2 PLATES); OUTFALL SEWER, RESERVOIR AND OUTLET (4 PLATES); OUTFALL SEWER, FILTH HOIST; SECTIONS OF SEWERS NORTH AND SOUTH SIDES).

THAMES EMBANKMENT.—SECTION OF RIVER WALL; STEAMBOAT PIER, WESTMINSTER (2 PLATES); LANDING STAIRS BETWEEN CHARING CROSS AND WATERLOO BRIDGES; YORK GATE (2 PLATES); OVERFLOW AND OUTLET AT SAVOY STREET SEWER (3 PLATES); STEAMBOAT PIER, WATERLOO BRIDGE (3 PLATES); JUNCTION OF SEWERS, PLANS AND SECTIONS; GULLIES, PLANS AND SECTIONS; ROLLING STOCK; GRANITE AND IRON FORTS.

HUMBER'S MODERN ENGINEERING.

FOURTH SERIES. Imp. 4to, with 36 Double Plates, Photographic Portrait of John Fowler, late Pres. Inst. C.E., and copious descriptive Letterpress, Specifications, &c. Half-morocco . . . . . **£3 3s.**

LIST OF THE PLATES AND DIAGRAMS.

ABBEY MILLS PUMPING STATION, MAIN DRAINAGE, METROPOLIS (4 PLATES) BARROW DOCKS (5 PLATES); MANQUIS VIADUCT, SANTIAGO AND VALPARAISO RAILWAY, (2 PLATES); ADAM'S LOCOMOTIVE, ST. HELEN'S CANAL RAILWAY (2 PLATES); CANNON STREET STATION ROOF, CHARING CROSS RAILWAY (3 PLATES); ROAD BRIDGE OVER THE RIVER MOKA (2 PLATES); TELEGRAPHIC APPARATUS FOR MESOPOTAMIA; VIADUCT OVER THE RIVER WYE, MIDLAND RAILWAY (3 PLATES); ST. GERMANS VIADUCT, CORNWALL RAILWAY (2 PLATES); WROUGHT-IRON CYLINDER FOR DIVING BELL; MILLWALL DOCKS (6 PLATES); MILROY'S PATENT EXCAVATOR; METROPOLITAN DISTRICT RAILWAY (6 PLATES); HARBOURS, PORTS, AND BREAKWATERS (3 PLATES).

Digitized by Google

MARINE ENGINEERING, SHIPBUILDING, NAVIGATION, &c.

THE NAVAL ARCHITECT'S AND SHIPBUILDER'S POCKET-BOOK of Formulæ, Rules, and Tables, and Marine Engineer's and Surveyor's Handy Book of Reference. By CLEMENT MACKROW, M.I.N.A. Seventh Edition, 700 pp., with 300 Illustrations. Fcap., leather . . **12/6**

SUMMARY OF CONTENTS:—SIGNS AND SYMBOLS, DECIMAL FRACTIONS.—TRIGONOMETRY.—PRACTICAL GEOMETRY.—MENSURATION.—CENTRES AND MOMENTS OF FIGURES.—MOMENTS OF INERTIA AND RADII OF GYRATION.—ALGEBRAICAL EXPRESSIONS FOR SIMPSON'S RULES.—MECHANICAL PRINCIPLES.—CENTRE OF GRAVITY.—LAWS OF MOTION.—DISPLACEMENT, CENTRE OF BUOYANCY.—CENTRE OF GRAVITY OF SHIP'S HULL.—STABILITY CURVES AND METACENTRES.—SEA AND SHALLOW-WATER WAVES.—ROLLING OF SHIPS.—PROPULSION AND RESISTANCE OF VESSELS.—SPEED TRIALS.—SAILING, CENTRE OF EFFORT.—DISTANCES DOWN RIVERS, COAST LINES.—STEERING AND RUDDERS OF VESSELS.—LAUNCHING CALCULATIONS AND VELOCITIES.—WEIGHT OF MATERIAL AND GEAR.—GUN PARTICULARS AND WEIGHT.—STANDARD GAUGES.—RIVETED JOINTS AND RIVETING.—STRENGTH AND TESTS OF MATERIALS.—BINDING AND SHEARING STRESSES, &c.—STRENGTH OF SHAFTING, PILLARS, WHEELS, &c.—HYDRAULIC DATA, &c.—CONIC SECTIONS, CATENARIAN CURVES.—MECHANICAL POWERS, WORK.—BOARD OF TRADE REGULATIONS FOR BOILERS AND ENGINES.—BOARD OF TRADE REGULATIONS FOR SHIPS.—LLOYD'S RULES FOR BOILERS.—LLOYD'S WEIGHT OF CHAINS.—LLOYD'S SCANTLINGS FOR SHIPS.—DATA OF ENGINES AND VESSELS.—SHIPS' FITTINGS AND TESTS.—SEASONING PRESERVING TIMBER.—MEASUREMENT OF TIMBER.—ALLOYS, PAINTS, VARNISHES.—DATA FOR STOWAGE.—ADMIRALTY TRANSPORT REGULATIONS.—RULES FOR HORSE-POWER, SCREW PROPELLERS, &c.—PERCENTAGES FOR BUTT STRAPS, &c.—PARTICULARS OF YACHTS.—MASTING AND RIGGING VESSELS.—DISTANCES OF FOREIGN PORTS.—TONNAGE TABLES.—VOCABULARY OF FRENCH AND ENGLISH TERMS.—ENGLISH WEIGHTS AND MEASURES.—FOREIGN WEIGHTS AND MEASURES.—DECIMAL EQUIVALENTS.—FOREIGN MONEY.—DISCOUNT AND WAGES TABLES.—USEFUL NUMBERS AND READY RECKONERS.—TABLES OF CIRCULAR MEASURES.—TABLES OF AREAS OF AND CIRCUMFERENCES OF CIRCLES.—TABLES OF AREAS OF SEGMENTS OF CIRCLES.—TABLES OF SQUARES AND CUBES AND ROOTS OF NUMBERS.—TABLES OF LOGARITHMS OF NUMBERS.—TABLES OF HYPERBOLIC LOGARITHMS.—TABLES OF NATURAL SINES, TANGENTS, &c.—TABLES OF LOGARITHMIC SINES, TANGENTS, &c.

"In these days of advanced knowledge a work like this is of the greatest value. It contains a vast amount of information. We unhesitatingly say that it is the most valuable compilation for its specific purpose that has ever been printed. No naval architect, engineer, surveyor, or seaman, wood or iron shipbuilder, can afford to be without this work."—*Nautical Magazine.*

"Should be used by all who are engaged in the construction or design of vessels. . . . Will be found to contain the most useful tables and formulæ required by shipbuilders, carefully collected from the best authorities, and put together in a popular and simple form. The book is one of exceptional merit."—*Engineer.*

"The professional shipbuilder has now, in a convenient and accessible form, reliable data for solving many of the numerous problems that present themselves in the course of his work."—*Iron.*

"There is no doubt that a pocket-book of this description must be a necessity in the shipbuilding trade. . . The volume contains a mass of useful information clearly expressed and presented in a handy form."—*Marine Engineer.*

WANNAN'S MARINE ENGINEER'S GUIDE

To Board of Trade Examinations for Certificates of Competency. Containing all Latest Questions to Date, with Simple, Clear, and Correct Solutions; Elementary and Verbal Questions and Answers; complete Set of Drawings with Statements completed. By A. C. WANNAN, C.E., and E. W. I. WANNAN, M.I.M.E. Illustrated with numerous Engravings. Crown 8vo, 370 pages, cloth. [*Just Published.* **8/6**

"The book is clearly and plainly written and avoids unnecessary explanations and formulas, and we consider it a valuable book for students of marine engineering."—*Nautical Magazine.*

WANNAN'S MARINE ENGINEER'S POCKET-BOOK.

Containing the Latest Board of Trade Rules and Data for Marine Engineers. By A. C. WANNAN. Second Edition, carefully Revised. Square 18mo, with thumb Index, leather. [*Just Published.* **5/0**

"There is a great deal of useful information in this little pocket-book. It is of the rule-of-thumb order, and is, on that account, well adapted to the uses of the sea-going engineer."—*Engineer.*

MARINE ENGINES AND STEAM VESSELS.

A Treatise on. By ROBERT MURRAY, C.E. Eighth Edition, thoroughly Revised, with considerable Additions by the Author and by GEORGE CARLISLE, C.E., Senior Surveyor to the Board of Trade. 12mo, cloth . **4/6**

Digitized by Google

SEA TERMS, PHRASES, AND WORDS

(Technical Dictionary of) used in the English and French Languages (English-French, French-English). For the Use of Seamen, Engineers, Pilots, Shipbuilders, Shipowners, and Ship-brokers. Compiled by W. PIRRIE, late of the African Steamship Company. Fcap. 8vo, cloth limp . . . **5/0**

"This volume will be highly appreciated by seamen, engineers, pilots, shipbuilders and shipowners. It will be found wonderfully accurate and complete."—*Scotsman.*

"A very useful dictionary, which has long been wanted by French and English engineers, masters, officers and others."—*Shipping World.*

ELECTRIC SHIP-LIGHTING.

A Handbook on the Practical Fitting and Running of Ships' Electrical Plant, for the Use of Shipowners and Builders, Marine Electricians and Sea-going Engineers in Charge. By J. W. URQUHART, Author of "Electric Light," "Dynamo Construction," &c. Second Edition, Revised and Extended. 326 pp., with 88 Illustrations. Crown 8vo, cloth. [*Just Published.* **7/6**

MARINE ENGINEER'S POCKET-BOOK.

Consisting of useful Tables and Formulæ. By FRANK PROCTOR, A.I.N.A. Third Edition. Royal 32mo, leather, gilt edges, with strap . . . **4/0**

"We recommend it to our readers as going far to supply a long-felt want."—*Naval Science.*

"A most useful companion to all marine engineers."—*United Service Gazette.*

ELEMENTARY ENGINEERING.

A Manual for Young Marine Engineers and Apprentices. In the Form of Questions and Answers on Metals, Alloys, Strength of Materials, Construction and Management of Marine Engines and Boilers, Geometry, &c., &c. With an Appendix of Useful Tables. By J. S. BREWER. Crown 8vo, cloth . **1/6**

"Contains much valuable information for the class for whom it is intended, especially in the chapters on the management of boilers and engines."—*Nautical Magazine.*

PRACTICAL NAVIGATION.

Consisting of THE SAILOR'S SEA-BOOK, by JAMES GREENWOOD and W. H. ROSSER; together with the exquisite Mathematical and Nautical Tables for the Working of the Problems, by HENRY LAW, C.E., and Professor J. R. YOUNG. Illustrated. 12mo, strongly half-bound **7/0**

MARINE ENGINEER'S DRAWING-BOOK.

Adapted to the Requirements of the Board of Trade Examinations. By JOHN LOCKIE, C.E. With 22 Plates, Drawn to Scale. Royal 8vo, cloth . **3/6**

THE ART AND SCIENCE OF SAILMAKING.

By SAMUEL B. SADLER, Practical Sailmaker, late in the employment of Messrs. Ratsey and Lapthorne, of Cowes and Gosport. With Plates and other Illustrations. Small 4to, cloth **12/6**

"This extremely practical work gives a complete education in all the branches of the manufacture, cutting out, roping, seaming, and goring. It is copiously illustrated, and will form a first rate text-book and guide."—*Portsmouth Times.*

CHAIN CABLES AND CHAINS.

Comprising Sizes and Curves of Links, Studs, &c., Iron for Cables and Chains, Chain Cable and Chain Making, Forming and Welding Links, Strength of Cables and Chains, Certificates for Cables, Marking Cables, Prices of Chain Cables and Chains, Historical Notes, Acts of Parliament, Statutory Tests, Charges for Testing, List of Manufacturers of Cables, &c., &c. By THOMAS W. TRAILL, F.E.R.N., M.Inst.C.E., Engineer-Surveyor-in-Chief, Board of Trade, Inspector of Chain Cable and Anchor Proving Establishments, and General Superintendent Lloyd's Committee on Proving Establishments. With numerous Tables, Illustrations, and Lithographic Drawings. Folio, cloth, bevelled boards . . . . . **£2 2s.**

"It contains a vast amount of valuable information. Nothing seems to be wanting to make it a complete and standard work of reference on the subject."—*Nautical Magazine.*

Digitized by Google

MINING AND METALLURGY.

COLLIERY WORKING AND MANAGEMENT.

Comprising the Duties of a Colliery Manager, the Oversight and Arrangement of Labour and Wages, and the different Systems of Working Coal Seams. By H. F. BULMAN and R. A. S. REDMAYNE. 350 pp., with 28 Plates and other Illustrations, including Underground Photographs. Medium 8vo, cloth. [*Just Published.* **15/0**

"This is, indeed, an admirable Handbook for Colliery Managers, in fact it is an indispensable adjunct to a Colliery Manager's education, as well as being a most useful and interesting work on the subject for all who in any way have to do with coal mining. The underground photographs are an attractive feature of the work, being very lifelike and necessarily true representations of the scenes they depict."—*Colliery Guardian.*

"Mr. Bulman and Mr. Redmayne, who are both experienced Colliery Managers of great literary ability, are to be congratulated on having supplied an authoritative work dealing with a side of the subject of coal mining which has hitherto received but scant treatment. The authors elucidate their text by 119 woodcuts and 28 plates, most of the latter being admirable reproductions of photographs taken underground with the aid of the magnesium flash-light. These illustrations are excellent."—*Nature.*

INFLAMMABLE GAS AND VAPOUR IN THE AIR

(The Detection and Measurement of). By FRANK CLOWES, D.Sc., Lond., F.I.C., Prof. of Chemistry in the University College, Nottingham. With a Chapter on THE DETECTION AND MEASUREMENT OF PETROLEUM VAPOUR by BOVERTON REDWOOD, F.R.S.E., Consulting Adviser to the Corporation of London under the Petroleum Acts. Crown 8vo, cloth.

[*Just Published. Net* **5/0**

"Professor Clowes has given us a volume on a subject of much industrial importance . . . Those interested in these matters may be recommended to study this book, which is easy of comprehension and contains many good things."—*The Engineer.*

"A convenient summary of the work on which Professor Clowes has been engaged for some considerable time. . . . It is hardly necessary to say that any work on these subjects with these names on the title-page must be a valuable one, and one that no mining engineer—certainly no coal miner—can afford to ignore or to leave unread."—*Mining Journal.*

MACHINERY FOR METALLIFEROUS MINES.

A Practical Treatise for Mining Engineers, Metallurgists, and Managers of Mines. By E. HENRY DAVIES, M.E., F.G.S. Crown 8vo, 580 pp., with upwards of 300 Illustrations, cloth. **12/6**

"Mr. Davies, in this handsome volume, has done the advanced student and the manager of mines good service. Almost every kind of machinery in actual use is carefully described, and the woodcuts and plates are good."—*Athenæum.*

"From cover to cover the work exhibits all the same characteristics which excite the confidence and attract the attention of the student as he peruses the first page. The work may safely be recommended. By its publication the literature connected with the industry will be enriched and the reputation of its author enhanced."—*Mining Journal.*

METALLIFEROUS MINERALS AND MINING.

By D. C. DAVIES, F.G.S., Mining Engineer, &c., Author of "A Treatise on Slate and Slate Quarrying." Fifth Edition, thoroughly Revised and much Enlarged by his Son, E. HENRY DAVIES, M.E., F.G.S. With about 150 Illustrations. Crown 8vo, cloth **12/6**

"Neither the practical miner nor the general reader, interested in mines, can have a better book for his companion and his guide."—*Mining Journal.*

"We are doing our readers a service in calling their attention to this valuable work."—*Mining World.*

"As a history of the present state of mining throughout the world this book has a real value and it supplies an actual want."—*Athenæum.*

EARTHY AND OTHER MINERALS AND MINING.

By D. C. DAVIES, F.G.S., Author of "Metalliferous Minerals," &c. Third Edition, Revised and Enlarged by his Son, E. HENRY DAVIES, M.E., F.G.S. With about 100 Illustrations. Crown 8vo, cloth **12/6**

"We do not remember to have met with any English work on mining matters that contains the same amount of information packed in equally convenient form."—*Academy.*

"We should be inclined to rank it as among the very best of the handy technical and trades manuals which have recently appeared."—*British Quarterly Review.*

Digitized by Google

BRITISH MINING.

A Treatise on the History, Discovery, Practical Development, and Future Prospects of Metalliferous Mines in the United Kingdom. By ROBERT HUNT, F.R.S., late Keeper of Mining Records. Upwards of 950 pp., with 230 Illustrations. Second Edition, Revised. Super-royal 8vo, cloth **£2 2s.**

"The book is a treasure-house of statistical information on mining subjects, and we know of no other work embodying so great a mass of matter of this kind. Were this the only merit of Mr. Hunt's volume it would be sufficient to render it indispensable in the library of every one interested in the development of the mining and metallurgical industries of this country."—*Athenæum.*

MINE DRAINAGE.

A Complete Practical Treatise on Direct-Acting Underground Steam Pumping Machinery. By STEPHEN MICHELL. Second Edition, Re-written and Enlarged, 390 pp. With about 250 Illustrations. Royal 8vo, cloth.
[*Just Published. Net* **25/0**

SUMMARY OF CONTENTS:—HORIZONTAL PUMPING ENGINES.—ROTARY AND NON-ROTARY HORIZONTAL ENGINES.—SIMPLE AND COMPOUND STEAM PUMPS.—VERTICAL PUMPING ENGINES.—ROTARY AND NON-ROTARY VERTICAL ENGINES.—SIMPLE AND COMPOUND STEAM PUMPS.—TRIPLE-EXPANSION STEAM PUMPS.—PULSATING STEAM PUMPS.—PUMP VALVES.—SINKING PUMPS, &c., &c.

"This volume contains an immense amount of important and interesting new matter. The book should undoubtedly prove of great use to all who wish for information on the subject, inasmuch as the different patterns of steam pumps are not alone lucidly described and clearly illustrated, but in addition numerous tables are supplied, in which their sizes, capacity, price, &c., are set forth, hence facilitating immensely the rational selection of a pump to suit any purpose that the reader may desire, or, on the other hand, supplying him with useful information about any of the pumps that come within the scope of the volume."—*The Engineer.*

THE PROSPECTOR'S HANDBOOK.

A Guide for the Prospector and Traveller in search of Metal-Bearing or other Valuable Minerals. By J. W. ANDERSON, M.A. (Camb.), F.R.G.S., Author of "Fiji and New Caledonia." Eighth Edition, thoroughly Revised and much Enlarged. Small crown 8vo, cloth, **3/6**; or, leather, pocket-book form, with tuck. [*Just Published.* **4/6**

"Will supply a much-felt want, especially among Colonists, in whose way are so often thrown many mineralogical specimens the value of which it is difficult to determine."—*Engineer.*

"How to find commercial minerals, and how to identify them when they are found, are the leading points to which attention is directed. The author has managed to pack as much practical detail into his pages as would supply material for a book three times its size."—*Mining Journal.*

NOTES AND FORMULÆ FOR MINING STUDENTS.

By JOHN HERMAN MERIVALE, M.A., Late Professor of Mining in the Durham College of Science, Newcastle-upon-Tyne. Fourth Edition, Revised and Enlarged. By H. F. BULMAN, A.M.Inst.C.E. Small crown 8vo, cloth.
[*Just Published.* **2/6**

"The author has done his work in a creditable manner, and has produced a book that will be of service to students and those who are practically engaged in mining operations."—*Engineer.*

THE MINER'S HANDBOOK.

A Handy Book of Reference on the subjects of Mineral Deposits, Mining Operations, Ore Dressing, &c. For the Use of Students and others interested in Mining Matters. By JOHN MILNE, F.R.S., Professor of Mining in the Imperial University of Japan. Revised Edition. Fcap. 8vo, leather . **7/6**

"Professor Milne's handbook is sure to be received with favour by all connected with mining, and will be extremely popular among students."—*Athenæum.*

POCKET-BOOK FOR MINERS AND METALLURGISTS.

Comprising Rules, Formulæ, Tables, and Notes for Use in Field and Office Work. By F. DANVERS POWER, F.G.S., M.E. Second Edition, Corrected. Fcap. 8vo, leather. [*Just Published.* **9/0**

"This excellent book is an admirable example of its kind, and ought to find a large sale amongst English-speaking prospectors and mining engineers."—*Engineering.*

FIELD TESTING FOR GOLD AND SILVER.

A Practical Manual for Prospectors and Miners. By W. H. MERRITT, M.N.E. Inst. M.E., A.R.S.M., &c. With Photographic Plates and other Illustrations. Fcap. 8vo, leather. [*Just Published. Net* **5/0**

Digitized by Google

THE COLLIERY MANAGER'S HANDBOOK.

A Comprehensive Treatise on the Laying-out and Working of Collieries, Designed as a Book of Reference for Colliery Managers, and for the Use of Coal Mining Students preparing for First-class Certificates. By CALEB PAMELY, Mining Engineer and Surveyor; Member of the North of England Institute of Mining and Mechanical Engineers; and Member of the South Wales Institute of Mining Engineers. With 700 Plans, Diagrams, and other Illustrations. Fourth Edition, Revised and Enlarged, medium 8vo, over 900 pp. Strongly bound . . . . . **£1 5s.**

SUMMARY OF CONTENTS:—GEOLOGY.—SEARCH FOR COAL.—MINERAL LEASES AND OTHER HOLDINGS.—SHAFT SINKING.—FITTING UP THE SHAFT AND SURFACE ARRANGEMENTS.—STEAM BOILERS AND THEIR FITTINGS.—TIMBERING AND WALLING.—NARROW WORK AND METHODS OF WORKING.—UNDERGROUND CONVEYANCE.—DRAINAGE.—THE GASES MET WITH IN MINES; VENTILATION.—ON THE FRICTION OF AIR IN MINES.—THE PRIESTMAN OIL ENGINE; PETROLEUM AND NATURAL GAS.—SURVEYING AND PLANNING.—SAFETY LAMPS AND FIREDAMP DETECTORS.—SUNDRY AND INCIDENTAL OPERATIONS AND APPLIANCES.—COLLIERY EXPLOSIONS.—MISCELLANEOUS QUESTIONS AND ANSWERS.—*Appendix:* SUMMARY OF REPORT OF H.M. COMMISSIONERS ON ACCIDENTS IN MINES.

"Mr. Pamely has not only given us a comprehensive reference book of a very high order, suitable to the requirements of mining engineers and colliery managers, but has also provided mining students with a class-book that is as interesting as it is instructive."—*Colliery Manager.*

"Mr. Pamely's work is eminently suited to the purpose for which it is intended, being clear, interesting, exhaustive, rich in detail, and up to date, giving descriptions of the latest machines in every department. A mining engineer could scarcely go wrong who followed this work."—*Colliery Guardian.*

"This is the most complete 'all-round' work on coal-mining published in the English language. . . . No library of coal-mining books is complete without it."—*Colliery Engineer* (Scranton, Pa., U.S.A.).

COAL & IRON INDUSTRIES of the UNITED KINGDOM.

Comprising a Description of the Coal Fields, and of the Principal Seams of Coal, with Returns of their Produce and its Distribution, and Analyses of Special Varieties. Also, an Account of the Occurrence of Iron Ores in Veins or Seams; Analyses of each Variety; and a History of the Rise and Progress of Pig Iron Manufacture. By RICHARD MEADE. 8vo, cloth . . **£1 8s.**

"Of this book we may unreservedly say that it is the best of its class which we have ever met. . . . A book of reference which no one engaged in the iron or coal trades should omit from his library."—*Iron and Coal Trades Review.*

TRAVERSE TABLES.

For use in Mine Surveying. By W. LINTERN, Mining Engineer. Crown 8vo, cloth. [*Just Published. Net* **3/0**

COAL AND COAL MINING.

By the late Sir WARINGTON W. SMYTH, F.R.S., Chief Inspector of the Mines of the Crown. Eighth Edition, Revised and Extended by T. FORSTER BROWN, Mining Engineer, Chief Inspector of the Mines of the Crown and of the Duchy of Cornwall. Crown 8vo, cloth. [*Just Published.* **3/6**

"As an outline is given of every known coal-field in this and other countries, as well as of the principal methods of working, the book will doubtless interest a very large number of readers."—*Mining Journal.*

ASBESTOS AND ASBESTIC.

Their Properties, Occurrence, and Use. By ROBERT H. JONES, F.S.A., Mineralogist, Hon. Mem. Asbestos Club, Black Lake, Canada. With Ten Collotype Plates and other Illustrations. Demy 8vo, cloth. [*Just Published.* **16/0**

"An interesting and invaluable work."—*Colliery Guardian.*

SUBTERRANEOUS SURVEYING

(Elementary and Practical Treatise on), with and without the Magnetic Needle. By THOMAS FENWICK, Surveyor of Mines, and THOMAS BAKER, C.E. Illustrated. 12mo, cloth **2/6**

GRANITES AND OUR GRANITE INDUSTRIES.

By GEORGE F. HARRIS, F.G.S., Membre de la Société Belge de Géologie, Lecturer on Economic Geology at the Birkbeck Institution, &c. With Illustrations. Crown 8vo, cloth **2/6**

"A clearly and well-written manual for persons engaged or interested in the granite industry."—*Scotsman.*

Digitized by Google

THE METALLURGY OF GOLD.

A Practical Treatise on the Metallurgical Treatment of Gold-bearing Ores. Including the Processes of Concentration, Chlorination, and Extraction by Cyanide, and the Assaying, Melting, and Refining of Gold. By M. EISSLER, Mining Engineer and Metallurgical Chemist, formerly Assistant Assayer of the U.S. Mint, San Francisco. Fourth Edition, Enlarged. With about 250 Illustrations and numerous Folding Plates and Working Drawings. Large crown 8vo, cloth. [*Just Published.* **16/0**

"This book thoroughly deserves its title of a 'Practical Treatise.' The whole process of gold milling, from the breaking of the quartz to the assay of the bullion, is described in clear and orderly narrative and with much, but not too much, fulness of detail."—*Saturday Review.*

"The work is a storehouse of information and valuable data, and we strongly recommend it to all professional men engaged in the gold-mining industry."—*Mining Journal.*

THE CYANIDE PROCESS OF GOLD EXTRACTION.

Including its Practical Application on the Witwatersrand Gold Fields in South Africa. By M. EISSLER, M.E., Author of "The Metallurgy of Gold," &c. With Diagrams and Working Drawings. Second Edition, Revised and Enlarged. 8vo, cloth. [*Just Published.* **7/6**

"This book is just what was needed to acquaint mining men with the actual working of a process which is not only the most popular, but is, as a general rule, the most successful for the extraction of gold from tailings."—*Mining Journal.*

"The work will prove invaluable to all interested in gold mining, whether metallurgists or as investors."—*Chemical News*

THE METALLURGY OF SILVER.

A Practical Treatise on the Amalgamation, Roasting, and Lixiviation of Silver Ores. Including the Assaying, Melting, and Refining of Silver Bullion. By M. EISSLER, Author of "The Metallurgy of Gold," &c. Third Edition. Crown 8vo, cloth **10/6**

"A practical treatise, and a technical work which we are convinced will supply a long-felt want amongst practical men, and at the same time be of value to students and others indirectly connected with the industries."—*Mining Journal.*

"From first to last the book is thoroughly sound and reliable."—*Colliery Guardian.*

"For chemists, practical miners, assayers, and investors alike we do not know of any work on the subject so handy and yet so comprehensive."—*Glasgow Herald.*

THE METALLURGY OF ARGENTIFEROUS LEAD.

A Practical Treatise on the Smelting of Silver-Lead Ores and the Refining of Lead Bullion. Including Reports on various Smelting Establishments and Descriptions of Modern Smelting Furnaces and Plants in Europe and America. By M. EISSLER, M.E., Author of "The Metallurgy of Gold," &c. Crown 8vo, 400 pp., with 183 Illustrations, cloth **12/6**

"The numerous metallurgical processes, which are fully and extensively treated of, embrace all the stages experienced in the passage of the lead from the various natural states to its issue from the refinery as an article of commerce."—*Practical Engineer.*

"The present volume fully maintains the reputation of the author. Those who wish to obtain a thorough insight into the present state of this industry cannot do better than read this volume, and all mining engineers cannot fail to find many useful hints and suggestions in it."—*Industries.*

METALLURGY OF IRON.

By H. BAUERMAN, F.G.S., A.R.S.M. Sixth Edition, Revised and Enlarged. 12mo, cloth **5/0**

THE IRON ORES of GREAT BRITAIN and IRELAND.

Their Mode of Occurrence, Age and Origin, and the Methods of Searching for and Working Them. With a Notice of some of the Iron Ores of Spain. By J. D. KENDALL, F.G.S., Mining Engineer. Crown 8vo, cloth . . **16/0**

"The author has a thorough practical knowledge of his subject, and has supplemented a careful study of the available literature by unpublished information derived from his own observations. The result is a very useful volume, which cannot fail to be of value to all interested in the iron industry of the country."—*Industries.*

Digitized by Google

ELECTRICITY, ELECTRICAL ENGINEERING, &c.

SUBMARINE TELEGRAPHS.

Their History, Construction, and Working. Founded in part on WÜNSCHENDORFF'S "Traité de Télégraphie Sous-Marine," and Compiled from Authoritative and Exclusive Sources. By CHARLES BRIGHT, F.R.S.E. Super-royal 8vo, about 780 pp., fully Illustrated, including Maps and Folding Plates.
[*Just Published. Net* **£3 3s.**

"There are few, if any, persons more fitted to write a treatise on submarine telegraphy than Mr. Charles Bright. The author has done his work admirably, and has written in a way which will appeal as much to the layman as to the engineer. This admirable volume must, for many years to come, hold the position of the English classic on submarine telegraphy."—*Engineer.*

"This book is full of information. It makes a book of reference which should be in every engineer's library."—*Nature.*

"Mr. Bright's interestingly written and admirably illustrated book will meet with a welcome reception from cable men."—*Electrician.*

"The author deals with his subject from all points of view—political and strategical as well as scientific. The work will be of interest, not only to men of science, but to the general public. We can strongly recommend it."—*Athenæum.*

"The work contains a great store of technical information concerning the making and working of submarine telegraphs. In bringing together the most valuable results relating to the evolution of the telegraph, the author has rendered a service that will be very widely appreciated."—*Morning Post.*

THE ELECTRICAL ENGINEER'S POCKET-BOOK.

Consisting of Modern Rules, Formulæ, Tables, and Data. By H. R. KEMPE, M.Inst.E.E., A.M.Inst.C.E., Technical Officer Postal Telegraphs, Author of "A Handbook of Electrical Testing," "The Engineer's Year-Book," &c. Second Edition, thoroughly Revised, with Additions. With numerous Illustrations. Royal 32mo, oblong, leather **5/0**

"It is the best book of its kind."—*Electrical Engineer.*

"The Electrical Engineer's Pocket-Book is a good one."—*Electrician.*

"Strongly recommended to those engaged in the electrical industries."—*Electrical Review.*

ELECTRIC LIGHT FITTING.

A Handbook for Working Electrical Engineers, embodying Practical Notes on Installation Management. By J. W. URQUHART, Electrician, Author of "Electric Light," &c. With numerous Illustrations. Third Edition, Revised, with Additions. Crown 8vo, cloth. [*Just Published.* **5/0**

"This volume deals with what may be termed the mechanics of electric lighting, and is addressed to men who are already engaged in the work, or are training for it. The work traverses a great deal of ground, and may be read as a sequel to the same author's useful work on 'Electric Light.'"—*Electrician.*

"Eminently practical and useful. . . . Ought to be in the hands of every one in charge of an electric light plant."—*Electrical Engineer.*

ELECTRIC LIGHT.

Its Production and Use, Embodying Plain Directions for the Treatment of Dynamo-Electric Machines, Batteries, Accumulators, and Electric Lamps. By J. W. URQUHART, C.E. Sixth Edition, Revised, with Additions and 145 Illustrations. Crown 8vo, cloth. [*Just Published.* **7/6**

"The whole ground of electric lighting is more or less covered and explained in a very clear and concise manner."—*Electrical Review.*

"A *vade-mecum* of the salient facts connected with the science of electric lighting."—*Electrician.*

"You cannot for your purpose have a better book than 'Electric Light' by Urquhart."—*Engineer.*

DYNAMO CONSTRUCTION.

A Practical Handbook for the Use of Engineer-Constructors and Electricians-in-Charge. Embracing Framework Building, Field Magnet and Armature Winding and Grouping, Compounding, &c. With Examples of leading English, American, and Continental Dynamos and Motors. By J. W. URQUHART, Author of "Electric Light," &c. Second Edition, Enlarged. With 114 Illustrations. Crown 8vo, cloth **7/6**

"Mr. Urquhart's book is the first one which deals with these matters in such a way that the engineering student can understand them. The book is very readable, and the author leads his readers up to difficult subjects by reasonably simple tests."—*Engineering Review.*

"A book for which a demand has long existed."—*Mechanical World.*

Digitized by Google

THE MANAGEMENT OF DYNAMOS.

A Handy Book of Theory and Practice for the Use of Mechanics, Engineers, Students, and others in Charge of Dynamos. By G. W. LUMMIS-PATERSON. Second Edition, thoroughly Revised and Enlarged. With numerous Illustrations. Crown 8vo, cloth. [*Just Published.* **4/6**

"An example which deserves to be taken as a model by other authors. The subject is treated in a manner which any intelligent man who is fit to be entrusted with charge of an engine should be able to understand. It is a useful book to all who make, tend, or employ electric machinery."—*Architect.*

THE STANDARD ELECTRICAL DICTIONARY.

A Popular Encyclopædia of Words and Terms Used in the Practice of Electrical Engineering. By T. O'CONOR SLOANE, A.M., Ph.D. Second Edition, with Appendix to date. Crown 8vo, 680 pp., 390 Illustrations, cloth.

[*Just Published.* **7/6**

"The work has many attractive features in it, and is, beyond doubt, a well put together and useful publication. The amount of ground covered may be gathered from the fact that in the index about 5,600 references will be found."—*Electrical Review.*

ELECTRIC SHIP-LIGHTING.

A Handbook on the Practical Fitting and Running of Ships' Electrical Plant. For the Use of Shipowners and Builders, Marine Electricians, and Seagoing Engineers-in-Charge. By J. W. URQUHART, C.E. Second Edition, Revised and Extended. 326 pp., with 88 Illustrations, Crown 8vo, cloth.

[*Just Published.* **7/6**

"The subject of ship electric lighting is one of vast importance, and Mr. Urquhart is to be highly complimented for placing such a valuable work at the service of marine electricians."—*The Steamship.*

ELECTRIC LIGHT FOR COUNTRY HOUSES.

A Practical Handbook on the Erection and Running of Small Installations, with Particulars of the Cost of Plant and Working. By J. H. KNIGHT. Second Edition, Revised. Crown 8vo, wrapper. [*Just Published.* **1/0**

"The book contains excellent advice and many practical hints for the help of those who wish to light their own houses."—*Building News.*

ELECTRIC LIGHTING (ELEMENTARY PRINCIPLES OF).

By ALAN A. CAMPBELL SWINTON, Associate I.E.E. Fourth Edition, Enlarged and Revised. With 16 Illustrations. Crown 8vo, cloth **1/6**

"Any one who desires a short and thoroughly clear exposition of the elementary principles of electric lighting cannot do better than read this little work."—*Bradford Observer.*

DYNAMIC ELECTRICITY AND MAGNETISM.

By PHILIP ATKINSON, A.M., Ph.D., Author of "Elements of Static Electricity," &c. Crown 8vo, 417 pp., with 120 Illustrations, cloth . **10/6**

POWER TRANSMITTED BY ELECTRICITY

And applied by the Electric Motor, including Electric Railway Construction. By P. ATKINSON, A.M., Ph.D. With 96 Illustrations. Crown 8vo, cloth **7/6**

HOW TO MAKE A DYNAMO.

A Practical Treatise for Amateurs. Containing numerous Illustrations and Detailed Instructions for Constructing a Small Dynamo to Produce the Electric Light. By ALFRED CROFTS. Fifth Edition, Revised and Enlarged. Crown 8vo, cloth. [*Just Published.* **2/0**

"The instructions given in this unpretentious little book are sufficiently clear and explicit to enable any amateur mechanic possessed of average skill and the usual tools to be found in an amateur's workshop to build a practical dynamo machine."—*Electrician.*

THE STUDENT'S TEXT-BOOK OF ELECTRICITY.

By H. M. NOAD, F.R.S. Cheaper Edition. 650 pp., with 470 Illustrations. Crown 8vo, cloth **9/0**

Digitized by Google

ARCHITECTURE, BUILDING, &c.

PRACTICAL BUILDING CONSTRUCTION.

A Handbook for Students Preparing for Examinations, and a Book of Reference for Persons Engaged in Building. By JOHN PARNELL ALLEN, Surveyor, Lecturer on Building Construction at the Durham College of Science, Newcastle-on-Tyne. Third Edition, Revised and Enlarged. Medium 8vo, 450 pp., with 1,000 Illustrations, cloth. [*Just Published.* **7/6**

"The most complete exposition of building construction we have seen. It contains all that is necessary to prepare students for the various examinations in building construction."—*Building News.*

"The author depends nearly as much on his diagrams as on his type. The pages suggest the hand of a man of experience in building operations—and the volume must be a blessing to many teachers as well as to students."—*The Architect.*

"The work is sure to prove a formidable rival to great and small competitors alike, and bids fair to take a permanent place as a favourite student's text-book. The large number of illustrations deserve particular mention for the great merit they possess for purposes of reference in exactly corresponding to convenient scales."—*Journal of the Royal Institute of British Architects.*

PRACTICAL MASONRY.

A Guide to the Art of Stone Cutting. Comprising the Construction, Setting Out, and Working of Stairs, Circular Work, Arches, Niches, Domes, Pendentives, Vaults, Tracery Windows, &c., &c. For the Use of Students, Masons, and other Workmen. By WILLIAM R. PURCHASE, Building Inspector to the Borough of Hove. Third Edition, with Glossary of Terms. Royal 8vo, 142 pp., with 52 Lithographic Plates, comprising nearly 400 separate Diagrams, cloth. [*Just Published.* **7/6**

"Mr. Purchase's 'Practical Masonry' will undoubtedly be found useful to all interested in this important subject, whether theoretically or practically. Most of the examples given are from actual work carried out, the diagrams being carefully drawn. The book is a practical treatise on the subject, the author himself having commenced as an operative mason, and afterwards acted as foreman mason on many large and important buildings prior to the attainment of his present position. It should be found of general utility to architectural students and others, as well as to those to whom it is specially addressed."—*Journal of the Royal Institute of British Architects.*

CONCRETE: ITS NATURE AND USES.

A Book for Architects, Builders, Contractors, and Clerks of Works. By GEORGE L. SUTCLIFFE, A.R.I.B.A. 350 pp., with numerous Illustrations. Crown 8vo, cloth **7/6**

"The author treats a difficult subject in a lucid manner. The manual fills a long-felt gap. It is careful and exhaustive; equally useful as a student's guide and an architect's book of reference."—*Journal of the Royal Institute of British Architects.*

"There is room for this new book, which will probably be for some time the standard work on the subject for a builder's purpose."—*Glasgow Herald.*

THE MECHANICS OF ARCHITECTURE.

A Treatise on Applied Mechanics, especially Adapted to the Use of Architects. By E. W. TARN, M.A., Author of "The Science of Building," &c. Second Edition, Enlarged. Illustrated with 125 Diagrams. Crown 8vo, cloth **7/6**

"The book is a very useful and helpful manual of architectural mechanics, and really contains sufficient to enable a careful and painstaking student to grasp the principles bearing upon the majority of building problems. . . . Mr. Tarn has added, by this volume, to the debt of gratitude which is owing to him by architectural students for the many valuable works which he has produced for their use."—*The Builder.*

LOCKWOOD'S BUILDER'S PRICE BOOK for 1900.

A Comprehensive Handbook of the Latest Prices and Data for Builders, Architects, Engineers, and Contractors. Re-constructed, Re-written, and Greatly Enlarged. By FRANCIS T. W. MILLER. 800 closely-printed pages, crown 8vo, cloth **4/0**

"This book is a very useful one, and should find a place in every English office connected with the building and engineering professions."—*Industries.*

"An excellent book of reference."—*Architect.*

"In its new and revised form this Price Book is what a work of this kind should be—comprehensive, reliable, well arranged, legible, and well bound."—*British Architect.*

THE DECORATIVE PART OF CIVIL ARCHITECTURE.

By Sir WILLIAM CHAMBERS, F.R.S. With Portrait, Illustrations, Notes, and an EXAMINATION OF GRECIAN ARCHITECTURE, by JOSEPH GWILT, F.S.A. Revised and Edited by W. H. LEEDS. 66 Plates, 4to, cloth . . **21/0**

Digitized by Google

A HANDY BOOK OF VILLA ARCHITECTURE.

Being a Series of Designs for Villa Residences in various Styles. With Outline Specifications and Estimates. By C. WICKES, Architect, Author of "The Spires and Towers of England," &c. 61 Plates, 4to, half-morocco, gilt edges . . . . . **£1 11s. 6d.**

"The whole of the designs bear evidence of their being the work of an artistic architect, and they will prove very valuable and suggestive."—*Building News.*

THE ARCHITECT'S GUIDE.

Being a Text-book of Useful Information for Architects, Engineers, Surveyors Contractors, Clerks of Works, &c., &c. By FREDERICK ROGERS, Architect. Third Edition. Crown 8vo, cloth **3/6**

"As a text-book of useful information for architects, engineers, surveyors, &c., it would be hard to find a handier or more complete little volume."—*Standard.*

ARCHITECTURAL PERSPECTIVE.

The whole Course and Operations of the Draughtsman in Drawing a Large House in Linear Perspective. Illustrated by 43 Folding Plates. By F. O. FERGUSON. Second Edition, Enlarged. 8vo, boards **3/6**

"It is the most intelligible of the treatises on this ill-treated subject that I have met with."—E. INGRESS BELL, ESQ., in the *R.I.B.A. Journal.*

PRACTICAL RULES ON DRAWING.

For the Operative Builder and Young Student in Architecture. By GEORGE PYNE. 14 Plates, 4to, boards **7/6**

MEASURING AND VALUING ARTIFICER'S WORK

(The Student's Guide to the Practice of). Containing Directions for taking Dimensions, Abstracting the same, and bringing the Quantities into Bill, with Tables of Constants for Valuation of Labour, and for the Calculation of Areas and Solidities. Originally edited by E. DOBSON, Architect. With Additions by E. W. TARN, M.A. Seventh Edition, Revised. With 8 Plates and 63 Woodcuts. Crown 8vo, cloth. [*Just Published.* **7/6**

"This edition will be found the most complete treatise on the principles of measuring and valuing artificer's work that has yet been published."—*Building News.*

TECHNICAL GUIDE, MEASURER, AND ESTIMATOR.

For Builders and Surveyors. Containing Technical Directions for Measuring Work in all the Building Trades, Complete Specifications for Houses, Roads, and Drains, and an Easy Method of Estimating the parts of a Building collectively. By A. C. BEATON. Eighth Edition. Waistcoat-pocket size, gilt edges **1/6**

"No builder, architect, surveyor, or valuer should be without his 'Beaton.'"—*Building News.*

CONSTRUCTIONAL IRON AND STEEL WORK.

As Applied to Public, Private, and Domestic Buildings. A Practical Treatise for Architects, Students, and Builders. By F. CAMPIN. Crown 8vo, cloth. [*Just Published.* **3/6**

"Any one who wants a book on ironwork, as employed in buildings for stanchions, columns, and beams, will find the present volume to be suitable. The author has had long and varied experience in designing this class of work. The illustrations have the character of working drawings. This practical book may be counted a most valuable work."—*British Architect.*

SPECIFICATIONS FOR PRACTICAL ARCHITECTURE.

A Guide to the Architect, Engineer, Surveyor, and Builder. With an Essay on the Structure and Science of Modern Buildings. Upon the Basis of the Work by ALFRED BARTHOLOMEW, thoroughly Revised, Corrected, and greatly added to by FREDERICK ROGERS, Architect. Third Edition, Revised. 8vo, cloth **15/0**

"The work is too well known to need any recommendation from us. It is one of the books with which every young architect must be equipped."—*Architect.*

THE HOUSE-OWNER'S ESTIMATOR.

Or, What will it Cost to Build, Alter, or Repair? A Price Book for Unprofessional People as well as the Architectural Surveyor and Builder. By J. D. SIMON. Edited by F. T. W. MILLER, A.R.I.B.A. Fourth Edition. Crown 8vo, cloth **3/6**

"In two years it will repay its cost a hundred times over."—*Field.*

Digitized by Google

SANITATION AND WATER SUPPLY.

THE PURIFICATION OF SEWAGE.

Being a Brief Account of the Scientific Principles of Sewage Purification, and their Practical Application. By SIDNEY BARWISE, M.D. (Lond.), M.R.C.S., D.P.H. (Camb.), Fellow of the Sanitary Institute, Medical Officer of Health to the Derbyshire County Council. Crown 8vo, cloth. [*Just Published.* **5/0**

"'What process shall we adopt to purify our sewage?' This question has rarely been treated from so many points of view in one book. This volume teems with practical hints, which show the intimate knowledge the author has of his subject."—*The Engineer.*

"We know of no book of the same size which gives so complete and accurate an account of the principles of sewage purification."—*The Builder.*

WATER AND ITS PURIFICATION.

A Handbook for the Use of Local Authorities, Sanitary Officers, and others interested in Water Supply. By S. RIDEAL, D.Sc. Lond., F.I.C. With numerous Illustrations and Tables. Crown 8vo, cloth. [*Just Published.* **7/6**

"Dr. Rideal's book is both interesting and accurate, and contains a most useful *résumé* of the latest knowledge upon the subject of which it treats. It ought to be of great service to all who are connected with the supply of water for domestic or manufacturing purposes."—*The Engineer.*

"Dealing as clearly as it does with the various ramifications of such an important subject as water and its purification it may be warmly recommended. Local authorities and all engaged in sanitary affairs, and others interested in water supply, will read its pages with profit."—*Lancet.*

RURAL WATER SUPPLY.

A Practical Handbook on the Supply of Water and Construction of Waterworks for Small Country Districts. By ALLAN GREENWELL, A.M.I.C.E., and W. T. CURRY, A.M.I.C.E. Revised Edition. Crown 8vo, cloth **5/0**

"We conscientiously recommend it as a very useful book for those concerned in obtaining water for small districts, giving a great deal of practical information in a smal compass."—*Builder.*

THE WATER SUPPLY OF CITIES AND TOWNS.

By WILLIAM HUMBER, A.M. Inst. C.E., and M.Inst. M.E. Imp. 4to, half-bound morocco. (See page 11.) . . . . . *Net* **£6 6s.**

THE WATER SUPPLY OF TOWNS AND THE CONSTRUCTION OF WATER-WORKS.

By PROFESSOR W. K. BURTON, A.M. Inst. C.E. Second Edition, Revised and Extended. Royal 8vo, cloth. (See page 10.) **25/0**

WATER ENGINEERING.

A Practical Treatise on the Measurement, Storage, Conveyance, and Utilisation of Water for the Supply of Towns, for Mill Power, and for other Purposes. By C. SLAGG, A.M. Inst. C.E. Second Edition. Crown 8vo, cloth . **7/6**

SANITARY WORK IN SMALL TOWNS AND VILLAGES.

By CHARLES SLAGG, A. M. Inst. C.E. Crown 8vo, cloth . . . **3/0**

SANITARY ARRANGEMENT OF DWELLING-HOUSES.

A Handbook for Householders and Owners of Houses. By A. J. WALLIS-TAYLER, A.M.Inst.C.E. Crown 8vo, cloth **2/6**

"This book will be largely read; it will be of considerable service to the public. It is we arranged, easily read, and for the most part devoid of technical terms."—*Lancet.*

VENTILATION.

A Text-book to the Practice of the Art of Ventilating Buildings. By W. P. BUCHAN, R.P. Crown 8vo, cloth **3/6**

PLUMBING.

A Text-book to the Practice of the Art or Craft of the Plumber. By W. P. BUCHAN, R.P. Seventh Edition, Enlarged. Crown 8vo, cloth . . **3/6**

THE HEALTH OFFICER'S POCKET-BOOK.

A Guide to Sanitary Practice and Law. For Medical Officers of Health, Sanitary Inspectors, Members of Sanitary Authorities, &c. By EDWARD F. WILLOUGHBY, M.D. (Lond.), &c. Fcap. 8vo, cloth **7/6**

"A mine of condensed information of a pertinent and useful kind on the various subjects of which it treats. The matter seems to have been carefully compiled and arranged for facility of reference, and it is well illustrated by diagrams and woodcuts. The different subjects are succinctly but fully and scientifically dealt with."—*The Lancet.*

Digitized by Google

CARPENTRY, TIMBER, &c.

THE ELEMENTARY PRINCIPLES OF CARPENTRY.

A Treatise on the Pressure and Equilibrium of Timber Framing, the Resistance of Timber, and the Construction of Floors, Arches, Bridges, Roofs, Uniting Iron and Stone with Timber, &c. To which is added an Essay on the Nature and Properties of Timber, &c., with Descriptions of the kinds of Wood used in Building; also numerous Tables of the Scantlings of Timber for different purposes, the Specific Gravities of Materials, &c. By THOMAS TREDGOLD, C.E. With an Appendix of Specimens of Various Roofs of Iron and Stone, Illustrated. Seventh Edition, thoroughly Revised and considerably Enlarged by E. WYNDHAM TARN, M.A., Author of "The Science of Building," &c. With 61 Plates, Portrait of the Author, and several Woodcuts. In One large Vol., 4to, cloth **25/0**

"Ought to be in every architect's and every builder's library."—*Builder.*

"A work whose monumental excellence must commend it wherever skilful carpentry is concerned. The author's principles are rather confirmed than impaired by time. The additional plates are of great intrinsic value."—*Building News.*

WOODWORKING MACHINERY.

Its Rise, Progress, and Construction. With Hints on the Management of Saw Mills and the Economical Conversion of Timber. Illustrated with Examples of Recent Designs by leading English, French, and American Engineers. By M. POWIS BALE, A.M.Inst.C.E., M.I.M.E. Second Edition, Revised, with large Additions, large crown 8vo, 440 pp., cloth **9/0**

"Mr. Bale is evidently an expert on the subject, and he has collected so much information that his book is all-sufficient for builders and others engaged in the conversion of timber."—*Architect.*

"The most comprehensive compendium of wood-working machinery we have seen. The author is a thorough master of his subject."—*Building News.*

SAW MILLS.

Their Arrangement and Management, and the Economical Conversion of Timber. By M. POWIS BALE, A.M.Inst.C.E. Second Edition, Revised. Crown 8vo, cloth. [*Just Published.* **10/6**

"The *administration* of a large sawing establishment is discussed, and the subject examined from a financial standpoint. Hence the size, shape, order, and disposition of saw mills and the like are gone into in detail, and the course of the timber is traced from its reception to its delivery in its converted state. We could not desire a more complete or practical treatise."—*Builder.*

THE CARPENTER'S GUIDE.

Or, Book of Lines for Carpenters; comprising all the Elementary Principles essential for acquiring a knowledge of Carpentry. Founded on the late PETER NICHOLSON'S standard work. A New Edition, Revised by ARTHUR ASHPITEL, F.S.A. Together with Practical Rules on Drawing, by GEORGE PYNE. With 74 Plates, 4to, cloth . . . . . **£1 1s.**

A PRACTICAL TREATISE ON HANDRAILING.

Showing New and Simple Methods for Finding the Pitch of the Plank, Drawing the Moulds, Bevelling, Jointing-up, and Squaring the Wreath. By GEORGE COLLINGS. Second Edition, Revised and Enlarged, to which is added A TREATISE ON STAIR-BUILDING. With Plates and Diagrams . . **2/6**

"Will be found of practical utility in the execution of this difficult branch of joinery."—*Builder*

"Almost every difficult phase of this somewhat intricate branch of joinery is elucidated by the aid of plates and explanatory letterpress."—*Furniture Gazette.*

CIRCULAR WORK IN CARPENTRY AND JOINERY.

A Practical Treatise on Circular Work of Single and Double Curvature. By GEORGE COLLINGS. With Diagrams. Third Edition, 12mo, cloth . **2/6**

"An excellent example of what a book of this kind should be. Cheap in price, clear in definition, and practical in the examples selected."—*Builder.*

THE CABINET-MAKER'S GUIDE TO THE ENTIRE CONSTRUCTION OF CABINET WORK.

Including the Art of Laying Veneers, &c. By RICHARD BITMEAD. 8vo, with numerous Illustrations, wrapper **3/6**

Digitized by Google

HANDRAILING COMPLETE IN EIGHT LESSONS.

On the Square-Cut System. By J. S. GOLDTHORP, Head of Building Department, Halifax Technical School. With Eight Plates and over 150 Practical Exercises. 4to, cloth **3/6**

"Likely to be of considerable value to joiners and others who take a pride in good work. The arrangement of the book is excellent. We heartily commend it to teachers and students."—*Timber Trades Journal.*

TIMBER MERCHANT'S and BUILDER'S COMPANION.

Containing New and Copious Tables of the Reduced Weight and Measurement of Deals and Battens, of all sizes, from One to a Thousand Pieces, and the relative Price that each size bears per Lineal Foot to any given Price per Petersburgh Standard Hundred; the Price per Cube Foot of Square Timber to any given Price per Load of 50 Feet, &c., &c. By WILLIAM DOWSING. Fourth Edition, Revised and Corrected. Crown 8vo, cloth . . . **3/0**

"We are glad to see a fourth edition of these admirable tables, which for correctness and simplicity of arrangement leave nothing to be desired."—*Timber Trades Journal.*

THE PRACTICAL TIMBER MERCHANT.

A Guide for the Use of Building Contractors, Surveyors, Builders, &c., comprising useful Tables for all purposes connected with the Timber Trade, Marks of Wood, Essay on the Strength of Timber, Remarks on the Growth of Timber, &c. By W. RICHARDSON. Second Edition. Fcap. 8vo, cloth . **3/6**

"Contains much valuable information for timber merchants, builders, foresters, and all others connected with the growth, sale, and manufacture of timber."—*Journal of Forestry.*

PACKING-CASE TABLES.

Showing the number of Superficial Feet in Boxes or Packing-Cases, from six inches square and upwards. By W. RICHARDSON, Timber Broker. Third Edition. Oblong 4to, cloth **3/6**

"Invaluable labour-saving tables."—*Ironmonger.*

GUIDE TO SUPERFICIAL MEASUREMENT.

Tables calculated from 1 to 200 inches in length by 1 to 108 inches in breadth. For the use of Architects, Surveyors, Engineers, Timber Merchants, Builders, &c. By JAMES HAWKINGS. Fourth Edition. Fcap., cloth. **3/6**

"A useful collection of tables to facilitate rapid calculation of surfaces. The exact area of any surface of which the limits have been ascertained can be instantly determined. The book will be found of the greatest utility to all engaged in building operations."—*Scotsman.*

PRACTICAL FORESTRY.

And its Bearing on the Improvement of Estates. By CHARLES E. CURTIS, F.S.I., Professor of Forestry, Field Engineering, and General Estate Management, at the College of Agriculture, Downton. Second Edition, Revised. Crown 8vo, cloth. [*Just Published.* **3/6**

SUMMARY OF CONTENTS:—PREFATORY REMARKS.—OBJECTS OF PLANTING.—CHOICE OF A FORESTER.—CHOICE OF SOIL AND SITE.—LAYING OUT OF LAND FOR PLANTATIONS.—PREPARATION OF THE GROUND FOR PLANTING.—DRAINAGE.—PLANTING.—DISTANCES AND DISTRIBUTION OF TREES IN PLANTATIONS.—TREES AND GROUND GAME.—ATTENTION AFTER PLANTING.—THINNING OF PLANTATIONS — PRUNING OF FOREST TREES.—REALIZATION.—METHODS OF SALE.—MEASUREMENT OF TIMBER.—MEASUREMENT AND VALUATION OF LARCH PLANTATION.—FIRE LINES.—COST OF PLANTING.

"Mr. Curtis has in the course of a series of short pithy chapters afforded much information of a useful and practical character on the planting and subsequent treatment of trees."—*Illustrated Carpenter and Builder.*

THE ELEMENTS OF FORESTRY.

Designed to afford Information concerning the Planting and Care of Forest Trees for Ornament or Profit, with suggestions upon the Creation and Care of Woodlands. By F. B. HOUGH. Large crown 8vo, cloth . . . **10/0**

THE TIMBER IMPORTER'S, TIMBER MERCHANT'S, AND BUILDER'S STANDARD GUIDE.

By RICHARD E. GRANDY. Comprising:—An Analysis of Deal Standards, Home and Foreign, with Comparative Values and Tabular Arrangements for fixing Net Landed Cost on Baltic and North American Deals, including all intermediate Expenses, Freight, Insurance, &c.; together with copious Information for the Retailer and Builder. Third Edition. 12mo, cloth . . **2/0**

Digitized by Google

DECORATIVE ARTS, &c.

SCHOOL OF PAINTING FOR THE IMITATION OF WOODS AND MARBLES.

As Taught and Practised by A. R. VAN DER BURG and P. VAN DER BURG, Directors of the Rotterdam Painting Institution. Royal folio, 18½ by 12½ in., Illustrated with 24 full-size Coloured Plates; also 12 plain Plates, comprising 154 Figures. Third Edition, cloth. [*Just Published.* **£1 11s. 6d.**

LIST OF PLATES:—1. VARIOUS TOOLS REQUIRED FOR WOOD PAINTING.—2, 3. WALNUT; PRELIMINARY STAGES OF GRAINING AND FINISHED SPECIMEN.—4. TOOLS USED FOR MARBLE PAINTING AND METHOD OF MANIPULATION.—5, 6. ST. REMI MARBLE; EARLIER OPERATIONS AND FINISHED SPECIMEN.—7. METHODS OF SKETCHING DIFFERENT GRAINS, KNOTS, &c.—8, 9. ASH: PRELIMINARY STAGES AND FINISHED SPECIMEN.—10. METHODS OF SKETCHING MARBLE GRAINS.—11, 12. BRECHE MARBLE; PRELIMINARY STAGES OF WORKING AND FINISHED SPECIMEN.—13. MAPLE; METHODS OF PRODUCING THE DIFFERENT GRAINS.—14, 15. BIRD'S-EYE MAPLE; PRELIMINARY STAGES AND FINISHED SPECIMEN.—16. METHODS OF SKETCHING THE DIFFERENT SPECIES OF WHITE MARBLE.—17, 18. WHITE MARBLE; PRELIMINARY STAGES OF PROCESS AND FINISHED SPECIMEN.—19. MAHOGANY; SPECIMENS OF VARIOUS GRAINS AND METHODS OF MANIPULATION.—20, 21. MAHOGANY; EARLIER STAGES AND FINISHED SPECIMEN.—22, 23, 24. SIENNA MARBLE; VARIETIES OF GRAIN, PRELIMINARY STAGES AND FINISHED SPECIMEN.—25, 26, 27. JUNIPER WOOD; METHODS OF PRODUCING GRAIN, &c.; PRELIMINARY STAGES AND FINISHED SPECIMEN.—28, 29, 30. VERT DE MER MARBLE; VARIETIES OF GRAIN AND METHODS OF WORKING, UNFINISHED AND FINISHED SPECIMENS.—31, 32, 33. OAK; VARIETIES OF GRAIN, TOOLS EMPLOYED AND METHODS OF MANIPULATION, PRELIMINARY STAGES AND FINISHED SPECIMEN.—34, 35, 36. WAULSORT MARBLE; VARIETIES OF GRAIN, UNFINISHED AND FINISHED SPECIMENS.

"Those who desire to attain skill in the art of painting woods and marbles will find advantage in consulting this book. . . . Some of the Working Men's Clubs should give their young men the opportunity to study it."—*Builder.*

"A comprehensive guide to the art. The explanations of the processes, the manipulation and management of the colours, and the beautifully executed plates will not be the least valuable to the student who aims at making his work a faithful transcript of nature."—*Building News.*

"Students and novices are fortunate who are able to become the possessors of so noble a work."—*The Architect.*

ELEMENTARY DECORATION.

A Guide to the Simpler Forms of Everyday Art. Together with PRACTICAL HOUSE DECORATION. By JAMES W. FACEY. With numerous Illustrations. In One Vol., strongly half-bound **5/0**

HOUSE PAINTING, GRAINING, MARBLING, AND SIGN WRITING.

A Practical Manual of. By ELLIS A. DAVIDSON. Seventh Edition. With Coloured Plates and Wood Engravings. 12mo, cloth boards . . . **6/0**

"A mass of information of use to the amateur and of value to the practical man."—*English Mechanic.*

THE DECORATOR'S ASSISTANT.

A Modern Guide for Decorative Artists and Amateurs, Painters, Writers, Gilders, &c. Containing upwards of 600 Receipts, Rules, and Instructions; with a variety of Information for General Work connected with every Class of Interior and Exterior Decorations, &c. Seventh Edition. 152 pp., cr. 8vo. **1/0**

"Full of receipts of value to decorators, painters, gilders, &c. The book contains the gist of larger treatises on colour and technical processes. It would be difficult to meet with a work so full of varied information on the painter's art."—*Building News.*

MARBLE DECORATION

And the Terminology of British and Foreign Marbles. A Handbook for Students. By GEORGE H. BLAGROVE, Author of "Shoring and its Application," &c. With 28 Illustrations. Crown 8vo, cloth **3/6**

"This most useful and much wanted handbook should be in the hands of every architect and builder."—*Building World*

"A carefully and usefully written treatise; the work is essentially practical."—*Scotsman.*

Digitized by Google

DELAMOTTE'S WORKS ON ALPHABETS AND ILLUMINATION.

ORNAMENTAL ALPHABETS, ANCIENT & MEDIÆVAL.

From the Eighth Century, with Numerals; including Gothic, Church-Text, large and small, German, Italian, Arabesque, Initials for Illumination, Monograms, Crosses, &c., &c., for the use of Architectural and Engineering Draughtsmen, Missal Painters, Masons, Decorative Painters, Lithographers, Engravers, Carvers, &c., &c. Collected and Engraved by F. DELAMOTTE, and printed in Colours. New and Cheaper Edition. Royal 8vo, oblong, ornamental boards **2/6**

"For those who insert enamelled sentences round gilded chalices, who blazon shop legends over shop-doors, who letter church walls with pithy sentences from the Decalogue, this book will be useful."—*Athenæum.*

MODERN ALPHABETS, PLAIN AND ORNAMENTAL.

Including German, Old English, Saxon, Italic, Perspective, Greek, Hebrew, Court Hand, Engrossing, Tuscan, Riband, Gothic, Rustic, and Arabesque; with several Original Designs, and an Analysis of the Roman and Old English Alphabets, large and small, and Numerals, for the use of Draughtsmen, Surveyors, Masons, Decorative Painters, Lithographers, Engravers, Carvers, &c. Collected and Engraved by F. DELAMOTTE, and printed in Colours. New and Cheaper Edition. Royal 8vo, oblong, ornamental boards . **2/6**

"There is comprised in it every possible shape into which the letters of the alphabet and numerals can be formed, and the talent which has been expended in the conception of the various plain and ornamental letters is wonderful."—*Standard.*

MEDIÆVAL ALPHABETS AND INITIALS FOR ILLUMINATORS.

By F. G. DELAMOTTE. Containing 21 Plates and Illuminated Title, printed in Gold and Colours. With an Introduction by J. WILLIS BROOKS. Fourth and Cheaper Edition. Small 4to, ornamental boards **4/0**

"A volume in which the letters of the alphabet come forth glorified in gilding and all the colours of the prism interwoven and intertwined and intermingled."—*Sun.*

A PRIMER OF THE ART OF ILLUMINATION.

For the Use of Beginners; with a Rudimentary Treatise on the Art, Practical Directions for its Exercise, and Examples taken from Illuminated MSS., printed in Gold and Colours. By F. DELAMOTTE. New and Cheaper Edition. Small 4to, ornamental boards **6/0**

"The examples of ancient MSS. recommended to the student, which, with much good sense, the author chooses from collections accessible to all, are selected with judgment and knowledge as well as taste."—*Athenæum.*

THE EMBROIDERER'S BOOK OF DESIGN.

Containing Initials, Emblems, Cyphers, Monograms, Ornamental Borders, Ecclesiastical Devices, Mediæval and Modern Alphabets, and National Emblems. Collected by F. DELAMOTTE, and printed in Colours. Oblong royal 8vo, ornamental wrapper **1/6**

"The book will be of great assistance to ladies and young children who are endowed with the art of plying the needle in this most ornamental and useful pretty work."—*East Anglian Times.*

INSTRUCTIONS IN WOOD-CARVING FOR AMATEURS.

With Hints on Design. By A LADY. With 10 Plates. New and Cheaper Edition. Crown 8vo, in emblematic wrapper **2/0**

"The handicraft of the wood-carver, so well as a book can impart it, may be learnt from 'A Lady's' publication."—*Athenæum.*

PAINTING POPULARLY EXPLAINED.

By THOMAS JOHN GULLICK, Painter, and JOHN TIMBS, F.S.A. Including Fresco, Oil, Mosaic, Water-Colour, Water-Glass, Tempera, Encaustic, Miniature, Painting on Ivory, Vellum, Pottery, Enamel, Glass, &c. Fifth Edition. Crown 8vo, cloth **5/0**

*** *Adopted as a Prize Book at South Kensington.*

"Much may be learned, even by those who fancy they do not require to be taught, from the careful perusal of this unpretending but comprehensive treatise."—*Art Journal.*

Digitized by Google

NATURAL SCIENCE, &c.

THE VISIBLE UNIVERSE.

Chapters on the Origin and Construction of the Heavens. By J. E. GORE, F.R.A.S., Author of "Star Groups," &c. Illustrated by 6 Stellar Photographs and 12 Plates. Demy 8vo, cloth **16/0**

"A valuable and lucid summary of recent astronomical theory, rendered more valuable and attractive by a series of stellar photographs and other illustrations."—*The Times.*

"In presenting a clear and concise account of the present state of our knowledge Mr. Gore has made a valuable addition to the literature of the subject."—*Nature.*

"Mr. Gore's 'Visible Universe' is one of the finest works on astronomical science that have recently appeared in our language. In spirit and in method it is scientific from cover to cover, but the style is so clear and attractive that it will be as acceptable and as readable to those who make no scientific pretensions as to those who devote themselves specially to matters astronomical."—*Leeds Mercury.*

STAR GROUPS.

A Student's Guide to the Constellations. By J. ELLARD GORE, F.R.A.S., M.R.I.A., &c., Author of "The Visible Universe," "The Scenery of the Heavens," &c. With 30 Maps. Small 4to, cloth **5/0**

"The volume contains thirty maps showing stars of the sixth magnitude—the usual naked-eye limit—and each is accompanied by a brief commentary adapted to facilitate recognition and bring to notice objects of special interest. For the purpose of a preliminary survey of the 'midnight pomp' of the heavens nothing could be better than a set of delineations averaging scarcely twenty square inches in area and including nothing that cannot at once be identified."—*Saturday Review.*

AN ASTRONOMICAL GLOSSARY.

Or, Dictionary of Terms used in Astronomy. With Tables of Data and Lists of Remarkable and Interesting Celestial Objects. By J. ELLARD GORE, F.R.A.S., Author of "The Visible Universe," &c. Small crown 8vo, cloth. **2/6**

"A very useful little work for beginners in astronomy, and not to be despised by more advanced students."—*The Times.*

"A very handy book . . . the utility of which is much increased by its valuable tables of astronomical data."—*Athenæum*

THE MICROSCOPE.

Its Construction and Management. Including Technique, Photo-micrography, and the Past and Future of the Microscope. By Dr. HENRI VAN HEURCK. Re-Edited and Augmented from the Fourth French Edition, and Translated by WYNNE E. BAXTER, F.G.S. 400 pp., with upwards of 250 Woodcuts, imp. 8vo, cloth **18/0**

"A translation of a well-known work, at once popular and comprehensive."—*Times.*

"The translation is as felicitous as it is accurate."—*Nature.*

ASTRONOMY.

By the late Rev. ROBERT MAIN, M.A., F.R.S. Third Edition, Revised by WILLIAM THYNNE LYNN, B.A., F.R.A.S., formerly of the Royal Observatory, Greenwich. 12mo, cloth **2/0**

"A sound and simple treatise, very carefully edited, and a capital book for beginners."—*Knowledge.*

"Accurately brought down to the requirements of the present time by Mr. Lynn."—*Educational Times.*

A MANUAL OF THE MOLLUSCA.

A Treatise on Recent and Fossil Shells. By S. P. WOODWARD, A.L.S., F.G.S. With an Appendix on RECENT AND FOSSIL CONCHOLOGICAL DISCOVERIES, by RALPH TATE, A.L.S., F.G.S. With 23 Plates and upwards of 300 Woodcuts. Reprint of Fourth Edition (1880). Crown 8vo, cloth **7/6**

"A most valuable storehouse of conchological and geological information."—*Science Gossip.*

THE TWIN RECORDS OF CREATION.

Or, Geology and Genesis, their Perfect Harmony and Wonderful Concord. By G. W. V. LE VAUX. 8vo, cloth **5/0**

"A valuable contribution to the evidences of Revelation, and disposes very conclusively of the arguments of those who would set God's Works against God's Word. No real difficulty is shirked, and no sophistry is left unexposed."—*The Rock.*

Digitized by Google

HANDBOOK OF MECHANICS.

By Dr. LARDNER. Enlarged and re-written by BENJAMIN LOEWY, F.R.A.S. 378 Illustrations. Post 8vo, cloth **6/0**

"The perspicuity of the original has been retained, and chapters which had become obsolete have been replaced by others of more modern character. The explanations throughout are studiously popular, and care has been taken to show the application of the various branches of physics to the industrial arts, and to the practical business of life."—*Mining Journal.*

HANDBOOK OF HYDROSTATICS AND PNEUMATICS.

By Dr. LARDNER. New Edition, Revised and Enlarged by BENJAMIN LOEWY, F.R.A.S. With 236 Illustrations. Post 8vo, cloth **5/0**

"For those 'who desire to attain an accurate knowledge of physical science without the profound methods of mathematical investigation,' this work is well adapted."—*Chemical News.*

HANDBOOK OF HEAT.

By Dr. LARDNER. Edited and re-written by BENJAMIN LOEWY, F.R.A.S., &c. 117 Illustrations. Post 8vo, cloth **6/0**

"The style is always clear and precise, and conveys instruction without leaving any cloudiness or lurking doubts behind."—*Engineering.*

HANDBOOK OF OPTICS.

By Dr. LARDNER. New Edition. Edited by T. OLVER HARDING, B.A. Lond. With 298 Illustrations. Small 8vo, 448 pp., cloth **5/0**

"Written by one of the ablest English scientific writers, beautifully and elaborately illustrated.'—*Mechanics' Magazine.*

ELECTRICITY, MAGNETISM, AND ACOUSTICS.

By Dr. LARDNER. Edited by GEO. CAREY FOSTER, B.A., F.C.S. With 400 Illustrations. Small 8vo, cloth **5/0**

"The book could not have been entrusted to any one better calculated to preserve the terse and lucid style of Lardner, while correcting his errors and bringing up his work to the present state of scientific knowledge."—*Popular Science Review.*

HANDBOOK OF ASTRONOMY.

By Dr. LARDNER. Fourth Edition. Revised and Edited by EDWIN DUNKIN, F.R.A.S., Royal Observatory, Greenwich. With 38 Plates and upwards of 100 Woodcuts. 8vo, cloth **9/6**

"Probably no other book contains the same amount of information in so compendious and well arranged a form—certainly none at the price at which this is offered to the public."—*Athenæum.*

"We can do no other than pronounce this work a most valuable manual of astronomy, and we strongly recommend it to all who wish to acquire a general—but at the same time correct—acquaintance with this sublime science."—*Quarterly Journal of Science*

MUSEUM OF SCIENCE AND ART.

Edited by Dr. LARDNER. With upwards of 1,200 Engravings on Wood. In Six Double Volumes, **£1 1s.** in a new and elegant cloth binding; or handsomely bound in half-morocco . . . . . **£1 11s. 6d.**

"A cheap and interesting publication, alike informing and attractive. The papers combine subjects of importance and great scientific knowledge, considerable inductive powers, and a popular style of treatment."—*Spectator.*

Separate books formed from the above.

Common Things Explained. 5s.
The Microscope. 2s. cloth.
Popular Geology. 2s. 6d. cloth.
Popular Physics. 2s. 6d. cloth.
Steam and its Uses. 2s. cloth.
Popular Astronomy. 4s. 6d. cloth.
The Bee and White Ants. 2s. cloth.
The Electric Telegraph. 1s. 6d.

NATURAL PHILOSOPHY FOR SCHOOLS.

By Dr. LARDNER. Fcap. 8vo **3/6**

"A very convenient class book for junior students in private schools."—*British Quarterly Review.*

ANIMAL PHYSIOLOGY FOR SCHOOLS.

By Dr. LARDNER. Fcap. 8vo **3/6**

"Clearly written, well arranged, and excellently illustrated."—*Gardener's Chronicle.*

THE ELECTRIC TELEGRAPH.

By Dr. LARDNER. Revised by E. B. BRIGHT, F.R.A.S. Fcap. 8vo. . **2/6**

"One of the most readable books extant on the Electric Telegraph."—*English Mechanic.*

Digitized by Google

CHEMICAL MANUFACTURES, CHEMISTRY, &c.

THE GAS ENGINEER'S POCKET-BOOK.

Comprising Tables, Notes and Memoranda relating to the Manufacture, Distribution and Use of Coal Gas and the Construction of Gas Works. By H. O'CONNOR, A.M.Inst.C.E., 450 pp., crown 8vo, fully Illustrated, leather. [*Just Published.* **10/6**

"The book contains a vast amount of information. The author goes consecutively through the engineering details and practical methods involved in each of the different processes or parts of a gas-works. He has certainly succeeded in making a compilation of hard matters of fact absolutely interesting to read."—*Gas World.*

"A useful work of reference for the gas engineer and all interested in lighting or heating by gas, while the analyses of the various descriptions of gas will be of value to the technical chemist. All matter in any way connected with the manufacture and use of gas is dealt with. The book has evidently been carefully compiled, and certainly constitutes a useful addition to gas literature."—*Builder.*

"The volume contains a great quantity of specialised information, compiled, we believe, from trustworthy sources, which should make it of considerable value to those for whom it is specifically produced."—*Engineer.*

LIGHTING BY ACETYLENE

Generators, Burners, and Electric Furnaces. By WILLIAM E. GIBBS, M.E. With 66 Illustrations. Crown 8vo, cloth. [*Just Published.* **7/6**

ENGINEERING CHEMISTRY.

A Practical Treatise for the Use of Analytical Chemists, Engineers, Iron Masters, Iron Founders, Students and others. Comprising Methods of Analysis and Valuation of the Principal Materials used in Engineering Work, with Analyses, Examples and Suggestions. By H. J. PHILLIPS, F.I.C., F.C.S. Second Edition, Enlarged. Crown 8vo, 400 pp., with Illustrations, cloth **10/6**

"In this work the author has rendered no small service to a numerous body of practical men. . . . The analytical methods may be pronounced most satisfactory, being as accurate as the despatch required of engineering chemists permits."—*Chemical News.*

"Full of good things. As a handbook of technical analysis, it is very welcome."—*Builder.*

"The analytical methods given are, as a whole, such as are likely to give rapid and trustworthy results in experienced hands. . . . There is much excellent descriptive matter in the work, the chapter on 'Oils and Lubrication' being specially noticeable in this respect."—*Engineer.*

NITRO-EXPLOSIVES.

A Practical Treatise concerning the Properties, Manufacture, and Analysis of Nitrated Substances, including the Fulminates, Smokeless Powders, and Celluloid. By P. G. SANFORD, F.I.C., Consulting Chemist to the Cotton Powder Company, &c. With Illustrations. Crown 8vo, cloth. [*Just Published.* **9/0**

"Any one having the requisite apparatus and materials could make nitro-glycerine or gun-cotton, to say nothing of other explosives, by the aid of the instructions in this volume. This is one of the very few text-books in which can be found just what is wanted. Mr. Sanford goes through the whole list of explosives commonly used, names any given explosive, and tells us of what it is composed and how it is manufactured. The book is excellent throughout."—*Engineer.*

A HANDBOOK ON MODERN EXPLOSIVES.

A Practical Treatise on the Manufacture and Use of Dynamite, Gun-Cotton, Nitro-Glycerine and other Explosive Compounds, including Collodion-Cotton. With Chapters on Explosives in Practical Application. By M. EISSLER, Mining Engineer and Metallurgical Chemist. Second Edition, Enlarged. With 150 Illustrations. Crown 8vo, cloth. [*Just Published.* **12/6**

"Useful not only to the miner, but also to officers of both services to whom blasting and the use of explosives generally may at any time become a necessary auxiliary."—*Nature.*

DANGEROUS GOODS.

Their Sources and Properties, Modes of Storage and Transport. With Notes and Comments on Accidents arising therefrom, together with the Government and Railway Classifications, Acts of Parliament, &c. A Guide for the Use of Government and Railway Officials, Steamship Owners, Insurance Companies and Manufacturers, and Users of Explosives and Dangerous Goods. By H. JOSHUA PHILLIPS, F.I.C., F.C.S. Crown 8vo, 374 pp., cloth . . **9/0**

"Merits a wide circulation, and an intelligent, appreciative study."—*Chemical News.*

Digitized by Google

A MANUAL OF THE ALKALI TRADE.

Including the Manufacture of Sulphuric Acid, Sulphate of Soda, and Bleaching Powder. By JOHN LOMAS, Alkali Manufacturer, Newcastle-upon-Tyne and London. 390 pp. of Text. With 232 Illustrations and Working Drawings, Second Edition, with Additions. Super-royal 8vo, cloth . . **£1 10s.**

"This book is written by a manufacturer for manufacturers. The working details of the most approved forms of apparatus are given, and these are accompanied by no less than 232 wood engravings, all of which may be used for the purposes of construction. Every step in the manufacture is very fully described in this manual, and each improvement explained."—*Athenæum.*

"We find not merely a sound and luminous explanation of the chemical principles of the trade, but a notice of numerous matters which have a most important bearing on the successful conduct of alkali works, but which are generally overlooked by even experienced technological authors."—*Chemical Review.*

THE BLOWPIPE IN CHEMISTRY, MINERALOGY, AND GEOLOGY.

Containing all known Methods of Anhydrous Analysis, many Working Examples, and Instructions for Making Apparatus. By Lieut.-Colonel W. A. Ross, R.A., F.G.S. With 120 Illustrations. Second Edition, Enlarged. Crown 8vo, cloth **5/0**

"The student who goes conscientiously through the course of experimentation here laid down will gain a better insight into inorganic chemistry and mineralogy than if he had 'got up' any of the best text-books of the day, and passed any number of examinations in their contents."—*Chemical News.*

THE MANUAL OF COLOURS AND DYE-WARES.

Their Properties, Applications, Valuations, Impurities and Sophistications. For the Use of Dyers, Printers, Drysalters, Brokers, &c. By J. W. SLATER. Second Edition, Revised and greatly Enlarged. Crown 8vo, cloth . **7/6**

"A complete encyclopædia of the *materia tinctoria.* The information given respecting each article is full and precise, and the methods of determining the value of articles such as these, so liable to sophistication, are given with clearness, and are practical as well as valuable."—*Chemist and Druggist.*

"There is no other work which covers precisely the same ground. To students preparing for examinations in dyeing and printing it will prove exceedingly useful."—*Chemical News.*

A HANDY BOOK FOR BREWERS.

Being a Practical Guide to the Art of Brewing and Malting. Embracing the Conclusions of Modern Research which bear upon the Practice of Brewing. By HERBERT EDWARDS WRIGHT, M.A. Second Edition, Enlarged. Crown 8vo, 530 pp., cloth. [*Just Published.* **12/6**

"May be consulted with advantage by the student who is preparing himself for examinational tests, while the scientific brewer will find in it a *résumé* of all the most important discoveries of modern times. The work is written throughout in a clear and concise manner, and the author takes great care to discriminate between vague theories and well-established facts."—*Brewers' Journal.*

"We have great pleasure in recommending this handy book, and have no hesitation in saying that it is one of the best—if not the best—which has yet been written on the subject of beer-brewing in this country; it should have a place on the shelves of every brewer's library."—*Brewers' Guardian.*

"Although the requirements of the student are primarily considered, an acquaintance of half-an-hour's duration cannot fail to impress the practical brewer with the sense of having found a trustworthy guide and practical counsellor in brewery matters."—*Chemical Trade Journal.*

FUELS: SOLID, LIQUID, AND GASEOUS.

Their Analysis and Valuation. For the Use of Chemists and Engineers. By H. J. PHILLIPS, F.C.S., formerly Analytical and Consulting Chemist to the G.E. Rlwy. Third Edition, Revised and Enlarged. Crown 8vo, cloth **2/0**

"Ought to have its place in the laboratory of every metallurgical establishment and wherever fuel is used on a large scale."—*Chemical News.*

Digitized by Google

THE ARTISTS' MANUAL OF PIGMENTS.

Showing their Composition, Conditions of Permanency, Non-Permanency, and Adulterations; Effects in Combination with Each Other and with Vehicles; and the most Reliable Tests of Purity. By H. C. STANDAGE. crown 8vo. **2/6**

"This work is indeed *multum-in-parvo*, and we can, with good conscience, recommend it to all who come in contact with pigments, whether as makers, dealers, or users."—*Chemical Review.*

A POCKET-BOOK OF MENSURATION AND GAUGING.

Containing Tables, Rules, and Memoranda for Revenue Officers, Brewers, Spirit Merchants, &c. By J. B. MANT, Inland Revenue. Second Edition Revised. 18mo, leather **4/0**

"This handy and useful book is adapted to the requirements of the Inland Revenue Department, and will be a favourite book of reference."—*Civilian.*

"Should be in the hands of every practical brewer."—*Brewers' Journal.*

INDUSTRIAL ARTS, TRADES, AND MANUFACTURES.

MODERN CYCLES.

A Practical Handbook on their Construction and Repair. By A. J. WALLIS-TAYLER, A. M. Inst. C. E. Author of "Refrigerating Machinery," &c. With upwards of 300 Illustrations. Crown 8vo, cloth. [*Just Published.* **10/6**

"The large trade that is done in the component parts of bicycles has placed in the way of men mechanically inclined extraordinary facilities for building bicycles for their own use. . . The book will prove a valuable guide for all those who aspire to the manufacture or repair of their own machines."—*The Field.*

"A most comprehensive and up-to-date treatise."—*The Cycle.*

"A very useful book, which is quite entitled to rank as a standard work for students of cycle construction."—*Wheeling.*

TEA MACHINERY AND TEA FACTORIES.

A Descriptive Treatise on the Mechanical Appliances required on Tea Plantations in the Preparation of Tea for the Market. By A. J. W. TAYLER, A.M. Inst. C.E. With about 200 Illustrations. Medium 8vo.

[*Nearly Ready. Price, about* **25/0**

TEA PLANTING AND MANUFACTURE

(A Text Book of). Comprising Chapters on the History and Development of the Industry, the Cultivation of the Plant, the Preparation of the Leaf for the Market, &c. By DAVID CROLE, late of the Jokai Tea Company, &c. With Plates and other Illustrations. Medium 8vo, cloth **16/0**

COTTON MANUFACTURE.

A Manual of Practical Instruction of the Processes of Opening, Carding, Combing, Drawing, Doubling and Spinning of Cotton, the Methods of Dyeing, &c. For the Use of Operatives, Overlookers, and Manufacturers. By JOHN LISTER, Technical Instructor, Pendleton. 8vo, cloth . . **7/6**

"A distinct advance in the literature of cotton manufacture."—*Machinery.*

"It is thoroughly reliable, fulfilling nearly all the requirements desired."—*Glasgow Herald.*

FLOUR MANUFACTURE.

A Treatise on Milling Science and Practice. By FRIEDRICH KICK, Imperial Regierungsrath, Professor of Mechanical Technology in the Imperial German Polytechnic Institute, Prague. Translated from the Second Enlarged and Revised Edition with Supplement. By H. H. P. POWLES, Assoc. Memb. Institution of Civil Engineers. Nearly 400 pp. Illustrated with 28 Folding Plates, and 167 Woodcuts. Royal 8vo, cloth . . . . . **£1 5s.**

"This valuable work is, and will remain, the standard authority on the science of milling. . . . The miller who has read and digested this work will have laid the foundation, so to speak, of a successful career; he will have acquired a number of general principles which he can proceed to apply. In this handsome volume we at last have the accepted text-book of modern milling in good, sound English, which has little, if any, trace of the German idiom."—*The Miller.*

Digitized by Google

CEMENTS, PASTES, GLUES, AND GUMS.

A Practical Guide to the Manufacture and Application of the various Agglutinants required in the Building, Metal-Working, Wood-Working, and Leather-Working Trades, and for Workshop, Laboratory or Office Use. With upwards of 900 Recipes and Formulæ. By H. C. STANDAGE, Chemist. Third Edition. Crown 8vo, cloth. [*Just Published.* **2/0**

"We have pleasure in speaking favourably of this volume. So far as we have had experience, which is not inconsiderable, this manual is trustworthy."—*Athenæum.*

"As a revelation of what are considered trade secrets, this book will arouse an amount of curiosity among the large number of industries it touches."—*Daily Chronicle.*

THE ART OF SOAP-MAKING.

A Practical Handbook of the Manufacture of Hard and Soft Soaps, Toilet Soaps, &c. Including many New Processes, and a Chapter on the Recovery of Glycerine from Waste Leys. By ALX. WATT. Fifth Edition, Revised, with an Appendix on Modern Candlemaking. Crown 8vo, cloth . . . **7/6**

"The work will prove very useful, not merely to the technological student, but to the practical soap boiler who wishes to understand the theory of his art."—*Chemical News.*

"A thoroughly practical treatise on an art which has almost no literature in our language. We congratulate the author on the success of his endeavour to fill a void in English technical literature."—*Nature.*

PRACTICAL PAPER-MAKING.

A Manual for Paper-Makers and Owners and Managers of Paper-Mills. With Tables, Calculations, &c. By G. CLAPPERTON, Paper-Maker. With Illustrations of Fibres from Micro-Photographs. Crown 8vo, cloth . . **5/0**

"The author caters for the requirements of responsible mill hands, apprentices, &c., whilst his manual will be found of great service to students of technology, as well as to veteran paper-makers and mill owners. The illustrations form an excellent feature."—*The World's Paper Trade Review.*

"We recommend everybody interested in the trade to get a copy of this thoroughly practical book."—*Paper Making.*

THE ART OF PAPER-MAKING.

A Practical Handbook of the Manufacture of Paper from Rags, Esparto, Straw, and other Fibrous Materials. Including the Manufacture of Pulp from Wood Fibre, with a Description of the Machinery and Appliances used. To which are added Details of Processes for Recovering Soda from Waste Liquors. By ALEXANDER WATT, Author of "The Art of Soap-Making." With Illustrations. Crown 8vo, cloth **7/6**

"It may be regarded as the standard work on the subject. The book is full of valuable information. The 'Art of Paper-Making' is in every respect a model of a text-book, either for a technical class, or for the private student."—*Paper and Printing Trades Journal.*

A TREATISE ON PAPER

For Printers and Stationers. With an Outline of Paper Manufacture; Complete Tables of Sizes, and Specimens of Different Kinds of Paper. By RICHARD PARKINSON, late of the Manchester Technical School. Demy 8vo, cloth. [*Just Published.* **3/6**

THE ART OF LEATHER MANUFACTURE.

Being a Practical Handbook, in which the Operations of Tanning, Currying, and Leather Dressing are fully Described, and the Principles of Tanning Explained, and many Recent Processes Introduced; as also Methods for the Estimation of Tannin, and a Description of the Arts of Glue Boiling, Gut Dressing, &c. By ALEXANDER WATT, Author of "Soap-Making," &c. Fourth Edition. Crown 8vo, cloth **9/0**

"A sound, comprehensive treatise on tanning and its accessories. The book is an eminently valuable production, which redounds to the credit of both author and publishers."—*Chemical Review.*

THE ART OF BOOT AND SHOE MAKING.

A Practical Handbook, including Measurement, Last-Fitting, Cutting-Out, Closing and Making, with a Description of the most approved Machinery Employed. By JOHN B. LENO, late Editor of *St. Crispin*, and *The Boot and Shoe-Maker.* 12mo, cloth. **2/0**

Digitized by Google

WOOD ENGRAVING.

A Practical and Easy Introduction to the Study of the Art. By W. N. BROWN. 12mo, cloth **1/6**

"The book is clear and complete, and will be useful to any one wanting to understand the first elements of the beautiful art of wood engraving."—*Graphic.*

MODERN HOROLOGY, IN THEORY AND PRACTICE.

Translated from the French of CLAUDIUS SAUNIER, ex-Director of the School of Horology at Macon, by JULIEN TRIPPLIN, F.R.A.S., Besancon Watch Manufacturer, and EDWARD RIGG, M.A., Assayer in the Royal Mint. With Seventy-eight Woodcuts and Twenty-two Coloured Copper Plates. Second Edition. Super-royal 8vo, cloth, **£2 2s.**; half-calf . . . **£2 10s.**

"There is no horological work in the English language at all to be compared to this production of M. Saunier's for clearness and completeness. It is alike good as a guide for the student and as a reference for the experienced horologist and skilled workman."—*Horological Journal.*

"The latest, the most complete, and the most reliable of those literary productions to which continental watchmakers are indebted for the mechanical superiority over their English brethren—in fact, the Book of Books, is M. Saunier's 'Treatise.'"—*Watchmaker, Jeweller, and Silversmith.*

THE WATCH ADJUSTER'S MANUAL.

A Practical Guide for the Watch and Chronometer Adjuster in Making, Springing, Timing and Adjusting for Isochronism, Positions and Temperatures. By C. E. FRITTS. 370 pp., with Illustrations, 8vo, cloth . . . **16/0**

THE WATCHMAKER'S HANDBOOK.

Intended as a Workshop Companion for those engaged in Watchmaking and the Allied Mechanical Arts. Translated from the French of CLAUDIUS SAUNIER, and enlarged by JULIEN TRIPPLIN, F.R.A.S., and EDWARD RIGG, M.A., Assayer in the Royal Mint. Third Edition. 8vo, cloth. **9/0**

"Each part is truly a treatise in itself. The arrangement is good and the language is clear and concise. It is an admirable guide for the young watchmaker."—*Engineering.*

"It is impossible to speak too highly of its excellence. It fulfils every requirement in a handbook intended for the use of a workman. Should be found in every workshop."—*Watch and Clockmaker*

A HISTORY OF WATCHES & OTHER TIMEKEEPERS.

By JAMES F. KENDAL, M.B.H. Inst. Boards, **1/6**; or cloth, gilt . **2/6**

"The best which has yet appeared on this subject in the English language."—*Industries.*

"Open the book where you may, there is interesting matter in it concerning the ingenious devices of the ancient or modern horologer."—*Saturday Review.*

ELECTRO-DEPOSITION.

A Practical Treatise on the Electrolysis of Gold, Silver, Copper, Nickel, and other Metals and Alloys. With Descriptions of Voltaic Batteries, Magneto and Dynamo-Electric Machines, Thermopiles, and of the Materials and Processes used in every Department of the Art, and several Chapters on ELECTRO-METALLURGY. By ALEXANDER WATT, Author of "Electro-Metallurgy," &c. Third Edition, Revised. Crown 8vo, cloth . . **9/0**

"Eminently a book for the practical worker in electro-deposition. It contains practical descriptions of methods, processes and materials, as actually pursued and used in the workshop."—*Engineer.*

ELECTRO-METALLURGY.

Practically Treated. By ALEXANDER WATT. Tenth Edition, including the most recent Processes. 12mo, cloth **3/6**

"From this book both amateur and artisan may learn everything necessary for the successful prosecution of electroplating."—*Iron.*

JEWELLER'S ASSISTANT IN WORKING IN GOLD.

A Practical Treatise for Masters and Workmen, Compiled from the Experience of Thirty Years' Workshop Practice. By GEORGE E. GEE, Author of "The Goldsmith's Handbook," &c. Crown 8vo, cloth **7/6**

"This manual of technical education is apparently destined to be a valuable auxiliary to a handicraft which is certainly capable of great improvement."—*The Times.*

Digitized by Google

ELECTROPLATING.

A Practical Handbook on the Deposition of Copper, Silver, Nickel, Gold, Aluminium, Brass, Platinum, &c., &c. By J. W. URQUHART, C.E. Fourth Edition, Revised. Crown 8vo, cloth [*Just Published.* **5/0**

"An excellent practical manual."—*Engineering.*
"An excellent work, giving the newest information."—*Horological Journal.*

ELECTROTYPING.

The Reproduction and Multiplication of Printing Surfaces and Works of Art by the Electro-Deposition of Metals. By J. W. URQUHART, C.E. Crown 8vo, cloth **5/0**

"The book is thoroughly practical; the reader is, therefore, conducted through the leading laws of electricity, then through the metals used by electrotypers, the apparatus, and the depositing processes, up to the final preparation of the work."—*Art Journal.*

GOLDSMITH'S HANDBOOK.

By GEORGE E. GEE, Jeweller, &c. Fifth Edition. 12mo, cloth . . **3/0**

"A good, sound educator, and will be generally accepted as an authority."—*Horological Journal.*

SILVERSMITH'S HANDBOOK.

By GEORGE E. GEE, Jeweller, &c. Third Edition, with numerous Illustrations. 12mo, cloth **3/0**

"The chief merit of the work is its practical character. . . . The workers in the trade will speedily discover its merits when they sit down to study it."—*English Mechanic.*

*** *The above two works together, strongly half-bound, price 7s.*

SHEET METAL WORKER'S INSTRUCTOR.

Comprising a Selection of Geometrical Problems and Practical Rules for Describing the Various Patterns Required by Zinc, Sheet-Iron, Copper, and Tin-Plate Workers. By REUBEN HENRY WARN. New Edition, Revised and greatly Enlarged by JOSEPH G. HORNER, A.M.I.M.E. Crown 8vo, 254 pp., with 430 Illustrations, cloth. [*Just Published.* **7/6**

BREAD & BISCUIT BAKER'S & SUGAR-BOILER'S ASSISTANT.

Including a large variety of Modern Recipes. With Remarks on the Art of Bread-making. By ROBERT WELLS. Third Edition. Crown 8vo, cloth . **2/0**

"A large number of wrinkles for the ordinary cook, as well as the baker."—*Saturday Review.*

PASTRYCOOK & CONFECTIONER'S GUIDE.

For Hotels, Restaurants, and the Trade in general, adapted also for Family Use. By R. WELLS, Author of "The Bread and Biscuit Baker." Crown 8vo, cloth **2/0**

"We cannot speak too highly of this really excellent work. In these days of keen competition our readers cannot do better than purchase this book."—*Bakers' Times.*

ORNAMENTAL CONFECTIONERY.

A Guide for Bakers, Confectioners and Pastrycooks; including a variety of Modern Recipes, and Remarks on Decorative and Coloured Work. With 129 Original Designs. By ROBERT WELLS. Second Edition. Crown 8vo . **5/0**

"A valuable work, practical, and should be in the hands of every baker and confectioner. The illustrative designs are alone worth treble the amount charged for the whole work."—*Bakers' Times.*

THE MODERN FLOUR CONFECTIONER, WHOLESALE AND RETAIL.

Containing a large Collection of Recipes or Cheap Cakes, Biscuits, &c. With remarks on the Ingredients Used in their Manufacture. By ROBERT WELLS, Author of "The Bread and Biscuit Baker," &c. Crown 8vo, cloth . **2/0**

"The work is of a decidedly practical character, and in every recipe regard is had to economical working."—*North British Daily Mail.*

RUBBER HAND STAMPS

And the Manipulation of Rubber. A Practical Treatise on the Manufacture of Indiarubber Hand Stamps, Small Articles of Indiarubber, The Hektograph, Special Inks, Cements, and Allied Subjects. By T. O'CONOR SLOANE, A.M., Ph.D. With numerous Illustrations. Square 8vo, cloth . . . **5/0**

Digitized by Google

HANDYBOOKS FOR HANDICRAFTS.

BY PAUL N. HASLUCK.

Editor of "Work" (New Series), Author of "Lathe Work," "Milling Machines,' &c.
Crown 8vo, 144 pp., price 1s. each.

These HANDYBOOKS *have been written to supply information for* WORKMEN, STUDENTS, *and* AMATEURS *in the several Handicrafts, on the actual* PRACTICE *of the* WORKSHOP, *and are intended to convey in plain language* TECHNICAL KNOWLEDGE *of the several* CRAFTS. *In describing the processes employed, and the manipulation of material, workshop terms are used; workshop practice is fully explained; and the text is freely illustrated with drawings of modern tools, appliances, and processes.*

THE METAL TURNER'S HANDYBOOK.

A Practical Manual for Workers at the Foot-Lathe. With over 100 Illustrations. 1/0

"The book will be of service alike to the amateur and the artisan turner. It displays thorough knowledge of the subject."—*Scotsman.*

THE WOOD TURNER'S HANDYBOOK.

A Practical Manual for Workers at the Lathe. With over 100 Illustrations. 1/0

"We recommend the book to young turners and amateurs. A multitude of workmen have hitherto sought in vain for a manual of this special industry."—*Mechanical World.*

THE WATCH JOBBER'S HANDYBOOK.

A Practical Manual on Cleaning, Repairing, and Adjusting. With upwards of 100 Illustrations 1/0

"We strongly advise all young persons connected with the watch trade to acquire and study this inexpensive work."—*Clerkenwell Chronicle.*

THE PATTERN MAKER'S HANDYBOOK.

A Practical Manual on the Construction of Patterns for Founders. With upwards of 100 Illustrations 1/0

"A most valuable, if not indispensable manual for the pattern maker."—*Knowledge.*

THE MECHANIC'S WORKSHOP HANDYBOOK.

A Practical Manual on Mechanical Manipulation, embracing Information on various Handicraft Processes. With Useful Notes and Miscellaneous Memoranda. Comprising about 200 Subjects 1/0

"A very clever and useful book, which should be found in every workshop; and it should certainly find a place in all technical schools."—*Saturday Review.*

THE MODEL ENGINEER'S HANDYBOOK.

A Practical Manual on the Construction of Model Steam Engines. With upwards of 100 Illustrations. 1/0

"Mr. Hasluck has produced a very good little book."—*Builder.*

THE CLOCK JOBBER'S HANDYBOOK.

A Practical Manual on Cleaning, Repairing, and Adjusting. With upwards o 100 Illustrations 1/0

"It is of inestimable service to those commencing the trade."—*Coventry Standard.*

THE CABINET MAKER'S HANDYBOOK.

A Practical Manual on the Tools, Materials, Appliances, and Processes employed in Cabinet Work. With upwards of 100 Illustrations . . 1/0

"Mr. Hasluck's thorough-going little Handybook is amongst the most practical guides we have seen for beginners in cabinet-work."—*Saturday Review.*

THE WOODWORKER'S HANDYBOOK OF MANUAL INSTRUCTION.

Embracing Information on the Tools, Materials, Appliances and Processes Employed in Woodworking. With 104 Illustrations. 1/0

OPINIONS OF THE PRESS.

"Written by a man who knows, not only how work ought to be done, but how to do it, and how to convey his knowledge to others."—*Engineering.*

"Mr. Hasluck writes admirably, and gives complete instructions."—*Engineer.*

"Mr. Hasluck combines the experience of a practical teacher with the manipulative skill and scientific knowledge of processes of the trained mechanician, and the manuals are marvels of what can be produced at a popular price."—*Schoolmaster.*

"Helpful to workmen of all ages and degrees of experience."—*Daily Chronicle.*

"Practical, sensible, and remarkably cheap."—*Journal of Education.*

"Concise, clear, and practical."—*Saturday Review.*

Digitized by Google

COMMERCE, COUNTING-HOUSE WORK, TABLES, &c.

LESSONS IN COMMERCE.

By Professor R. GAMBARO, of the Royal High Commercial School at Genoa. Edited and Revised by JAMES GAULT, Professor of Commerce and Commercial Law in King's College, London. Second Edition, Revised. Crown 8vo . **3/6**

"The publishers of this work have rendered considerable service to the cause of commercial education by the opportune production of this volume. . . . The work is peculiarly acceptable to English readers and an admirable addition to existing class books. In a phrase, we think the work attains its object in furnishing a brief account of those laws and customs of British trade with which the commercial man interested therein should be familiar."—*Chamber of Commerce Journal.*

"An invaluable guide in the hands of those who are preparing for a commercial career, and, in fact, the information it contains on matters of business should be impressed on every one."—*Counting House.*

THE FOREIGN COMMERCIAL CORRESPONDENT.

Being Aids to Commercial Correspondence in Five Languages—English, French, German, Italian, and Spanish. By CONRAD E. BAKER. Second Edition. Crown 8vo, cloth **3/6**

"Whoever wishes to correspond in all the languages mentioned by Mr. Baker cannot do better than study this work, the materials of which are excellent and conveniently arranged. They consist not of entire specimen letters, but—what are far more useful—short passages, sentences, or phrases expressing the same general idea in various forms."—*Athenæum.*

"A careful examination has convinced us that it is unusually complete, well arranged and reliable. The book is a thoroughly good one."—*Schoolmaster.*

FACTORY ACCOUNTS: their PRINCIPLES & PRACTICE.

A Handbook for Accountants and Manufacturers, with Appendices on the Nomenclature of Machine Details; the Income Tax Acts; the Rating of Factories; Fire and Boiler Insurance; the Factory and Workshop Acts, &c., including also a Glossary of Terms and a large number of Specimen Rulings. By EMILE GARCKE and J. M. FELLS. Fourth Edition, Revised and Enlarged. Demy 8vo, 250 pp., strongly bound **6/0**

"A very interesting description of the requirements of Factory Accounts. . . . The principle of assimilating the Factory Accounts to the general commercial books is one which we thoroughly agree with."—*Accountants' Journal.*

"Characterised by extreme thoroughness. There are few owners of factories who would not derive great benefit from the perusal of this most admirable work."—*Local Government Chronicle.*

MODERN METROLOGY.

A Manual of the Metrical Units and Systems of the present Century. With an Appendix containing a proposed English System. By LOWIS D. A. JACKSON, A. M. Inst. C. E., Author of "Aid to Survey Practice," &c. Large crown 8vo, cloth **12/6**

"We recommend the work to all interested in the practical reform of our weights and measures."—*Nature.*

A SERIES OF METRIC TABLES.

In which the British Standard Measures and Weights are compared with those of the Metric System at present in Use on the Continent. By C. H. DOWLING, C.E. 8vo, strongly bound **10/6**

"Mr. Dowling's Tables are well put together as a ready reckoner for the conversion of one system into the other."—*Athenæum.*

THE IRON AND METAL TRADES' COMPANION.

For Expeditiously Ascertaining the Value of any Goods bought or sold by Weight, from 1s. per cwt. to 112s. per cwt., and from one farthing per pound to one shilling per pound. By THOMAS DOWNIE. 396 pp., leather . . **9/0**

"A most useful set of tables, nothing like them before existed."—*Building News.*

"Although specially adapted to the Iron and metal trades, the tables will be found useful n every other business in which merchandise is bought and sold by weight."—*Railway News.*

Digitized by Google

NUMBER, WEIGHT, AND FRACTIONAL CALCULATOR.

Containing upwards of 250,000 Separate Calculations, showing at a Glance the Value at 422 Different Rates, ranging from $\frac{1}{192}$th of a Penny to 20s. each, or per cwt., and £20 per ton, of any number of articles consecutively, from 1 to 470. Any number of cwts., qrs., and lbs., from 1 cwt. to 470 cwts. Any number of tons, cwts., qrs., and lbs., from 1 to 1,000 tons. By WILLIAM CHADWICK, Public Accountant. Third Edition, Revised. 8vo, strongly bound . **18/0**

"It is as easy of reference for any answer or any number of answers as a dictionary. For making up accounts or estimates the book must prove invaluable to all who have any considerable quantity of calculations involving price and measure in any combination to do."—*Engineer.*

"The most perfect work of the kind yet prepared."—*Glasgow Herald.*

THE WEIGHT CALCULATOR.

Being a Series of Tables upon a New and Comprehensive Plan, exhibiting at one Reference the exact Value of any Weight from 1 lb. to 15 tons, at 300 Progressive Rates, from 1*d.* to 168*s.* per cwt., and containing 186,000 Direct Answers, which, with their Combinations, consisting of a single addition (mostly to be performed at sight), will afford an aggregate of 10,266,000 Answers; the whole being calculated and designed to ensure correctness and promote despatch. By HENRY HARBEN, Accountant. Fifth Edition, carefully Corrected. Royal 8vo, strongly half-bound . . . . . **£1 5s.**

"A practical and useful work of reference for men of business generally."—*Ironmonger.*

"Of priceless value to business men. It is a necessary book in all mercantile offices."—*Sheffield Independent.*

THE DISCOUNT GUIDE.

Comprising several Series of Tables for the Use of Merchants, Manufacturers, Ironmongers, and Others, by which may be ascertained the Exact Profit arising from any mode of using Discounts, either in the Purchase or Sale of Goods, and the method of either Altering a Rate of Discount, or Advancing a Price, so as to produce, by one operation, a sum that will realise any required Profit after allowing one or more Discounts: to which are added Tables of Profit or Advance from $1\frac{1}{2}$ to 90 per cent., Tables of Discount from $1\frac{1}{2}$ to $98\frac{3}{4}$ per cent., and Tables of Commission, &c., from $\frac{1}{8}$ to 10 per cent. By HENRY HARBEN, Accountant. New Edition, Corrected. Demy 8vo, half-bound . **£1 5s.**

"A book such as this can only be appreciated by business men, to whom the saving of time means saving of money. The work must prove of great value to merchants, manufacturers, and general traders."—*British Trade Journal.*

TABLES OF WAGES.

At 54, 52, 50 and 48 Hours per Week. Showing the Amounts of Wages from One quarter of an hour to Sixty-four hours, in each case at Rates of Wages advancing by One Shilling from 4*s.* to 55*s.* per week. By THOS. GARBUTT, Accountant. Square crown 8vo, half-bound **6/0**

IRON-PLATE WEIGHT TABLES.

For Iron Shipbuilders, Engineers, and Iron Merchants. Containing the Calculated Weights of upwards of 150,000 different sizes of Iron Plates from 1 foot by 6 in. by $\frac{1}{2}$ in. to 10 feet by 5 feet by 1 in. Worked out on the Basis of 40 lbs. to the square foot of Iron of 1 inch in thickness. By H. BURLINSON and W. H. SIMPSON. 4to, half-bound . . . . . **£1 5s.**

MATHEMATICAL TABLES (ACTUARIAL).

Comprising Commutation and Conversion Tables, Logarithms, Cologarithms, Antilogarithms and Reciprocals. By J. W. GORDON. Royal 8vo, mounted on canvas, in cloth case. [*Just Published.* **5/0**

Digitized by Google

AGRICULTURE, FARMING, GARDENING, &c.

THE COMPLETE GRAZIER AND FARMER'S AND CATTLE BREEDER'S ASSISTANT.

A Compendium of Husbandry. Originally Written by WILLIAM YOUATT, Fourteenth Edition, entirely Re-written, considerably Enlarged, and brought up to Present Requirements, by WILLIAM FREAM, LL.D., Assistant Commissioner, Royal Commission on Agriculture, 1893, Author of "The Elements of Agriculture," &c. Royal 8vo, 1,100 pp., with over 450 Illustrations, handsomely bound. [*Just Published.* **£1 11s. 6d.**

SUMMARY OF CONTENTS.

BOOK I. ON THE VARIETIES, BREEDING, REARING, FATTENING AND MANAGEMENT OF CATTLE.
BOOK II. ON THE ECONOMY AND MANAGEMENT OF THE DAIRY.
BOOK III. ON THE BREEDING, REARING, AND MANAGEMENT OF HORSES.
BOOK IV. ON THE BREEDING, REARING, AND FATTENING OF SHEEP.
BOOK V. ON THE BREEDING, REARING, AND FATTENING OF SWINE.
BOOK VI. ON THE DISEASES OF LIVE STOCK.
BOOK VII. ON THE BREEDING, REARING, AND MANAGEMENT OF POULTRY.
BOOK VIII. ON FARM OFFICES AND IMPLEMENTS OF HUSBANDRY.
BOOK IX. ON THE CULTURE AND MANAGEMENT OF GRASS LANDS.
BOOK X. ON THE CULTIVATION AND APPLICATION OF GRASSES, PULSE AND ROOTS.
BOOK XI. ON MANURES AND THEIR APPLICATION TO GRASS LAND AND CROPS.
BOOK XII. MONTHLY CALENDARS OF FARMWORK.

*** OPINIONS OF THE PRESS ON THE NEW EDITION.

"Dr. Fream is to be congratulated on the successful attempt he has made to give us a work which will at once become the standard classic of the farm practice of the country. We believe that it will be found that it has no compeer among the many works at present in existence. . . . The illustrations are admirable, while the frontispiece, which represents the well-known bull, New Year's Gift, owned by the Queen, is a work of art."—*The Times.*

"The book must be recognised as occupying the proud position of the most exhaustive work of reference in the English language on the subject with which it deals."—*Athenæum.*

"The most comprehensive guide to modern farm practice that exists in the English language to-day. . . . . The book is one that ought to be on every farm and in the library of every land owner."—*Mark Lane Express.*

"In point of exhaustiveness and accuracy the work will certainly hold a pre-eminent and unique position among books dealing with scientific agricultural practice. It is, in fact, an agricultural library of itself."—*North British Agriculturist.*

"A compendium of authoritative and well-ordered knowledge on every conceivable branch of the work of the live stock farmer; probably without an equal in this or any other country."—*Yorkshire Post.*

FARM LIVE STOCK OF GREAT BRITAIN.

By ROBERT WALLACE, F.L.S., F.R.S.E., &c., Professor of Agriculture and Rural Economy in the University of Edinburgh. Third Edition, thoroughly Revised and considerably Enlarged. With over 120 Phototypes of Prize Stock. Demy 8vo, 384 pp., with 79 Plates and Maps, cloth. . . **12/6**

"A really complete work on the history, breeds, and management of the farm stock of Great Britain, and one which is likely to find its way to the shelves of every country gentleman's library. —*The Times.*

"The latest edition of 'Farm Live Stock of Great Britain' is a production to be proud of, and its issue not the least of the services which its author has rendered to agricultural science."—*Scottish Farmer.*

"The book is very attractive, . . . and we can scarcely imagine the existence of a farmer who would not like to have a copy of this beautiful and useful work."—*Mark Lane Express.*

NOTE-BOOK OF AGRICULTURAL FACTS & FIGURES FOR FARMERS AND FARM STUDENTS.

By PRIMROSE MCCONNELL, B.Sc., Fellow of the Highland and Agricultural Society, Author of "Elements of Farming." Sixth Edition, Re-written, Revised, and greatly Enlarged. Fcap. 8vo, 480 pp., leather. [*Just Published.* **6/0**

SUMMARY OF CONTENTS: SURVEYING AND LEVELLING.—WEIGHTS AND MEASURES.—MACHINERY AND BUILDINGS.—LABOUR.—OPERATIONS.—DRAINING.—EMBANKING.—GEOLOGICAL MEMORANDA.—SOILS.—MANURES.—CROPPING.—CROPS.—ROTATIONS.—WEEDS.—FEEDING.—DAIRYING.—LIVE STOCK.—HORSES.—CATTLE.—SHEEP.—PIGS.—POULTRY.—FORESTRY.—HORTICULTURE.—MISCELLANEOUS.

"No farmer, and certainly no agricultural student, ought to be without this *multum-in-parvo* manual of all subjects connected with the farm."—*North British Agriculturist.*

"This little pocket-book contains a large amount of useful information upon all kinds of agricultural subjects. Something of the kind has long been wanted."—*Mark Lane Express.*

"The amount of information it contains is most surprising; the arrangement of the matter is so methodical—although so compressed—as to be intelligible to everyone who takes a glance through its pages. They teem with information."—*Farm and Home.*

Digitized by Google

BRITISH DAIRYING.

A Handy Volume on the Work of the Dairy-Farm. For the Use of Technical Instruction Classes, Students in Agricultural Colleges and the Working Dairy-Farmer. By Prof. J. P. SHELDON. With Illustrations. Second Edition, Revised. Crown 8vo, cloth. [*Just Published.* **2/6**

"Confidently recommended as a useful text-book on dairy farming."—*Agricultural Gazette.*
"Probably the best half-crown manual on dairy work that has yet been produced."—*North British Agriculturist.*
"It is the soundest little work we have yet seen on the subject."—*The Times.*

MILK, CHEESE, AND BUTTER.

A Practical Handbook on their Properties and the Processes of their Production. Including a Chapter on Cream and the Methods of its Separation from Milk. By JOHN OLIVER, late Principal of the Western Dairy Institute, Berkeley. With Coloured Plates and 200 Illustrations. Crown 8vo, cloth. **7/6**

"An exhaustive and masterly production. It may be cordially recommended to all students and practitioners of dairy science."—*North British Agriculturist.*
"We recommend this very comprehensive and carefully-written book to dairy-farmers and students of dairying. It is a distinct acquisition to the library of the agriculturist."—*Agricultural Gazette.*

SYSTEMATIC SMALL FARMING.

Or, The Lessons of My Farm. Being an Introduction to Modern Farm Practice for Small Farmers. By R. SCOTT BURN, Author of "Outlines of Modern Farming," &c. Crown 8vo, cloth. **6/0**

"This is the completest book of its class we have seen, and one which every amateur farmer will read with pleasure, and accept as a guide."—*Field.*

OUTLINES OF MODERN FARMING.

By R. SCOTT BURN. Soils, Manures, and Crops—Farming and Farming Economy—Cattle, Sheep, and Horses—Management of Dairy, Pigs, and Poultry—Utilisation of Town-Sewage, Irrigation, &c. Sixth Edition. In One Vol., 1,250 pp., half-bound, profusely Illustrated **12/0**

FARM ENGINEERING, The COMPLETE TEXT-BOOK of.

Comprising Draining and Embanking; Irrigation and Water Supply; Farm Roads, Fences and Gates; Farm Buildings; Barn Implements and Machines; Field Implements and Machines; Agricultural Surveying, &c. By Professor JOHN SCOTT. In One Vol., 1,150 pp., half-bound, with over 600 Illustrations. **12/0**

"Written with great care, as well as with knowledge and ability. The author has done his work well; we have found him a very trustworthy guide wherever we have tested his statements. The volume will be of great value to agricultural students."—*Mark Lane Express.*

THE FIELDS OF GREAT BRITAIN.

A Text-Book of Agriculture. Adapted to the Syllabus of the Science and Art Department. For Elementary and Advanced Students. By HUGH CLEMENTS (Board of Trade). Second Edition, Revised, with Additions. 18mo, cloth **2/6**

"It is a long time since we have seen a book which has pleased us more, or which contains such a vast and useful fund of knowledge."—*Educational Times.*

TABLES and MEMORANDA for FARMERS, GRAZIERS, AGRICULTURAL STUDENTS, SURVEYORS, LAND AGENTS, AUCTIONEERS, &c.

With a New System of Farm Book-keeping. By SIDNEY FRANCIS. Fourth Edition. 272 pp., waistcoat-pocket size, limp leather **1/6**

"Weighing less than 1 oz., and occupying no more space than a match-box, it contains a mass of facts and calculations which has never before, in such handy form, been obtainable. Every operation on the farm is dealt with. The work may be taken as thoroughly accurate, the whole of the tables having been revised by Dr. Fream. We cordially recommend it."—*Bell's Weekly Messenger.*

THE ROTHAMSTED EXPERIMENTS AND THEIR PRACTICAL LESSONS FOR FARMERS.

Part I. STOCK. Part II. CROPS. By C. J. R. TIPPER. Crown 8vo, cloth. [*Just Published.* **3/6**

"We have no doubt that the book will be welcomed by a large class of farmers and others interested in agriculture."—*Standard.*

Digitized by Google

FERTILISERS AND FEEDING STUFFS.

A Handbook for the Practical Farmer. By BERNARD DYER, D.Sc. (Lond.) With the Text of the Fertilisers and Feeding Stuffs Act of 1893, &c. Third Edition, Revised. Crown 8vo, cloth. [*Just Published.* **1/0**

"This little book is precisely what it professes to be—'A Handbook for the Practical Farmer.' Dr. Dyer has done farmers good service in placing at their disposal so much useful information in so intelligible a form."—*The Times.*

BEES FOR PLEASURE AND PROFIT.

A Guide to the Manipulation of Bees, the Production of Honey, and the General Management of the Apiary. By G. GORDON SAMSON. With numerous Illustrations. Crown 8vo, cloth **1/0**

BOOK-KEEPING for FARMERS and ESTATE OWNERS.

A Practical Treatise, presenting, in Three Plans, a System adapted for all Classes of Farms. By JOHNSON M. WOODMAN, Chartered Accountant. Second Edition, Revised. Crown 8vo, cloth boards, **3/6**; or, cloth limp, **2/6**

"The volume is a capital study of a most important subject."—*Agricultural Gazette.*

WOODMAN'S YEARLY FARM ACCOUNT BOOK.

Giving Weekly Labour Account and Diary, and showing the Income and Expenditure under each Department of Crops, Live Stock, Dairy, &c., &c. With Valuation, Profit and Loss Account, and Balance Sheet at the End of the Year. By JOHNSON M. WOODMAN, Chartered Accountant. Second Edition. Folio, half-bound . . . . . *Net* **7/6**

"Contains every requisite form for keeping farm accounts readily and accurately."—*Agriculture.*

THE FORCING GARDEN.

Or, How to Grow Early Fruits, Flowers and Vegetables. With Plans and Estimates for Building Glasshouses, Pits and Frames. With Illustrations. By SAMUEL WOOD. Crown 8vo, cloth **3/6**

"A good book, containing a great deal of valuable teaching. —*Gardeners' Magazine.*

A PLAIN GUIDE TO GOOD GARDENING.

Or, How to Grow Vegetables, Fruits, and Flowers. By S. WOOD. Fourth Edition, with considerable Additions, and numerous Illustrations. Crown 8vo, cloth **3/6**

"A very good book, and one to be highly recommended as a practical guide. The practical directions are excellent."—*Athenæum.*

MULTUM-IN-PARVO GARDENING.

Or, How to Make One Acre of Land produce £620 a year, by the Cultivation of Fruits and Vegetables; also, How to Grow Flowers in Three Glass Houses, so as to realise £176 per annum clear Profit. By SAMUEL WOOD, Author of "Good Gardening," &c. Sixth Edition, Crown 8vo, sewed . . . **1/0**

"We are bound to recommend it as not only suited to the case of the amateur and gentleman's gardener, but to the market grower."—*Gardeners' Magazine.*

THE LADIES' MULTUM-IN-PARVO FLOWER GARDEN.

And Amateur's Complete Guide. By S. WOOD. Crown 8vo, cloth . **3/6**

"Full of shrewd hints and useful instructions, based on a lifetime of experience."—*Scotsman.*

POTATOES: HOW TO GROW AND SHOW THEM.

A Practical Guide to the Cultivation and General Treatment of the Potato. By J. PINK. Crown 8vo **2/0**

MARKET AND KITCHEN GARDENING.

By C. W. SHAW, late Editor of *Gardening Illustrated.* Cloth . . **3/6**

"The most valuable compendium of kitchen and market-garden work published."—*Farmer.*

Digitized by Google

AUCTIONEERING, VALUING, LAND SURVEYING, ESTATE AGENCY, &c.

INWOOD'S TABLES FOR PURCHASING ESTATES AND FOR THE VALUATION OF PROPERTIES,

Including Advowsons, Assurance Policies, Copyholds, Deferred Annuities, Freeholds, Ground Rents, Immediate Annuities, Leaseholds, Life Interests, Mortgages, Perpetuities, Renewals of Leases, Reversions, Sinking Funds, &c., &c. 25th Edition, Revised and Extended by WILLIAM SCHOOLING, F.R.A.S., with Logarithms of Natural Numbers and THOMAN'S Logarithmic Interest and Annuity Tables. 336 pp., Demy 8vo, cloth.

[*Just published. Net* **8/0**

"Those interested in the purchase and sale of estates, and in the adjustment of compensation cases, as well as in transactions in annuities, life insurances, &c., will find the present edition of eminent service."—*Engineering.*

"This valuable book has been considerably enlarged and improved by the labours of Mr. Schooling, and is now very complete indeed."—*Economist.*

"Altogether this edition will prove of extreme value to many classes of professional men in saving them many long and tedious calculations."—*Investors' Review.*

THE APPRAISER, AUCTIONEER, BROKER, HOUSE AND ESTATE AGENT AND VALUER'S POCKET ASSISTANT.

For the Valuation for Purchase, Sale, or Renewal of Leases, Annuities, and Reversions, and of Property generally; with Prices for Inventories, &c. By JOHN WHEELER, Valuer, &c. Sixth Edition, Re-written and greatly Extended by C. NORRIS, Surveyor, Valuer, &c. Royal 32mo, cloth . . . **5/0**

"A neat and concise book of reference, containing an admirable and clearly-arranged list of prices for inventories, and a very practical guide to determine the value of furniture, &c."—*Standard.*

"Contains a large quantity of varied and useful information as to the valuation for purchase, sale, or renewal of leases, annuities and reversions, and of property generally, with prices for inventories, and a guide to determine the value of interior fittings and other effects."—*Builder.*

AUCTIONEERS: THEIR DUTIES AND LIABILITIES.

A Manual of Instruction and Counsel for the Young Auctioneer. By ROBERT SQUIBBS, Auctioneer. Second Edition, Revised and partly Re-written. Demy 8vo, cloth **12/6**

"The standard text-book on the topics of which it treats."—*Athenæum.*

"The work is one of general excellent character, and gives much information in a compendious and satisfactory form."—*Builder.*

"May be recommended as giving a great deal of information on the law relating to auctioneers, in a very readable form."—*Law Journal.*

"Auctioneers may be congratulated on having so pleasing a writer to minister to their special needs."—*Solicitors' Journal.*

THE AGRICULTURAL VALUER'S ASSISTANT.

A Practical Handbook on the Valuation of Landed Estates; including Rules and Data for Measuring and Estimating the Contents, Weights and Values of Agricultural Produce and Timber, and the Values of Feeding Stuffs, Manures, and Labour; with Forms of Tenant-Right Valuations, Lists of Local Agricultural Customs, Scales of Compensation under the Agricultural Holdings Act, &c., &c. By TOM BRIGHT, Agricultural Surveyor. Second Edition, Enlarged. Crown 8vo, cloth **5/0**

"Full of tables and examples in connection with the valuation of tenant-right, estates, labour, contents and weights of timber, and farm produce of all kinds."—*Agricultural Gazette.*

"An eminently practical handbook, full of practical tables and data of undoubted interest and value to surveyors and auctioneers in preparing valuations of all kinds."—*Farmer.*

POLE PLANTATIONS AND UNDERWOODS.

A Practical Handbook on Estimating the Cost of Forming, Renovating, Improving, and Grubbing Plantations and Underwoods, their Valuation for Purposes of Transfer, Rental, Sale or Assessment. By TOM BRIGHT. Crown 8vo, cloth **3/6**

"To valuers, foresters and agents it will be a welcome aid."—*North British Agriculturist.*

"Well calculated to assist the valuer in the discharge of his duties, and of undoubted interest and use both to surveyors and auctioneers in preparing valuations of all kinds."—*Kent Herald.*

Digitized by Google

AGRICULTURAL SURVEYOR AND ESTATE AGENT'S HANDBOOK.

Of Practical Rules, Formulæ, Tables, and Data. A Comprehensive Manual for the Use of Surveyors, Agents, Landowners, and others interested in the Equipment, the Management, or the Valuation of Landed Estates. By TOM BRIGHT, Agricultural Surveyor and Valuer, Author of "The Agricultural Valuer's Assistant," &c. With Illustrations. Fcap 8vo, Leather.

[*Just Published. Net* **7/6**

"An exceedingly useful book, the contents of which are admirably chosen. The classes for whom the work is intended will find it convenient to have this comprehensive handbook accessible for reference."—*Live Stock Journal.*

"It is a singularly compact and well informed compendium of the facts and figures likely to be required in estate work, and is certain to prove of much service to those to whom it is addressed."—*Scotsman.*

THE LAND VALUER'S BEST ASSISTANT.

Being Tables on a very much Improved Plan, for Calculating the Value of Estates. With Tables for reducing Scotch, Irish, and Provincial Customary Acres to Statute Measure, &c. By R. HUDSON, C.E. New Edition. Royal 32mo, leather, elastic band **4/0**

"Of incalculable value to the country gentleman and professional man."—*Farmers' Journal.*

THE LAND IMPROVER'S POCKET-BOOK.

Comprising Formulæ, Tables, and Memoranda required in any Computation relating to the Permanent Improvement of Landed Property. By JOHN EWART, Surveyor. Second Edition, Revised. Royal 32mo, oblong, leather . **4/0**

"A compendious and handy little volume."—*Spectator.*

THE LAND VALUER'S COMPLETE POCKET-BOOK.

Being the above Two Works bound together. Leather **7/6**

HANDBOOK OF HOUSE PROPERTY.

A Popular and Practical Guide to the Purchase, Mortgage, Tenancy, and Compulsory Sale of Houses and Land, including Dilapidations and Fixtures: with Examples of all kinds of Valuations, Information on Building and on the right use of Decorative Art. By E. L. TARBUCK, Architect and Surveyor. Sixth Edition. 12mo, cloth **5/0**

"The advice is thoroughly practical."—*Law Journal.*

"For all who have dealings with house property, this is an indispensable guide."—*Decoration.*

"Carefully brought up to date, and much improved by the addition of a division on Fine Art. . . . A well-written and thoughtful work."—*Land Agent's Record.*

LAW AND MISCELLANEOUS.

MODERN JOURNALISM.

A Handbook of Instruction and Counsel for the Young Journalist. By JOHN B. MACKIE, Fellow of the Institute of Journalists. Crown 8vo, cloth . **2/0**

"This invaluable guide to journalism is a work which all aspirants to a journalistic career wil read with advantage."—*Journalist.*

HANDBOOK FOR SOLICITORS AND ENGINEERS

Engaged in Promoting Private Acts of Parliament and Provisional Orders for the Authorisation of Railways, Tramways, Gas and Water Works, &c. By L. LIVINGSTONE MACASSEY, of the Middle Temple, Barrister-at-Law, M. Inst. C.E. 8vo, cloth . . . . . **£1 5s.**

PATENTS for INVENTIONS, HOW to PROCURE THEM.

Compiled for the Use of Inventors, Patentees and others. By G. G. M. HARDINGHAM, Assoc. Mem. Inst. C.E., &c. Demy 8vo, cloth . . **1/6**

CONCILIATION & ARBITRATION in LABOUR DISPUTES.

A Historical Sketch and Brief Statement of the Present Position of the Question at Home and Abroad. By J. S. JEANS, Author of "England's Supremacy," &c. Crown 8vo, 200 pp., cloth **2/6**

Digitized by Google

EVERY MAN'S OWN LAWYER.

A Handy-Book of the Principles of Law and Equity. With a Concise Dictionary of Legal Terms. By A BARRISTER. Thirty-seventh Edition, carefully Revised, and including New Acts of Parliament of 1899. Comprising the *London Government Act, 1899; Sale of Food and Drugs Act, 1899; Infectious Diseases Notification Act, 1899; Small Dwellings Acquisition Act, 1899; Commons Act, 1899;* besides the *Benefices Act, 1898; Marriage Act, 1898; Inebriates Acts, 1898* and *1899; Criminal Evidence Act, 1898; Vaccination Act, 1898, &c. Judicial Decisions during the year have also been duly noted.* Crown 8vo, 750 pp., strongly bound in cloth. [*Just Published.* **6/8**

*** *This Standard Work of Reference forms* A COMPLETE EPITOME OF THE LAWS OF ENGLAND, *comprising (amongst other matter):*

THE RIGHTS AND WRONGS OF INDIVIDUALS—LANDLORD AND TENANT—VENDORS AND PURCHASERS—LEASES AND MORTGAGES—PRINCIPAL AND AGENT—PARTNERSHIP AND COMPANIES—MASTERS, SERVANTS AND WORKMEN—CONTRACTS AND AGREEMENTS—BORROWERS, LENDERS AND SURETIES—SALE AND PURCHASE OF GOODS—CHEQUES, BILLS AND NOTES—BILLS OF SALE—BANKRUPTCY—RAILWAY AND SHIPPING LAW—LIFE, FIRE, AND MARINE INSURANCE—ACCIDENT AND FIDELITY INSURANCE—CRIMINAL LAW—PARLIAMENTARY ELECTIONS—COUNTY COUNCILS—DISTRICT COUNCILS—PARISH COUNCILS—MUNICIPAL CORPORATIONS—LIBEL AND SLANDER—PUBLIC HEALTH AND NUISANCES—COPYRIGHT, PATENTS, TRADE MARKS—HUSBAND AND WIFE—DIVORCE—INFANCY—CUSTODY OF CHILDREN—TRUSTEES AND EXECUTORS—CLERGY, CHURCHWARDENS, &C.—GAME LAWS AND SPORTING—INNKEEPERS—HORSES AND DOGS—TAXES AND DEATH DUTIES—FORMS OF AGREEMENTS, WILLS, CODICILS, NOTICES, &C.

☛ *The object of this work is to enable those who consult it to help themselves to the law; and thereby to dispense, as far as possible, with professional assistance and advice. There are many wrongs and grievances which persons submit to from time to time through not knowing how or where to apply for redress; and many persons have as great a dread of a lawyer's office as of a lion's den. With this book at hand it is believed that many a* SIX-AND-EIGHTPENCE *may be saved; many a wrong redressed; many a right reclaimed; many a law suit avoided; and many an evil abated. The work has established itself as the standard legal adviser of all classes, and has also made a reputation for itself as a useful book of reference for lawyers residing at a distance from law libraries, who are glad to have at hand a work embodying recent decisions and enactments.*

OPINIONS OF THE PRESS.

"It is a complete code of English Law written in plain language, which all can understand. . . . Should be in the hands of every business man, and all who wish to abolish lawyers bills."—*Weekly Times.*

"A useful and concise epitome of the law, compiled with considerable care."—*Law Magazine.*

"A complete digest of the most useful facts which constitute English law."—*Globe.*

"This excellent handbook. . . . Admirably done, admirably arranged, and admirably cheap."—*Leeds Mercury.*

"A concise, cheap, and complete epitome of the English law. So plainly written that he who runs may read, and he who reads may understand."—*Figaro.*

"A dictionary of legal facts well put together. The book is a very useful one."—*Spectator.*

THE PAWNBROKER'S, FACTOR'S, AND MERCHANT'S GUIDE TO THE LAW OF LOANS AND PLEDGES.

With the Statutes and a Digest of Cases. By H. C. FOLKARD, Barrister-at-Law. Cloth **3/6**

LABOUR CONTRACTS.

A Popular Handbook on the Law of Contracts for Works and Services. By DAVID GIBBONS. Fourth Edition, with Appendix of Statutes by T. F. UTTLEY, Solicitor. Fcap. 8vo, cloth **3/6**

SUMMARY OF THE FACTORY AND WORKSHOP ACTS

(1878-1891). For the Use of Manufacturers and Managers. By EMILE GARCKE and J. M. FELLS. (Reprinted from "FACTORY ACCOUNTS.") Crown 8vo, sewed . . . . . **6D.**

BRADBURY, AGNEW, & CO. LD., PRINTERS, LONDON AND TONBRIDGE.

Digitized by Google

TABLES,

ETC.,

FOR THE USE OF

MATHEMATICIANS, SURVEYORS, ENGINEERS,

AND OTHER PRACTICAL COMPUTERS.

Royal 8vo, cloth, **21s.** *net.*

TABLES FOR THE FORMATION OF LOGARITHMS AND ANTI-LOGARITHMS TO TWENTY-FOUR OR ANY LESS NUMBER OF PLACES, with Explanatory Introduction and Historical Preface. By PETER GRAY.

Medium 8vo, with Marginal Index, **5s.** *net.*

TABLE OF LOGARITHMS AND ANTI-LOGARITHMS (Four Figures) 1 to 10,000. By MAJOR-GENERAL HANNYNGTON.

London: CROSBY LOCKWOOD & SON, 7, Stationers' Hall Court, E.C.

Digitized by Google

Super Royal 8vo, cloth, **21s.** *net.*

TABLE OF QUARTER-SQUARES OF ALL INTEGER NUMBERS UP TO 100,000, by which the product of Two Factors may be found by the aid of Addition and Subtraction alone. By S. L. LAUNDY.

Royal 4to, cloth, **5s.** *net.*

A TABLE OF PRODUCTS, BY THE FACTORS 1 TO 9, OF ALL NUMBERS FROM 1 TO 100,000, by the aid of which Multiplication may be performed by inspection; with an Introduction explanatory of its use, and also of the Method of obtaining the Products of Numbers exceeding the limits of the Table. By S. L. LAUNDY.

Royal 8vo, cloth, **£2. 2s.** *net.*

TABLES OF COMPOUND INTEREST, for each rate between $\frac{3}{4}$ and 10 per Cent. per Annum, proceeding by Intervals of One-Eighth, and from 1 Year to 100 Years.—I. Present Value of £1.—II. Present Value of £1 per Annum.—III. Amount of £1.—IV. Amount of £1 per annum. By LIEUT.-COL. W. H. OAKES, A.I.A.

Super Royal 8vo, cloth, **21s.** *net.*

TABLES OF THE RECIPROCALS OF NUMBERS, FROM 1 TO 100,000, with their Differences, by which the Reciprocals of Numbers may be obtained up to 10,000,000. By LIEUT.-COL. W. H. OAKES, A.I.A.

London: CROSBY LOCKWOOD & SON, 7, Stationers' Hall Court, E.C.

Digitized by Google

Imperial 8vo, cloth, **10s. 6d.** *net.*

TABLES FOR FINDING THE HALF-YEARLY RATE OF INTEREST, FROM 1¼ PER CENT. UPWARDS, realised on **Stock or Bonds,** bearing 1½, 1¾, 2, 2¼, 2½, 2¾, and 3 per Cent. Half-Yearly Interest, issued at any Premium and redeemable at Par in any number of Half-Years not exceeding 60. By LIEUT.-COL. W. H. OAKES, A.I.A.

Demy 8vo, cloth, **£1. 11s. 6d.** *net.*

LOANS PAYABLE BY DRAWINGS AND DEBENTURE INTEREST TABLES. By LIEUT.-COL. W. H. OAKES, A.I.A.

Royal 8vo, with Index complete. Half-calf, **£2. 2s.** *net.*

New Edition.

TWO TABLES OF LOGARITHMS TO NATURAL NUMBERS, and Natural Numbers to Logarithms, for all Numbers from 1 to 99,999, and all Logarithms from ·00001 to ·99999; arranged so that the Logarithm or Number required is at once obtained correctly to Five Places of Decimals, by means of a Marginal Index, and without Reference to Tables of Differences in any case. By E. ERSKINE SCOTT.

London: CROSBY LOCKWOOD & SON, 7, Stationers' Hall Court, E.C.

Digitized by Google

Royal 8vo. Price **10s.** *net.*

A SHORT TABLE OF LOGARITHMS AND ANTI-LOGARITHMS TO TEN PLACES,

in Two Parts, whereby the Logarithm of any Number to Ten Places of Decimals, and the Number corresponding to any Logarithm to Ten Places of Decimals, may be readily and correctly found, to which is added a Complete List of Constants, with Formulæ for their Application. By E. ERSKINE SCOTT.

Demy 8vo, 76 pp. Price **7s. 6d.** *net; with Marginal Thumb Index,* **12s. 6d.** *net.*

AN IMPROVED TABLE OF FIVE-FIGURE LOGARITHMS,

arranged with a view to securing the best possible combination of accuracy and speed in use, and with special regard to avoiding unnecessary fatigue to the eyes. By E. ERSKINE SCOTT.

Super Royal 8vo, 602 pp., cloth, **30s.** *net.*

LOGARITHMIC TABLES TO SEVEN PLACES OF DECIMALS,

containing Logarithmic Sines and Tangents to every Second of the Circle, with Arguments in Space and Time. *Revised Edition.* With additional Preface and Examples, by Major-General Hannyngton, F.I.A., F.S.S. By ROBERT SHORTREDE, F.R.A.S., &c.

London: CROSBY LOCKWOOD & SON, 7, Stationers' Hall Court, E.C.

Digitized by Google

WEALE'S SERIES

OF

SCIENTIFIC AND TECHNICAL WORKS.

"It is not too much to say that no books have ever proved more popular with or more useful to young engineers and others than the excellent treatises comprised in WEALE'S SERIES."—**Engineer.**

A New Classified List.

	PAGE		PAGE
CIVIL ENGINEERING AND SURVEYING	2	ARCHITECTURE AND BUILDING	6
MINING AND METALLURGY	3	INDUSTRIAL AND USEFUL ARTS	9
MECHANICAL ENGINEERING	4	AGRICULTURE, GARDENING, ETC.	10
NAVIGATION, SHIPBUILDING, ETC.	5	MATHEMATICS, ARITHMETIC, ETC.	12

BOOKS OF REFERENCE AND MISCELLANEOUS VOLUMES . . 14

CROSBY LOCKWOOD AND SON,

7, STATIONERS' HALL COURT, LONDON, E.C.

1900.

Digitized by Google

CIVIL ENGINEERING & SURVEYING.

Civil Engineering.
By HENRY LAW, M.Inst.C.E. Including a Treatise on HYDRAULIC ENGINEERING by G. R. BURNELL, M.I.C.E. Seventh Edition, revised, with LARGE ADDITIONS by D. K. CLARK, M.I.C.E. 6/6

Pioneer Engineering:
A Treatise on the Engineering Operations connected with the Settlement of Waste Lands in New Countries. By EDWARD DOBSON, M.INST.C.E. With numerous Plates. Second Edition 4/6

Iron Bridges of Moderate Span:
Their Construction and Erection. By HAMILTON W. PENDRED. With 40 Illustrations 2/0

Iron and Steel Bridges and Viaducts.
A Practical Treatise upon their Construction for the use of Engineers, Draughtsmen, and Students. By FRANCIS CAMPIN, C.E. With numerous Illustrations 3/6

Constructional Iron and Steel Work,
As applied to Public, Private, and Domestic Buildings. By FRANCIS CAMPIN, C.E. 3/6

Tubular and other Iron Girder Bridges.
Describing the Britannia and Conway Tubular Bridges. By G. DRYSDALE DEMPSEY, C.E. Fourth Edition 2/0

Materials and Construction:
A Theoretical and Practical Treatise on the Strains, Designing, and Erection of Works of Construction. By FRANCIS CAMPIN, C.E. . . . 3/0

Sanitary Work in the Smaller Towns and in Villages.
By CHARLES SLAGG, Assoc. M.Inst.C.E. Third Edition . . 3/0

Roads and Streets (The Construction of).
In Two Parts: I. THE ART OF CONSTRUCTING COMMON ROADS, by H. LAW, C.E., Revised by D. K. CLARK, C.E.; II. RECENT PRACTICE: Including Pavements of Wood, Asphalte, &c. By D. K. CLARK, C.E. 4/6

Gas Works (The Construction of),
And the Manufacture and Distribution of Coal Gas. By S. HUGHES, C.E. Re-written by WILLIAM RICHARDS, C.E. Eighth Edition . . 5/6

Water Works
For the Supply of Cities and Towns. With a Description of the Principal Geological Formations of England as influencing Supplies of Water. By SAMUEL HUGHES, F.G.S., C.E. Enlarged Edition 4/0

The Power of Water,
As applied to drive Flour Mills, and to give motion to Turbines and other Hydrostatic Engines. By JOSEPH GLYNN, F.R.S. New Edition . 2/0

Wells and Well-Sinking.
By JOHN GEO. SWINDELL, A.R.I.B.A., and G. R. BURNELL, C.E. Revised Edition. With a New Appendix on the Qualities of Water. Illustrated 2/0

The Drainage of Lands, Towns, and Buildings.
By G. D. DEMPSEY, C.E. Revised, with large Additions on Recent Practice, by D. K. CLARK, M.I.C.E. Third Edition 4/6

The Blasting and Quarrying of Stone,
For Building and other Purposes. With Remarks on the Blowing up of Bridges. By Gen. Sir J. BURGOYNE, K.C.B. 1/6

Foundations and Concrete Works.
With Practical Remarks on Footings, Planking, Sand, Concrete, Béton, Pile-driving, Caissons, and Cofferdams. By E. DOBSON, M.R.I.B.A. Eighth Edition 1/6

Digitized by Google

Pneumatics,
Including Acoustics and the Phenomena of Wind Currents, for the Use of Beginners. By CHARLES TOMLINSON, F.R.S. Fourth Edition . 1/6

Land and Engineering Surveying.
For Students and Practical Use. By T. BAKER, C.E. Eighteenth Edition, Revised and Extended by F. E. DIXON, A.M. Inst. C.E., Professional Associate of the Institution of Surveyors. With numerous Illustrations and two Lithographic Plates . . . . . *[Just published* 2/0

Mensuration and Measuring.
For Students and Practical Use. With the Mensuration and Levelling of Land for the purposes of Modern Engineering. By T. BAKER, C.E. New Edition by E. NUGENT, C.E. 1/6

MINING AND METALLURGY.

Mineralogy,
Rudiments of. By A. RAMSAY, F.G.S. Fourth Edition, revised and enlarged. Woodcuts and Plates 3/6

Coal and Coal Mining,
A Rudimentary Treatise on. By the late Sir WARINGTON W. SMYTH, F.R.S. Eighth Edition, revised and extended by T. FORSTER BROWN. *[Just published* 3/6

Metallurgy of Iron.
Containing Methods of Assay, Analyses of Iron Ores, Processes of Manufacture of Iron and Steel, &c. By H. BAUERMAN, F.G.S. With numerous Illustrations. Sixth Edition, revised and enlarged 5/0

The Mineral Surveyor and Valuer's Complete Guide.
By W. LINTERN. Fourth Edition, with an Appendix on Magnetic and Angular Surveying 3/6

Slate and Slate Quarrying:
Scientific, Practical, and Commercial. By D. C. DAVIES, F.G.S. With numerous Illustrations and Folding Plates. Fourth Edition . . 3/0

A First Book of Mining and Quarrying,
With the Sciences connected therewith, for Primary Schools and Self Instruction. By J. H. COLLINS, F.G.S. Second Edition . . . 1/6

Subterraneous Surveying,
With and without the Magnetic Needle. By T. FENWICK and T. BAKER, C.E. Illustrated 2/6

Mining Tools.
Manual of. By WILLIAM MORGANS, Lecturer on Practical Mining at the Bristol School of Mines 2/6

Mining Tools, Atlas
Of Engravings to Illustrate the above, containing 235 Illustrations of Mining Tools, drawn to Scale. 4to 4/6

Physical Geology,
Partly based on Major-General PORTLOCK's "Rudiments of Geology." By RALPH TATE, A.L.S., &c. Woodcuts. 2/0

Historical Geology,
Partly based on Major-General PORTLOCK's "Rudiments." By RALPH TATE, A.L.S., &c. Woodcuts 2/6

Geology, Physical and Historical.
Consisting of "Physical Geology," which sets forth the Leading Principles of the Science; and "Historical Geology," which treats of the Mineral and Organic Conditions of the Earth at each successive epoch. By RALPH TATE, F.G.S. 4/6

Electro-Metallurgy,
Practically Treated. By ALEXANDER WATT. Tenth Edition, enlarged and revised, including the most Recent Processes 3/6

Digitized by Google

MECHANICAL ENGINEERING.

The Workman's Manual of Engineering Drawing.
By JOHN MAXTON, Instructor in Engineering Drawing, Royal Naval College, Greenwich. Seventh Edition. 300 Plates and Diagrams . 3/6

Fuels: Solid, Liquid, and Gaseous.
Their Analysis and Valuation. For the Use of Chemists and Engineers. By H. J. PHILLIPS, F.C.S., formerly Analytical and Consulting Chemist to the Great Eastern Railway. Third Edition 2/0

Fuel, Its Combustion and Economy.
Consisting of an Abridgment of "A Treatise on the Combustion of Coal and the Prevention of Smoke." By C. W. WILLIAMS, A.I.C.E. With Extensive Additions by D. K. CLARK, M.Inst.C.E. Fourth Edition . 3/6

The Boilermaker's Assistant
In Drawing, Templating, and Calculating Boiler Work, &c. By J. COURTNEY, Practical Boilermaker. Edited by D. K. CLARK, C.E. . 2/0

The Boiler-Maker's Ready Reckoner,
With Examples of Practical Geometry and Templating for the Use of Platers, Smiths, and Riveters. By JOHN COURTNEY. Edited by D. K. CLARK, M.I.C.E. Fourth Edition 4/0

*** *The last two Works in One Volume, half-bound, entitled* "THE BOILER-MAKER'S READY-RECKONER AND ASSISTANT." By J. COURTNEY and D. K. CLARK. *Price* 7/0.

Steam Boilers:
Their Construction and Management. By R. ARMSTRONG, C.E. Illustrated 1/6

Steam and Machinery Management.
A Guide to the Arrangement and Economical Management of Machinery. By M. POWIS BALE, M.Inst.M.E. 2/6

Steam and the Steam Engine,
Stationary and Portable. Being an Extension of the Treatise on the Steam Engine of Mr. J. SEWELL. By D. K. CLARK, C.E. Fourth Edition 3/6

The Steam Engine,
A Treatise on the Mathematical Theory of, with Rules and Examples for Practical Men. By T. BAKER, C.E. 1/6

The Steam Engine.
By Dr. LARDNER. Illustrated 1/6

Locomotive Engines,
By G. D. DEMPSEY, C.E. With large Additions treating of the Modern Locomotive, by D. K. CLARK, M.Inst.C.E. 3/0

Locomotive Engine-Driving.
A Practical Manual for Engineers in charge of Locomotive Engines. By MICHAEL REYNOLDS. Tenth Edition. 3*s.* 6*d.* limp; cloth boards . 4/6

Stationary Engine-Driving.
A Practical Manual for Engineers in charge of Stationary Engines. By MICHAEL REYNOLDS. Sixth Edition. 3*s.* 6*d.* limp; cloth boards . 4/6

The Smithy and Forge.
Including the Farrier's Art and Coach Smithing. By W. J. E. CRANE. Fourth Edition 2/6

Modern Workshop Practice,
As applied to Marine, Land, and Locomotive Engines, Floating Docks, Dredging Machines, Bridges, Ship-building, &c. By J. G. WINTON. Fourth Edition, Illustrated 3/6

Mechanical Engineering.
Comprising Metallurgy, Moulding, Casting, Forging, Tools, Workshop Machinery, Mechanical Manipulation, Manufacture of the Steam Engine, &c. By FRANCIS CAMPIN, C.E. Third Edition 2/6

Details of Machinery.
Comprising Instructions for the Execution of various Works in Iron in the Fitting-Shop, Foundry, and Boiler-Yard. By FRANCIS CAMPIN, C.E. 3/0

Digitized by Google

Elementary Engineering:
A Manual for Young Marine Engineers and Apprentices. In the Form of Questions and Answers on Metals, Alloys, Strength of Materials, &c. By J. S. BREWER. Fourth Edition 1/6

Power in Motion:
Horse-power Motion, Toothed-Wheel Gearing, Long and Short Driving Bands, Angular Forces, &c. By JAMES ARMOUR, C.E. Third Edition 2/0

Iron and Heat,
Exhibiting the Principles concerned in the Construction of Iron Beams, Pillars, and Girders. By J. ARMOUR, C.E. 2/6

Practical Mechanism,
And Machine Tools. By T. BAKER, C.E. With Remarks on Tools and Machinery, by J. NASMYTH, C.E. 2/6

Mechanics:
Being a concise Exposition of the General Principles of Mechanical Science, and their Applications. By CHARLES TOMLINSON, F.R.S. . 1/6

Cranes (The Construction of),
And other Machinery for Raising Heavy Bodies for the Erection of Buildings, &c. By JOSEPH GLYNN, F.R.S. 1/6

NAVIGATION, SHIPBUILDING, ETC.

The Sailor's Sea Book:
A Rudimentary Treatise on Navigation. By JAMES GREENWOOD, B.A. With numerous Woodcuts and Coloured Plates. New and enlarged Edition. By W. H. ROSSER 2/6

Practical Navigation.
Consisting of THE SAILOR'S SEA-BOOK, by JAMES GREENWOOD and W. H. ROSSER; together with Mathematical and Nautical Tables for the Working of the Problems, by HENRY LAW, C.E., and Prof. J. R. YOUNG. 7/0

Navigation and Nautical Astronomy,
In Theory and Practice. By Prof. J. R. YOUNG. New Edition. 2/6

Mathematical Tables,
For Trigonometrical, Astronomical, and Nautical Calculations; to which is prefixed a Treatise on Logarithms. By H. LAW, C.E. Together with a Series of Tables for Navigation and Nautical Astronomy. By Professor J. R. YOUNG. New Edition 4/0

Masting, Mast-Making, and Rigging of Ships.
Also Tables of Spars, Rigging, Blocks; Chain, Wire, and Hemp Ropes, &c., relative to every class of vessels. By ROBERT KIPPING, N.A. . 2/0

Sails and Sail-Making.
With Draughting, and the Centre of Effort of the Sails. By ROBERT KIPPING, N.A. 2/6

Marine Engines and Steam Vessels.
By R. MURRAY, C.E. Eighth Edition, thoroughly revised, with Additions by the Author and by GEORGE CARLISLE, C.E. 4/6

Naval Architecture:
An Exposition of Elementary Principles. By JAMES PEAKE . . 3/6

Ships for Ocean and River Service,
Principles of the Construction of. By HAKON A. SOMMERFELDT . 1/6

Atlas of Engravings
To Illustrate the above. Twelve large folding Plates. Royal 4to, cloth 7/6

The Forms of Ships and Boats.
By W. BLAND. Ninth Edition, with numerous Illustrations and Models 1/6

Digitized by Google

ARCHITECTURE AND THE BUILDING ARTS.

Constructional Iron and Steel Work,
As applied to Public, Private, and Domestic Buildings. By FRANCIS CAMPIN, C.E. 3/6

Building Estates:
A Treatise on the Development, Sale, Purchase, and Management of Building Land. By F. MAITLAND. Third Edition 2/0

The Science of Building:
An Elementary Treatise on the Principles of Construction. By E. WYNDHAM TARN, M.A. Lond. Fourth Edition 3/6

The Art of Building:
General Principles of Construction, Strength, and Use of Materials, Working Drawings, Specifications, &c. By EDWARD DOBSON, M.R.I.B.A. . 2/0

A Book on Building,
Civil and Ecclesiastical. By Sir EDMUND BECKETT, Q.C. (Lord GRIMTHORPE). Second Edition 4/6

Dwelling-Houses (The Erection of),
Illustrated by a Perspective View, Plans, and Sections of a Pair of Villas, with Specification, Quantities, and Estimates. By S. H. BROOKS, Architect 2/6

Cottage Building.
By C. BRUCE ALLEN. Eleventh Edition, with Chapter on Economic Cottages for Allotments, by E. E. ALLEN, C.E. 2/0

Acoustics in Relation to Architecture and Building:
The Laws of Sound as applied to the Arrangement of Buildings. By Professor T. ROGER SMITH, F.R.I.B.A. New Edition, Revised . . 1/6

The Rudiments of Practical Bricklaying.
General Principles of Bricklaying; Arch Drawing, Cutting, and Setting; Pointing; Paving, Tiling, &c. By ADAM HAMMOND. With 68 Woodcuts 1/6

The Art of Practical Brick Cutting and Setting.
By ADAM HAMMOND. With 90 Engravings 1/6

Brickwork:
A Practical Treatise, embodying the General and Higher Principles of Bricklaying, Cutting and Setting; with the Application of Geometry to Roof Tiling, &c. By F. WALKER 1/6

Bricks and Tiles,
Rudimentary Treatise on the Manufacture of; containing an Outline of the Principles of Brickmaking. By E. DOBSON, M.R.I.B.A. Additions by C. TOMLINSON, F.R.S. Illustrated 3/0

The Practical Brick and Tile Book.
Comprising: BRICK AND TILE MAKING, by E. DOBSON, M.INST.C.E.; Practical BRICKLAYING, by A. HAMMOND; BRICK-CUTTING AND SETTING, by A. HAMMOND. 550 pp. with 270 Illustrations, half-bound . . 6/0

Carpentry and Joinery—
THE ELEMENTARY PRINCIPLES OF CARPENTRY. Chiefly composed from the Standard Work of THOMAS TREDGOLD, C.E. With Additions, and TREATISE ON JOINERY, by E. W. TARN, M.A. Seventh Edition . . . 3/6

Carpentry and Joinery—Atlas
Of 35 Plates to accompany and Illustrate the foregoing book. With Descriptive Letterpress. 4to 6/0

Digitized by Google

A Practical Treatise on Handrailing;
Showing New and Simple Methods. By GEO. COLLINGS. Second Edition, Revised, including a TREATISE ON STAIRBUILDING. With Plates . 2/6

Circular Work in Carpentry and Joinery.
A Practical Treatise on Circular Work of Single and Double Curvature. By GEORGE COLLINGS. Third Edition 2/6

Roof Carpentry:
Practical Lessons in the Framing of Wood Roofs. For the Use of Working Carpenters. By GEO. COLLINGS 2/0

The Construction of Roofs of Wood and Iron;
Deduced chiefly from the Works of Robison, Tredgold, and Humber. By E. WYNDHAM TARN, M.A., Architect. Third Edition . . . 1/6

The Joints Made and Used by Builders.
By WYVILL J. CHRISTY, Architect. With 160 Woodcuts . 3/0

Shoring
And its Application: A Handbook for the Use of Students. By GEORGE H. BLAGROVE. With 31 Illustrations 1/6

The Timber Importer's, Timber Merchant's, and Builder's Standard Guide.
By R. E. GRANDY 2/0

Plumbing:
A Text-Book to the Practice of the Art or Craft of the Plumber. With Chapters upon House Drainage and Ventilation. By WM. PATON BUCHAN. Eighth Edition, Re-written and Enlarged, with 500 Illustrations . 3/6

Ventilation:
A Text Book to the Practice of the Art of Ventilating Buildings. By W. P. BUCHAN, R.P., Author of "Plumbing," &c. With 170 Illustrations 3/6

The Practical Plasterer:
A Compendium of Plain and Ornamental Plaster Work. By W. KEMP 2/0

House Painting, Graining, Marbling, & Sign Writing.
With a Course of Elementary Drawing, and a Collection of Useful Receipts. By ELLIS A. DAVIDSON. Seventh Edition. Coloured Plates . . 5/0

*** *The above, in cloth boards, strongly bound,* 6/0

A Grammar of Colouring,
Applied to Decorative Painting and the Arts. By GEORGE FIELD. New Edition, enlarged, by ELLIS A. DAVIDSON. With Coloured Plates . 3/0

Elementary Decoration
As applied to Dwelling Houses, &c. By JAMES W. FACEY. Illustrated 2/0

Practical House Decoration.
A Guide to the Art of Ornamental Painting, the Arrangement of Colours in Apartments, and the Principles of Decorative Design. By JAMES W. FACEY. 2/6

*** *The last two Works in One handsome Vol., half-bound, entitled* "HOUSE DECORATION, ELEMENTARY AND PRACTICAL," *price* 5/0

Portland Cement for Users.
By HENRY FAIJA, A.M.Inst.C.E. Third Edition, Corrected . . 2/0

Limes, Cements, Mortars, Concretes, Mastics, Plastering, &c.
By G. R. BURNELL C.E. Fifteenth Edition 1/6

Digitized by Google

Masonry and Stone-Cutting.
The Principles of Masonic Projection and their application to Construction. By EDWARD DOBSON, M.R.I.B.A. 2/6

Arches, Piers, Buttresses, &c.:
Experimental Essays on the Principles of Construction. By W. BLAND. 1/6

Quantities and Measurements,
In Bricklayers', Masons', Plasterers', Plumbers', Painters', Paperhangers'. Gilders', Smiths', Carpenters' and Joiners' Work. By A. C. BEATON 1/6

The Complete Measurer:
Setting forth the Measurement of Boards, Glass, Timber and Stone. By R. HORTON. Sixth Edition 4/0

*** *The above, strongly bound in leather, price* 5/0.

Light:
An Introduction to the Science of Optics. Designed for the Use of Students of Architecture, Engineering, and other Applied Sciences. By E. WYNDHAM TARN, M.A., Author of "The Science of Building," &c. . . 1/6

Hints to Young Architects.
By GEORGE WIGHTWICK, Architect. Sixth Edition, revised and enlarged by G. HUSKISSON GUILLAUME, Architect 3/6

Architecture—Orders:
The Orders and their Æsthetic Principles. By W. H. LEEDS. Illustrated. 1/6

Architecture—Styles:
The History and Description of the Styles of Architecture of Various Countries, from the Earliest to the Present Period. By T. TALBOT BURY, F.R.I.B.A. Illustrated 2/0

*** ORDERS AND STYLES OF ARCHITECTURE, *in One Vol.*, 3/6.

Architecture—Design:
The Principles of Design in Architecture, as deducible from Nature and exemplified in the Works of the Greek and Gothic Architects. By EDW. LACY GARBETT, Architect. Illustrated 2/6

*** *The three preceding Works in One handsome Vol., half bound, entitled* "MODERN ARCHITECTURE," *price* 6/0.

Perspective for Beginners.
Adapted to Young Students and Amateurs in Architecture, Painting, &c. By GEORGE PYNE 2/0

Architectural Modelling in Paper.
By T. A. RICHARDSON. With Illustrations, engraved by O. JEWITT 1/6

Glass Staining, and the Art of Painting on Glass.
From the German of Dr. GESSERT and EMANUEL OTTO FROMBERG. With an Appendix on THE ART OF ENAMELLING 2/6

Vitruvius—The Architecture of.
In Ten Books. Translated from the Latin by JOSEPH GWILT, F.S.A., F.R.A.S. With 23 Plates 5/0

N.B.—This is the only Edition of VITRUVIUS *procurable at a moderate price*

Grecian Architecture,
An Inquiry into the Principles of Beauty in. With an Historical View of the Rise and Progress of the Art in Greece. By the EARL OF ABERDEEN 1/0

*** *The two preceding Works in One handsome Vol., half bound, entitled* "ANCIENT ARCHITECTURE," *price* 6/0.

Digitized by Google

INDUSTRIAL AND USEFUL ARTS.

Cements, Pastes, Glues, and Gums.
A Practical Guide to the Manufacture and Application of the various Agglutinants required for Workshop, Laboratory, or Office Use. With upwards of 900 Recipes and Formulæ. By H. C. STANDAGE . . 2/0

Clocks and Watches, and Bells,
A Rudimentary Treatise on. By Sir EDMUND BECKETT, Q.C. (Lord GRIMTHORPE). Seventh Edition 4/6

The Goldsmith's Handbook.
Containing full Instructions in the Art of Alloying, Melting, Reducing, Colouring, Collecting and Refining, Recovery of Waste, Solders, Enamels. &c., &c. By GEORGE E. GEE. Fifth Edition 3/0

The Silversmith's Handbook,
On the same plan as the GOLDSMITH'S HANDBOOK. By GEORGE E. GEE. Third Edition 3/0
*** *The last two Works, in One handsome Vol., half-bound,* 7/0.

The Hall-Marking of Jewellery.
Comprising an account of all the different Assay Towns of the United Kingdom; with the Stamps and Laws relating to the Standards and Hall-Marks at the various Assay Offices. By GEORGE E. GEE . . 3/0

French Polishing and Enamelling.
A Practical Work of Instruction, including numerous Recipes for making Polishes, Varnishes, Glaze-Lacquers, Revivers, &c. By R. BITMEAD. [*Just Published.* 1/6

Practical Organ Building.
By W. E. DICKSON, M.A. Second Edition, Revised, with Additions 2/6

Coach-Building:
A Practical Treatise. By JAMES W. BURGESS. With 57 Illustrations 2/6

The Brass Founder's Manual:
Instructions for Modelling, Pattern Making, Moulding, Turning, &c. By W. GRAHAM 2/0

The Sheet-Metal Worker's Guide.
A Practical Handbook for Tinsmiths, Coppersmiths, Zincworkers, &c., with 46 Diagrams. By W. J. E. CRANE. Third Edition, revised . . 1/6

Sewing Machinery:
Its Construction, History, &c. With full Technical Directions for Adjusting, &c. By J. W. URQUHART, C.E. 2/0

Gas Fitting:
A Practical Handbook. By JOHN BLACK. New Edition . . 2/6

Construction of Door Locks.
From the Papers of A. C. HOBBS. Edited by C. TOMLINSON, F.R.S. 2/6

The Model Locomotive Engineer, Fireman, and Engine-Boy.
Comprising an Historical Notice of the Pioneer Locomotive Engines and their Inventors. By MICHAEL REYNOLDS 3/6

The Art of Letter Painting made Easy.
By J. G. BADENOCH. With 12 full-page Engravings of Examples . 1/6

The Art of Boot and Shoemaking.
Including Measurement, Last-fitting, Cutting-out, Closing and Making. By JOHN BEDFORD LENO. With numerous Illustrations. Fourth Edition 2/0

Mechanical Dentistry:
A Practical Treatise on the Construction of the Various Kinds of Artificial Dentures. By CHARLES HUNTER. Fourth Edition . . . 3/0

Wood Engraving:
A Practical and Easy Introduction to the Art. By W. N. BROWN . 1/6

Laundry Management.
A Handbook for Use in Private and Public Laundries. By the EDITOR of "The Laundry Journal." 2/0

Digitized by Google

AGRICULTURE, GARDENING, ETC.

Draining and Embanking:
A Practical Treatise. By Prof. JOHN SCOTT. With 68 Illustrations 1/6

Irrigation and Water Supply:
A Practical Treatise on Water Meadows, Sewage Irrigation, Warping, &c.; on the Construction of Wells, Ponds, Reservoirs, &c. By Prof. JOHN SCOTT. With 34 Illustrations 1/6

Farm Roads, Fences, and Gates:
A Practical Treatise on the Roads, Tramways, and Waterways of the Farm; the Principles of Enclosures; and the different kinds of Fences, Gates, and Stiles. By Prof. JOHN SCOTT. With 75 Illustrations . 1/6

Farm Buildings:
A Practical Treatise on the Buildings necessary for various kinds of Farms, their Arrangement and Construction, with Plans and Estimates. By Prof. JOHN SCOTT. With 105 Illustrations 2/0

Barn Implements and Machines:
Treating of the Application of Power and Machines used in the Threshing-barn, Stockyard, Dairy, &c. By Prof. J. SCOTT. With 123 Illustrations. 2/0

Field Implements and Machines:
With Principles and Details of Construction and Points of Excellence; their Management, &c. By Prof. JOHN SCOTT. With 138 Illustrations 2/0

Agricultural Surveying:
A Treatise on Land Surveying, Levelling, and Setting-out; with Directions for Valuing Estates. By Prof. J. SCOTT. With 62 Illustrations . 1/6

Farm Engineering.
By Professor JOHN SCOTT. Comprising the above Seven Volumes in One, 1,150 pages, and over 600 Illustrations. Half-bound . . . 12/0

Outlines of Farm Management.
Treating of the General Work of the Farm; Stock; Contract Work; Labour, &c.. By R. SCOTT BURN 2/6

Outlines of Landed Estates Management.
Treating of the Varieties of Lands, Methods of Farming, Setting-out of Farms, Roads, Fences, Gates, Drainage, &c. By R. SCOTT BURN. 2/6
*** *The above Two Vols. in One, handsomely half-bound, price* 6/0

Soils, Manures, and Crops.
(Vol. I. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN . 2/0

Farming and Farming Economy.
(Vol. II. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN 3/0

Stock: Cattle, Sheep, and Horses.
(Vol. III. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN 2/6

Dairy, Pigs, and Poultry.
(Vol. IV. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN 2/0

Utilization of Sewage, Irrigation, and Reclamation of Waste Land.
(Vol. V. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN . 2/6

Outlines of Modern Farming.
By R. SCOTT BURN. Consisting of the above Five Volumes in One, 1,250 pp., profusely Illustrated, half-bound 12/0

Digitized by Google

Book-keeping for Farmers and Estate Owners.
A Practical Treatise, presenting, in Three Plans, a System adapted for all classes of Farms. By J. M. WOODMAN. Third Edition, revised . 2/6

Ready Reckoner for the Admeasurement of Land.
By A. ARMAN. Fourth Edition, revised and extended by C. NORRIS 2/0

Miller's, Corn Merchant's, and Farmer's Ready Reckoner.
Second Edition, revised, with a Price List of Modern Flour Mill Machinery, by W. S. HUTTON, C.E. 2/0

The Hay and Straw Measurer.
New Tables for the Use of Auctioneers, Valuers, Farmers, Hay and Straw Dealers, &c. By JOHN STEELE 2/0

Meat Production.
A Manual for Producers, Distributors, and Consumers of Butchers' Meat. By JOHN EWART 2/6

Sheep:
The History, Structure, Economy, and Diseases of. By W. C. SPOONER, M.R.V.S. Fifth Edition, with fine Engravings 3/6

Market and Kitchen Gardening.
By C. W. SHAW, late Editor of "Gardening Illustrated" . . . 3/0

Kitchen Gardening Made Easy.
Showing the best means of Cultivating every known Vegetable and Herb, &c., with directions for management all the year round. By GEORGE M. F. GLENNY. Illustrated 1/6

Cottage Gardening:
Or Flowers, Fruits, and Vegetables for Small Gardens. By E. HOBDAY. 1/6

Garden Receipts.
Edited by CHARLES W. QUIN 1/6

Fruit Trees,
The Scientific and Profitable Culture of. From the French of M. DU BREUIL. Fifth Edition, carefully Revised by GEORGE GLENNY. With 187 Woodcuts 3/6

The Tree Planter and Plant Propagator:
With numerous Illustrations of Grafting, Layering, Budding, Implements, Houses, Pits, &c. By SAMUEL WOOD 2/0

The Tree Pruner:
A Practical Manual on the Pruning of Fruit Trees, Shrubs, Climbers, and Flowering Plants. With numerous Illustrations. By SAMUEL WOOD 1/6

*** *The above Two Vols. in One, handsomely half-bound, price* 3/6

The Art of Grafting and Budding.
By CHARLES BALTET. With Illustrations 2/6

Digitized by Google

MATHEMATICS, ARITHMETIC, ETC.

Descriptive Geometry,
An Elementary Treatise on; with a Theory of Shadows and of Perspective, extracted from the French of G. MONGE. To which is added a Description of the Principles and Practice of Isometrical Projection. By J. F. HEATHER, M.A. With 14 Plates 2/0

Practical Plane Geometry:
Giving the Simplest Modes of Constructing Figures contained in one Plane and Geometrical Construction of the Ground. By J. F. HEATHER, M.A. With 215 Woodcuts 2/0

Analytical Geometry and Conic Sections,
A Rudimentary Treatise on. By JAMES HANN. A New Edition, re-written and enlarged by Professor J. R. YOUNG 2/0

Euclid (The Elements of).
With many Additional Propositions and Explanatory Notes; to which is prefixed an Introductory Essay on Logic. By HENRY LAW, C.E. . 2/6

*** *Sold also separately, viz:—*

Euclid. The First Three Books. By HENRY LAW, C.E. . . . 1/6
Euclid. Books 4, 5, 6, 11, 12. By HENRY LAW, C.E. . . . 1/6

Plane Trigonometry,
The Elements of. By JAMES HANN. 1/6

Spherical Trigonometry,
The Elements of. By JAMES HANN. Revised by CHARLES H. DOWLING, C.E. 1/0
*** *Or with "The Elements of Plane Trigonometry," in One Volume,* 2/6

Differential Calculus,
Elements of the. By W. S. B. WOOLHOUSE, F.R.A.S., &c. . . 1/6

Integral Calculus.
By HOMERSHAM COX, B.A. 1/6

Algebra,
The Elements of. By JAMES HADDON, M.A. With Appendix, containing Miscellaneous Investigations, and a Collection of Problems . . 2/0

A Key and Companion to the Above.
An extensive Repository of Solved Examples and Problems in Algebra. By J. R. YOUNG 1/6

Commercial Book-keeping.
With Commercial Phrases and Forms in English, French, Italian, and German. By JAMES HADDON, M.A. 1/6

Arithmetic,
A Rudimentary Treatise on. With full Explanations of its Theoretical Principles, and numerous Examples for Practice. For the Use of Schools and for Self-Instruction. By J. R. YOUNG, late Professor of Mathematics in Belfast College. Thirteenth Edition 1/6

A Key to the Above.
By J. R. YOUNG 1/6

Equational Arithmetic,
Applied to Questions of Interest, Annuities, Life Assurance, and General Commerce; with various Tables by which all Calculations may be greatly facilitated. By W. HIPSLEY 1/6

Arithmetic,
Rudimentary, for the Use of Schools and Self-Instruction. By JAMES HADDON, M.A. Revised by ABRAHAM ARMAN 1/6

A Key to the Above.
By A. ARMAN 1/6

Digitized by Google

Mathematical Instruments:
Their Construction, Adjustment, Testing, and Use concisely Explained. By J. F. HEATHER, M.A., of the Royal Military Academy, Woolwich. Fourteenth Edition, Revised, with Additions, by A. T. WALMISLEY, M.I.C.E. Original Edition, in 1 vol., Illustrated **2/0**

*** *In ordering the above, be careful to say "Original Edition," or give the number in the Series* (32), *to distinguish it from the Enlarged Edition in* 3 *vols.* (*as follows*)—

Drawing and Measuring Instruments.
Including—I. Instruments employed in Geometrical and Mechanical Drawing, and in the Construction, Copying, and Measurement of Maps and Plans. II. Instruments used for the purposes of Accurate Measurement, and for Arithmetical Computations. By J. F. HEATHER, M.A. . **1/6**

Optical Instruments.
Including (more especially) Telescopes, Microscopes, and Apparatus for producing copies of Maps and Plans by Photography. By J. F. HEATHER, M.A. Illustrated **1/6**

Surveying and Astronomical Instruments.
Including—I. Instruments used for Determining the Geometrical Features of a portion of Ground. II. Instruments employed in Astronomical Observations. By J. F. HEATHER, M.A. Illustrated. . . . **1/6**

*** *The above three volumes form an enlargement of the Author's original work, "Mathematical Instruments," price* **2/0**. (*Described at top of page.*)

Mathematical Instruments:
Their Construction, Adjustment, Testing and Use. Comprising Drawing, Measuring, Optical, Surveying, and Astronomical Instruments. By J. F. HEATHER, M.A. Enlarged Edition, for the most part entirely re-written. The Three Parts as above, in One thick Volume. **4/6**

The Slide Rule, and How to Use It.
Containing full, easy, and simple Instructions to perform all Business Calculations with unexampled rapidity and accuracy. By CHARLES HOARE, C.E. With a Slide Rule, in tuck of cover. Seventh Edition . . **2/6**

Logarithms.
With Mathematical Tables for Trigonometrical, Astronomical, and Nautical Calculations. By HENRY LAW, C.E. Revised Edition . . . **3/0**

Compound Interest and Annuities (Theory of).
With Tables of Logarithms for the more Difficult Computations of Interest, Discount, Annuities, &c., in all their Applications and Uses for Mercantile and State Purposes. By FEDOR THOMAN, Paris. Fourth Edition . **4/0**

Mathematical Tables,
For Trigonometrical, Astronomical, and Nautical Calculations; to which is prefixed a Treatise on Logarithms. By H. LAW, C.E. Together with a Series of Tables for Navigation and Nautical Astronomy. By Professor J. R. YOUNG. New Edition **4/0**

Mathematics,
As applied to the Constructive Arts. By FRANCIS CAMPIN, C.E., &c. Third Edition **3/0**

Astronomy.
By the late Rev. ROBERT MAIN, F.R.S. Third Edition, revised and corrected to the Present Time. By W. T. LYNN, F.R.A.S. . . . **2/0**

Statics and Dynamics.
The Principles and Practice of. Embracing also a clear development of Hydrostatics, Hydrodynamics, and Central Forces. By T. BAKER, C.E. Fourth Edition **1/6**

Digitized by Google

Portuguese Grammar,
In a Simple and Practical Form. With Exercises. By ALFRED ELWES 1/6

Portuguese-English and English-Portuguese Dictionary.
Including a large number of Technical Terms used in Mining, Engineering, &c., with the proper Accents and the Gender of every Noun. By ALFRED ELWES. Third Edition, revised 5/0
*** *Or with the* GRAMMAR, 7/0.

Animal Physics,
Handbook of. By DIONYSIUS LARDNER, D.C.L. With 520 Illustrations. In One Vol. (732 pages), cloth boards 7/6
*** *Sold also in Two Parts, as follows:—*
ANIMAL PHYSICS. By Dr. LARDNER. Part I., Chapters I.—VII. 4/0
ANIMAL PHYSICS. By Dr. LARDNER. Part II., Chapters VIII.—XVIII. 3/0

BRADBURY, AGNEW & CO., LD., PRINTERS, LONDON AND TONBRIDGE.

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

CABOT SCIENCE LIBRARY
CANCELLED
MAY 06 1997
CABOT
OCT 30 1997
BOOK DUE
CANCELLED
OCT 27 1997
CABOT
NOV 20 2003
BOOK DUE
CANCELLED
DEC 08 2003
Digitized by Google

3 2044 044 828

This book should be returned to the Library on or before the last date stamped below.

A fine of five cents a day is incurred by retaining it beyond the specified time.

Please return promptly.

JAN 7 55 H

JUN 11 '69 H

Digitized by Google

3 2044 044 828 796